

# Cone Ceiling


RENAISSANCE

16"


24"

32"


## Sloped Trim



**RIC2010**




**RIC2012**




**RIC2014**


## Stepped Trim



**RIC2020**



**RIC2022**



**RIC2024**

### Specifications:

- Trim rings are spun from .063" thick base material (brass or aluminum) or 18 gauge steel (plated or painted).
- Chassis is formed from 18 gauge cold-rolled steel.
- Formed acrylic bowl with a minimum wall thickness of .118". Opal finish is standard.
- Integral fluorescent ballasts are HPF electronic with low harmonic distortion.
- Ballasts are thermally protected and have Class "A" sound rating.
- Backplate attaches to standard 4" octagonal junction box.
- UL listed (US and Canada) for damp locations. (Not recommended for exterior use.)

Design modification rights reserved.



**RIC2014**

Chrome Plated Polished Brass



**RIC2024**

Brushed Aluminum

Sample model number: **RIC2012 - 2F39 - 120 - BAL - HP02**



	Select Style	Select any Lamping (indirect/bowl illumination)	Lamping Detail (indirect - bowl illumination)	Optical Pkg. Photometry	Select Voltage	Select Finish	Select Options
16"	RIC2010 RIC2020	1N60 1F22	60W A19 INC 22W CIRC T5	A E433-35 B NA	120 277	PT_ Painted. (Include Paint Number.) PBR Polished solid brass BBR Brushed solid brass ABR Antique solid brass CPBR Chrome plated polished brass BAL Brushed aluminum ABST Antique brass over steel BBST Brushed brass over steel CPST Polished chrome over steel PBST Polished brass over steel	SP Spacer canopy (Not available for RIC2014 and 2024.) F Fuse option EMI' Emergency ballast(s) integral EMR Emergency ballast(s) remote SBA Sandblasted acrylic HP01 Silver hand-painted acrylic HP02 Beige hand-painted acrylic HP03 Amber hand-painted acrylic FIN Finial option
24"	RIC2012 RIC2022	1F40 2F26' 2F39'	40W CIRC T5 (2) CFQ26W/G24q (2) FT39W/2G11	B NA C E433-71 C E433-71			
32"	RIC2014 RIC2024	3F39 3F39DM 4F39 3N100	(3) FT39W/2G11 (3) FT39W/2G11 (4) FT39W/2G11 (3) 100W A19 INC	D E433-74 D E433-74 E NA F NA			

**DM** = Dimming ballast(s) provided

<sup>1</sup>Denotes lamping options available with **EMI** (Requires **SP**-Spacer canopy)

*If Photometry is not available, consult factory for further details.*

**See Finish Selection Guide, pages 268-269.**

**For further detail on options, see Technical Notes on page 264.**

**OPTICAL PACKAGES**

