

HORIZONTAL REACTIONS AT DUMBWAITER ATTACHMENT POINTS

	REVISIONS		
LETTER:	DESCRIPTION:	DATE:	BY:





HORIZONTAL
PULLOUT FORCES
CW 50 27#
CW100 56#

NOTE: THESE CALCULATIONS ARE
BASED ON THE RAIL & DRIVE
MACHINERY BEING SUPPORTED BY
THE HOISTWAY FLOOR & NOT
FROM A RAIL THAT IS SUPPORTED
IN SHEAR FROM ITS' ATTACHMENT
POINTS.

## NOTE:

- 1. IT IS THE RESPONSIBILITY OF THE INSTALLER/CONTRACTOR OR ENGINEER TO DESIGN AND SPECIFY STRUCTURAL SUPPORTS.
- 2. ALL CONSTRUCTION TO BE IN COMPLIANCE WITH LOCAL CODES.

