Installation Instructions
1500i/1500iW/G1500i Wall Guard

FIG. 1


1501L
LEFT END CAP
($1^7/_{16}$" ALLOWANCE)

1500A
2" ALUMINUM
RETAINER SUPPORT
.080"

1503
INSIDE CORNER
($1^7/_{16}$" ALLOWANCE

SPACE HOLES
A MAXIMUM OF
EVERY 27" O.C.

1502
OUTSIDE CORNER
($1^3/_{16}$" ALLOWANCE)

1501R
RIGHT END CAP
($1^7/_{16}$" ALLOWANCE)

FIG. 2

#10 x $1^3/_4$"
SHEET METAL
SCREW WITH
ALLIGATOR® ANCHOR

Please read all instructions before installing wall guard.

1. Determine height of wall guard on wall. Measure down $2^1/_2$" and snap chalk line. Mark mounting holes leaving allowance for returns, outside corners and inside corners.

   See Figure 1.

2. Drill marked holes on wall using a $1/_4$" drill bit and position Alligator anchors into holes. Mount retainer supports on wall and tighten screws to secure.

   NOTE: For concrete or brick wall installation, drill $1/_4$" holes, $3/_8$" from end of retainer for end caps/corners. See Figure 2.

IPC.425/REV.3

FIG. 3

3. Slide end caps and corners onto the retainer support and secure, leaving a $1/16$" gap between returns/corners and retainer to allow for adjustment. See Figure 3.

NOTE: For concrete or brick wall installation, use #10 x $1 3/4$" Phillips pan head screws to secure end caps and corners.

$1 1/4$"
SELF-TAPPING
SCREW

FIG. 4

4. Cut the impact bumper to the length between the inside edge of the end caps/corners. Position and snap bumper in place. Cut the cover to length between end caps and/ or corners. (Note: Trim factory edges square before installation). Position cover on retainer and adjust returns and/or corners for a tight fit. Starting at one end of retainer supports, push cover over the retainer supports until it snaps into place. See Figure 4.

COVER
.080" 2mm

CONTINUOUS
IMPACT BUMPER
.070" 1.8mm