

Dividends Horizon

Price List
August 2017



Knoll

Introduction	Knoll and Sustainable Design	3
	Knoll Color Program Finishes	4
	Dividends Legacy Finishes	6
	Dividends Horizon Fabrics	7
Planning Guidelines	Panel Specifications	8
Panels, Pre-Configured	Monolithic Panels	14
	Tiled Panels	22
	Beltway Panels	40
Panels, Build-To-Spec	Topway and Full View Panel Frame Assemblies	46
	Stack Frames	52
	Monolithic Panel Fabric Inserts	56
	Monolithic Laminate Inserts	60
	Tiled Fabric Inserts	66
	Tiled Laminate Inserts	70
	Beltway Inserts	74
	High Acoustic Core Inserts	78
	Window Insert Kits	80
	Markerboard Tiles	82
	Steel Insert Kits	86
	Slatwall Tiles	94
	Technology Tiles	96
	Rolling Door	100
	Open Weave and Glass Screens	104
	Open Weave and Glass Stacking Screens	112
Frameless Add Up	118	
Post Connectors/End Trim	Dividends Horizon DP8 Post Assemblies	122
	Dividends Horizon DP8 Post Components	124
	Panel End Trim and Panel Top Caps	130
	Panel Wall Starter, Panel-to-Panel Top Cap Transition	136
	Wall Mount Tracks and Components	138
	Coat Hooks and Reveal Fillers	142
Alternative Planning	Concealed Post	146
	120° Planning	166
Electrical/Data Components	Electrical Specifications	174
	Base Raceway Electrical	177
	Receptacles	182
	Vertical Electrical	186
	Desktop Power and Data Modules	191
	Beltway Electrical	196
	Electrical Infeeds and Power Poles	200
	New York City, San Francisco and Chicago Electrical	204
Cable Management	208	
Storage Components	Flip-Up Door Overheads	212
	Sliding Door Overheads	216
	Up Mounted Overheads	228
	Overhead Bookshelf and Corner Shelf	230
	Mounting Brackets and Accessories	232
	Task Lights	236
	Pedestals	238
	Credenzas	246
	Flip-up Door Overdesk and Tackboards	268
	Sliding Door Overdesks	272
Sliding Door Overdesks with Tackboard	281	

Worksurfaces	Worksurface Specifications	292
	Rectangular Worksurfaces	296
	Curvilinear Wave End Worksurfaces	302
	Smooth Wave Worksurfaces	304
	Faceted Worksurfaces	306
	Trapezoidal Worksurfaces	312
	Corner Worksurfaces	314
	Peninsula Worksurfaces	320
	Curvilinear Half- and Corner-Round Worksurfaces	322
Transaction Counter Worksurfaces	324	
Cascade Edge Worksurfaces	Rectangular with Cascade Edge	326
	Blended “D” and Curvilinear Corner with Cascade Edge	327
	Blended “L” with Cascade Edge	328
	Half Round and Corner Round with Cascade Edge	329
	Wave End with Cascade Edge	330
Worksurface Supports	Panel Mounted Worksurface Brackets	332
	Screen-to-Worksurface Brackets	336
	Panel Mounted Worksurface Supports	338
	Peninsula Worksurface Supports	340
Tables	Y Leg Tables	342
	X Base Tables	350
	Table Supports	355
	Rectangular, Corner & 120°, C-Leg and T-Leg Worksurface	360
	Conference Tables	362
	Dividends Horizon EQ Tables	366
Freestanding Desks	Preconfigured Desks	368
	Desk Components	380
	Desk Accessories	386
Wall Mounting of Knoll Products		389
Alpha-Numeric Index		391
Selling Policy		404
KnollKey Lock Program		406
General Ordering Information		407

Knoll and Sustainable Design

Each year Knoll sets key initiatives in our journey to sustainability. We are members of a global consortium on energy, have adopted a scientific, metrics-based approach to sustainable product design, and maintain a leadership position in establishing universal, verifiable, sustainability standards for our industry.

Knoll promotes independent third-party certification because it provides the most impartial and trustworthy foundation for industry-wide environmental compliance. Certification by established and respected third parties ensures that all manufacturers are held to the same high standards and that customers can trust a company's declaration about the environmental benefits of its products. Knoll third-party partners include: the International Standards Organization (ISO); Forest Stewardship Council (FSC®); Rainforest Alliance; GREENGUARD® Environmental Institute; and The Business and Institutional Furniture Manufacturer's Association (BIFMA) level® certification from Scientific Certification Systems (SCS).

In addition, Knoll is aligned with the U.S. Green Building Council and can help companies, healthcare organizations and educational institutions achieve Leadership in Energy and Environmental Design (LEED®) workplace certification.

Global Climate Change

- Knoll is a sponsor of the Clinton Global Initiative, which brings together a community of global leaders to devise and implement solutions to some of the world's most pressing challenges, including environmental change.
- Knoll has a comprehensive Energy Management Program to increase energy efficiency in products and processes.

Life Cycle Assessment (LCA) Tool

- Life Cycle Assessment is a science-based measurement of a product's environmental impacts throughout its life cycle, from raw materials sourcing through manufacture, shipping, use and re-use or end-of-life. LCA enables cradle-to-cradle implementation of sustainable practices.

Setting Industry Standards

- Knoll partners with MTS (The Institute for Market Transformation to Sustainability) to develop the SMaRT® Consensus Sustainable Products Standards, a set of consensus-based sustainable product standards based on the LEED® model, for all building products, fabric, apparel, flooring and carpet. MTS, the developer of SMaRT®, is an accredited American National Standards Institute (ANSI) standard developer.
- Knoll also partners with BIFMA (Business and Institutional Furniture Manufacturers Association) to promote level® sustainability standards for the contract furniture industry.
- Knoll has established FSC® (Forest Stewardship Council) certified wood as the standard for general office open plan office systems, casegoods and tables.
- Knoll has launched Full Circle, a resource recovery program developed with ANEW, to help customers extend the life cycle of surplus furniture, fixtures and equipment (FF&E) in an economically, socially and environmentally responsible manner.
- Our goal is to encourage all manufacturers in the contract furniture industry and related industries to adopt standards that will lead to sustainable products and practices.

For more information about Knoll and sustainable design, visit knoll.com/environment.

Specify Core finishes for all new customers**Paint Finishes:**

Beige Mist Metallic (611T)
 Bright White (118T)
 Brown (112T)
 Dark Grey (113T)
 Folkstone Grey (114T)
 Jet Black (111T)
 Medium Grey (115T)
 Medium Metallic Grey (612T)
 Sandstone (116T)
 Silver (613)
 Soft Grey (117T)

Paint Finish Applications:

Panel base raceway covers
 Screen frames
 Steel and slatwall tile inserts
 D1 style tile supports
 DP8 metal panel trim
 DP8 power poles
 Worksurface supports
 Overhead and overdesk cases and doors
 Credenza case, top and door
 Pedestal case and fronts
 Table bases

Laminate Finishes:

Bright White (118)
 Brushed Grey (123)*
 Brushed Sand (122)*
 Classic Oak (143)
 Fog (128)*
 Folkstone Grey (114)**
 Graphite Pear (144)
 Grey Ash (142)
 Jet Black (111)*
 Light Ash (139)
 Medium Cherry (124)
 Medium Grey (115)
 Micro Grey (121)*
 Micro Sand (129)*
 Natural Cherry (126)
 Natural Maple (125)**
 Pumice (119)**
 Soft Grey (117)**
 Walnut (127)
 Warm Ash (140)
 Whitened Ash (141)
 Zebra (145)

*Finish not available on laminate panel inserts

**Melamine worksurface finish

Laminate Finish Applications:

Worksurfaces
 Overhead and overdesk doors
 Credenza top and door
 Laminate tile inserts
 Freestanding desk worksurfaces
 Table tops

2mm Edgeband Finishes:

Bright White (118)
 Classic Oak (143)
 Fog (128)
 Folkstone Grey (114)
 Graphite Pear (144)
 Grey Ash (142)
 Jet Black (111)
 Light Ash (139)
 Medium Cherry (124)
 Medium Grey (115)
 Natural Cherry (126)
 Natural Maple (125)
 Pumice (119)
 Soft Grey (117)
 Walnut (127)
 Warm Ash (140)
 Whitened Ash (141)
 Zebra (145)

2mm Edgeband Finish Applications:

Worksurfaces
 Freestanding desk worksurfaces
 Table tops

Cascade Worksurface Finishes:

Bright White (118)
 Folkstone Grey (114)
 Medium Cherry (124)
 Natural Cherry (126)
 Natural Maple (125)
 Pumice (119)
 Soft Grey (117)
 Walnut (127)

Cascade Worksurface Finish**Applications:**

Cascade edge worksurface

Techwood Finishes:

Black Oak (Y851)
 Blond Maple (Y821) (formerly known as maple techgrain)
 Cherry (Y319)
 Dark Grey Oak (Y343)
 Dark Mahogany (Y326)
 Espresso (Y344)

Light Cherry (Y831) (formerly known as cherry techgrain)
 Maple (Y316)
 Medium Oak (Y329)
 Medium Teak (Y342)
 Medium Walnut (Y323)
 Natural (Y811)
 Wenge (Y883)

Techwood Finish Applications:

Worksurfaces
 Overhead and overdesk doors
 Credenza top and door
 Panel trim
 Veneer tile inserts
 Table tops

DS1 Storage Plastic Finishes:

Bright White (118)
 Brown (112)
 Dark Grey (113)
 Folkstone Grey (114)
 Jet Black (111)
 Medium Grey (115)
 Sandstone (116)
 Soft Grey (117)

DS1 Storage Plastic Finish**Applications:**

DS1 pedestal drawer plugs and handles
 DS1 overhead door end plugs

Note: All Dividends Horizon products except DS1 and DS2 pedestals and doublewide pedestals are painted with a textured finish excluding 613 Silver, which is available as a smooth finish only. X and Y base tables and the freestanding screen kits are always painted with a textured finish, including 613 Silver.

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Note: Worksurfaces, overhead and overdesk doors, credenza tops and doors, and veneer tile inserts will have the same Techwood finish on the surface and the edge.

Order Code	Color Name	Old Order Code	Paint Grade	Paint Finishes	Laminate Finishes	2mm Edgeband Finishes	Cascade Worksurface Finishes	Techwood Finishes	Plastic Trim Finishes	DS1 Storage Plastic Finishes
Paints and Laminates										
611T*	Beige Mist Metallic		P2	•						
118T*	Bright White	LH	P1	•	•	•	•			•
112T*	Brown		P1	•						•
123	Brushed Grey				•					
122	Brushed Sand				•					
143	Classic Oak				•	•				
113T*	Dark Grey	Y3	P1	•		•			•	•
128	Fog	G			•	•				
114T*	Folkstone Grey		P1	•	•	•	•			•
144	Graphite Pear				•	•				
142	Grey Ash				•	•				
111T*	Jet Black	27	P1	•	•	•				•
139	Light Ash				•	•				
124	Medium Cherry				•	•	•			
115	Medium Grey				•	•				
115T*	Medium Grey	Y2	P1	•					•	•
612T*	Medium Metallic Grey	J	P2	•						
121	Micro Grey				•					
129	Micro Sand				•					
126	Natural Cherry				•	•	•			
125	Natural Maple				•	•	•			
119	Pumice	LB, F			•	•	•			
116T*	Sandstone		P1	•						•
613	Silver	3	P3	•						
117T*	Soft Grey	E, M42	P1	•	•	•	•		•	•
127	Walnut				•	•	•			
140	Warm Ash				•	•				
141	Whitened Ash				•	•				
145	Zebra				•	•				
Techwoods										
Y851	Black Oak							•		
Y821	Blond Maple (formerly known as maple techgrain)							•		
Y319	Cherry							•		
Y326	Dark Mahogany							•		
Y344	Espresso							•		
Y831	Light Cherry (formerly known as cherry techgrain)							•		
Y316	Maple							•		
Y329	Medium Oak							•		
Y342	Medium Teak							•		
Y323	Medium Walnut							•		
Y811	Natural							•		
Y881	Light Walnut							•		
Y882	Dove Grey							•		
Y883	Pangar Wenge							•		

**T' suffix is for paint finish only

Most products introduced after 2004 are not available in Legacy finishes. See individual pricing pages for availability. Specify Legacy finishes to match existing product only. Legacy finishes are not available for new customers.

Trim Finishes

- Panel top caps
- Panel post trim
- Pedestal drawer top caps
- Overhead drawer top caps
- Pedestal drawer pulls
 - Y1 Pewter

Paint Finishes

- Panel base raceway covers
- Panel tiled insert supports
- Solid Steel panel inserts
- Perforated steel panel inserts
- Embossed steel panel inserts
- Overhead storage components
- Pedestals
- Desk components
- Metal panel topcaps and trim

P1 Finishes

- Y1 Pewter

P2 Finishes

- H Beige Metallic
- W Light Tan Metallic

All other Knoll paint finishes and custom finishes (Series 2 components only)

Laminates

Worksurfaces

An upcharge applies where specifying Legacy laminates. Add an amount equal to 10% of the solid PVC edgeband list price to the price of any product specified with a Legacy laminate.

- MC Caramel Maple
- CM Clear Maple
- M1 Light Grey
- PA Pearwood
- SD Sand
- B Snow
- WM Warm Cherry
- MR6 Winter Grey Matrix

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Worksurface Edges

2mm edgeband

- MC Caramel Maple
- Y3 Dark Grey
- Y2 Medium Grey
- MT Metal
- Y1 Pewter
- SD Sand
- B Snow
- WM Warm Cherry

Fabric Options**Grade 10**

Annex (W1360)
 Beacon (W14975)
 Broadcloth II (W1619)
 Circuit (W17545)
 Element (W1077)
 Foundation (W351)
 Growth Spurt (W692)
 Messa (W2061)
 Skylark (W17187)
 Symbolic Details (W693)
 Tailor Made II (1610)
 Versatility (W432)

Grade 20

Bauhaus Block (W296)
 Circle Line (W1146)
 Clarity (W281)
 Criss Cross (W305)
 Delite (K2026)
 Mainframe (W17835)
 Namatic II (W16201)
 Photon (W1293)
 Reflect (W884)
 Weave Three (W298)

Grade 30

Flow (W565)
 Harmony (W232)
 Micro (W465)
 Relay (W1020)
 Commuter Cloth (K1779)

Grade 40

Amplify (W1215)
 Bandwidth (W1219)
 Hourglass (K1523)
 Ornament (W1078)
 Palladium (W1030)
 Spellbound (W1464)

Grade 50

Presto (K1000)

Grade 55

Transition (W816)

Open Weave Fabrics**Warpnet**

White (W1113/1)
 Medium Grey (W1113/2)
 Dark Value Grey (W1113/3)
 Warm Cool Neutral (W1113/4)
 Brushed Gold (W1113/5)

COM (Customer's Own Material)

COM can be applied to Dividends Horizon product on a select basis. Please consult your Knoll Customer Service Representative for details on the COM approval process and testing requirements.

Pricing for COM fabrics is at Grade 10.

Note: Always contact your Customer Service Representative prior to sending any COM (including pre-approved KnollTextiles) to the manufacturing facility.

Note: All fabric components greater than 60" wide may need to have the fabric railroaded (turned 90°). If any larger panels are railroaded, the smaller panels will also be railroaded to match. This must be considered when utilizing a patterned textile.

Dividends Horizon Panels

Dividends Horizon is a furniture system comprised of a wide variety of panels, hanging components, storage, screens and freestanding desks.

At the heart of the system is a universal panel frame. The universal frame is an open design that accepts many styles of panel inserts. These include:

- Monolithic Fabric Insert
- Monolithic Laminate Insert
- Tiled Fabric Insert
- Tiled Laminate Insert
- Technology Tile
- Painted Steel
- Perforated Steel
- Embossed Steel
- Window Kits
- Markerboard

Panel Dimensions

- Widths: 15", 18", 24", 30", 36", 42", 48" and 60"
- Heights: worksurface height, 36", 42", 50", 57", 64" and 78"
- Thickness: 3"


Panel Frame Options

Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels.

Topway panel frames feature an integral top cable trough, and are used with D1 style stack frames.

Full View frames have no top trough, leaving a larger window opening in the top position. Full View frames are used with D2 style stack frames.

Dividends Horizon Panels and Components (Base Raceway shown)



Monolithic Panel

Beltway Panel

Tiled Panel

Panel Frame Construction

Panel frames are robotically welded and consist of vertical channels, horizontal rails and panel feet with leveling glides.

- Topway trough: 22-gauge roll-formed steel (topway frames only)
- Vertical channels: 16-gauge roll-formed steel with 5/8" integral slotted standard with adjustments in 1-1/2" increments
- Horizontal rails: 15-gauge roll-formed steel
- Panel feet: extruded aluminum
- Leveling glides: Steel threads with 2-1/4" height adjustment and 1-1/2" diameter nylon foot

Preconfigured Panels

Dividends Horizon panels can be specified "Preconfigured" in various styles including:

- Monolithic Panel
- Tiled Panel
- Beltway Panel

Monolithic Panel Components

Monolithic panels provide a single fabric or laminate insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with panel frame, base components, top cap, panel to panel connection hardware and one full height panel insert per side.

Tiled Panel Components

Individual tiled panels allow for a "segmented" aesthetic. Individual tile supports create separation within the panel frame.

"Preconfigured" Dividends Horizon panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, tile supports and tiles.

Beltway Panel Components

Beltway panels allow for electrical and/or data to be accessed above worksurface height. Beltway electrical/data can be specified on one or both sides of a panel. "Preconfigured" Dividends Horizon beltway panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, beltway panel inserts, beltway covers and beltway insert supports.

Base Options


- Base Raceway
- Open Base
- Tile to the Floor

Note: Standard base, Open base and Tile to the floor components can be retrofitted in either a topway or full view frame.


Stack Frames

Dividends Horizon stack frames increase the overall height of a standard panel.

The stack frame is available in three panel heights, 14", 21" and 28". Dividends Horizon stack panels may be attached to standard 36", 42", 50", 57", 64" and 78" high panel. Maximum stacking height above a base panel height is 28".



Topway Frame Construction



Panel Foot Construction

Open Position Planner

Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panels in virtually any configuration.

This powerful specification tool eliminates the need for most built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to electronic specification users, and is not available in this price list.

“Build-to-Spec” Panels

“Build-to-Spec” panels are specified by component for special applications. These include: when a different fabric is required on each panel side and when retrofitting existing panels to another style. Panels and components are not shipped assembled.


Modular Panel Connections

Modular panel connections are made from two parts: Universal Panel Connection Hardware and Panel Top Connectors.

Panel connection hardware includes:

- lower connectors: 14 gauge steel cactus style connectors
- Upper frame connector: Die cast wedge block with 7 " torx head screw.

Panel Top Connectors, depending upon application, are either 11 gauge stamped steel or 1/4" HSLA steel.



Panel to Panel Specification Tip:

- When connecting same height DP8 Full View to DP8 Full View, select the 'V' Top Connector option
- When connecting same height DP8 Top Way to DP8 Top Way, select the 'C' Top Connector option
- All other applications require the 'U' Universal Top Connector option

Panel Attachment

The lower cactus style connectors engage the lower frames of adjacent panels. The upper wedge block engages the upper frames. The connection is secured by tightening the upper connector's tension screw.

Panel-to-Panel Top Cap Transition

Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.


- **Construction:** Trim-color black when used with veneer top caps
- **Size:** 1" wide by 3" deep
- **Attachment:** Snaps between top cap sections in straight, same-height panel configurations

Note: Panel-to-panel top cap transitions are ordered separately from panels.


Top Cap

Top cap is included with preconfigured panels.

- **Construction:** Panel top caps are trim colored and are either radius or flat metal. Veneer top caps are techgrain veneer over radius or flat metal substrate.



Panel Connection Hardware



Panel Attachment

- **Attachment:** Snaps onto the trough of a topway panel frame. Retainer clips are used to attach the top cap to the top rail of a full view frame.

Panel End Trim

Panel end trim matches the aesthetics of the panel top cap. It is used to end a panel run and for high-low, panel-to-panel applications.

Three panel end trim options are available:

- Radius Metal
- Flat Metal
- Thin Profile Flat

Note: Panel end trim is ordered separately from panels. Included with the panel end trim are panel end trim brackets.

- **Construction:** End trims are trim colored with a die cast aluminum end cap.

Panel top caps and end trim are either extruded aluminum or roll formed steel.


Metal trim is extruded aluminum with powder coat finish. All metal trim have a powder coat finish.

- **Attachment:** Panel-mount brackets are fastened to the panel with thread-forming screws into pre-punched holes. End trim snaps onto panel mount brackets.

The panel end top cap snaps over the panel end trim and panel top trim.

Panel to Panel Specification Tip:

- When connecting DP8 Full View to DP8 Full View, select the 'V' Top Connector option
- When connecting DP8 Top Way to DP8 Top Way, select the 'C' Top Connector option
- All other applications require the 'U' Universal Top Connector option



Panel End Trim Attachment

Post Connectors

Post connectors are required for all "L", "T", and "X" configurations. For same-height applications, post connectors are available as an assembly and include the post, vertical trim and top cap.

For high-low panel-to-post applications, post connectors are specified by component.

Post and Post Component Construction

- Post: 3" square extruded aluminum
- Metal Post Cover: 18 gauge steel with powder coat finish
- Post Top Cap: Powder coated metal in Knoll core colors

Attachment: Post connectors use the universal panel connection hardware from adjacent panels

Electrical and data access: Posts have cut-outs that match the wire and cable access channels provided by panel frames. This allows wire conduits and data cables to be routed through the post at the topway, beltway and base raceway.

Electrical and Communications
Dividends Horizon provides a logical approach for planning and installing electrical systems and communication cables.

Power is installed along the base raceway with access available in both the base raceway and optional beltway.



Topway Panel Frame Electrical

Allows data cables to be routed horizontally and vertically within the panel.


- Interior dimension: 2 1/2"H x 3/4"W

Cables can be routed along the tops of panels, routed through the interior of panels and along both the beltway and base raceway. The primary channel for distributing cable is provided in the horizontal topway along the top of panels. The topway allows cables to be easily laid-in during initial installation and additional cables to be added as required. It also separates data from power to reduce the chance of interference. A vertical wire pathway is provided in the center of the topway. This allows cables to be run vertically through the interior of the panel to the beltway or base raceway without the use of exterior cable managers.


Data Cabling Bend Radius




Beltway Electrical




"L" Post Connection



"L" Post Cover Attachment



Base Raceway Electrical



Beltway Electrical

Provides duplex receptacle and data port access at desk-height level.

- Exterior dimension: 4 1/4"H x 3"D
- Interior dimension: 3 1/2"H x 2 3/4"D
- Height from floor: 32 3/4" to center of beltway cover
- Beltway cover construction: Trim-color painted steel
- Beltway cover attachment: Snaps onto beltway panel insert supports
- Duplex access: 30" and wider beltway covers have two duplex knockouts per panel side (18" and 24" wide beltways do not have duplex knockouts)
- Duplex location: Knockouts located 12" on center from each end of cover
- Data access: All beltway covers (except 30 wide) have one center-located data port knockout per panel side
- Additional data access: In panels 30" and wider, the two duplex knockouts can be used as additional data ports when the beltway is not used for duplex receptacles.
- Power capacity: One power module per panel (single or double-sided).

Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor.

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway

Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.


- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)

- Duplex location: 9" on center from each end
- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper


Note: Knockouts are standard unless specified without.

Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric or steel tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.



- Openings in frame sides permit data and communications cables to be run between frames at up to five levels in a 78" frame.
- Cables can enter/exit through frame sides at junctions between panels or up through the base of the panel.



Cable Management Capacities

This chart shows the number of category 6 4-pair cables that can be routed through various Dividends Horizon pathways. Cable capacities are based on 0.280, 0.300, and 0.310 diameter cables at a full fill capacity.

Pathway Description	Cable Pathway Area (Square Inches)	Cable Dia. 0.28"	Cable Dia. 0.30"	Cable Dia. 0.31"
Panel Top Way (thru post)	1.90	24	21	19
Panel Top Way	4.8	61	53	49
Panel Base Raceway (without electrical)	8.4	107	93	87
Panel Base Raceway (with electrical)	3.5	44	38	36
Beltway (w/o electrical)	3.9	50	43	40
Beltway (with electrical)	3.5	45	38	36
Vertical Drop (within panel)	2.1	26	23	21
5" Vertical Hole	3.9	50	43	40
2" Vertical Hole	1.6	20	17	16

Panel Planning Guidelines

The following panel planning guidelines are provided to ensure stability of Dividends Horizon panels.


Three different scenarios are shown:

- Panel run supported by panels on one end
- Panel run supported by panels on both ends
- High density storage



Panel Run Supported by Panels at One End

- Minimum of an "L" panel connection on one end
- Maximum number of panels in run: 4
- End of panel run must be supported by a pedestal, panel-mounted Open Leg Support, C-leg Support or any height panel



Formula for Depth of Return





Panel Run Supported by Panels at One End





End of Run Supported by Pedestal



End of Run Supported by Panel Mount C-Leg Support



End of Run Supported by Open Leg Support



End of Run Supported by Panel of Any Height

Panel Run Supported by Panels at Both Ends

- Minimum of an "L" panel connection on both ends (see Formulas 2 and 3 below)
- Maximum length panel run: 12'
- Maximum number of panels in run: 4





- Both ends of panel run must be supported by matching height panels (see Formulas 2 and 3 below)
- Panel run must be floor supported every 8' with a pedestal, panel mounted Open Support Leg or C-Leg support

High Density Storage



If hanging more than one overhead component vertically per panel side the following is required:

- Panel must be supported by matching height return panels on both ends of the panel

Panel Run Supported by Panels at Both Ends




High Density Storage




Formulas for Depth Return


Formula 1



Formula 2



Formula 3



Return panel must be a minimum of 36" wide when laminate tiles are used along the spine panel run.

Monolithic Panel

Monolithic panels provide a single fabric insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with topway or full view panel frame, base components, top cap, panel to panel connection hardware and one full height fabric panel insert per side.

Panels may also be ordered by components for "Build-to-Spec" applications. This includes when different fabric insert is required on each side of the panel.

Monolithic Panel Insert Construction

Fabric laminated with web adhesive heat-cured to 7/16" thick tackable acoustical board.

Monolithic Panel Ratings

- Noise Reduction Coefficient (NRC) rating: .70
- Sound Transmission Class (STC) rating: 11

Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furnishings.

Monolithic Panel Insert Attachment

Fabric panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting spring clips are attached to inserts for connection to the

vertical frame for additional support. No tools are required for the insert attachment.

Top Cap Options

Two top cap options are available:

- Radius Metal
- Flat Metal

Top Cap Construction

Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment

Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to a full view frame.

If additional support for monolithic panel inserts is required, a beltway cable tray can be installed.

Three Base Options Available:

- Base Raceway
- Tile to the Floor
- Open Base

Base Raceway covers are available with or without knockouts.

See the preconfigured tiled panel pages for more information on base options.

Carpet Grippers

Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Carpet grippers have a black finish.

Universal Panel Connectors

Dividends Horizon panels include universal panel connectors to allow same-height straight panel-to-panel connections, high-low straight panel-to-panel connections and straight and high-low panel-to-post connections.


Modular Panel Connections

Modular panel connections are made from two parts: Universal Panel Connection Hardware and Panel Top Connectors.


Electrical

Panels 24" and wider will accept two duplex receptacles per panel base side. 18" wide panels will provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

Preconfigured Monolithic Panel







Panel Base Options



Monolithic Panels

Standard Base Raceway

Worksurface Height, 36", 42" and 50" High

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
 Worksurface Height Monolithic Standard Base Raceway	28 1/2"	15"	3"	DP8CMMRRWH15	\$452.	\$466.	\$486.	\$491.	\$508.	\$514.	\$521.	\$533.
	28 1/2"	18"	3"	DP8CMMRRWH18	452.	466.	486.	491.	508.	514.	521.	533.
	28 1/2"	24"	3"	DP8CMMRRWH24	501.	514.	539.	546.	559.	568.	578.	590.
	28 1/2"	30"	3"	DP8CMMRRWH30	524.	541.	563.	572.	587.	596.	605.	621.
	28 1/2"	36"	3"	DP8CMMRRWH36	587.	604.	632.	642.	660.	671.	681.	699.
	28 1/2"	42"	3"	DP8CMMRRWH42	649.	667.	699.	710.	727.	740.	752.	771.
	28 1/2"	48"	3"	DP8CMMRRWH48	684.	704.	735.	746.	767.	779.	795.	812.
	28 1/2"	60"	3"	DP8CMMRRWH60	814.	837.	874.	889.	915.	931.	947.	967.
 36" High, Monolithic Standard Base Raceway	35 1/8"	15"	3"	DP8CMMRR3615	452.	466.	486.	491.	508.	514.	521.	533.
	35 1/8"	18"	3"	DP8CMMRR3618	452.	466.	486.	491.	508.	514.	521.	533.
	35 1/8"	24"	3"	DP8CMMRR3624	501.	514.	539.	546.	559.	568.	578.	590.
	35 1/8"	30"	3"	DP8CMMRR3630	524.	541.	563.	572.	587.	596.	605.	621.
	35 1/8"	36"	3"	DP8CMMRR3636	587.	604.	632.	642.	660.	671.	681.	699.
	35 1/8"	42"	3"	DP8CMMRR3642	649.	667.	699.	710.	727.	740.	752.	771.
	35 1/8"	48"	3"	DP8CMMRR3648	684.	704.	735.	746.	767.	779.	795.	812.
	35 1/8"	60"	3"	DP8CMMRR3660	814.	837.	874.	889.	915.	931.	947.	967.
 42" High, Monolithic Standard Base Raceway	42 3/16"	15"	3"	DP8CMMRR4215	470.	486.	508.	515.	527.	539.	546.	556.
	42 3/16"	18"	3"	DP8CMMRR4218	470.	486.	508.	515.	527.	539.	546.	556.
	42 3/16"	24"	3"	DP8CMMRR4224	508.	520.	545.	551.	567.	576.	583.	599.
	42 3/16"	30"	3"	DP8CMMRR4230	551.	568.	594.	604.	621.	631.	640.	658.
	42 3/16"	36"	3"	DP8CMMRR4236	600.	617.	645.	658.	675.	684.	696.	711.
	42 3/16"	42"	3"	DP8CMMRR4242	660.	678.	709.	720.	738.	752.	765.	782.
	42 3/16"	48"	3"	DP8CMMRR4248	698.	716.	748.	763.	782.	796.	807.	829.
	42 3/16"	60"	3"	DP8CMMRR4260	829.	852.	890.	909.	932.	949.	962.	986.
 50" High, Monolithic Standard Base Raceway	49 1/2"	15"	3"	DP8CMMRR5015	501.	514.	539.	546.	559.	568.	578.	590.
	49 1/2"	18"	3"	DP8CMMRR5018	501.	514.	539.	546.	559.	568.	578.	590.
	49 1/2"	24"	3"	DP8CMMRR5024	541.	554.	579.	589.	603.	611.	623.	638.
	49 1/2"	30"	3"	DP8CMMRR5030	593.	609.	636.	647.	666.	677.	686.	704.
	49 1/2"	36"	3"	DP8CMMRR5036	649.	667.	699.	710.	727.	740.	752.	771.
	49 1/2"	42"	3"	DP8CMMRR5042	711.	730.	765.	778.	800.	812.	823.	844.
	49 1/2"	48"	3"	DP8CMMRR5048	766.	786.	822.	838.	859.	873.	886.	911.
	49 1/2"	60"	3"	DP8CMMRR5060	911.	936.	980.	997.	1,022.	1,041.	1,058.	1,081.




Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Standard Base Raceway: 1. Pattern number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Panel fabric	Monolithic Panel Standard Base Raceway <i>Example:</i> DP8CMMRR3618 4/117/K/117/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> MM Monolithic both sides <hr/> RR Base Raceway <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> B191 Fairfield fabric	Monolithic Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Base raceway covers Top cap Connection hardware Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	Monolithic Panel with Standard Base Raceway Options: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Options: (K) = Knockouts both side (N) = No Knockouts

Monolithic Panels

Standard Base Raceway

57", 64" and 78" High

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
57" High, Monolithic Standard Base Raceway 	56 ¹³ / ₁₆ "	15"	3"	DP8CMMRR5715	\$539.	\$551.	\$576.	\$584.	\$602.	\$610.	\$621.	\$636.
	56 ¹³ / ₁₆ "	18"	3"	DP8CMMRR5718	539.	551.	576.	584.	602.	610.	621.	636.
	56 ¹³ / ₁₆ "	24"	3"	DP8CMMRR5724	578.	593.	621.	631.	647.	659.	670.	684.
	56 ¹³ / ₁₆ "	30"	3"	DP8CMMRR5730	638.	658.	685.	699.	716.	727.	738.	759.
	56 ¹³ / ₁₆ "	36"	3"	DP8CMMRR5736	696.	716.	746.	763.	781.	795.	806.	824.
	56 ¹³ / ₁₆ "	42"	3"	DP8CMMRR5742	754.	775.	811.	823.	846.	859.	873.	897.
	56 ¹³ / ₁₆ "	48"	3"	DP8CMMRR5748	809.	831.	871.	885.	910.	924.	938.	962.
	56 ¹³ / ₁₆ "	60"	3"	DP8CMMRR5760	912.	937.	983.	999.	1,025.	1,042.	1,060.	1,083.
64" High, Monolithic Standard Base Raceway 	64 ¹ / ₁₆ "	15"	3"	DP8CMMRR6415	572.	587.	615.	625.	640.	652.	664.	678.
	64 ¹ / ₁₆ "	18"	3"	DP8CMMRR6418	572.	587.	615.	625.	640.	652.	664.	678.
	64 ¹ / ₁₆ "	24"	3"	DP8CMMRR6424	615.	632.	662.	672.	687.	701.	713.	729.
	64 ¹ / ₁₆ "	30"	3"	DP8CMMRR6430	682.	703.	734.	745.	765.	777.	793.	809.
	64 ¹ / ₁₆ "	36"	3"	DP8CMMRR6436	740.	763.	798.	809.	832.	844.	859.	879.
	64 ¹ / ₁₆ "	42"	3"	DP8CMMRR6442	796.	818.	854.	871.	890.	910.	923.	949.
	64 ¹ / ₁₆ "	48"	3"	DP8CMMRR6448	852.	875.	917.	934.	958.	976.	989.	1,018.
	64 ¹ / ₁₆ "	60"	3"	DP8CMMRR6460	1,016.	1,044.	1,097.	1,111.	1,144.	1,162.	1,182.	1,212.
78" High, Monolithic Standard Base Raceway 	78 ⁹ / ₁₆ "	15"	3"	DP8CMMRR7815	801.	822.	861.	875.	904.	915.	929.	953.
	78 ⁹ / ₁₆ "	18"	3"	DP8CMMRR7818	801.	822.	861.	875.	904.	915.	929.	953.
	78 ⁹ / ₁₆ "	24"	3"	DP8CMMRR7824	878.	908.	950.	964.	989.	1,004.	1,023.	1,051.
	78 ⁹ / ₁₆ "	30"	3"	DP8CMMRR7830	952.	978.	1,023.	1,041.	1,070.	1,089.	1,105.	1,132.
	78 ⁹ / ₁₆ "	36"	3"	DP8CMMRR7836	1,035.	1,068.	1,114.	1,135.	1,166.	1,185.	1,206.	1,236.
	78 ⁹ / ₁₆ "	42"	3"	DP8CMMRR7842	1,119.	1,155.	1,211.	1,230.	1,260.	1,281.	1,305.	1,338.
	78 ⁹ / ₁₆ "	48"	3"	DP8CMMRR7848	1,193.	1,229.	1,288.	1,308.	1,343.	1,368.	1,388.	1,423.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Standard Base Raceway: 1. Pattern number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Panel fabric	Monolithic Panel Standard Base Raceway <hr/> <i>Example:</i> DP8CMMRR3618 4/117/K/117/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> MM Monolithic both sides <hr/> RR Base Raceway <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> B191 Fairfield fabric	Monolithic Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Base raceway covers Top cap Connection hardware <p>Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Monolithic Panel with Standard Base Raceway Options: <p>Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge.</p> <p>Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4</p> <p>Raceway Options: (K) = Knockouts both side (N) = No Knockouts</p>





Monolithic Panels

Dividends Horizon

Open Base

Worksurface Height, 36", 42" and 50" High

Panels, Pre-Configured

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
 Worksurface Height, Monolithic Open Base	28 1/2"	18"	3"	DP8CMMLLWH18	\$452.	\$466.	\$486.	\$491.	\$508.	\$514.	\$521.	\$533.
	28 1/2"	24"	3"	DP8CMMLLWH24	501.	514.	539.	546.	559.	568.	578.	590.
	28 1/2"	30"	3"	DP8CMMLLWH30	524.	541.	563.	572.	587.	596.	605.	621.
	28 1/2"	36"	3"	DP8CMMLLWH36	587.	604.	632.	642.	660.	671.	681.	699.
	28 1/2"	42"	3"	DP8CMMLLWH42	649.	667.	699.	710.	727.	740.	752.	771.
	28 1/2"	48"	3"	DP8CMMLLWH48	684.	704.	735.	746.	767.	779.	795.	812.
	28 1/2"	60"	3"	DP8CMMLLWH60	814.	837.	874.	889.	915.	931.	947.	967.
 36" High, Monolithic Open Base	35 1/8"	18"	3"	DP8CMMLL3618	452.	466.	486.	491.	508.	514.	521.	533.
	35 1/8"	24"	3"	DP8CMMLL3624	501.	514.	539.	546.	559.	568.	578.	590.
	35 1/8"	30"	3"	DP8CMMLL3630	524.	541.	563.	572.	587.	596.	605.	621.
	35 1/8"	36"	3"	DP8CMMLL3636	587.	604.	632.	642.	660.	671.	681.	699.
	35 1/8"	42"	3"	DP8CMMLL3642	649.	667.	699.	710.	727.	740.	752.	771.
	35 1/8"	48"	3"	DP8CMMLL3648	684.	704.	735.	746.	767.	779.	795.	812.
	35 1/8"	60"	3"	DP8CMMLL3660	814.	837.	874.	889.	915.	931.	947.	967.
 42" High, Monolithic Open Base	42 3/16"	18"	3"	DP8CMMLL4218	470.	486.	508.	515.	527.	539.	546.	556.
	42 3/16"	24"	3"	DP8CMMLL4224	508.	520.	545.	551.	567.	576.	583.	599.
	42 3/16"	30"	3"	DP8CMMLL4230	551.	568.	594.	604.	621.	631.	640.	658.
	42 3/16"	36"	3"	DP8CMMLL4236	600.	617.	645.	658.	675.	684.	696.	711.
	42 3/16"	42"	3"	DP8CMMLL4242	660.	678.	709.	720.	738.	752.	765.	782.
	42 3/16"	48"	3"	DP8CMMLL4248	698.	716.	748.	763.	782.	796.	807.	829.
	42 3/16"	60"	3"	DP8CMMLL4260	829.	852.	890.	909.	932.	949.	962.	986.
 50" High, Monolithic Open Base	49 1/2"	18"	3"	DP8CMMLL5018	501.	514.	539.	546.	559.	568.	578.	590.
	49 1/2"	24"	3"	DP8CMMLL5024	541.	554.	579.	589.	603.	611.	623.	638.
	49 1/2"	30"	3"	DP8CMMLL5030	593.	609.	636.	647.	666.	677.	686.	704.
	49 1/2"	36"	3"	DP8CMMLL5036	649.	667.	699.	710.	727.	740.	752.	771.
	49 1/2"	42"	3"	DP8CMMLL5042	711.	730.	765.	778.	800.	812.	823.	844.
	49 1/2"	48"	3"	DP8CMMLL5048	766.	786.	822.	838.	859.	873.	886.	911.
	49 1/2"	60"	3"	DP8CMMLL5060	911.	936.	980.	997.	1,022.	1,041.	1,058.	1,081.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Monolithic Panel with Open Base:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Base finish
5. Panel fabric

Order Code

Monolithic Panel with Open Base

Example: **DP8CMMLL 3618 4/117/117/B191**

DP8	Dividends Horizon Panel
C	Topway frame
MM	Monolithic both sides
LL	Open base
4	Radius Metal top cap
117	Soft Grey top cap finish
117	Soft Grey raceway finish
B191	Fairfield light fabric

Included with:

Monolithic Panel with Open Base:

- Panel frame
- Acoustic panel inserts (2)
- Open base
- Top cap
- Connection hardware

Note: Preconfigured Worksurface Height panels are not available with plastic top caps.

Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.

Options

Monolithic Panel with Open Base:

Full View Frame Option:

To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Top Cap Options:




No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Monolithic Panels

Open Base

57", 64" and 78" High

Dividends Horizon

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
57" High, Monolithic Open Base 	56 ^{13/16} "	18"	3"	DP8CMMLL5718	\$539.	\$551.	\$576.	\$584.	\$602.	\$610.	\$621.	\$636.
	56 ^{13/16} "	24"	3"	DP8CMMLL5724	578.	593.	621.	631.	647.	659.	670.	684.
	56 ^{13/16} "	30"	3"	DP8CMMLL5730	638.	658.	685.	699.	716.	727.	738.	759.
	56 ^{13/16} "	36"	3"	DP8CMMLL5736	696.	716.	746.	763.	781.	795.	806.	824.
	56 ^{13/16} "	42"	3"	DP8CMMLL5742	754.	775.	811.	823.	846.	859.	873.	897.
	56 ^{13/16} "	48"	3"	DP8CMMLL5748	809.	831.	871.	885.	910.	924.	938.	962.
	56 ^{13/16} "	60"	3"	DP8CMMLL5760	912.	937.	983.	999.	1,025.	1,042.	1,060.	1,083.
64" High, Monolithic Open Base 	64 ^{1/16} "	18"	3"	DP8CMMLL6418	572.	587.	615.	625.	640.	652.	664.	678.
	64 ^{1/16} "	24"	3"	DP8CMMLL6424	615.	632.	662.	672.	687.	701.	713.	729.
	64 ^{1/16} "	30"	3"	DP8CMMLL6430	682.	703.	734.	745.	765.	777.	793.	809.
	64 ^{1/16} "	36"	3"	DP8CMMLL6436	740.	763.	798.	809.	832.	844.	859.	879.
	64 ^{1/16} "	42"	3"	DP8CMMLL6442	796.	818.	854.	871.	890.	910.	923.	949.
	64 ^{1/16} "	48"	3"	DP8CMMLL6448	852.	875.	917.	934.	958.	976.	989.	1,018.
	64 ^{1/16} "	60"	3"	DP8CMMLL6460	1,016.	1,044.	1,097.	1,111.	1,144.	1,162.	1,182.	1,212.
78" High, Monolithic Open Base 	78 ^{9/16} "	18"	3"	DP8CMMLL7818	801.	822.	861.	875.	904.	915.	929.	953.
	78 ^{9/16} "	24"	3"	DP8CMMLL7824	878.	908.	950.	964.	989.	1,004.	1,023.	1,051.
	78 ^{9/16} "	30"	3"	DP8CMMLL7830	952.	978.	1,023.	1,041.	1,070.	1,089.	1,105.	1,132.
	78 ^{9/16} "	36"	3"	DP8CMMLL7836	1,035.	1,068.	1,114.	1,135.	1,166.	1,185.	1,206.	1,236.
	78 ^{9/16} "	42"	3"	DP8CMMLL7842	1,119.	1,155.	1,211.	1,230.	1,260.	1,281.	1,305.	1,338.
	78 ^{9/16} "	48"	3"	DP8CMMLL7848	1,193.	1,229.	1,288.	1,308.	1,343.	1,368.	1,388.	1,423.




Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Open Base:	Monolithic Panel with Open Base	Monolithic Panel with Open Base:	Monolithic Panel with Open Base:
1. Pattern Number	<i>Example:</i> DP8CMMLL3618	<ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Open base Top cap Connection hardware 	Full View Frame Option:
2. Top cap type	4/117/117/B191	Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.
3. Top cap finish	DP8 Dividends Horizon Panel		Top Cap Options:
4. Base finish	C Topway frame		No Top Cap - Deduct \$40;
5. Panel fabric	MM Monolithic both sides		Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
	LL Open Base		
	4 Radius Metal top cap		
	117 Soft Grey top cap finish		
	117 Soft Grey base raceway finish		
	B191 Fairfield light fabric		

Monolithic Panels

Tile to Floor One Side

Worksurface Height, 36" and 42" High

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
Worksurface Height, Monolithic Tile to Floor 	28 1/2"	15"	3"	DP8CMMFRWH15	\$487.	\$501.	\$521.	\$526.	\$543.	\$449.	\$556.	\$568.
	28 1/2"	18"	3"	DP8CMMFRWH18	487.	501.	521.	526.	541.	549.	556.	568.
	28 1/2"	24"	3"	DP8CMMFRWH24	536.	549.	574.	581.	594.	603.	613.	625.
	28 1/2"	30"	3"	DP8CMMFRWH30	559.	576.	598.	607.	622.	631.	640.	656.
	28 1/2"	36"	3"	DP8CMMFRWH36	622.	639.	667.	677.	695.	706.	716.	734.
	28 1/2"	42"	3"	DP8CMMFRWH42	684.	702.	734.	745.	762.	775.	787.	806.
	28 1/2"	48"	3"	DP8CMMFRWH48	719.	739.	770.	781.	802.	814.	830.	847.
	28 1/2"	60"	3"	DP8CMMFRWH60	849.	872.	909.	924.	950.	966.	982.	1,002.
36" High, Monolithic Tile to Floor 	35 1/8"	15"	3"	DP8CMMFR3615	487.	501.	521.	526.	543.	549.	556.	568.
	35 1/8"	18"	3"	DP8CMMFR3618	487.	501.	521.	526.	543.	549.	556.	568.
	35 1/8"	24"	3"	DP8CMMFR3624	536.	549.	574.	581.	594.	603.	613.	625.
	35 1/8"	30"	3"	DP8CMMFR3630	559.	576.	598.	607.	622.	631.	640.	656.
	35 1/8"	36"	3"	DP8CMMFR3636	622.	639.	667.	677.	695.	706.	716.	734.
	35 1/8"	42"	3"	DP8CMMFR3642	684.	702.	734.	745.	762.	775.	787.	806.
	35 1/8"	48"	3"	DP8CMMFR3648	719.	739.	770.	781.	802.	814.	830.	847.
	35 1/8"	60"	3"	DP8CMMFR3660	849.	872.	909.	924.	950.	966.	982.	1,002.
42" High, Monolithic Tile to Floor 	42 3/16"	15"	3"	DP8CMMFR4215	505.	521.	543.	550.	562.	574.	581.	591.
	42 3/16"	18"	3"	DP8CMMFR4218	505.	521.	543.	550.	562.	574.	581.	591.
	42 3/16"	24"	3"	DP8CMMFR4224	543.	555.	580.	586.	602.	611.	618.	634.
	42 3/16"	30"	3"	DP8CMMFR4230	586.	603.	629.	639.	656.	666.	675.	693.
	42 3/16"	36"	3"	DP8CMMFR4236	635.	652.	680.	693.	710.	719.	731.	746.
	42 3/16"	42"	3"	DP8CMMFR4242	695.	713.	744.	755.	773.	787.	800.	817.
	42 3/16"	48"	3"	DP8CMMFR4248	733.	751.	783.	798.	817.	831.	842.	864.
	42 3/16"	60"	3"	DP8CMMFR4260	864.	887.	925.	944.	967.	984.	997.	1,021.




Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> MM Monolithic both sides <hr/> FR Tile to Floor <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts one side <hr/> 117 Soft Grey base raceway finish <hr/> B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Top cap Connection hardware Base raceway on one side Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Monolithic Panels

Tile to Floor One Side

50", 57" and 64" High

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
50" High, Monolithic Tile to Floor 	49 1/2"	15"	3"	DP8CMMFR5015	\$536.	\$549.	\$574.	\$581.	\$594.	\$603.	\$613.	\$625.
	49 1/2"	18"	3"	DP8CMMFR5018	536.	549.	574.	581.	594.	603.	613.	625.
	49 1/2"	24"	3"	DP8CMMFR5024	576.	589.	614.	624.	638.	646.	658.	673.
	49 1/2"	30"	3"	DP8CMMFR5030	628.	644.	671.	682.	701.	712.	721.	739.
	49 1/2"	36"	3"	DP8CMMFR5036	684.	702.	734.	745.	762.	775.	787.	806.
	49 1/2"	42"	3"	DP8CMMFR5042	746.	765.	800.	813.	835.	847.	858.	879.
	49 1/2"	48"	3"	DP8CMMFR5048	801.	821.	857.	873.	895.	908.	921.	946.
	49 1/2"	60"	3"	DP8CMMFR5060	946.	971.	1,015.	1,032.	1,057.	1,076.	1,093.	1,116.
57" High, Monolithic Tile to Floor 	56 13/16"	15"	3"	DP8CMMFR5715	574.	586.	611.	619.	637.	645.	656.	671.
	56 13/16"	18"	3"	DP8CMMFR5718	574.	586.	611.	619.	637.	645.	656.	671.
	56 13/16"	24"	3"	DP8CMMFR5724	613.	628.	656.	666.	682.	694.	705.	719.
	56 13/16"	30"	3"	DP8CMMFR5730	673.	693.	720.	734.	751.	762.	773.	794.
	56 13/16"	36"	3"	DP8CMMFR5736	731.	751.	781.	798.	816.	830.	841.	859.
	56 13/16"	42"	3"	DP8CMMFR5742	789.	810.	846.	858.	881.	894.	908.	932.
	56 13/16"	48"	3"	DP8CMMFR5748	844.	866.	906.	920.	945.	959.	973.	997.
	56 13/16"	60"	3"	DP8CMMFR5760	947.	972.	1,018.	1,034.	1,060.	1,077.	1,095.	1,118.
64" High, Monolithic Tile to Floor 	64 1/16"	15"	3"	DP8CMMFR6415	607.	622.	650.	660.	675.	687.	699.	713.
	64 1/16"	18"	3"	DP8CMMFR6418	607.	622.	650.	660.	675.	687.	699.	713.
	64 1/16"	24"	3"	DP8CMMFR6424	650.	667.	697.	707.	722.	736.	748.	764.
	64 1/16"	30"	3"	DP8CMMFR6430	717.	738.	769.	780.	800.	812.	828.	844.
	64 1/16"	36"	3"	DP8CMMFR6436	775.	798.	833.	844.	867.	879.	894.	914.
	64 1/16"	42"	3"	DP8CMMFR6442	831.	853.	889.	906.	925.	945.	955.	984.
	64 1/16"	48"	3"	DP8CMMFR6448	887.	910.	952.	969.	993.	1,011.	1,024.	1,053.
	64 1/16"	60"	3"	DP8CMMFR6460	1,051.	1,079.	1,132.	1,146.	1,179.	1,197.	1,217.	1,247.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> MM Monolithic both sides <hr/> FR Tile to Floor <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts one side <hr/> 117 Soft Grey raceway finish <hr/> B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Top cap Connection hardware Base raceway on one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Monolithic Panels

Tile to Floor One Side

78" High

description	h	w	d	pattern no.	grade							
					10	15	20	25	30	35	40	45
78" High, Monolithic Tile to Floor	78 ¹ / ₁₆ "	15"	3"	DP8CMMFR7815	\$836.	\$857.	\$896.	\$910.	\$939.	\$950.	\$964.	\$988.
	78 ¹ / ₁₆ "	18"	3"	DP8CMMFR7818	836.	857.	896.	910.	939.	950.	964.	988.
	78 ¹ / ₁₆ "	24"	3"	DP8CMMFR7824	913.	943.	985.	999.	1,024.	1,039.	1,058.	1,086.
	78 ¹ / ₁₆ "	30"	3"	DP8CMMFR7830	987.	1,013.	1,058.	1,076.	1,105.	1,124.	1,140.	1,167.
	78 ¹ / ₁₆ "	36"	3"	DP8CMMFR7836	1,070.	1,103.	1,149.	1,170.	1,201.	1,220.	1,241.	1,271.
	78 ¹ / ₁₆ "	42"	3"	DP8CMMFR7842	1,154.	1,190.	1,246.	1,265.	1,295.	1,316.	1,340.	1,373.
	78 ¹ / ₁₆ "	48"	3"	DP8CMMFR7848	1,228.	1,264.	1,323.	1,343.	1,378.	1,403.	1,423.	1,458.



Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> MM Monolithic both sides <hr/> FR Tile to Floor <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts one side <hr/> 117 Soft Grey raceway finish <hr/> B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts (2) Top cap Connection hardware Base raceway on one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Tiled Panel Components

"Preconfigured" Dividends Horizon tiled panels ship completely assembled with a topway or full view panel frame, choice of standard base options including a standard raceway, open base, and tile to the floor. Also, included with every tiled panel are the panel-to-panel connection hardware, top cap, tile inserts and supports.

Tiled Panel Insert Construction

Fabric laminated with roll coat adhesive, heat-cured to 7/16" thick tackable acoustical board.

One-Sided Tiled Panel

Tiled panels are available with fabric tiled inserts attached to one or both panel sides. Non-tiled panel side will have a monolithic insert.

Tiled Panel Insert Supports

All Dividends Horizon panel frames are prepunched to accept tiled panel insert supports which span horizontally across the panel frame. Tiled panel insert supports are mounted above a tiled insert with the exception of the uppermost tile. D2 style recessed insert supports are available in black only.

Tiled Panel Insert Attachment

Tiled panel inserts attach to the troughs in the horizontal panel frame and tiled insert supports. Mounting clips are attached to inserts for connection to frame for additional support. No tools are required for attachment.

Top Cap Options

Two Top Cap Options Available:

- Radius Metal
- Flat Metal


Top Cap Construction

Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment

Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Tiled Panel




Tiled Panel Standard Configurations

Tiled panels include the following inserts and insert supports per panel side:


- 36" High**
- Two 14"H tiles
 - One tile supports




- 50" High**
- Three 14"H tiles
 - Two tile supports



- 64" High**
- Four 14"H tiles
 - Three tile supports



- 42" High**
- One 7"H tile and two 14"H tiles
 - Two tile supports



- 57" High**
- One 7"H tile and three 14"H tiles
 - Three tile supports



- 78" High**
- Five 14"H tiles
 - Four tile supports



Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

Open Base panels feature two extruded aluminum feet with triangular profile, positioned at the end of each panel. Open base panels offer a lighter aesthetic and improved ventilation over raceway panels.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If electrical access is required, one-sided electrical and one-sided base cable trays must be used.

Open Position Planner

Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panel frames in virtually any configuration.

This powerful specification tool eliminates the need for built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to Electronic Specification users, and is not available in this price list.


Panels may be ordered by component throughout the “Built-to-Spec” option, allowing personalized combinations of the tile types and colors.

Note: Standard configurations of “Preconfigured” tiled panels are also available with 28” base tiles with a standard base raceway, open base or tile to the floor options.


Note: Overheads can only be attached to the upper most position of tiled panels. On 78” high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.

Note: Insert dimensions are nominal


Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)






Open Base

Tiled Panels

Base Raceway

36", 42" and 50" High

description	h	w	d	pattern no.	grade								Deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
 36" High Tiled Standard Base Raceway	35 1/8"	15"	3"	DP8CTTRR3615	\$705.	\$723.	\$760.	\$771.	\$793.	\$804.	\$817.	\$837.	\$88.
	35 1/8"	18"	3"	DP8CTTRR3618	705.	723.	760.	771.	793.	804.	817.	837.	88.
	35 1/8"	24"	3"	DP8CTTRR3624	746.	768.	804.	818.	838.	852.	868.	886.	89.
	35 1/8"	30"	3"	DP8CTTRR3630	791.	812.	847.	866.	884.	906.	916.	938.	90.
	35 1/8"	36"	3"	DP8CTTRR3636	861.	881.	924.	946.	965.	985.	999.	1,023.	92.
	35 1/8"	42"	3"	DP8CTTRR3642	921.	949.	989.	1,005.	1,034.	1,053.	1,070.	1,099.	91.
	35 1/8"	48"	3"	DP8CTTRR3648	962.	989.	1,036.	1,057.	1,080.	1,102.	1,118.	1,149.	93.
	35 1/8"	60"	3"	DP8CTTRR3660	1,148.	1,181.	1,236.	1,257.	1,290.	1,311.	1,334.	1,367.	95.
 42" High Tiled Standard Base Raceway	42 3/16"	15"	3"	DP8CTTRR4215	722.	742.	777.	793.	812.	823.	838.	859.	88.
	42 3/16"	18"	3"	DP8CTTRR4218	722.	742.	777.	793.	812.	823.	838.	859.	88.
	42 3/16"	24"	3"	DP8CTTRR4224	765.	786.	821.	837.	858.	872.	885.	910.	89.
	42 3/16"	30"	3"	DP8CTTRR4230	817.	839.	878.	898.	917.	934.	951.	974.	90.
	42 3/16"	36"	3"	DP8CTTRR4236	872.	901.	936.	956.	980.	996.	1,015.	1,036.	92.
	42 3/16"	42"	3"	DP8CTTRR4242	931.	957.	1,000.	1,020.	1,043.	1,064.	1,077.	1,106.	91.
	42 3/16"	48"	3"	DP8CTTRR4248	978.	1,004.	1,054.	1,072.	1,101.	1,116.	1,136.	1,166.	93.
	42 3/16"	60"	3"	DP8CTTRR4260	1,167.	1,202.	1,257.	1,278.	1,313.	1,335.	1,356.	1,389.	95.
 50" High Tiled Standard Base Raceway	49 1/2"	15"	3"	DP8CTTRR5015	746.	768.	804.	818.	838.	852.	868.	886.	87.
	49 1/2"	18"	3"	DP8CTTRR5018	746.	768.	804.	818.	838.	852.	868.	886.	87.
	49 1/2"	24"	3"	DP8CTTRR5024	803.	823.	866.	876.	906.	916.	932.	955.	90.
	49 1/2"	30"	3"	DP8CTTRR5030	846.	872.	912.	926.	953.	966.	985.	1,005.	87.
	49 1/2"	36"	3"	DP8CTTRR5036	898.	921.	962.	983.	1,004.	1,023.	1,040.	1,068.	81.
	49 1/2"	42"	3"	DP8CTTRR5042	952.	980.	1,025.	1,041.	1,070.	1,089.	1,105.	1,133.	76.
	49 1/2"	48"	3"	DP8CTTRR5048	1,000.	1,030.	1,076.	1,100.	1,124.	1,146.	1,165.	1,193.	74.
	49 1/2"	60"	3"	DP8CTTRR5060	1,190.	1,224.	1,281.	1,305.	1,339.	1,364.	1,385.	1,420.	95.




Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway finish 6. Tile Support profile 7. Panel fabric	Tiled Panel with Standard Base Raceway <i>Example:</i> DP8CTTRR3618 4/117/K/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> TT Tiled both sides <hr/> RR Base raceway <hr/> 36 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with Standard Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Base Raceway

57", 64" and 78" High

description	h	w	d	pattern no.	grade								deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
 57" High Tiled Standard Base Raceway	56 13/16"	15"	3"	DP8CTTRR5715	\$901.	\$923.	\$966.	\$984.	\$1,009.	\$1,026.	\$1,043.	\$1,070.	\$109.
	56 13/16"	18"	3"	DP8CTTRR5718	901.	923.	966.	984.	1,009.	1,026.	1,043.	1,070.	109.
	56 13/16"	24"	3"	DP8CTTRR5724	962.	989.	1,035.	1,054.	1,079.	1,101.	1,118.	1,148.	113.
	56 13/16"	30"	3"	DP8CTTRR5730	1,016.	1,044.	1,097.	1,111.	1,144.	1,162.	1,182.	1,212.	116.
	56 13/16"	36"	3"	DP8CTTRR5736	1,076.	1,107.	1,160.	1,182.	1,213.	1,232.	1,252.	1,287.	118.
	56 13/16"	42"	3"	DP8CTTRR5742	1,139.	1,173.	1,225.	1,248.	1,280.	1,303.	1,326.	1,356.	121.
	56 13/16"	48"	3"	DP8CTTRR5748	1,201.	1,236.	1,293.	1,315.	1,349.	1,373.	1,395.	1,432.	123.
	56 13/16"	60"	3"	DP8CTTRR5760	1,432.	1,471.	1,542.	1,571.	1,612.	1,640.	1,667.	1,709.	125.
 64" High Tiled Standard Base Raceway	64 1/16"	15"	3"	DP8CTTRR6415	950.	977.	1,021.	1,038.	1,068.	1,081.	1,103.	1,129.	131.
	64 1/16"	18"	3"	DP8CTTRR6418	950.	977.	1,021.	1,038.	1,068.	1,081.	1,103.	1,129.	131.
	64 1/16"	24"	3"	DP8CTTRR6424	1,016.	1,042.	1,097.	1,110.	1,140.	1,160.	1,181.	1,212.	138.
	64 1/16"	30"	3"	DP8CTTRR6430	1,072.	1,104.	1,155.	1,176.	1,210.	1,224.	1,248.	1,278.	134.
	64 1/16"	36"	3"	DP8CTTRR6436	1,136.	1,173.	1,223.	1,247.	1,278.	1,302.	1,322.	1,355.	135.
	64 1/16"	42"	3"	DP8CTTRR6442	1,203.	1,237.	1,296.	1,319.	1,353.	1,376.	1,398.	1,435.	137.
	64 1/16"	48"	3"	DP8CTTRR6448	1,266.	1,302.	1,361.	1,385.	1,423.	1,450.	1,471.	1,508.	138.
	64 1/16"	60"	3"	DP8CTTRR6460	1,508.	1,551.	1,628.	1,658.	1,701.	1,730.	1,758.	1,803.	138.
 78" High Tiled Standard Base Raceway	78 1/16"	15"	3"	DP8CTTRR7815	1,467.	1,508.	1,581.	1,609.	1,650.	1,681.	1,710.	1,751.	235.
	78 1/16"	18"	3"	DP8CTTRR7818	1,467.	1,508.	1,581.	1,609.	1,650.	1,681.	1,710.	1,751.	235.
	78 1/16"	24"	3"	DP8CTTRR7824	1,575.	1,619.	1,698.	1,726.	1,775.	1,804.	1,834.	1,883.	234.
	78 1/16"	30"	3"	DP8CTTRR7830	1,667.	1,715.	1,793.	1,829.	1,878.	1,908.	1,942.	1,988.	237.
	78 1/16"	36"	3"	DP8CTTRR7836	1,779.	1,831.	1,917.	1,950.	2,004.	2,040.	2,074.	2,126.	258.
	78 1/16"	42"	3"	DP8CTTRR7842	1,883.	1,937.	2,026.	2,064.	2,123.	2,156.	2,194.	2,250.	263.
	78 1/16"	48"	3"	DP8CTTRR7848	1,991.	2,052.	2,149.	2,190.	2,247.	2,287.	2,326.	2,383.	315.

Dimensions listed under h w d are actual to the nearest 1/8"




Ordering Information	Order Code	Included with:	Options
Tiled Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway finish 6. Tile support profile 7. Tile support finish 8. Panel fabric	Tiled Panel with Standard Base Raceway <i>Example:</i> DP8CTTRR3618 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides RR Base raceway 36 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with Standard Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: (2) = Extruded Plastic (Smooth Radius) (3) = No Top Cap (4) = Radius Metal, add \$40 P1, \$42 P2, \$44 P3 paint grades (5) = Flat Metal, add \$40 P1, \$42 P2, \$44 P3 paint grades Raceway Knockout Options: (K) = Knockouts (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Open Base

36", 42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.									Deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
36" High Tiled Open Base 	35 1/8"	18"	3"	DP8CTTLL3618	\$705.	\$723.	\$760.	\$771.	\$793.	\$804.	\$817.	\$837.	\$88.
	35 1/8"	24"	3"	DP8CTTLL3624	746.	768.	804.	818.	838.	852.	868.	886.	89.
	35 1/8"	30"	3"	DP8CTTLL3630	791.	812.	847.	866.	884.	906.	916.	938.	90.
	35 1/8"	36"	3"	DP8CTTLL3636	861.	881.	924.	946.	965.	985.	999.	1,023.	92.
	35 1/8"	42"	3"	DP8CTTLL3642	921.	949.	989.	1,005.	1,034.	1,053.	1,070.	1,099.	91.
	35 1/8"	48"	3"	DP8CTTLL3648	962.	989.	1,036.	1,057.	1,080.	1,102.	1,118.	1,149.	93.
	35 1/8"	60"	3"	DP8CTTLL3660	1,148.	1,181.	1,236.	1,257.	1,290.	1,311.	1,334.	1,367.	95.
42" High Tiled Open Base 	42 3/16"	18"	3"	DP8CTTLL4218	722.	742.	777.	793.	812.	823.	838.	859.	88.
	42 3/16"	24"	3"	DP8CTTLL4224	765.	786.	821.	837.	858.	872.	885.	910.	89.
	42 3/16"	30"	3"	DP8CTTLL4230	817.	839.	878.	898.	917.	934.	951.	974.	90.
	42 3/16"	36"	3"	DP8CTTLL4236	872.	901.	938.	956.	980.	996.	1,015.	1,036.	92.
	42 3/16"	42"	3"	DP8CTTLL4242	931.	957.	1,000.	1,020.	1,043.	1,064.	1,077.	1,106.	91.
	42 3/16"	48"	3"	DP8CTTLL4248	978.	1,004.	1,054.	1,072.	1,101.	1,116.	1,136.	1,166.	93.
	42 3/16"	60"	3"	DP8CTTLL4260	1,167.	1,202.	1,257.	1,278.	1,313.	1,335.	1,356.	1,389.	95.
50" High Tiled Open Base 	49 1/2"	18"	3"	DP8CTTLL5018	746.	768.	804.	818.	838.	852.	868.	886.	87.
	49 1/2"	24"	3"	DP8CTTLL5024	803.	823.	866.	876.	906.	916.	932.	955.	90.
	49 1/2"	30"	3"	DP8CTTLL5030	846.	872.	912.	926.	953.	966.	985.	1,005.	87.
	49 1/2"	36"	3"	DP8CTTLL5036	898.	921.	962.	983.	1,004.	1,023.	1,040.	1,068.	81.
	49 1/2"	42"	3"	DP8CTTLL5042	952.	980.	1,025.	1,041.	1,070.	1,089.	1,105.	1,133.	76.
	49 1/2"	48"	3"	DP8CTTLL5048	1,000.	1,030.	1,076.	1,100.	1,124.	1,146.	1,165.	1,193.	74.
	49 1/2"	60"	3"	DP8CTTLL5060	1,190.	1,224.	1,281.	1,305.	1,339.	1,364.	1,385.	1,420.	95.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Open Base: 1. Pattern Number 2. Top cap type 3. Top Cap finish 4. Base finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Open Base <hr/> <i>Example:</i> DP8CTTLL3618 4/117/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> TT Tiled both sides <hr/> LL Open base <hr/> 36 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> 117 Soft Grey base finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panel with Open Base: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Open base Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panel with Open Base: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal




Tiled Panels

Open Base

57", 64" and 78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.									deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
57" High Tiled Open Base 	56 ¹³ / ₁₆ "	18"	3"	DP8CTTLL5718	\$901.	\$923.	\$966.	\$984.	\$1,009.	\$1,026.	\$1,043.	\$1,070.	\$109.
	56 ¹³ / ₁₆ "	24"	3"	DP8CTTLL5724	962.	989.	1,035.	1,054.	1,079.	1,101.	1,118.	1,148.	113.
	56 ¹³ / ₁₆ "	30"	3"	DP8CTTLL5730	1,016.	1,044.	1,097.	1,111.	1,144.	1,162.	1,182.	1,212.	116.
	56 ¹³ / ₁₆ "	36"	3"	DP8CTTLL5736	1,076.	1,107.	1,160.	1,182.	1,213.	1,232.	1,252.	1,287.	118.
	56 ¹³ / ₁₆ "	42"	3"	DP8CTTLL5742	1,139.	1,173.	1,225.	1,248.	1,280.	1,303.	1,326.	1,356.	121.
	56 ¹³ / ₁₆ "	48"	3"	DP8CTTLL5748	1,201.	1,236.	1,293.	1,315.	1,349.	1,373.	1,395.	1,432.	123.
	56 ¹³ / ₁₆ "	60"	3"	DP8CTTLL5760	1,432.	1,471.	1,542.	1,571.	1,612.	1,640.	1,667.	1,709.	125.
64" High Tiled Open Base 	64 ¹ / ₁₆ "	18"	3"	DP8CTTLL6418	950.	977.	1,021.	1,038.	1,068.	1,081.	1,103.	1,129.	131.
	64 ¹ / ₁₆ "	24"	3"	DP8CTTLL6424	1,016.	1,042.	1,097.	1,110.	1,140.	1,160.	1,181.	1,212.	138.
	64 ¹ / ₁₆ "	30"	3"	DP8CTTLL6430	1,072.	1,104.	1,155.	1,176.	1,210.	1,224.	1,248.	1,278.	134.
	64 ¹ / ₁₆ "	36"	3"	DP8CTTLL6436	1,136.	1,173.	1,223.	1,247.	1,278.	1,302.	1,322.	1,355.	135.
	64 ¹ / ₁₆ "	42"	3"	DP8CTTLL6442	1,203.	1,237.	1,296.	1,319.	1,353.	1,376.	1,398.	1,435.	137.
	64 ¹ / ₁₆ "	48"	3"	DP8CTTLL6448	1,266.	1,302.	1,361.	1,385.	1,423.	1,450.	1,471.	1,508.	138.
	64 ¹ / ₁₆ "	60"	3"	DP8CTTLL6460	1,508.	1,551.	1,628.	1,658.	1,701.	1,730.	1,758.	1,803.	138.
78" High Tiled Open Base 	78 ⁷ / ₁₆ "	18"	3"	DP8CTTLL7818	1,467.	1,508.	1,581.	1,609.	1,650.	1,681.	1,710.	1,751.	235.
	78 ⁷ / ₁₆ "	24"	3"	DP8CTTLL7824	1,575.	1,619.	1,698.	1,726.	1,775.	1,804.	1,834.	1,883.	243.
	78 ⁷ / ₁₆ "	30"	3"	DP8CTTLL7830	1,667.	1,715.	1,793.	1,829.	1,878.	1,908.	1,942.	1,988.	237.
	78 ⁷ / ₁₆ "	36"	3"	DP8CTTLL7836	1,779.	1,831.	1,917.	1,950.	2,004.	2,040.	2,074.	2,126.	258.
	78 ⁷ / ₁₆ "	42"	3"	DP8CTTLL7842	1,883.	1,937.	2,026.	2,064.	2,123.	2,156.	2,194.	2,250.	263.
	78 ⁷ / ₁₆ "	48"	3"	DP8CTTLL7848	1,991.	2,052.	2,149.	2,190.	2,247.	2,287.	2,326.	2,383.	315.

Dimensions listed under h w d are actual to the nearest 1/8"



Ordering Information	Order Code	Included with:	Options
Tiled Panel with Open Base:	Tiled Panel with Open Base	Tiled Panel with Open Base:	Tiled Panel with Open Base:
1. Pattern Number	<i>Example:</i> DP8CTTLL3618	<ul style="list-style-type: none"> Panel frame Acoustic panel inserts Open base Top cap Connection hardware 	Full View Frame Option:
2. Top cap type	4/117/117/2/B191		To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.
3. Top Cap finish	DP8 Dividends Horizon Panel	Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Side Option:
4. Base finish	C Topway frame		For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column.
5. Tile support profile	TT Tiled both sides		Top Cap Options:
6. Panel fabric	LL Open base		No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
	36 Height		Tile Support Options:
	18 Width		(1) = D1 External Reveal
	4 Radius Metal top cap		(2) = D2 Recessed Reveal
	117 Soft Grey top cap finish		
	117 Soft Grey base finish		
	2 D2 style tile supports		
	B191 Fairfield light fabric		

Tiled Panels

Tile To Floor One Side

36" and 42" High

Dividends Horizon

description	h	w	d	pattern no.									Deduct for
					10	15	20	25	30	35	40	45	Monolithic One Side
36" High Tiled Panel Tile to Floor One Side 	35 1/8"	15"	3"	DP8CTTFR3615	\$740.	\$758.	\$795.	\$806.	\$828.	\$839.	\$852.	\$872.	\$88.
	35 1/8"	18"	3"	DP8CTTFR3618	740.	758.	795.	806.	828.	839.	852.	872.	88.
	35 1/8"	24"	3"	DP8CTTFR3624	781.	803.	839.	853.	873.	887.	903.	921.	89.
	35 1/8"	30"	3"	DP8CTTFR3630	826.	847.	882.	901.	919.	941.	951.	973.	90.
	35 1/8"	36"	3"	DP8CTTFR3636	896.	916.	959.	981.	1,000.	1,020.	1,034.	1,058.	92.
	35 1/8"	42"	3"	DP8CTTFR3642	956.	984.	1,024.	1,040.	1,069.	1,088.	1,105.	1,134.	91.
	35 1/8"	48"	3"	DP8CTTFR3648	997.	1,024.	1,071.	1,092.	1,115.	1,137.	1,153.	1,184.	93.
	35 1/8"	60"	3"	DP8CTTFR3660	1,183.	1,216.	1,271.	1,292.	1,325.	1,346.	1,369.	1,402.	95.
42" High Tiled Panel Tile to Floor One Side 	42 3/16"	15"	3"	DP8CTTFR4215	757.	777.	812.	828.	847.	858.	873.	894.	88.
	42 3/16"	18"	3"	DP8CTTFR4218	757.	777.	812.	828.	847.	858.	873.	894.	88.
	42 3/16"	24"	3"	DP8CTTFR4224	800.	821.	856.	872.	893.	907.	920.	945.	89.
	42 3/16"	30"	3"	DP8CTTFR4230	852.	874.	913.	933.	952.	969.	986.	1,009.	90.
	42 3/16"	36"	3"	DP8CTTFR4236	907.	936.	973.	991.	1,015.	1,031.	1,050.	1,071.	92.
	42 3/16"	42"	3"	DP8CTTFR4242	966.	992.	1,035.	1,055.	1,078.	1,098.	1,112.	1,141.	91.
	42 3/16"	48"	3"	DP8CTTFR4248	1,013.	1,039.	1,089.	1,107.	1,136.	1,151.	1,171.	1,201.	93.
	42 3/16"	60"	3"	DP8CTTFR4260	1,202.	1,237.	1,292.	1,313.	1,348.	1,370.	1,391.	1,424.	95.


Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR3618 4/117/K/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> TT Tiled both sides <hr/> FR Tile to floor side one, raceway side two <hr/> 36 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Knockouts for one-sided base raceway <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Base raceway with knockout one side Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "TT" in pattern number to "MT" and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Tile To Floor One Side

50" and 57" High

description	h	w	d	pattern no.	grade								deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
50" High Tiled Panel Tile to Floor One Side 	49 1/2"	15"	3"	DP8CTTFR5015	\$781.	\$803.	\$839.	\$853.	\$873.	\$887.	\$903.	\$921.	\$87.
	49 1/2"	18"	3"	DP8CTTFR5018	781.	803.	839.	853.	873.	887.	903.	921.	87.
	49 1/2"	24"	3"	DP8CTTFR5024	838.	858.	901.	911.	941.	951.	967.	990.	90.
	49 1/2"	30"	3"	DP8CTTFR5030	881.	907.	947.	961.	988.	1,001.	1,020.	1,040.	87.
	49 1/2"	36"	3"	DP8CTTFR5036	933.	956.	997.	1,018.	1,039.	1,058.	1,075.	1,103.	81.
	49 1/2"	42"	3"	DP8CTTFR5042	987.	1,015.	1,060.	1,076.	1,105.	1,124.	1,140.	1,168.	76.
	49 1/2"	48"	3"	DP8CTTFR5048	1,035.	1,065.	1,111.	1,135.	1,159.	1,181.	1,200.	1,228.	74.
	49 1/2"	60"	3"	DP8CTTFR5060	1,225.	1,259.	1,316.	1,340.	1,374.	1,399.	1,420.	1,455.	95.

57" High Tiled Panel Tile to Floor One Side 	56 13/16"	15"	3"	DP8CTTFR5715	936.	958.	1,001.	1,019.	1,044.	1,061.	1,078.	1,105.	109.
	56 13/16"	18"	3"	DP8CTTFR5718	936.	958.	1,001.	1,019.	1,044.	1,061.	1,078.	1,105.	109.
	56 13/16"	24"	3"	DP8CTTFR5724	997.	1,024.	1,070.	1,089.	1,114.	1,136.	1,153.	1,183.	113.
	56 13/16"	30"	3"	DP8CTTFR5730	1,051.	1,079.	1,132.	1,146.	1,179.	1,197.	1,217.	1,247.	116.
	56 13/16"	36"	3"	DP8CTTFR5736	1,111.	1,142.	1,195.	1,217.	1,248.	1,267.	1,287.	1,322.	118.
	56 13/16"	42"	3"	DP8CTTFR5742	1,174.	1,208.	1,260.	1,283.	1,315.	1,338.	1,361.	1,391.	121.
	56 13/16"	48"	3"	DP8CTTFR5748	1,236.	1,271.	1,328.	1,350.	1,384.	1,408.	1,430.	1,467.	123.
	56 13/16"	60"	3"	DP8CTTFR5760	1,467.	1,506.	1,577.	1,606.	1,647.	1,675.	1,702.	1,744.	125.


Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR5018 4/117/K/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> TT Tiled both sides <hr/> FR Tile to floor side one, raceway side two <hr/> 50 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Knockouts for one-sided base raceway <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Base raceway with knockout one side Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Options: For side 1 monolithic, side 2 tiled, change "TT" in pattern number to "MT" and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Tile To Floor One Side

64" and 78" High

description	h	w	d	pattern no.	grade								deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
64" High Tiled Panel Tile to Floor One Side 	64 1/16"	15"	3"	DP8CTTFR6415	\$985.	\$1,012.	\$1,056.	\$1,073.	\$1,103.	\$1,116.	\$1,138.	\$1,164.	\$131.
	64 1/16"	18"	3"	DP8CTTFR6418	985.	1,012.	1,056.	1,073.	1,103.	1,116.	1,138.	1,164.	131.
	64 1/16"	24"	3"	DP8CTTFR6424	1,051.	1,077.	1,132.	1,145.	1,175.	1,195.	1,216.	1,247.	138.
	64 1/16"	30"	3"	DP8CTTFR6430	1,107.	1,139.	1,190.	1,211.	1,245.	1,259.	1,283.	1,313.	134.
	64 1/16"	36"	3"	DP8CTTFR6436	1,172.	1,209.	1,259.	1,283.	1,314.	1,337.	1,358.	1,390.	135.
	64 1/16"	42"	3"	DP8CTTFR6442	1,238.	1,272.	1,331.	1,354.	1,388.	1,411.	1,433.	1,470.	137.
	64 1/16"	48"	3"	DP8CTTFR6448	1,301.	1,337.	1,396.	1,420.	1,458.	1,485.	1,506.	1,543.	138.
	64 1/16"	60"	3"	DP8CTTFR6460	1,543.	1,586.	1,663.	1,693.	1,736.	1,765.	1,793.	1,838.	138.

78" High Tiled Panel Tile to Floor One Side 	78 1/16"	15"	3"	DP8CTTFR7815	1,502.	1,543.	1,617.	1,644.	1,685.	1,716.	1,745.	1,786.	235.
	78 1/16"	18"	3"	DP8CTTFR7818	1,502.	1,543.	1,616.	1,644.	1,685.	1,716.	1,745.	1,786.	235.
	78 1/16"	24"	3"	DP8CTTFR7824	1,610.	1,654.	1,733.	1,761.	1,810.	1,839.	1,869.	1,918.	243.
	78 1/16"	30"	3"	DP8CTTFR7830	1,702.	1,750.	1,828.	1,864.	1,913.	1,943.	1,977.	2,023.	237.
	78 1/16"	36"	3"	DP8CTTFR7836	1,814.	1,866.	1,952.	1,985.	2,039.	2,075.	2,109.	2,161.	258.
	78 1/16"	42"	3"	DP8CTTFR7842	1,918.	1,972.	2,061.	2,099.	2,158.	2,191.	2,229.	2,285.	263.
	78 1/16"	48"	3"	DP8CTTFR7848	2,026.	2,087.	2,184.	2,225.	2,282.	2,322.	2,361.	2,418.	315.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR6418 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides FR Tile to floor side one, raceway side two 64 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Knockouts for one-sided base raceway 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Tile to Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Base raceway with knockout one side Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Options: For side 1 monolithic, side 2 tiled, change "TT" in pattern number to "MT" and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Base Raceway

42" and 50" High

description	h	w	d	pattern no.	grade								Deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
42" High Tiled Panel with 28" Lower Tile and Base Raceway 	42 3/16"	15"	3"	DP8CPPRR4215	\$658.	\$676.	\$710.	\$725.	\$744.	\$759.	\$772.	\$793.	\$59.
	42 3/16"	18"	3"	DP8CPPRR4218	658.	676.	710.	725.	744.	759.	772.	793.	59.
	42 3/16"	24"	3"	DP8CPPRR4224	699.	720.	757.	771.	791.	806.	819.	842.	59.
	42 3/16"	30"	3"	DP8CPPRR4230	751.	774.	813.	829.	849.	868.	880.	909.	60.
	42 3/16"	36"	3"	DP8CPPRR4236	806.	831.	872.	887.	914.	930.	950.	969.	62.
	42 3/16"	42"	3"	DP8CPPRR4242	863.	889.	933.	954.	977.	996.	1,012.	1,040.	62.
	42 3/16"	48"	3"	DP8CPPRR4248	912.	936.	987.	1,005.	1,034.	1,050.	1,071.	1,100.	63.
	42 3/16"	60"	3"	DP8CPPRR4260	1,101.	1,132.	1,189.	1,213.	1,245.	1,268.	1,292.	1,325.	64.
50" High Tiled Panel with 28" Lower Tile and Base Raceway 	49 1/2"	15"	3"	DP8CPPRR5015	680.	703.	736.	752.	772.	785.	802.	820.	58.
	49 1/2"	18"	3"	DP8CPPRR5018	680.	703.	736.	752.	772.	785.	802.	820.	58.
	49 1/2"	24"	3"	DP8CPPRR5024	735.	759.	800.	812.	837.	848.	866.	886.	60.
	49 1/2"	30"	3"	DP8CPPRR5030	779.	806.	844.	859.	884.	902.	918.	937.	58.
	49 1/2"	36"	3"	DP8CPPRR5036	829.	852.	898.	916.	936.	957.	973.	1,000.	54.
	49 1/2"	42"	3"	DP8CPPRR5042	881.	914.	958.	974.	1,002.	1,022.	1,038.	1,069.	50.
	49 1/2"	48"	3"	DP8CPPRR5048	933.	962.	1,011.	1,033.	1,061.	1,076.	1,099.	1,124.	49.
	49 1/2"	60"	3"	DP8CPPRR5060	1,122.	1,159.	1,216.	1,239.	1,272.	1,297.	1,319.	1,353.	64.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Tile support profile 7. Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <i>Example:</i> DP8CPPRR4218 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile RR Raceway both sides 42 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panel with 28" Lower Tile and Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal


Tiled Panels

28" Lower Tile and Base Raceway


57" and 64" High

Dividends Horizon

description	h	w	d	pattern no.	grade								Deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
57" High Tiled Panel with 28" Lower Tile and Base Raceway	56 ¹³ / ₁₆ "	15"	3"	DP8CPPRR5715	\$831.	\$854.	\$902.	\$917.	\$942.	\$959.	\$977.	\$1,002.	\$73.
	56 ¹³ / ₁₆ "	18"	3"	DP8CPPRR5718	831.	854.	902.	917.	942.	959.	977.	1,002.	73.
	56 ¹³ / ₁₆ "	24"	3"	DP8CPPRR5724	898.	924.	967.	987.	1,015.	1,034.	1,052.	1,077.	76.
	56 ¹³ / ₁₆ "	30"	3"	DP8CPPRR5730	951.	978.	1,029.	1,044.	1,074.	1,097.	1,114.	1,146.	78.
	56 ¹³ / ₁₆ "	36"	3"	DP8CPPRR5736	1,011.	1,041.	1,093.	1,114.	1,148.	1,166.	1,185.	1,217.	79.
	56 ¹³ / ₁₆ "	42"	3"	DP8CPPRR5742	1,072.	1,104.	1,160.	1,182.	1,215.	1,237.	1,259.	1,292.	81.
	56 ¹³ / ₁₆ "	48"	3"	DP8CPPRR5748	1,130.	1,168.	1,224.	1,248.	1,281.	1,305.	1,329.	1,365.	82.
	56 ¹³ / ₁₆ "	60"	3"	DP8CPPRR5760	1,365.	1,409.	1,472.	1,501.	1,545.	1,574.	1,600.	1,641.	85.



64" High Tiled Panel with 28" Lower Tile and Base Raceway	64 ¹ / ₁₆ "	15"	3"	DP8CPPRR6415	879.	911.	955.	972.	1,000.	1,018.	1,036.	1,065.	89.
	64 ¹ / ₁₆ "	18"	3"	DP8CPPRR6418	879.	911.	955.	972.	1,000.	1,018.	1,036.	1,065.	89.
	64 ¹ / ₁₆ "	24"	3"	DP8CPPRR6424	951.	976.	1,029.	1,043.	1,073.	1,093.	1,113.	1,146.	93.
	64 ¹ / ₁₆ "	30"	3"	DP8CPPRR6430	1,005.	1,037.	1,084.	1,107.	1,144.	1,159.	1,182.	1,213.	90.
	64 ¹ / ₁₆ "	36"	3"	DP8CPPRR6436	1,071.	1,104.	1,158.	1,181.	1,213.	1,236.	1,257.	1,291.	91.
	64 ¹ / ₁₆ "	42"	3"	DP8CPPRR6442	1,133.	1,172.	1,229.	1,252.	1,289.	1,309.	1,331.	1,368.	92.
	64 ¹ / ₁₆ "	48"	3"	DP8CPPRR6448	1,201.	1,236.	1,296.	1,319.	1,355.	1,382.	1,409.	1,444.	93.
	64 ¹ / ₁₆ "	60"	3"	DP8CPPRR6460	1,444.	1,488.	1,561.	1,589.	1,634.	1,664.	1,692.	1,737.	93.



Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Tile support style 7. Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <i>Example:</i> DP8CPPRR5718 4/117/K/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> PP Tiled both sides, 28" Lower Tile <hr/> RR Raceway both sides <hr/> 57 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile support <hr/> B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Base Raceway

78" High

description	h	w	d	pattern no.	grade								deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
78" High Tiled Panel with 28" Lower Tile and Base Raceway	78 ¹ / ₁₆ "	15"	3"	DP8CPRR7815	\$1,405.	\$1,444.	\$1,513.	\$1,543.	\$1,583.	\$1,613.	\$1,642.	\$1,686.	\$158.
	78 ¹ / ₁₆ "	18"	3"	DP8CPRR7818	1,405.	1,444.	1,513.	1,543.	1,583.	1,613.	1,642.	1,686.	158.
	78 ¹ / ₁₆ "	24"	3"	DP8CPRR7824	1,507.	1,551.	1,632.	1,661.	1,710.	1,738.	1,766.	1,815.	163.
	78 ¹ / ₁₆ "	30"	3"	DP8CPRR7830	1,600.	1,647.	1,726.	1,761.	1,808.	1,842.	1,877.	1,924.	160.
	78 ¹ / ₁₆ "	36"	3"	DP8CPRR7836	1,713.	1,763.	1,848.	1,883.	1,938.	1,973.	2,005.	2,057.	173.
	78 ¹ / ₁₆ "	42"	3"	DP8CPRR7842	1,815.	1,872.	1,960.	1,997.	2,053.	2,091.	2,130.	2,184.	176.
	78 ¹ / ₁₆ "	48"	3"	DP8CPRR7848	1,927.	1,985.	2,084.	2,125.	2,182.	2,220.	2,259.	2,316.	211.



Dimensions listed under h w d are actual to the nearest 1/8"



Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Tile support style 7. Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <hr/> <i>Example:</i> DP8CPRR7818 4/117/K/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> PP Tiled both sides, 28" Lower Tile <hr/> RR Raceway both sides <hr/> 78 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile support <hr/> B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Top cap Connection hardware <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Tiled Panels with 28" Lower Tile and Base Raceway: <p>Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.</p> <p>Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column.</p> <p>Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4</p> <p>Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts</p> <p>Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal</p>

Tiled Panels

28" Lower Tile and Open Base

42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.	grade								Deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
42" High Tiled Panel with 28" Lower Tile and Open Base 	42 3/16"	18"	3"	DP8CPPLL4218	\$658.	\$676.	\$710.	\$725.	\$744.	\$759.	\$772.	\$793.	\$59.
	42 3/16"	24"	3"	DP8CPPLL4224	699.	720.	757.	771.	791.	806.	819.	842.	59.
	42 3/16"	30"	3"	DP8CPPLL4230	751.	774.	813.	829.	849.	868.	880.	909.	60.
	42 3/16"	36"	3"	DP8CPPLL4236	806.	831.	872.	887.	914.	930.	950.	969.	62.
	42 3/16"	42"	3"	DP8CPPLL4242	863.	889.	933.	954.	977.	996.	1,012.	1,040.	62.
	42 3/16"	48"	3"	DP8CPPLL4248	912.	936.	987.	1,005.	1,034.	1,050.	1,071.	1,100.	63.
	42 3/16"	60"	3"	DP8CPPLL4260	1,101.	1,132.	1,189.	1,213.	1,245.	1,268.	1,292.	1,325.	64.
50" High Tiled Panel with 28" Lower Tile and Open Base 	49 1/2"	18"	3"	DP8CPPLL5018	680.	703.	736.	752.	772.	785.	802.	820.	58.
	49 1/2"	24"	3"	DP8CPPLL5024	735.	759.	800.	812.	837.	848.	866.	886.	60.
	49 1/2"	30"	3"	DP8CPPLL5030	779.	806.	844.	859.	884.	902.	918.	937.	58.
	49 1/2"	36"	3"	DP8CPPLL5036	829.	852.	898.	916.	936.	957.	973.	1,000.	54.
	49 1/2"	42"	3"	DP8CPPLL5042	881.	914.	958.	974.	1,002.	1,022.	1,038.	1,069.	50.
	49 1/2"	48"	3"	DP8CPPLL5048	933.	962.	1,011.	1,033.	1,061.	1,076.	1,099.	1,124.	49.
	49 1/2"	60"	3"	DP8CPPLL5060	1,122.	1,159.	1,216.	1,239.	1,272.	1,297.	1,319.	1,353.	64.

Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric	Tiled Panels with 28" Lower Tile and Open Base <i>Example:</i> DP8CPPLL4218 4/117/KK/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> PP Tiled both sides, 28" Lower Tile <hr/> LL Open Base <hr/> 42 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> 117 Soft Grey base support finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Open base Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels


28" Lower Tile and Open Base

57" and 64" High

description	h	w	d	pattern no.	grade								deduct for Monolithic One Side
					10	15	20	25	30	35	40	45	
57" High Tiled Panel with 28" Lower Tile and Open Base	56 ^{13/16"}	18"	3"	DP8CPPLL5718	\$831.	\$854.	\$902.	\$917.	\$942.	\$959.	\$977.	\$1,002.	\$73.
	56 ^{13/16"}	24"	3"	DP8CPPLL5724	898.	924.	967.	987.	1,015.	1,034.	1,052.	1,077.	76.
	56 ^{13/16"}	30"	3"	DP8CPPLL5730	951.	978.	1,029.	1,044.	1,074.	1,097.	1,114.	1,146.	78.
	56 ^{13/16"}	36"	3"	DP8CPPLL5736	1,011.	1,041.	1,093.	1,114.	1,148.	1,166.	1,185.	1,217.	79.
	56 ^{13/16"}	42"	3"	DP8CPPLL5742	1,072.	1,104.	1,160.	1,182.	1,215.	1,237.	1,259.	1,292.	81.
	56 ^{13/16"}	48"	3"	DP8CPPLL5748	1,130.	1,168.	1,224.	1,248.	1,281.	1,305.	1,329.	1,365.	82.
	56 ^{13/16"}	60"	3"	DP8CPPLL5760	1,365.	1,409.	1,472.	1,501.	1,545.	1,574.	1,600.	1,641.	85.



64" High Tiled Panel with 28" Lower Tile and Open Base	64 ^{1/16"}	18"	3"	DP8CPPLL6418	879.	911.	955.	972.	1,000.	1,018.	1,036.	1,065.	89.
	64 ^{1/16"}	24"	3"	DP8CPPLL6424	951.	976.	1,029.	1,043.	1,073.	1,093.	1,113.	1,146.	93.
	64 ^{1/16"}	30"	3"	DP8CPPLL6430	1,005.	1,037.	1,084.	1,107.	1,144.	1,159.	1,182.	1,213.	90.
	64 ^{1/16"}	36"	3"	DP8CPPLL6436	1,071.	1,104.	1,158.	1,181.	1,213.	1,236.	1,257.	1,291.	91.
	64 ^{1/16"}	42"	3"	DP8CPPLL6442	1,133.	1,172.	1,229.	1,252.	1,289.	1,309.	1,331.	1,368.	92.
	64 ^{1/16"}	48"	3"	DP8CPPLL6448	1,201.	1,236.	1,296.	1,319.	1,355.	1,382.	1,409.	1,444.	93.
	64 ^{1/16"}	60"	3"	DP8CPPLL6460	1,444.	1,488.	1,561.	1,589.	1,634.	1,664.	1,692.	1,737.	93.



Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric	Tiled Panels with 28" Lower Tile and Open Base <i>Example:</i> DP8CPPLL5718 4/117/KK/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> PP Tiled both sides, 28" Lower Tile <hr/> LL Open Base <hr/> 57 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> 117 Soft Grey base support finish <hr/> 2 D2 style tile support <hr/> B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Open base Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Open Base

78" High

description	h	w	d	pattern no.	grade							deduct for Monolithic One Side	
					10	15	20	25	30	35	40		45
78" High Tiled Panel with 28" Lower Tile and Open Base	78 ¹ / ₁₆ "	18"	3"	DP8CPPLL7818	\$1,405.	\$1,444.	\$1,513.	\$1,543.	\$1,583.	\$1,613.	\$1,642.	\$1,686.	\$158.
	78 ¹ / ₁₆ "	24"	3"	DP8CPPLL7824	1,507.	1,551.	1,632.	1,661.	1,710.	1,738.	1,766.	1,815.	163.
	78 ¹ / ₁₆ "	30"	3"	DP8CPPLL7830	1,600.	1,647.	1,726.	1,761.	1,808.	1,842.	1,877.	1,924.	160.
	78 ¹ / ₁₆ "	36"	3"	DP8CPPLL7836	1,713.	1,763.	1,848.	1,883.	1,938.	1,973.	2,005.	2,057.	173.
	78 ¹ / ₁₆ "	42"	3"	DP8CPPLL7842	1,815.	1,872.	1,960.	1,997.	2,053.	2,091.	2,130.	2,184.	176.
	78 ¹ / ₁₆ "	48"	3"	DP8CPPLL7848	1,927.	1,985.	2,084.	2,125.	2,182.	2,220.	2,259.	2,316.	211.





Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: <ol style="list-style-type: none"> 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric 	Tiled Panels with 28" Lower Tile and Open Base <hr/> <i>Example:</i> DP8CPPLL7818 4/117/KK/117/2/B191 <hr/> DP8 Dividends Horizon Panel <hr/> C Topway frame <hr/> PP Tiled both sides, 28" Lower Tile <hr/> LL Open Base <hr/> 78 Height <hr/> 18 Width <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> 117 Soft Grey base support finish <hr/> 2 D2 style tile support <hr/> B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: <ul style="list-style-type: none"> • Panel frame • Acoustic panel inserts • Open base • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: <p>Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.</p> <p>Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column.</p> <p>Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4</p> <p>Base Raceway Knockout Options:</p> <p>(K) = Knockouts on raceway side (N) = No knockouts</p> <p>Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal</p>

Tiled Panels

28" Lower Tile and Tile To Floor

42" and 50" High

description	h	w	d	pattern no.	grade								Deduct for 1 side Monolithic
					10	15	20	25	30	35	40	45	
42" High Tiled Panel with 28" Lower Tile and Tile to Floor 	42 3/16"	15"	3"	DP8CPPFR4215	\$693.	\$711.	\$745.	\$760.	\$779.	\$794.	\$807.	\$828.	\$59.
	42 3/16"	18"	3"	DP8CPPFR4218	693.	711.	745.	760.	779.	794.	807.	828.	59.
	42 3/16"	24"	3"	DP8CPPFR4224	734.	755.	792.	806.	826.	841.	854.	877.	59.
	42 3/16"	30"	3"	DP8CPPFR4230	786.	809.	848.	864.	884.	903.	915.	944.	60.
	42 3/16"	36"	3"	DP8CPPFR4236	841.	866.	907.	922.	949.	965.	985.	1,004.	62.
	42 3/16"	42"	3"	DP8CPPFR4242	898.	924.	968.	989.	1,012.	1,031.	1,047.	1,075.	62.
	42 3/16"	48"	3"	DP8CPPFR4248	947.	972.	1,022.	1,040.	1,069.	1,085.	1,106.	1,135.	63.
	42 3/16"	60"	3"	DP8CPPFR4260	1,136.	1,167.	1,224.	1,248.	1,280.	1,303.	1,327.	1,360.	64.
50" High Tiled Panel with 28" Lower Tile and Tile to Floor 	49 1/2"	15"	3"	DP8CPPFR5015	715.	738.	771.	787.	807.	820.	837.	855.	58.
	49 1/2"	18"	3"	DP8CPPFR5018	715.	738.	771.	787.	807.	820.	837.	855.	58.
	49 1/2"	24"	3"	DP8CPPFR5024	770.	794.	835.	847.	875.	883.	901.	921.	60.
	49 1/2"	30"	3"	DP8CPPFR5030	814.	841.	879.	894.	919.	937.	953.	972.	58.
	49 1/2"	36"	3"	DP8CPPFR5036	864.	887.	933.	951.	971.	992.	1,008.	1,035.	54.
	49 1/2"	42"	3"	DP8CPPFR5042	916.	949.	993.	1,009.	1,037.	1,057.	1,073.	1,104.	50.
	49 1/2"	48"	3"	DP8CPPFR5048	968.	997.	1,046.	1,068.	1,096.	1,111.	1,134.	1,159.	49.
	49 1/2"	60"	3"	DP8CPPFR5060	1,157.	1,194.	1,251.	1,274.	1,307.	1,332.	1,354.	1,388.	64.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information

Tiled Panels with 28" Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28" Lower Tile and Tile To Floor:

Example: **DP8CPPFF4218**
4/117/K/117/2B191

DP8CPP	Pattern number
FF4218	
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28" Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Tile to floor side 1
- Base raceway with knockout when required side 2

Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others

Options

Tiled Panels with 28" Lower Tile and Tile To Floor:

Full View Frame Option:

To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Tile to Floor Side Option:

Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF".

Monolithic Side Option:

To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. **Top Cap Options:**

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:


(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Tiled Panels


28" Lower Tile and Tile To Floor

57" and 64" High

description	h	w	d	pattern no.	grade								deduct for
					10	15	20	25	30	35	40	45	1 side Monolithic
57" High Tiled Panel with 28" Lower Tile and Tile to Floor	56 ¹³ / ₁₆ "	15"	3"	DP8CPPFR5715	\$866.	\$889.	\$937.	\$952.	\$977.	\$994.	\$1,012.	\$1,037.	\$73.
	56 ¹³ / ₁₆ "	18"	3"	DP8CPPFR5718	866.	889.	937.	952.	977.	994.	1,012.	1,037.	73.
	56 ¹³ / ₁₆ "	24"	3"	DP8CPPFR5724	933.	959.	1,002.	1,022.	1,050.	1,069.	1,087.	1,112.	76.
	56 ¹³ / ₁₆ "	30"	3"	DP8CPPFR5730	986.	1,013.	1,065.	1,079.	1,110.	1,132.	1,149.	1,181.	78.
	56 ¹³ / ₁₆ "	36"	3"	DP8CPPFR5736	1,046.	1,076.	1,128.	1,149.	1,183.	1,201.	1,220.	1,252.	79.
	56 ¹³ / ₁₆ "	42"	3"	DP8CPPFR5742	1,107.	1,139.	1,195.	1,217.	1,250.	1,272.	1,294.	1,327.	81.
	56 ¹³ / ₁₆ "	48"	3"	DP8CPPFR5748	1,165.	1,203.	1,259.	1,283.	1,316.	1,340.	1,364.	1,400.	82.
	56 ¹³ / ₁₆ "	60"	3"	DP8CPPFR5760	1,400.	1,444.	1,507.	1,536.	1,580.	1,609.	1,635.	1,676.	85.



64" High Tiled Panel with 28" Lower Tile and Tile to Floor	64 ¹ / ₁₆ "	15"	3"	DP8CPPFR6415	914.	946.	990.	1,007.	1,035.	1,053.	1,071.	1,100.	89.
	64 ¹ / ₁₆ "	18"	3"	DP8CPPFR6418	914.	946.	990.	1,007.	1,035.	1,053.	1,071.	1,100.	89.
	64 ¹ / ₁₆ "	24"	3"	DP8CPPFR6424	986.	1,011.	1,064.	1,078.	1,108.	1,128.	1,148.	1,181.	93.
	64 ¹ / ₁₆ "	30"	3"	DP8CPPFR6430	1,040.	1,072.	1,119.	1,142.	1,179.	1,194.	1,217.	1,248.	90.
	64 ¹ / ₁₆ "	36"	3"	DP8CPPFR6436	1,106.	1,139.	1,193.	1,216.	1,248.	1,271.	1,292.	1,326.	91.
	64 ¹ / ₁₆ "	42"	3"	DP8CPPFR6442	1,168.	1,207.	1,264.	1,287.	1,324.	1,344.	1,366.	1,403.	92.
	64 ¹ / ₁₆ "	48"	3"	DP8CPPFR6448	1,236.	1,271.	1,331.	1,354.	1,390.	1,417.	1,444.	1,479.	93.
	64 ¹ / ₁₆ "	60"	3"	DP8CPPFR6460	1,479.	1,523.	1,596.	1,624.	1,669.	1,699.	1,727.	1,772.	93.



Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Tile To Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Knockout option 5. Base raceway finish 6. Tile support style 7. Panel fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: <hr/> <i>Example:</i> DP8CPPFF4218 4/117/K/117/2/B191 <hr/> DP8CPP Pattern number <hr/> FF4218 <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts <hr/> 117 Soft Grey base raceway finish <hr/> 2 D2 style tile supports <hr/> B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Tile to floor side 1 Base raceway with knockout when required side 2 <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Tiled Panels with 28" Lower Tile and Tile To Floor: <p>Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.</p> <p>Tile to Floor Side Option: Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF".</p> <p>Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column.</p> <p>Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4</p> <p>Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts</p> <p>Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal</p>

Tiled Panels

28" Lower Tile and Tile To Floor

78" High

description	h	w	d	pattern no.	grade								deduct for
					10	15	20	25	30	35	40	45	Monolithic
78" High Tiled Panel with 28" Lower Tile and Tile to Floor	78 ¹ / ₁₆ "	15"	3"	DP8CPPFR7815	\$1,440.	\$1,479.	\$1,548.	\$1,578.	\$1,618.	\$1,648.	\$1,677.	\$1,721.	\$158.
	78 ¹ / ₁₆ "	18"	3"	DP8CPPFR7818	1,440.	1,479.	1,548.	1,578.	1,618.	1,648.	1,677.	1,721.	158.
	78 ¹ / ₁₆ "	24"	3"	DP8CPPFR7824	1,542.	1,586.	1,667.	1,696.	1,745.	1,773.	1,801.	1,850.	163.
	78 ¹ / ₁₆ "	30"	3"	DP8CPPFR7830	1,635.	1,682.	1,761.	1,796.	1,843.	1,877.	1,912.	1,959.	160.
	78 ¹ / ₁₆ "	36"	3"	DP8CPPFR7836	1,748.	1,798.	1,883.	1,918.	1,973.	2,008.	2,040.	2,092.	173.
	78 ¹ / ₁₆ "	42"	3"	DP8CPPFR7842	1,850.	1,907.	1,996.	2,033.	2,089.	2,127.	2,165.	2,220.	176.
	78 ¹ / ₁₆ "	48"	3"	DP8CPPFR7848	1,962.	2,020.	2,119.	2,160.	2,217.	2,255.	2,294.	2,351.	211.



Ordering Information

Tiled Panels with 28" Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28" Lower Tile and Tile To Floor:

Example: **DP8CPPFF4218**
4/117/K/117/2/B191

DP8CPP	Pattern number
FF4218	
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28" Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout when required

Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others

Options

Tiled Panels with 28" Lower Tile and Tile To Floor:

Full View Frame Option:

To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Tile to Floor Side Option:

Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF".

Monolithic Side Option:

To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column.

Top Cap Options:

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:

(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Beltway Panel Components

"Preconfigured" Dividends Horizon beltway panels ship completely assembled with a universal panel frame, choice of standard base raceway, open base or tiled to the floor base options, top cap, panel-to-panel connection hardware and beltway inserts.

Beltway panels may be ordered by component for "Build-to-Spec" applications. This includes when panel inserts are required on one side only or when a different fabric color or material is required on opposite panel sides.

Beltway Panel Insert Supports

All Dividends Horizon panel frames are pre-punched to accept beltway supports which span horizontally across the panel frame. Beltway panel inserts are mounted above and below the beltway and attach to the upper and lower panel frame and the beltway supports. Beltway supports are painted black.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Panel Insert Construction

Fabric inserts are constructed of fabric laminated with a web adhesive and heat cured to 1/2" thick tackable acoustic board. Laminate inserts are constructed of a particle board core with laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish.

Beltway Cover Construction

Painted steel in Knoll core paint colors.

Electrical

Panel base raceways 24" and wider will accept two duplex receptacles per panel side. 18" wide panels provide pass-through electrical only. Beltway raceways 30" and wider will accept two duplex receptacles per panel side. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel

Beltway panels are available with one beltway per panel or per panel sides. Non-beltway side will have a monolithic insert.

Two Top Cap Options Available

- Radius Metal
- Flat Metal


Top Cap Construction

Radius and flat metal top caps are made from extruded aluminum.


Top Cap Attachment

Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Beltway Panel




Panel Base Options



Beltway Panel Standard Configurations

42"H Panels

- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




57"H Panels

- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




64"H Panels

- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




50"H Panels

- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



78"H Panels

- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert





Beltway Panels

Standard Base Raceway

42" and 50" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade								Deduct for Monolithic on side 2
					10	15	20	25	30	35	40	45	
42" Beltway Panels with Standard Base Raceway 	42 ³ / ₁₆ "	18"	3"	DP8CBBRR4218	\$690.	\$708.	\$744.	\$753.	\$775.	\$787.	\$800.	\$819.	\$92.
	42 ³ / ₁₆ "	24"	3"	DP8CBBRR4224	779.	801.	835.	853.	872.	891.	903.	928.	114.
	42 ³ / ₁₆ "	30"	3"	DP8CBBRR4230	851.	873.	916.	932.	957.	971.	985.	1,013.	123.
	42 ³ / ₁₆ "	36"	3"	DP8CBBRR4236	930.	955.	1,000.	1,015.	1,044.	1,057.	1,079.	1,106.	136.
	42 ³ / ₁₆ "	42"	3"	DP8CBBRR4242	1,003.	1,033.	1,081.	1,097.	1,130.	1,150.	1,166.	1,194.	142.
	42 ³ / ₁₆ "	48"	3"	DP8CBBRR4248	1,069.	1,096.	1,152.	1,170.	1,199.	1,223.	1,242.	1,273.	153.
	42 ³ / ₁₆ "	60"	3"	DP8CBBRR4260	1,207.	1,242.	1,301.	1,324.	1,358.	1,384.	1,405.	1,439.	153.
50" Beltway Panels with Standard Base Raceway 	49 ¹ / ₂ "	18"	3"	DP8CBBRR5018	715.	736.	770.	784.	802.	816.	829.	851.	91.
	49 ¹ / ₂ "	24"	3"	DP8CBBRR5024	814.	835.	873.	892.	914.	931.	943.	968.	115.
	49 ¹ / ₂ "	30"	3"	DP8CBBRR5030	883.	904.	945.	965.	985.	1,005.	1,021.	1,048.	119.
	49 ¹ / ₂ "	36"	3"	DP8CBBRR5036	950.	976.	1,022.	1,042.	1,069.	1,085.	1,102.	1,132.	125.
	49 ¹ / ₂ "	42"	3"	DP8CBBRR5042	1,023.	1,054.	1,102.	1,125.	1,155.	1,173.	1,193.	1,224.	131.
	49 ¹ / ₂ "	48"	3"	DP8CBBRR5048	1,089.	1,124.	1,176.	1,195.	1,227.	1,248.	1,272.	1,303.	136.
	49 ¹ / ₂ "	60"	3"	DP8CBBRR5060	1,233.	1,269.	1,327.	1,351.	1,388.	1,412.	1,435.	1,470.	136.

Dimensions listed under h w d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Beltway Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Standard Base Raceway <i>Example:</i> DP8CBBRR4218 4/117/K/117/117/B191 DP8CBB Pattern number RR4218 4 Radius Metal top cap 117 Soft Grey top cap finish K Base Raceway with knockouts both sides 117 Soft Grey base raceway finish 117 Beltway finish B191 Fairfield light fabric	Beltway Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Beltway covers Top cap Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Standard Raceway Options: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "BB" in pattern number to "MB" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Beltway Panels

Standard Base Raceway

57", 64" and 78" High

Dividends Horizon

description	h	w	d	pattern no.	grade									Deduct for Monolithic on side 2
					10	15	20	25	30	35	40	45		
 57" Beltway Panels with Standard Base Raceway	56 ^{13/16"}	18"	3"	DP8CBRR5718	\$762.	\$785.	\$819.	\$832.	\$855.	\$869.	\$887.	\$906.	\$91.	
	56 ^{13/16"}	24"	3"	DP8CBRR5724	858.	887.	927.	942.	966.	981.	999.	1,023.	115.	
	56 ^{13/16"}	30"	3"	DP8CBRR5730	927.	952.	996.	1,014.	1,042.	1,056.	1,077.	1,101.	119.	
	56 ^{13/16"}	36"	3"	DP8CBRR5736	1,014.	1,043.	1,091.	1,110.	1,140.	1,160.	1,179.	1,207.	125.	
	56 ^{13/16"}	42"	3"	DP8CBRR5742	1,084.	1,117.	1,169.	1,190.	1,221.	1,242.	1,264.	1,294.	131.	
	56 ^{13/16"}	48"	3"	DP8CBRR5748	1,161.	1,193.	1,249.	1,273.	1,307.	1,327.	1,350.	1,386.	136.	
	56 ^{13/16"}	60"	3"	DP8CBRR5760	1,302.	1,340.	1,403.	1,429.	1,466.	1,491.	1,516.	1,553.	136.	
 64" Beltway Panels with Standard Base Raceway	64 ^{1/16"}	18"	3"	DP8CBRR6418	806.	829.	867.	888.	905.	924.	937.	961.	98.	
	64 ^{1/16"}	24"	3"	DP8CBRR6424	904.	932.	973.	994.	1,016.	1,036.	1,051.	1,079.	121.	
	64 ^{1/16"}	30"	3"	DP8CBRR6430	969.	999.	1,044.	1,059.	1,088.	1,108.	1,128.	1,157.	121.	
	64 ^{1/16"}	36"	3"	DP8CBRR6436	1,077.	1,106.	1,158.	1,178.	1,207.	1,228.	1,248.	1,279.	138.	
	64 ^{1/16"}	42"	3"	DP8CBRR6442	1,149.	1,180.	1,234.	1,255.	1,289.	1,313.	1,331.	1,365.	146.	
	64 ^{1/16"}	48"	3"	DP8CBRR6448	1,230.	1,268.	1,325.	1,349.	1,386.	1,409.	1,432.	1,468.	159.	
	64 ^{1/16"}	60"	3"	DP8CBRR6460	1,385.	1,425.	1,491.	1,518.	1,558.	1,584.	1,612.	1,653.	159.	
 78" Beltway Panels with Standard Base Raceway	78 ^{9/16"}	18"	3"	DP8CBRR7818	1,003.	1,033.	1,081.	1,097.	1,130.	1,150.	1,166.	1,194.	89.	
	78 ^{9/16"}	24"	3"	DP8CBRR7824	1,122.	1,153.	1,206.	1,226.	1,256.	1,279.	1,303.	1,331.	102.	
	78 ^{9/16"}	30"	3"	DP8CBRR7830	1,198.	1,233.	1,293.	1,316.	1,350.	1,372.	1,395.	1,432.	105.	
	78 ^{9/16"}	36"	3"	DP8CBRR7836	1,323.	1,361.	1,426.	1,451.	1,491.	1,516.	1,543.	1,580.	123.	
	78 ^{9/16"}	42"	3"	DP8CBRR7842	1,420.	1,462.	1,526.	1,554.	1,600.	1,626.	1,654.	1,692.	126.	
	78 ^{9/16"}	48"	3"	DP8CBRR7848	1,558.	1,606.	1,681.	1,713.	1,756.	1,789.	1,818.	1,863.	156.	



Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Standard Base Raceway <i>Example:</i> DP8CBRR4218 4/117/K/117/117/B191 <hr/> DP8CBB Pattern number <hr/> RR4218 <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base Raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 117 Beltway finish <hr/> B191 Fairfield light fabric	Beltway Panel with Standard Base Raceway: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Base raceway covers Beltway covers Top cap Connection hardware <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Beltway Panel with Standard Raceway Options: <p>Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.</p> <p>Monolithic Side Option: To specify monolithic on side one of panel, change "BB" in pattern number to "MB" and deduct amount in far right column.</p> <p>Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4</p> <p>Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts </p>

Beltway Panels

Tile to the Floor

42" and 50" High

description	h	w	d	pattern no.	grade								Deduct for Monolithic side 1
					10	15	20	25	30	35	40	45	
 42" Beltway Panels with Tile to the Floor	42 ³ / ₁₆ "	18"	3"	DP8CBBFR4218	\$725.	\$743.	\$779.	\$788.	\$810.	\$822.	\$835.	\$854.	\$92.
	42 ³ / ₁₆ "	24"	3"	DP8CBBFR4224	814.	836.	870.	888.	907.	926.	938.	963.	114.
	42 ³ / ₁₆ "	30"	3"	DP8CBBFR4230	886.	908.	951.	967.	992.	1,006.	1,020.	1,048.	123.
	42 ³ / ₁₆ "	36"	3"	DP8CBBFR4236	965.	990.	1,035.	1,050.	1,079.	1,092.	1,114.	1,141.	136.
	42 ³ / ₁₆ "	42"	3"	DP8CBBFR4242	1,038.	1,068.	1,116.	1,132.	1,165.	1,185.	1,201.	1,229.	142.
	42 ³ / ₁₆ "	48"	3"	DP8CBBFR4248	1,104.	1,131.	1,187.	1,205.	1,234.	1,258.	1,277.	1,308.	153.
	42 ³ / ₁₆ "	60"	3"	DP8CBBFR4260	1,242.	1,277.	1,336.	1,359.	1,393.	1,419.	1,440.	1,474.	153.
 50" Beltway Panels with Tile to the Floor	49 ¹ / ₂ "	18"	3"	DP8CBBFR5018	750.	771.	805.	819.	837.	851.	864.	886.	91.
	49 ¹ / ₂ "	24"	3"	DP8CBBFR5024	849.	870.	908.	927.	949.	966.	978.	1,003.	115.
	49 ¹ / ₂ "	30"	3"	DP8CBBFR5030	918.	939.	980.	1,000.	1,020.	1,040.	1,056.	1,083.	119.
	49 ¹ / ₂ "	36"	3"	DP8CBBFR5036	985.	1,011.	1,057.	1,077.	1,104.	1,120.	1,137.	1,167.	125.
	49 ¹ / ₂ "	42"	3"	DP8CBBFR5042	1,058.	1,089.	1,137.	1,160.	1,190.	1,208.	1,228.	1,259.	131.
	49 ¹ / ₂ "	48"	3"	DP8CBBFR5048	1,124.	1,159.	1,211.	1,230.	1,262.	1,283.	1,307.	1,338.	136.
	49 ¹ / ₂ "	60"	3"	DP8CBBFR5060	1,268.	1,304.	1,362.	1,386.	1,423.	1,447.	1,470.	1,505.	136.

Dimensions listed under h w c are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR4218 4/117/K/117/117/B191 <hr/> DP8CBB Pattern number <hr/> FR4218 <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 117 Soft Grey beltway cover finish <hr/> B191 Fairfield light fabric	Beltway Panel with Tile to the Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Base raceway side 2 Beltway with covers Tile to the floor side 1 <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Beltway Panels


Tile to the Floor

57" and 64" High

description	height	width	depth	pattern number									Deduct for Monolithic side 1
					10	15	20	25	30	35	40	45	
57" Beltway Panels with Tile to the Floor	56 ¹³ / ₁₆ "	18"	3"	DP8CBBFR5718	\$797.	\$820.	\$854.	\$867.	\$890.	\$904.	\$922.	\$941.	\$91.
	56 ¹³ / ₁₆ "	24"	3"	DP8CBBFR5724	893.	922.	962.	977.	1,001.	1,016.	1,034.	1,058.	115.
	56 ¹³ / ₁₆ "	30"	3"	DP8CBBFR5730	962.	987.	1,031.	1,049.	1,077.	1,091.	1,112.	1,136.	119.
	56 ¹³ / ₁₆ "	36"	3"	DP8CBBFR5736	1,049.	1,078.	1,126.	1,145.	1,175.	1,195.	1,214.	1,242.	125.
	56 ¹³ / ₁₆ "	42"	3"	DP8CBBFR5742	1,119.	1,152.	1,204.	1,225.	1,256.	1,277.	1,299.	1,329.	131.
	56 ¹³ / ₁₆ "	48"	3"	DP8CBBFR5748	1,196.	1,228.	1,284.	1,308.	1,342.	1,362.	1,385.	1,421.	136.
	56 ¹³ / ₁₆ "	60"	3"	DP8CBBFR5760	1,337.	1,375.	1,438.	1,464.	1,501.	1,526.	1,551.	1,588.	136.



64" Beltway Panels with Tile to the Floor	64 ¹ / ₁₆ "	18"	3"	DP8CBBFR6418	841.	864.	902.	923.	940.	959.	972.	996.	98.
	64 ¹ / ₁₆ "	24"	3"	DP8CBBFR6424	939.	967.	1,008.	1,029.	1,051.	1,071.	1,086.	1,114.	121.
	64 ¹ / ₁₆ "	30"	3"	DP8CBBFR6430	1,004.	1,034.	1,079.	1,094.	1,123.	1,143.	1,163.	1,192.	121.
	64 ¹ / ₁₆ "	36"	3"	DP8CBBFR6436	1,112.	1,141.	1,193.	1,213.	1,242.	1,263.	1,283.	1,314.	138.
	64 ¹ / ₁₆ "	42"	3"	DP8CBBFR6442	1,184.	1,215.	1,269.	1,290.	1,324.	1,348.	1,366.	1,400.	146.
	64 ¹ / ₁₆ "	48"	3"	DP8CBBFR6448	1,265.	1,303.	1,360.	1,384.	1,421.	1,444.	1,467.	1,503.	159.
	64 ¹ / ₁₆ "	60"	3"	DP8CBBFR6460	1,420.	1,460.	1,526.	1,553.	1,593.	1,619.	1,647.	1,688.	159.



Dimensions listed under h w c are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR5718 4/117/K/117/117/B191 <hr/> DP8CBB Pattern number <hr/> FR5718 <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 117 Soft Grey beltway cover finish <hr/> B191 Fairfield light fabric	Beltway Panel with Tile to the Floor: <ul style="list-style-type: none"> Panel frame Acoustic panel inserts Top cap Connection hardware Base raceway Beltway with covers Tile to the floor side 1 <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Beltway Panels

Tile to the Floor

78" High

description	height	width	depth	pattern number									Deduct for Monolithic side 1
					10	15	20	25	30	35	40	45	
78" Beltway Panels with Tile to the Floor	78 ⁹ / ₁₆ "	18"	3"	DP8CBBFR7818	\$1,038.	\$1,068.	\$1,116.	\$1,132.	\$1,165.	\$1,185.	\$1,201.	\$1,229.	\$89.
	78 ⁹ / ₁₆ "	24"	3"	DP8CBBFR7824	1,157.	1,188.	1,241.	1,261.	1,291.	1,314.	1,338.	1,366.	102.
	78 ⁹ / ₁₆ "	30"	3"	DP8CBBFR7830	1,233.	1,268.	1,328.	1,351.	1,385.	1,407.	1,430.	1,467.	105.
	78 ⁹ / ₁₆ "	36"	3"	DP8CBBFR7836	1,358.	1,396.	1,461.	1,486.	1,526.	1,551.	1,578.	1,615.	123.
	78 ⁹ / ₁₆ "	42"	3"	DP8CBBFR7842	1,455.	1,497.	1,561.	1,589.	1,635.	1,661.	1,689.	1,727.	126.
	78 ⁹ / ₁₆ "	48"	3"	DP8CBBFR7848	1,593.	1,641.	1,716.	1,748.	1,791.	1,824.	1,853.	1,898.	156.



Dimensions listed under h w c are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR7818 4/117/K/117/117/B191 <hr/> DP8CBB Pattern number <hr/> FR7818 <hr/> 4 Radius Metal top cap <hr/> 117 Soft Grey top cap finish <hr/> K Base raceway with knockouts both sides <hr/> 117 Soft Grey base raceway finish <hr/> 117 Soft Grey beltway cover finish <hr/> B191 Fairfield light fabric	Beltway Panel with Tile to the Floor: <ul style="list-style-type: none"> • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Base raceway • Beltway with covers • Tile to the floor side 1 <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others</p>	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Panel Frame Options

Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels, and may also be specified in CAP.

Dividends Horizon panel frames may be specified separately for "Build-to-Spec" applications. These include when panel inserts are only required on one side or when a beltway is required on one side and tiled inserts are on the other.

Panel frames may be specified with a standard base raceway, an open base or a tile to the floor. Panel frames ship complete with the base components, top cap and universal connection hardware. Raceway cover knockouts are standard with standard base raceway. If not required raceway covers without knockouts may can be specified.

Topway panel frames feature an integral top cable trough, and are used with D1 style stack panels.

Full View frames have no top trough, leaving a larger window opening in the top position. Full view panels frames are designed for use with windows in the top position. They are also required when stacking with D2 style stack frames or DP8 stacking screens.

Topway and full view panel frames are offered in worksurface height, 36", 42", 50", 57", 64" and 78" high.

Two Top Cap Options Available:

- Radius Metal
- Flat Metal

Top Cap Construction

Radius and flat metal top caps are made from steel.


Top Cap Attachment

Full view frames ordered with top caps include top cap attachment clips on the panel frame.


If top caps are ordered separately, top cap attachment clips ship with the top cap and must be field-installed to the panel frame.

Open Position Planner

Open Position Planner allows specifiers to design and order factory assembled panels in virtually any configuration. Open Position Planner is available only through CAP, and is not available in this price list.



Topway Panel Frame



Full View Panel Frame

Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor.


Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway


Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)
- Duplex location: 9" on center from each end


Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)



Open Base

- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper

Note: Knockouts are standard unless specified without.

Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Note: 24"H inserts are to only be used below beltways.

Monolithic and Tiled Panel Standard Configuration

Worksurface Height



- Monolithic
- One worksurface height monolithic insert

36"H Panel Frames



- Monolithic
- One 28"H monolithic insert



- Tiled
- Two 14"H tiled inserts

42"H Panel Frames



- Monolithic
- One 35"H monolithic insert



- Tiled
- One 7"H tiled insert
 - Two 14"H tiled inserts



- Beltway
- One 7"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert

50"H Panel Frames



- Monolithic
- One 42"H monolithic insert



- Tiled
- Three 14"H tiled inserts




- Beltway
- One 14"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert


57"H Panel Frames



- Monolithic
- One 49"H monolithic insert



- Tiled
- One 7"H tiled inserts
 - Three 14"H tiled inserts




- Beltway
- One 7"H tiled insert
 - One 14"H tiled insert
 - One 4"H beltway cover
 - One 24"H lower insert


64"H Panel Frames



- Monolithic
- One 56"H monolithic insert




- Tiled
- Four 14" H tiled inserts



- Beltway
- One 28"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert

78"H Panel Frames



- Monolithic
- One 70"H monolithic insert



- Tiled
- Five 14"H tiled inserts






- Beltway
- One 50"H Upper insert
 - One 4"H Beltway cover
 - One 24"H Lower insert

Note: Insert dimensions are nominal. Inserts are for one side only.

Topway and Full View Panel Frame Assemblies

Worksurface Height, 36" and 42" High

Dividends Horizon




description	h	w	d	pattern no.	list
Worksurface Height	28 1/2"	15"	3"	DP8()RRWH15	\$289.
Panel Frame Assembly	28 1/2"	18"	3"	DP8()RRWH18	289.
Standard Base Raceway	28 1/2"	24"	3"	DP8()RRWH24	296.
	28 1/2"	30"	3"	DP8()RRWH30	305.
	28 1/2"	36"	3"	DP8()RRWH36	323.
	28 1/2"	42"	3"	DP8()RRWH42	354.
	28 1/2"	48"	3"	DP8()RRWH48	354.
	28 1/2"	60"	3"	DP8()RRWH60	403.
36" High Panel Frame Assembly	35 1/8"	15"	3"	DP8()RR3615	289.
Standard Base Raceway	35 1/8"	18"	3"	DP8()RR3618	289.
	35 1/8"	24"	3"	DP8()RR3624	296.
(topway and full view shown)	35 1/8"	30"	3"	DP8()RR3630	305.
	35 1/8"	36"	3"	DP8()RR3636	323.
	35 1/8"	42"	3"	DP8()RR3642	354.
	35 1/8"	48"	3"	DP8()RR3648	354.
	35 1/8"	60"	3"	DP8()RR3660	403.
42" High Panel Frame Assembly	42 3/16"	15"	3"	DP8()RR4215	263.
Standard Base Raceway	42 3/16"	18"	3"	DP8()RR4218	263.
	42 3/16"	24"	3"	DP8()RR4224	269.
(topway and full view shown)	42 3/16"	30"	3"	DP8()RR4230	289.
	42 3/16"	36"	3"	DP8()RR4236	305.
	42 3/16"	42"	3"	DP8()RR4242	327.
	42 3/16"	48"	3"	DP8()RR4248	342.
	42 3/16"	60"	3"	DP8()RR4260	386.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly	Topway Panel Frame Assembly	Panel Frame Assembly:	Panel Frame Assembly:
1. Pattern Number	<i>Example:</i> DP8CRR6448	<ul style="list-style-type: none"> Panel frame Top cap (optional) Connection hardware Base raceway 	Option:
2. Top cap type	4/117K/117		(C) = Topway Panel Frame
3. Top cap trim finish			(V) = Full View Panel Frame
4. Raceway knockout option	DP8CRR Topway Panel Frame	Note: Worksurface Height panel frame assemblies are not available with plastic top caps.	Panel Base Options
5. Base raceway finish if required	6448 Assemblies with Base Raceway	Note: 15" wide panels are only available with standard base raceway or tile to floor.	Open Panel Base Option:
		Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	For open panel base, change 'RR' to 'LL'.
	4 Radius metal topcap		Tile to Floor Option:
	117 Soft Grey top cap finish		For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price.
	K Raceway knockouts		Top Cap Options:
	117 Soft Grey raceway finish		No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
			Base Raceway Knockout Options:
			(for RR and RF bases only)
			(K) = Knockouts on raceway side
			(N) = No knockouts

Topway and Full View Panel Frame Assemblies

50", 57" and 64" High

description	h	w	d	pattern no.	list
50" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	49 1/2"	15"	3"	DP8()RR5015	\$269.
	49 1/2"	18"	3"	DP8()RR5018	269.
	49 1/2"	24"	3"	DP8()RR5024	282.
	49 1/2"	30"	3"	DP8()RR5030	299.
	49 1/2"	36"	3"	DP8()RR5036	312.
	49 1/2"	42"	3"	DP8()RR5042	334.
	49 1/2"	48"	3"	DP8()RR5048	348.
	49 1/2"	60"	3"	DP8()RR5060	375.
57" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	56 13/16"	15"	3"	DP8()RR5715	269.
	56 13/16"	18"	3"	DP8()RR5718	269.
	56 13/16"	24"	3"	DP8()RR5724	282.
	56 13/16"	30"	3"	DP8()RR5730	294.
	56 13/16"	36"	3"	DP8()RR5736	310.
	56 13/16"	42"	3"	DP8()RR5742	326.
	56 13/16"	48"	3"	DP8()RR5748	343.
	56 13/16"	60"	3"	DP8()RR5760	359.
64" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	64 1/16"	15"	3"	DP8()RR6415	284.
	64 1/16"	18"	3"	DP8()RR6418	284.
	64 1/16"	24"	3"	DP8()RR6424	302.
	64 1/16"	30"	3"	DP8()RR6430	312.
	64 1/16"	36"	3"	DP8()RR6436	330.
	64 1/16"	42"	3"	DP8()RR6442	348.
	64 1/16"	48"	3"	DP8()RR6448	366.
	64 1/16"	60"	3"	DP8()RR6460	417.


Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Raceway knockout option 5. Base raceway finish if required	Topway Panel Frame Assembly <i>Example:</i> DP8CRR6448 4/117K/117 DP8CRR Topway Panel Frame 6448 Assembly with Base Raceway 4 Radius metal topcap 117 Soft Grey top cap finish K Raceway knockouts 117 Soft Grey raceway finish	Panel Frame Assembly: <ul style="list-style-type: none"> Panel frame Top cap (optional) Connection hardware Base raceway Note: 15" wide panels are only available with a standard base raceway or tile to floor. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Panel Frame Assembly: Option: (C) = Topway Panel Frame (V) = Full View Panel Frame Panel Base Options Open Panel Base Option: For open panel base, change 'RR' to 'LL'. Tile to Floor Option: For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (for RR and RF base only) (K) = Knockouts on raceway side (N) = No knockouts

Topway and Full View Panel Frame Assemblies 78" High

Dividends Horizon

description	h	w	d	pattern no.	list
78" High Panel Frame Assembly	78 ⁹ / ₁₆ "	15"	3"	DP8()RR7815	\$412.
Standard Base Raceway	78 ⁹ / ₁₆ "	18"	3"	DP8()RR7818	412.
	78 ⁹ / ₁₆ "	24"	3"	DP8()RR7824	432.
	78 ⁹ / ₁₆ "	30"	3"	DP8()RR7830	450.
	78 ⁹ / ₁₆ "	36"	3"	DP8()RR7836	478.
	78 ⁹ / ₁₆ "	42"	3"	DP8()RR7842	504.
	78 ⁹ / ₁₆ "	48"	3"	DP8()RR7848	523.



(topway and full view shown)

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Raceway knockout option 5. Base raceway finish if required	Topway Panel Frame Assembly <i>Example:</i> DP8CRR7848 4/117K/117 DP8CRR Topway Panel Frame 7848 Assembly with Base Raceway <hr/> 4 Radius metal topcap <hr/> 117 Soft Grey top cap finish <hr/> K Raceway knockouts <hr/> 117 Soft Grey raceway finish	Panel Frame Assembly: <ul style="list-style-type: none"> Panel frame Top cap (optional) Connection hardware Base raceway <p>Note: 15" wide panels are only available with a standard base raceway or tile to floor.</p> <p>Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.</p>	Panel Frame Assembly: Option: (C) = Topway Panel Frame (V) = Full View Panel Frame Panel Base Options Open Panel Base Option: For open panel base, change 'RR' to 'LL'. Tile to Floor Option: For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (for RR and RF base only) (K) = Knockouts on raceway side (N) = No knockouts

This page intentionally left blank

Stack Frames

Dividends Horizon stack frames provide the flexibility to increase the overall height of a standard Dividends Horizon panel.

Stack frames are available in three panel heights, 14", 21" and 28" all capable of attaching to any panel height. Maximum stacking height above the "base" standard panel is 28". This can be accomplished with one 28" high stack panel or by stacking two 14" high panels on each other.

21" Stack panel frames may be attached to 42" standard Dividends Horizon panels allowing the overall panel height to be 64" or to 57" panels for an overall height of 78".

Note: If stacking is added to 78" high panels, 36" wide returns must be used for stability.

The 28" high stack panel frame is prepunched to accept tile insert support rails to provide a tiled look if required.

Note: Stack panels must have matching height stack or full height return panels to support load bearing.

Stack Frame Options

Dividends Horizon offers two stack panel frame options, which are selected depending on customer's aesthetic and functional needs.

D1 Style Stack Frame Planning

D1 style stack frames feature a D1 style painted aluminum horizontal trim at the bottom of each stack frame. D1 style stack frames mount on top of Dividends Horizon topway panel frames only. D1 style stack panels are load bearing on the first tier only.

Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway to be able to accept the second tier stack frame.

D2 Style Stack Frame Planning

D2 style stack frames feature a D2 style black recessed horizontal reveal at the bottom of each stack frame. D2 style stack frames mount on top of Dividends Horizon DP8V full view panel frames only. D2 style stack frames are load bearing on the first or second tier, and are designed to align overhead storage components hung at 64" with overhead components hung off 64" full height panels. Components hung on stack panels at 50" or 57" will not align with components hung off 50" or 57" full height panels.

D2 style stack frames also have the option to be used with tiled or monolithic tiles on one or both side of the base/stack panel assembly. See options on panel pricing page.

Note: The single and double pane window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with single or double pane window insert kits.

Note: D2 style stack frames are not compatible with slatwall tiles.

Stack Panel Dimensions

- Widths: 18", 24", 30", 36", 42", and 48"
- Heights: 14", 21" and 28"
- Thickness: 3"

Construction

The stack panel frame is an all-welded steel construction.

- Topway: 22-gauge roll-formed steel (if applicable)
- Vertical channels: 16-gauge roll-formed steel
- Horizontal rails: 16-gauge steel tubing

Panel Trim

When stack panels are installed, the "base" standard panel's top cap is utilized by attaching to the top of the stack panel.

Panel end trim is ordered separately from the stack panel. To specify panel end trim for the end of a panel run, simply add the stack panel and base panel frame height (i.e. a 50" high base panel frame with one 14 high stack panel will require a 64" high panel end trim kit).

In a high-to-low panel-to-panel application where stack panels are used, simply deduct the panel height difference between the two panels to determine size of the high-to-low panel end trim required.

Post Trim

Post trim covers must match the overall height of the "base" standard post and stack post.

Stack Post (Same-height panels)

When two or more stack panels are connected together in a 2-way "L", 3-way "T" or a 4-way "X" condition, and all the panel heights are of the same height, a stack panel post kit may be used.

The stack post kit attaches to the top of a base universal post and is available in a 14" or 28" height and ships with connecting hardware.


Stack Post (Multi-height panels)

When stack panels are used in a high-to-low panel-to-post applications, high-to-low post trim must be ordered separately.


Note: A universal post must match the height of the tallest base standard panel being connected.

Construction

Posts are 3" square extruded aluminum construction.



Stack Frame







Stack Post (Same-Height Panels)

Stack Frames

D1 Style With External Reveal

(For Use With Topway Panels Only)




description	h	w	d	pattern no.	with topway	full view (without topway)
28" High Stack Panel Frame Only (full view shown) 	29 1/4"	18"	3"	DP2S(T/N)F 2818	\$194.	\$231.
	29 1/4"	24"	3"	DP2S(T/N)F 2824	197.	244.
	29 1/4"	30"	3"	DP2S(T/N)F 2830	214.	258.
	29 1/4"	36"	3"	DP2S(T/N)F 2836	241.	279.
	29 1/4"	42"	3"	DP2S(T/N)F 2842	257.	301.
	29 1/4"	48"	3"	DP2S(T/N)F 2848	270.	310.
21" High Stack Panel Frame Only 	21 7/8"	18"	3"	DP2STF 2118	198.	n/a
	21 7/8"	24"	3"	DP2STF 2124	212.	n/a
	21 7/8"	30"	3"	DP2STF 2130	227.	n/a
	21 7/8"	36"	3"	DP2STF 2136	250.	n/a
	21 7/8"	42"	3"	DP2STF 2142	274.	n/a
	21 7/8"	48"	3"	DP2STF 2148	286.	n/a
14" High Stack Panel, load bearing 	14"	18"	3"	DP2 STFL1418	161.	n/a
	14"	24"	3"	DP2 STFL1424	166.	n/a
	14"	30"	3"	DP2 STFL1430	194.	n/a
	14"	36"	3"	DP2 STFL1436	213.	n/a
	14"	42"	3"	DP2 STFL1442	237.	n/a
	14"	48"	3"	DP2 STFL1448	253.	n/a
14" High Stack Panel non-load bearing 	14"	18"	3"	DP2S(T/N)F 1418	161.	194.
	14"	24"	3"	DP2S(T/N)F 1424	166.	197.
	14"	30"	3"	DP2S(T/N)F 1430	194.	214.
	14"	36"	3"	DP2S(T/N)F 1436	213.	241.
	14"	42"	3"	DP2S(T/N)F 1442	237.	257.
	14"	48"	3"	DP2S(T/N)F 1448	253.	270.

Panels, Build-To-Spec

NOTE: D1 Stack Frames may be used with Topway Panels only.

Ordering Information	Order Code	Included with:	Options
Stack Panel Frame 1. Pattern Number 2. Trim Finish	Stack Panel Frame <i>Example:</i> DP2STF 1448, 113 DP1STF Pattern Number 1448 113 Dark grey paint finish Stack Panel Post <i>Example:</i> DP2ASPO 14 DP2ASPO Pattern Number 14	Stack Panel Frame Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway trough to be able to accept the second tier stack frame.	Stack Panel Frame Stack frame option: (T) = with topway (N) = without topway Note: 21" stack panel frame not available without a topway. Note: D1 Stack Frames are load bearing on first tier only.

Stack Frames
D2 Style With Recessed Reveal
(For Use With DP8 Full View Panels Only)

description	w	h	d	pattern no.	list
 14" High Dividends Stack Frame	18"	14 ⁵ / ₈ "	3"	DPS7V1418()	\$244.
	24"	14 ⁵ / ₈ "	3"	DPS7V1424()	247.
	30"	14 ⁵ / ₈ "	3"	DPS7V1430()	268.
	36"	14 ⁵ / ₈ "	3"	DPS7V1436()	292.
	42"	14 ⁵ / ₈ "	3"	DPS7V1442()	301.
	48"	14 ⁵ / ₈ "	3"	DPS7V1448()	309.
 21" High Dividends Stack Frame	18"	21 ⁷ / ₈ "	3"	DPS7V2118()	283.
	24"	21 ⁷ / ₈ "	3"	DPS7V2124()	298.
	30"	21 ⁷ / ₈ "	3"	DPS7V2130()	310.
	36"	21 ⁷ / ₈ "	3"	DPS7V2136()	332.
	42"	21 ⁷ / ₈ "	3"	DPS7V2142()	342.
	48"	21 ⁷ / ₈ "	3"	DPS7V2148()	352.
 28" High Dividends Stack Frame	18"	29 ¹ / ₄ "	3"	DPS7V2818()	269.
	24"	29 ¹ / ₄ "	3"	DPS7V2824()	285.
	30"	29 ¹ / ₄ "	3"	DPS7V2830()	302.
	36"	29 ¹ / ₄ "	3"	DPS7V2836()	327.
	42"	29 ¹ / ₄ "	3"	DPS7V2842()	342.
	48"	29 ¹ / ₄ "	3"	DPS7V2848()	353.

NOTE: D2 Stack Frames may be used with DP8 Full View Panels only.

Ordering Information	Order Code	Included with:	Options
Stack Frames: 1. Pattern Number 2. Tile Support Configuration	Stack Panel Frame Assembly <i>Example:</i> DPS7V1418TT <hr/> DPS7 Stack Panel Frame <hr/> V Full View <hr/> 14 Height <hr/> 18 Width <hr/> TT Segmented Tile Supports Both Side	Stack Panel Frame: <ul style="list-style-type: none"> Stack Frame <p>Note: Slatwall tiles, single pane and double pane window kits cannot be used with D2 stack frames.</p> <p>Note: D2 Stack Frames are load bearing on first and second tier.</p>	Tile Options/Pattern Number Suffix: <p>(TT) = Tile support located at the base of stacker to support segmented tiles on both sides of a panel.</p> <p>(TM) = Tile support located at the base of the stacker to support segmented tiles on one side and a monolithic tile on the other side of the panel.</p> <p>(MM) = Monolithic tiles on both sides of the panel.</p>

This page intentionally left blank

Monolithic Fabric Inserts

Dividends Horizon monolithic inserts are available by component for use with panel frames or wall mount tracks for "Build-to-Spec" applications. These applications include when inserts are only required on one panel side, when a different fabric is required on each panel side, or when wall mount tracks are being used.

Tile to floor option available for worksurface height, 36", 42", 50", 57", 64" and 78" panel heights.

Monolithic Fabric Insert Construction

Fabric laminated with adhesive, heat-cured to 7/16" thick tackable acoustical board.

Monolithic Fabric Insert Ratings

Noise Reduction Coefficient (NRC) rating: .70
Sound Transmission Class (STC) rating: 11

The materials in Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furniture.

Monolithic Fabric Insert Attachment



Panel inserts flex to attach to the troughs in the upper and lower horizontal panel frame supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to panel inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: If additional mid-span support for monolithic panel inserts is required, a beltway cable tray can be installed.

Note: Insert dimensions are nominal. Inserts are for one side only.

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Fabric Insert



Monolithic Fabric Insert Attachment

Monolithic Fabric Insert Configurations



Worksurface Height
• One worksurface height monolithic insert



36"H Panel Frames
• One 28"H monolithic insert



42"H Panel Frames
• One 35"H monolithic insert



50"H Panel Frames
• One 42"H monolithic insert



57"H Panel Frames
• One 49"H monolithic insert



64"H Panel Frames
• One 56"H monolithic insert







78"H Panel Frames
• One 70"H monolithic insert

Monolithic Panel Fabric Inserts

For Worksurface Height, 36", 42" and 50" High Panel Frames

Dividends Horizon

description	w*	w	h	d	pattern no.	grade									
						10	15	20	25	30	35	40	45		
Worksurface Height Individual Monolithic Fabric Insert (For worksurface height Panel Frame only) 	15"	14 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH15	\$102.	\$112.	\$117.	\$124.	\$130.	\$135.	\$141.	\$145.		
	18"	17 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH18	102.	112.	117.	124.	130.	135.	141.	145.		
	24"	23 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH24	128.	132.	145.	153.	159.	162.	167.	182.		
	30"	29 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH30	139.	145.	159.	165.	172.	182.	186.	197.		
	36"	35 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH36	152.	159.	172.	183.	194.	200.	204.	212.		
	42"	41 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH42	158.	164.	174.	184.	196.	201.	208.	218.		
	48"	47 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH48	164.	172.	186.	197.	202.	210.	221.	233.		
	60"	59 ³ / ₈ "	22 ¹ / ₂ "	3"	DP1SOWH60	187.	194.	201.	204.	212.	215.	225.	240.		
28" High Individual Tiled Fabric Insert 	15"	14 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2815	108.	112.	115.	122.	124.	131.	137.	142.		
	18"	17 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2818	108.	112.	115.	122.	124.	131.	137.	142.		
	24"	23 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2824	123.	131.	142.	148.	156.	159.	163.	174.		
	30"	29 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2830	136.	142.	156.	161.	167.	174.	180.	191.		
	36"	35 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2836	147.	156.	167.	175.	189.	196.	200.	205.		
	42"	42 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2842	153.	160.	168.	179.	190.	197.	203.	212.		
	48"	47 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2848	160.	167.	180.	191.	198.	204.	213.	227.		
	60"	59 ³ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2860	189.	194.	202.	205.	210.	215.	221.	225.		
35" High Individual Monolithic Fabric Insert (For 42"H Panel Frame) 	15"	14 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4215	118.	124.	136.	143.	149.	152.	159.	163.		
	18"	17 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4218	118.	124.	136.	143.	149.	152.	159.	163.		
	24"	23 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4224	136.	142.	153.	159.	165.	172.	175.	185.		
	30"	29 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4230	149.	159.	172.	175.	189.	192.	197.	203.		
	36"	35 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4236	165.	174.	191.	197.	199.	210.	215.	225.		
	42"	41 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4242	190.	197.	212.	221.	228.	235.	242.	252.		
	48"	47 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4248	199.	206.	227.	233.	245.	252.	258.	268.		
	60"	59 ³ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4260	206.	213.	224.	228.	234.	239.	242.	248.		
42" High Individual Monolithic Fabric Insert (For 50"H Panel Frame) 	15"	14 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5015	132.	139.	149.	153.	161.	165.	172.	179.		
	18"	17 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5018	132.	139.	149.	153.	161.	165.	172.	179.		
	24"	23 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5024	147.	156.	167.	172.	179.	189.	192.	199.		
	30"	29 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5030	165.	174.	191.	197.	203.	210.	215.	224.		
	36"	35 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5036	191.	199.	213.	221.	228.	234.	244.	253.		
	42"	41 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5042	210.	222.	240.	245.	255.	261.	269.	281.		
	48"	47 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5048	232.	245.	260.	269.	281.	288.	295.	307.		
	60"	59 ³ / ₈ "	43 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5060	266.	275.	289.	294.	302.	306.	310.	319.		

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Fabric Inserts 1. Pattern Number 2. Fabric	Monolithic Fabric Inserts <hr/> <i>Example:</i> DP1 SO6442, W351-3 DP1 Pattern Number SO6442 <hr/> W351-3 Foundation Corn Silk Fabric	Monolithic Fabric Inserts • Attachment clips Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.	Monolithic Fabric Inserts Tile to Floor Option: To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for Worksurface Heights, 36", 42", 50", 57", 64" and 78" panel heights.

Panels, Build-To-Spec

Monolithic Panel Fabric Inserts

For 57", 64" and 78" High Panel Frames

Dividends Horizon

description	w*	w	h	d	pattern no.	grade							
						10	15	20	25	30	35	40	45
49" High Individual Monolithic Fabric Insert (For 57"H Panel Frame)	15"	14 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5715	\$145.	\$149.	\$159.	\$161.	\$165.	\$167.	\$170.	\$174.
	18"	17 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5718	145.	149.	159.	161.	165.	167.	170.	174.
	24"	23 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5724	162.	165.	173.	177.	183.	187.	191.	196.
	30"	29 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5730	187.	192.	201.	203.	207.	213.	216.	223.
	36"	35 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5736	207.	215.	226.	231.	235.	241.	245.	252.
	42"	41 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5742	231.	237.	248.	253.	259.	263.	269.	276.
	48"	47 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5748	252.	258.	268.	276.	283.	289.	292.	302.
	60"	59 ³ / ₈ "	50 ¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5760	290.	299.	310.	318.	328.	335.	340.	346.
56" High Individual Monolithic Fabric Insert (For 64"H Panel Frame)	15"	14 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6415	161.	168.	185.	191.	198.	203.	206.	216.
	18"	17 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6418	161.	168.	185.	191.	198.	203.	206.	216.
	24"	23 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6424	174.	185.	200.	204.	213.	222.	225.	235.
	30"	29 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6430	204.	215.	232.	241.	250.	255.	261.	273.
	36"	35 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6436	227.	241.	258.	262.	276.	282.	290.	301.
	42"	41 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6442	248.	259.	279.	288.	299.	304.	312.	328.
	48"	47 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6448	270.	282.	303.	311.	327.	335.	342.	354.
	60"	59 ³ / ₈ "	58 ¹ / ₄ "	7 ¹ / ₁₆ "	DP1SO6460	281.	289.	303.	307.	314.	323.	330.	338.
70" High Individual Monolithic Fabric Insert (For 78"H Panel Frame)	15"	14 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7815	189.	192.	200.	203.	210.	213.	216.	224.
	18"	17 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7818	189.	192.	200.	203.	210.	213.	216.	224.
	24"	23 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7824	221.	225.	235.	241.	246.	252.	255.	261.
	30"	29 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7830	248.	255.	268.	273.	281.	286.	290.	298.
	36"	35 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7836	276.	283.	298.	303.	310.	314.	325.	333.
	42"	41 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7842	307.	317.	334.	340.	346.	354.	361.	371.
	48"	47 ³ / ₈ "	72 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO7848	338.	346.	367.	372.	383.	390.	394.	403.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts
1. Pattern Number 2. Fabric	<i>Example:</i> DP1 SO6442, W351-3 DP1 Pattern Number SO6442 W351-3 Foundation Corn Silk Fabric	<ul style="list-style-type: none"> Attachment clips Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.	Tile to Floor Option: To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for Worksurface Heights, 36", 42", 50" 57", 64" and 78" panel heights.

This page intentionally left blank

Monolithic Laminate Inserts

Dividends Horizon monolithic laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Monolithic tile sizes are for use with frames from worksurface height to 57", and widths of up to 48" in tile to raceway, open base and tile to floor applications. Monolithic laminate tiles may also be wall mounted using wall mount tracks. Monolithic laminate inserts with matching surface and edge are available in the following finishes:

- (114) Folkstone Grey
- (117) Soft Grey
- (118) Bright White
- (119) Pumice
- (124) Medium Cherry
- (125) Natural Maple
- (126) Natural Cherry

- (127) Walnut
- (139) Light Ash
- (140) Warm Ash
- (141) Whitened Ash
- (142) Grey Ash
- (143) Classic Oak
- (144) Graphite Pear
- (145) Zebra

Legacy finishes are not available.

Monolithic Laminate Insert Construction

Surface material: laminate on front and back surface

Edge material: .5mm edgeband

Core material: particle board

Thickness: 7/16 inches

Monolithic Laminate Insert Attachment


Laminate tiles are installed on one side or both sides of a panel frame, or attach to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Note: Insert dimensions are nominal. Insert configurations shown below are for one side only.

Note: Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP).

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Insert



Monolithic Laminate Insert Configurations



- Worksurface Height**
- One worksurface height monolithic insert



- 36"H Panel Frames**
- One 28"H monolithic insert



- 42"H Panel Frames**
- One 35"H monolithic insert



- 50"H Panel Frames**
- One 42"H monolithic insert






- 57"H Panel Frames**
- One 49"H monolithic insert

Monolithic Laminate Inserts

For Worksurface Height, 36" and 42" High Panel Frames

Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
Worksurface Height Individual Monolithic Laminate Insert Base Raceway or Open Base (For worksurface height panel frame only) 	15"	14 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH15	\$184.
	18"	17 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH18	195.
	24"	23 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH24	222.
	30"	29 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH30	259.
	36"	35 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH36	281.
	42"	41 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH42	335.
	48"	47 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP3L1WH48	340.
28" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 36"H Panel Frame) 	15"	14 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12815	184.
	18"	17 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12818	195.
	24"	23 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12824	222.
	30"	29 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12830	259.
	36"	35 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12836	281.
	42"	41 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12842	335.
	48"	47 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12848	340.
35" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 42"H Panel Frame) 	15"	14 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14215	221.
	18"	17 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14218	243.
	24"	23 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14224	276.
	30"	29 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14230	332.
	36"	35 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14236	449.
	42"	41 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14242	472.
	48"	47 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP3L14248	476.

Panels, Build-To-Spec




w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:
Monolithic Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Monolithic Laminate Inserts <hr/> <i>Example:</i> DP3L14224 <hr/> DP3L1 Pattern Number <hr/> 4224 <hr/> 118 Bright White Laminate <hr/> 118 Bright White Edgeband	Monolithic Laminate Inserts • Attachment clips Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

Dividends Horizon

For Worksurface Height, 36" and 42" High Panel Frames Tile To Floor

description	w*	w	d	pattern no.	List
Worksurface Height Individual Monolithic Laminate Insert Tile To Floor (For worksurface height panel frame only) 	15"	14 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH15F	\$184.
	18"	17 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH18F	195.
	24"	23 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH24F	222.
	30"	29 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH30F	259.
	36"	35 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH36F	281.
	42"	41 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH42F	335.
	48"	47 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L1WH48F	340.
36" High Individual Monolithic Laminate Insert Tile To Floor (For 36"H panel frame) 	15"	14 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12815F	184.
	18"	17 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12818F	195.
	24"	23 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12824F	222.
	30"	29 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12830F	259.
	36"	35 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12836F	281.
	42"	41 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12842F	335.
	48"	47 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L12848F	340.
42" High Individual Monolithic Laminate Insert Tile To Floor (For 42"H panel frame) 	15"	14 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14215F	224.
	18"	17 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14218F	259.
	24"	23 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14224F	290.
	30"	29 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14230F	335.
	36"	35 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14236F	453.
	42"	41 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14242F	476.
	48"	47 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP3L14248F	481.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example: **DP3L14224F**

DP3L1 Pattern Number

4224F

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

For 50" and 57" High Panel Frames

Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
42" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 50"H Panel Frame)	15"	14 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15015	\$226.
	18"	17 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15018	261.
	24"	23 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15024	292.
	30"	29 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15030	338.
	36"	35 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15036	455.
	42"	41 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15042	478.
	48"	47 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15048	483.
49" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 57"H Panel Frame)	15"	14 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15715	263.
	18"	17 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15718	284.
	24"	23 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15724	339.
	30"	29 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15730	424.
	36"	35 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15736	461.
	42"	41 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15742	563.
	48"	47 ⁵ / ₈ "	50 ¹ / ₁₆ "	7 ⁷ / ₁₆ "	DP3L15748	568.



Panels, Build-To-Spec

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

<i>Example:</i> DP3L15024	
DP3L1	Pattern Number
5024	
118	Bright White Laminate
118	Bright White Edgeband

Included with:

Monolithic Laminate Inserts



- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

For 50" and 57" High Panel Frames

Tile To Floor

description	w *	w	d	pattern no.	List
50" High Individual Monolithic Laminate Insert Tile To Floor (For 50"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15015F	\$262.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15018F	282.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15024F	337.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15030F	422.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15036F	458.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15042F	560.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15048F	565.
57" High Individual Monolithic Laminate Insert Tile To Floor (for 57"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15715F	268.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15718F	288.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15724F	342.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15730F	427.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15736F	465.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15742F	566.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15748F	570.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information

Monolithic Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Monolithic Laminate Inserts

Example: **DP3L15024F**

DP3L1 Pattern Number

5024F

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Monolithic Laminate Inserts

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

This page intentionally left blank

Tiled Inserts

Dividends Horizon tiled inserts are available by component for use with panel frames or wall mount tracks for "Build-to-Spec" applications. These applications include when inserts are only required on one panel side, when fabrics are mixed tile-to-tile or side-to-side, or when wall mount tracks are being used.

Tiled inserts are also included in "Preconfigured" tiled panel assemblies.

Tiled Insert Construction

Fabric laminated with web adhesive, heat-cured to $\frac{7}{16}$ " thick tackable acoustical board.

Tiled Insert Supports

All Dividends Horizon panel frames and wall mount tracks are pre-punched to accept tiled panel insert supports which span horizontally across the panel frame.

Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets

D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.


Tiled Insert Attachment

Tiled inserts attach to the troughs in the horizontal panel frame and tiled insert supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: When attaching cantilevers to tiled panels, they can only be hung at the 28 1/2" worksurface height.

Note: Insert dimensions are nominal. Inserts and tiled supports are for one side only.


Note: Overheads can only be attached to the uppermost position of tiled panels. On 78" H panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.




Tiled Insert Configurations




- 36"H Panels**
- Two 14"H tiled inserts
 - One tile support




- 42"H Panels**
- One 7"H tiled insert
 - Two 14"H tiled inserts
 - Two tile supports



- 50"H Panels**
- Three 14"H tiled inserts
 - Two tile supports



- 57"H Panels**
- One 7"H tiled insert
 - Three 14"H tiled inserts
 - Three tile supports




- 64"H Panels**
- Four 14"H tiled inserts
 - Three tile supports




- 78"H Panels**
- Five 14"H tiled inserts
 - Four tile supports

Tiled Insert Attachment (D1 Style)






Tiled Insert Attachment (D2 Style)



Tiled Fabric Inserts

7", 10" and 14" High

Dividends Horizon

description	w*	w	h	d	pattern no.	grade							
						10	15	20	25	30	35	40	45
7" High Individual Tiled Fabric Insert 	15"	14 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO715	\$56.	\$59.	\$64.	\$72.	\$79.	\$80.	\$83.	\$90.
	18"	17 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO718	56.	59.	64.	72.	79.	80.	83.	90.
	24"	23 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO724	59.	63.	76.	79.	81.	88.	89.	91.
	30"	29 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO730	67.	76.	83.	88.	91.	93.	97.	102.
	36"	35 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO736	79.	81.	91.	93.	97.	98.	102.	106.
	42"	41 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO742	83.	90.	96.	98.	104.	106.	108.	118.
	48"	47 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO748	90.	95.	100.	104.	108.	113.	126.	131.
	60"	59 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO760	97.	100.	105.	106.	109.	111.	113.	118.
10" High Individual Tiled Fabric Insert 	15"	14 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1015	72.	75.	80.	81.	85.	87.	88.	91.
	18"	17 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1018	72.	75.	80.	81.	85.	87.	88.	91.
	24"	23 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1024	78.	80.	86.	87.	89.	92.	94.	98.
	30"	29 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1030	80.	83.	88.	91.	93.	96.	98.	105.
	36"	35 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1036	85.	88.	93.	94.	101.	105.	116.	117.
	42"	41 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1042	88.	91.	98.	101.	113.	117.	119.	121.
	48"	47 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1048	93.	94.	107.	116.	119.	120.	122.	129.
	60"	59 ⁵ / ₈ "	10 ⁷ / ₈ "	7 ¹ / ₁₆ "	DP1SO1060	98.	103.	108.	110.	114.	116.	118.	120.
14" High Individual Tiled Fabric Insert 	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1415	87.	91.	97.	100.	103.	106.	107.	111.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1418	87.	91.	97.	100.	103.	106.	107.	111.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1424	95.	97.	105.	106.	108.	112.	116.	121.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1430	97.	102.	107.	111.	113.	118.	121.	128.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1436	103.	107.	113.	116.	123.	128.	140.	142.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1442	107.	111.	121.	123.	138.	142.	144.	148.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1448	113.	116.	132.	140.	144.	146.	149.	158.
	60"	59 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO1460	121.	126.	133.	134.	139.	140.	143.	146.

Panels, Build-To-Spec

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

- Tiled Inserts**
1. Pattern Number
2. Fabric

Order Code

Tiled Inserts
Example: **DP1 SO1436, W234-5**
DP1 Pattern Number
SO1436
W234-5 Peano Sand fabric

Included with:

- Tiled Inserts**
• Attachment clips
Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).



Options

- Tiled Inserts**
Tile to Floor Option:
To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price.
Note: Tile to floor option available for 14" and 28" High inserts.

Tiled Fabric Inserts

21" and 28" High

Dividends Horizon



description	w*	w	h	d	pattern no.	grade							
						10	15	20	25	30	35	40	45
21" High Individual Tiled Fabric Insert 	15"	14 5/8"	21 3/16"	7/16"	DP1SO2115	\$103.	\$114.	\$120.	\$124.	\$131.	\$137.	\$142.	\$148.
	18"	17 5/8"	21 3/16"	7/16"	DP1SO2118	103.	114.	120.	124.	131.	137.	142.	148.
	24"	23 5/8"	21 3/16"	7/16"	DP1SO2124	128.	134.	148.	154.	161.	165.	170.	182.
	30"	29 5/8"	21 3/16"	7/16"	DP1SO2130	139.	148.	161.	168.	173.	182.	187.	199.
	36"	35 5/8"	21 3/16"	7/16"	DP1SO2136	152.	161.	173.	183.	194.	203.	209.	214.
	42"	41 5/8"	21 3/16"	7/16"	DP1SO2142	159.	167.	175.	184.	198.	205.	212.	220.
	48"	47 5/8"	21 3/16"	7/16"	DP1SO2148	167.	173.	187.	199.	207.	213.	223.	236.
	60"	59 5/8"	21 3/16"	7/16"	DP1SO2160	182.	187.	198.	201.	208.	211.	213.	217.
28" High Individual Tiled Fabric Insert 	15"	14 5/8"	29"	7/16"	DP1SO2815	108.	112.	115.	122.	124.	131.	137.	142.
	18"	17 5/8"	29"	7/16"	DP1SO2818	108.	112.	115.	122.	124.	131.	137.	142.
	24"	23 5/8"	29"	7/16"	DP1SO2824	123.	131.	142.	148.	156.	159.	163.	174.
	30"	29 5/8"	29"	7/16"	DP1SO2830	136.	142.	156.	161.	167.	174.	180.	191.
	36"	35 5/8"	29"	7/16"	DP1SO2836	147.	156.	167.	175.	189.	196.	200.	205.
	42"	42 5/8"	29"	7/16"	DP1SO2842	153.	160.	168.	179.	190.	197.	203.	212.
	48"	47 5/8"	29"	7/16"	DP1SO2848	160.	167.	180.	191.	198.	204.	213.	227.
	60"	59 5/8"	29"	7/16"	DP1SO2860	189.	194.	202.	205.	210.	215.	221.	225.


w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included With:	Options
Tiled Inserts 1. Pattern Number 2. Fabric	Tiled Inserts <hr/> <i>Example:</i> DP1 SO1436, W234-5 <hr/> DP1 Pattern Number <hr/> SO1436 <hr/> W234-5 Peano Sand fabric	Tiled Inserts • Attachment clips Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).	Tiled Inserts Title to Floor Option: To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for 14" and 28" High inserts.

Tiled Fabric Inserts

Tile Supports

description	w*	d	pattern no.	list
 D1 Tile Support/ External Reveal	15"	5/8"	DP1SOS15	\$33.
	18"	5/8"	DP1SOS18	33.
	24"	5/8"	DP1SOS24	34.
	30"	5/8"	DP1SOS30	37.
	36"	5/8"	DP1SOS36	38.
	42"	5/8"	DP1SOS42	40.
	48"	5/8"	DP1SOS48	40.
	60"	5/8"	DP1SOS60	44.
 D2 Tile Support/ Recessed Reveal	15"		DP2SOS15	30.
	18"		DP2SOS18	30.
	24"		DP2SOS24	31.
	30"		DP2SOS30	33.
	36"		DP2SOS36	34.
	42"		DP2SOS42	37.
	48"		DP2SOS48	37.
	60"		DP2SOS60	40.
D2 Tile Support Mounting Brackets (pair)			DP2SOSC	25.



Panels, Build-To-Spec

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
D1 Tile Support / External Reveal 1. Pattern Number 2. Trim Finish	D1 Tile Support / External Reveal Supports <i>Example:</i> DP1 SOS18, 117	Note: D2 insert supports require mounting brackets.	Tiled Insert Supports
D2 Tile Support / Recessed Reveal 1. Pattern Number	DP1 Pattern Number SOS18 <hr/> 117 Soft Grey trim finish		

Tiled Laminate Inserts

Dividends Horizon tiled laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Tiled sizes are for use with frames from 36" to 78" high, and widths of up to 48" in tile to raceway, open base and tile to floor applications. Tiled laminate inserts may also be wall mounted using wall mount tracks. Tiled laminate inserts with matching surface and edge are available in the following finishes:

- (114) Folkstone Grey
- (117) Soft Grey
- (118) Bright White
- (119) Pumice
- (124) Medium Cherry
- (125) Natural Maple
- (126) Natural Cherry
- (127) Walnut
- (139) Light Ash
- (140) Warm Ash
- (141) Whitened Ash

- (142) Grey Ash
- (143) Classic Oak
- (144) Graphite Pear
- (145) Zebra

Legacy finishes are not available.

Tiled Laminate Insert Construction

- Surface material: laminate on front and back surface
- Edge material: .5 mm edgeband
- Core material: particle board
- Thickness: 7/16"

Tiled Insert Supports

All Dividends Horizon panel frames are pre-punched to accept tiled panel insert supports, which span horizontally across the panel frame. Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets


D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.

Tiled Laminate Insert Attachment


Laminate tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Tiled Laminate Insert Planning Guidelines

Insert dimensions are nominal. Insert configurations shown below are for one side only. Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP). When attaching cantilevers to tiled panels, they can only be hung at 28-1/2" worksurface height. Overheads can only be attached to the uppermost position of tiled panels. On 78"-high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.



Tiled Insert Configurations








Tiled Laminate Inserts

7", 10", 14", 21" and 28" High

Base Raceway or Open Base

Dividends Horizon

description	w*	w	h	d	pattern no.	list
 7" High Individual Tiled Laminate Insert Base Raceway or Open Base	15"	14 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10715	\$122.
	18"	17 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10718	124.
	24"	23 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10724	129.
	30"	29 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10730	133.
	36"	35 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10736	151.
	42"	41 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10742	156.
	48"	47 ⁵ / ₈ "	7 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L10748	160.
 10" High Individual Tiled Laminate Insert Base Raceway or Open Base	15"	14 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11015	126.
	18"	17 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11018	129.
	24"	23 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11024	133.
	30"	29 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11030	147.
	36"	35 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11036	167.
	42"	41 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11042	173.
	48"	47 ⁵ / ₈ "	10 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11048	179.
 14" High Individual Tiled Laminate Insert Base Raceway or Open Base	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11415	129.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11418	131.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11424	143.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11430	159.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11436	186.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11442	191.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L11448	195.
 21" High Individual Tiled Laminate Insert Base Raceway or Open Base	15"	14 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12115	141.
	18"	17 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12118	156.
	24"	23 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12124	183.
	30"	29 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12130	187.
	36"	35 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12136	268.
	42"	41 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12142	272.
	48"	47 ⁵ / ₈ "	21 ³ / ₁₆ "	7 ¹ / ₁₆ "	DP3L12148	276.
 28" High Individual Tiled Laminate Insert Base Raceway or Open Base	15"	14 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12815	184.
	18"	17 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12818	195.
	24"	23 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12824	222.
	30"	29 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12830	259.
	36"	35 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12836	281.
	42"	41 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12842	335.
	48"	47 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP3L12848	340.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Tiled Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Tiled Laminate Inserts

Example: **DP3L10724**

DP3L1 Pattern Number

0724

118 Bright White Laminate

118 Bright White Edgeband



Included with:

Tiled Laminate Inserts

- Attachment clips

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

Tiled Laminate Inserts
 14" and 28" High
 Tile To Floor

description	w*	w	d	pattern no.	list
14" High Individual Tiled Laminate Insert Tile to Floor 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11415F	\$136.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11418F	144.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11424F	158.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11430F	177.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11436F	210.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11442F	225.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11448F	228.
28" High Individual Tiled Laminate Insert Tile to Floor 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12815F	184.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12818F	195.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12824F	222.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12830F	259.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12836F	281.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12842F	335.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12848F	340.

w* = nominal width
 Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information

Tiled Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Tiled Laminate Inserts

Example: **DP3L11424F**

DP3L1 Pattern Number

1424F

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Tiled Laminate Inserts

- Attachment clips

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

This page intentionally left blank

Beltway Inserts

Dividends Horizon beltway panel inserts are available by component for use with panel frames for "build-to-spec" applications. These applications include when inserts are only required on one panel side and when fabrics or materials are mixed insert-to-insert or side-to-side.

Beltway inserts are also included in "Preconfigured" beltway panel assemblies.

Beltway Insert Construction

Fabric inserts are constructed of fabric laminated with web adhesive and heat-cured to 7/16" thick acoustical board. Laminate inserts are constructed of a particle laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish. 24" high inserts are to only be used below beltways.

Beltway Insert Attachment

Beltway panel inserts attach to the troughs in the upper and lower horizontal frame supports and beltway insert supports. Beltway top and bottom panel inserts require beltway cover and insert supports. Mounting clips attach to panel inserts and connect to vertical frame for additional support. No tools are required for insert attachment.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Cover

Beltway covers snap into the beltway supports and are constructed of painted steel. Beltway covers include knockouts with covers for duplex receptacles centered 12" from each panel end (except for 18 and 24" wide). A single communications knockout cover in the center of the beltway is included on all beltways except for 30" wide. Electrical knockouts are the same size as communications

knockouts and can be used for communications cables and data ports if terminal blocks are not installed within the beltway.

Beltway covers and insert supports can be installed on one or both sides of panels. Beltway cover and insert supports require top and bottom beltway panel inserts.

Beltway Cover Construction

Steel painted in knoll core paint colors.

Electrical


Beltways 30" and wider accept two duplex receptacles per beltway. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel


Beltway panels are available with one beltway per panel or per panel side.

Note: Insert dimensions are nominal. Inserts and beltway cover/supports are for one side only.


Beltway Insert Locations



Beltway Insert Locations




Beltway Insert Attachment



Beltway Insert Configurations


42"H Panels

- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




50"H Panels

- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



57"H Panels

- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




78"H Panels

- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert



64"H Panels




- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert



Beltway Inserts

Lower Fabric Inserts

Beltway Cover and Insert Supports

description	w*	w	h	d	pattern no.	grade							
						10	15	20	25	30	35	40	45
24" High Fabric Beltway Lower Insert, (For Beltway Panels only) 	18"	17 5/8"	25 1/2"	7/16"	DP1SO2418	\$100.	\$110.	\$115.	\$122.	\$127.	\$132.	\$138.	\$142.
	24"	23 5/8"	25 1/2"	7/16"	DP1SO2424	125.	129.	142.	150.	156.	159.	164.	178.
	30"	29 5/8"	25 1/2"	7/16"	DP1SO2430	136.	142.	156.	162.	169.	178.	182.	193.
	36"	35 5/8"	25 1/2"	7/16"	DP1SO2436	149.	156.	169.	179.	190.	196.	200.	208.
	42"	41 5/8"	25 1/2"	7/16"	DP1SO2442	155.	161.	171.	180.	192.	197.	204.	214.
	48"	47 5/8"	25 1/2"	7/16"	DP1SO2448	161.	169.	182.	193.	198.	206.	217.	228.
	60"	59 5/8"	25 1/2"	7/16"	DP1SO2460	183.	190.	197.	200.	208.	211.	221.	235.
Beltway Cover and Insert Supports 	18"			7/16"	DP8BC18K	110.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	24"			7/16"	DP8BC24K	127.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	30"			7/16"	DP8BC30K	140.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	36"			7/16"	DP8BC36K	155.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	42"			7/16"	DP8BC42K	171.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	48"			7/16"	DP8BC48K	192.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
	60"			7/16"	DP8BC60K	222.	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Beltway Knockout Replacement Cover for Electrical and Data 	Pkg of 10				DE2KC10	78.	n/a	n/a	n/a	n/a	n/a	n/a	n/a

Panels, Build-To-Spec




w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Cover/Insert Supports 1. Pattern Number 2. Beltway Cover/Trim Finish Beltway Inserts 1. Pattern Number 2. Fabric	Beltway Inserts <i>Example:</i> DP1 SO2442, W257-6 DP1 Pattern Number SO2442 W257-6 Solid Crepe Blue Pine fabric Beltway Cover/Insert Supports <i>Example:</i> DP2 BC42K, 117 DP2 Pattern Number BC42K 117 Soft Grey Beltway Cover Trim	Beltway Inserts Beltway Cover/Insert Supports <ul style="list-style-type: none"> Individual beltway cover Insert supports (top and bottom rail) Attachment hardware Beltway knockout covers Note: 24"H inserts are to only be used below beltways.	Beltway Panel Inserts Beltway Cover/Insert Supports Beltway cover has a smooth finish Title to Floor Option: To specify tile to floor, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for 24" high inserts.

Beltway Inserts

Lower Steel Inserts

Dividends Horizon

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
24" High Solid Steel Insert 	18"	17 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2418	\$111.	\$133.	\$142.	\$193.	\$225.	\$247.
	24"	23 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2424	138.	158.	172.	241.	275.	299.
	30"	29 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2430	146.	171.	186.	256.	299.	325.
	36"	35 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2436	164.	187.	208.	285.	325.	362.
	42"	41 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2442	170.	188.	209.	297.	330.	366.
	48"	47 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3SS()2448	174.	199.	218.	306.	352.	384.
24" High Perforated Steel Insert 	18"	17 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2418	167.	198.	217.	289.	339.	370.
	24"	23 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2424	206.	237.	258.	362.	414.	453.
	30"	29 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2430	222.	256.	277.	386.	453.	488.
	36"	35 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2436	248.	279.	311.	428.	488.	540.
	42"	41 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2442	255.	282.	312.	447.	495.	549.
	48"	47 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3PSB()2448	261.	298.	326.	464.	529.	576.
24" High Embossed Steel Insert 	18"	17 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2418	167.	198.	217.	289.	339.	370.
	24"	23 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2424	206.	237.	258.	362.	414.	453.
	30"	29 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2430	222.	256.	277.	386.	453.	488.
	36"	35 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2436	248.	279.	311.	428.	488.	540.
	42"	41 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2442	255.	282.	312.	447.	495.	549.
	48"	47 ⁵ / ₈ "	25 ¹ / ₂ "	⁷ / ₁₆ "	DP3ESB()2448	261.	298.	326.	464.	529.	576.

w* = nominal width
 Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information

Steel Insert

1. Pattern number
2. Paint finish

Order Code

Steel Insert

Example: **DP3SS()2418 115**

DP3 Pattern number

SS22418

115 Medium Grey paint

Included with:

Steel Insert

Note: 24"H inserts are to only be used below beltways.

Options

Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack or \$33 for a double pack.



Note: Tile to Floor option available for 24" high inserts.

Beltway Inserts

Lower Laminate Inserts

Dividends Horizon

description	w*	w	d	pattern no.	list
24" High Laminate Beltway Lower Insert Base Raceway or Open Base	15"	14 7/8"	7/16"	DP3L12415	\$153.
	18"	17 7/8"	7/16"	DP3L12418	162.
	24"	23 7/8"	7/16"	DP3L12424	181.
	30"	29 7/8"	7/16"	DP3L12430	217.
	36"	35 7/8"	7/16"	DP3L12436	265.
	42"	41 7/8"	7/16"	DP3L12442	270.
	48"	47 7/8"	7/16"	DP3L12448	274.
24" High Laminate Beltway Lower Insert Tile to Floor	15"	14 7/8"	7/16"	DP3L12415F	153.
	18"	17 7/8"	7/16"	DP3L12418F	162.
	24"	23 7/8"	7/16"	DP3L12424F	181.
	30"	29 7/8"	7/16"	DP3L12430F	217.
	36"	35 7/8"	7/16"	DP3L12436F	265.
	42"	41 7/8"	7/16"	DP3L12442F	270.
	48"	47 7/8"	7/16"	DP3L12448F	274.



Panels, Build-To-Spec

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Beltway Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Beltway Laminate Inserts

Example: **DP3L12436**

DP3L1 Pattern Number

2436

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Beltway Laminate Inserts

- Attachment clips

Note: 24"H inserts are to only be used below beltways.

High Acoustic Core Inserts and Sound Transmission Septum Inserts

Optional high acoustic core inserts or sound transmission septum inserts combine with tiles to provide enhanced acoustics.

High acoustic core inserts can be installed in monolithic and tiled panels but must be field-cut to be installed in beltway panels.

Sound transmission septum inserts can be installed in monolithic and tiled panels and single-sided beltway panels.

High Acoustic Core Insert Construction

1 1/2" thick, three-ply insert with an inner septum and outer fiberglass with polywrap.

Sound Transmission Septum Insert Construction

1/16" thick black asphalt paper.

Core Insert Attachment

High acoustic core inserts and sound transmission septum inserts are inserted into the center of the panel frame. Core inserts are sized to fit into the panel frame without the use of fasteners. In-field installation is required.

High Acoustic Core Insert Panel Ratings

Noise Reduction Coefficient (NRC) rating: .80 when combined with tiles.

Sound Transmission Class (STC) rating: 26 when combined with tiles.

Sound Transmission Septum Insert Panel Ratings

Noise Reduction Coefficient (NRC) rating: .60 when combined with tiles.

Sound Transmission Class (STC) rating: 17 when combined with tiles.

Available Sizes


High acoustic core inserts and sound transmission septum inserts are available for all widths of 50", 64" and 78" high monolithic and tiled panels.

Beltway electrical panels require the high acoustic core inserts or the sound transmission septum inserts to be field-cut prior to installation.


Packaging

High acoustic cores and sound transmission septum inserts are shipped in separate containers.


High Acoustic Core Insert



High Acoustic Core Insert Construction






Sound Transmission Septum Insert Construction



High Acoustic Core Inserts

Sound Transmission Septum Inserts

description	type	pattern no.	High Acoustic Core Insert	Sound Transmission Septum Insert
 50" High	For 18" panel width	DP1() 5018	\$120.	\$48.
	For 24" panel width	DP1() 5024	132.	48.
	For 30" panel width	DP1() 5030	140.	48.
	For 36" panel width	DP1() 5036	152.	75.
	For 42" panel width	DP1() 5042	165.	75.
	For 48" panel width	DP1() 5048	190.	75.
 64" High	For 18" panel width	DP1() 6418	140.	48.
	For 24" panel width	DP1() 6424	152.	48.
	For 30" panel width	DP1() 6430	160.	48.
	For 36" panel width	DP1() 6436	187.	75.
	For 42" panel width	DP1() 6442	215.	75.
	For 48" panel width	DP1() 6448	235.	75.
 78" High	For 18" panel width	DP1() 7818	162.	80.
	For 24" panel width	DP1() 7824	185.	80.
	For 30" panel width	DP1() 7830	208.	80.
	For 36" panel width	DP1() 7836	225.	91.
	For 42" panel width	DP1() 7842	240.	91.
	For 48" panel width	DP1() 7848	290.	91.

Panels, Build-To-Spec

Ordering Information

Inserts

1. Pattern Number

Order Code

Inserts

Example: **DP1(AC) 6448**
DP1(AC) Pattern Number
6448

Included with:

Inserts

- High Acoustic Core Insert
- Sound Transmission Septum Insert

Options

Inserts

Insert the appropriate letters for insert required within the parentheses of the pattern number.
(AC) = High Acoustic
(ST) = Sound Transmission

Single Pane Window Insert Kit

Single pane windows are available for three applications:

- Top position, with topway - for use in the top position of panels and D1 style stack frame with a topway trough.
- Top position, full view - for use in the top position of full view panels and D1 style stack frames (use with D2 tile supports)
- Middle position - for use in the middle positions of topway and full view panels.

Note: Window insert kits may not be specified in the bottom position of panels. Specify D2 tile supports and insert support mounting brackets separately.

Note: Single window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with top position single or double pane window insert kits.

Construction

Single pane windows are shipped in two components - an "open" frame, and a "window" frame. Each frame snaps onto a Dividends Horizon panel frame. Both frames are constructed of extruded, then robotically-welded aluminum. Single pane windows have 1/4" tempered glass inserts with PVC glazing strip.

Single Pane Window Insert Kit

Available Sizes


- Heights: 14", 21" and 28"
- Widths: 24", 30", 36", 42", and 48"

Attachment

Window insert kits are installed on each side of a panel frame. Glazed insert kits consist of two inserts. Individual tile support rails must be ordered separately.

Note: Window types are aesthetically different, and are not designed to be mixed together within a single installation.




Single Pane Window Insert Kit



Window Insert Kits

Single Pane Windows

Dividends Horizon

description	h	w	pattern no.	P1	P2	P3
 Window, top position with topway	14"	24"	D2P1()T1424	\$464.	\$492.	\$514.
	14"	30"	D2P1()T1430	540.	564.	593.
	14"	36"	D2P1()T1436	566.	595.	624.
	14"	42"	D2P1()T1442	673.	706.	741.
	14"	48"	D2P1()T1448	687.	723.	759.
	21"	24"	D2P1()T2124	505.	530.	554.
	21"	30"	D2P1()T2130	595.	625.	656.
	21"	36"	D2P1()T2136	640.	673.	703.
	21"	42"	D2P1()T2142	764.	804.	839.
	21"	48"	D2P1()T2148	851.	896.	938.
	28"	24"	D2P1()T2824	554.	583.	614.
	28"	30"	D2P1()T2830	656.	687.	722.
	28"	36"	D2P1()T2836	703.	741.	775.
	28"	42"	D2P1()T2842	839.	884.	927.
28"	48"	D2P1()T2848	938.	984.	1,031.	
 Window, top position full view	14"	24"	D2P1()VT1424	432.	458.	478.
	14"	30"	D2P1()VT1430	503.	526.	552.
	14"	36"	D2P1()VT1436	566.	595.	624.
	14"	42"	D2P1()VT1442	673.	706.	741.
	14"	48"	D2P1()VT1448	687.	723.	759.
	21"	24"	D2P1()VT2124	505.	530.	554.
	21"	30"	D2P1()VT2130	595.	625.	656.
	21"	36"	D2P1()VT2136	640.	673.	703.
	21"	42"	D2P1()VT2142	764.	804.	839.
	21"	48"	D2P1()VT2148	851.	896.	938.
	28"	24"	D2P1()VT2824	554.	583.	614.
	28"	30"	D2P1()VT2830	656.	687.	722.
	28"	36"	D2P1()VT2836	703.	741.	775.
	28"	42"	D2P1()VT2842	839.	884.	927.
28"	48"	D2P1()VT2848	938.	984.	1,031.	
 Window, middle position	14"	24"	D2P1()VL1424	432.	458.	478.
	14"	30"	D2P1()VL1430	503.	526.	552.
	14"	36"	D2P1()VL1436	566.	595.	624.
	14"	42"	D2P1()VL1442	673.	706.	741.
	14"	48"	D2P1()VL1448	687.	723.	759.

Panels, Build-To-Spec

Ordering Information

Single Pane Window Kit

1. Pattern number
2. Paint finish

Order Code

Single Pane Window Kit

Example:	D2P1GT1448, 117
D2P1	Single Pane Window w/
GT1448	Clear Glass
117	Soft Grey Paint

Included with:

Single Pane Window Kit

Note: The single pane window insert kit is not compatible with the D2 style stack frame. Use D1 style stack frames with single pane window insert kits.

Note: Use top position window insert kits when using with D1 style stack frames.

Options

Single Pane Window Kit

Note: Single Pane Window Kit must be used with D2 Style Supports

Glass Options:
(G) = Clear Tempered Glass
(F) = Powder Glass

Markerboard Tiles

Markerboard tiles may be attached to any Dividends Horizon universal panel frame or wall mount tracks.

Construction

Markerboard tiles are constructed of 20 gauge steel, powder coated with paint suitable for use with standard dry erase markers.

Available Sizes

- Heights: 7", 10", 14", 21", 24" and 28"
- Widths: 18", 24", 30", 36", 42", and 48"

Attachment

Markerboard tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.



Markerboard Trays

Markerboard trays are positioned directly below markerboard tiles, and are designed to hold dry erase markers and erasers. Trays mount to the outside of tile frames, and replace a D1 or D2 tile support.

Markerboard trays may not be positioned directly above or below a beltway raceway and may not be used with stack frames.

Note: Markerboard tiles can use D1 or D2 tile supports. Legacy D1 and D2 Markerboard tiles use D1 tile supports only.

Markerboard Tile



DP8 Stack Frame/Steel Tile Planning Note

When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP8 SSTK (\$10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

Proper use and regular cleaning of your markerboard surface is essential for preventing permanent stains and/or ghosting typically associated with dry erase markers. By following the care and use instructions below, you will minimize the possibility of permanent stains and ghosting.

Initial Cleaning of Markerboards Before First Use:

- Using a clean, dry cloth and a nonabrasive cleaner, gently clean the entire board to loosen any residue
- Using a dry cloth, wipe the entire surface to remove all dirt and residue from the prior step
- Rinse the entire board with clean water
- Using a dry cloth, wipe dry the entire surface

Daily Use, Care and Maintenance:





- *Use the proper markers.* All dry erase markers will write legibly on the marker board surface, but not all will erase properly due to their composition. Do not use low odor dry erase markers or permanent (indelible) markers. Use of these markers will lead to staining or ghosting, even with regular cleaning.
- *Clean the markerboard regularly.* It is recommended that markerboards be erased daily using an eraser designated for use with dry erase markers. If the markerboard is used daily, we recommend that a complete cleaning is performed at least 2-3 times a week using EXPO® whiteboard cleaner.
- *Remove ghosting.* Using EXPO® whiteboard cleaner and a paper towel, wipe the entire surface and let dry. Mix Joy® dishwashing detergent with warm water and apply to the board using a paper towel, then wipe dry with a clean cloth. Repeat as necessary.
- *Remove permanent marker.* Using a dry erase marker, write on top of the permanent marker, erase with a dry eraser, and then clean with EXPO® whiteboard cleaner.

Note: Do not use other painted tiles as markerboards or product damage will occur and the tile warranty will be voided.

Markerboard Tiles

7", 10", 14" and 21" High

Dividends Horizon

description	h	w	pattern no.	1 pack	6 pack
D3 7" Markerboard tile 	7"	18"	DP3MB()718	\$83.	\$367.
	7"	24"	DP3MB()724	87.	389.
	7"	30"	DP3MB()730	94.	430.
	7"	36"	DP3MB()736	114.	502.
	7"	42"	DP3MB()742	123.	537.
	7"	48"	DP3MB()748	128.	568.
D3 10" Markerboard tile 	10"	18"	DP3MB()1018	114.	511.
	10"	24"	DP3MB()1024	123.	545.
	10"	30"	DP3MB()1030	124.	568.
	10"	36"	DP3MB()1036	139.	603.
	10"	42"	DP3MB()1042	143.	638.
	10"	48"	DP3MB()1048	152.	681.
D3 14" Markerboard tile 	14"	18"	DP3MB()1418	114.	511.
	14"	24"	DP3MB()1424	123.	545.
	14"	30"	DP3MB()1430	124.	568.
	14"	36"	DP3MB()1436	139.	603.
	14"	42"	DP3MB()1442	143.	638.
	14"	48"	DP3MB()1448	152.	681.
D3 21" Markerboard tile 	21"	18"	DP3MB()2118	147.	763.
	21"	24"	DP3MB()2124	183.	955.
	21"	30"	DP3MB()2130	197.	1,026.
	21"	36"	DP3MB()2136	221.	1,139.
	21"	42"	DP3MB()2142	226.	1,181.
	21"	48"	DP3MB()2148	232.	1,229.

Ordering Information

Markerboard Tiles
1. Pattern Number

Order Code

Markerboard Tiles
Example: **DP3MB(1) 1436**
DP3MB(1) Pattern Number
1436

Included with:




Markerboard Tiles

Options

Markerboard Tiles
(1) = 1 Pack
(6) = 6 Pack

Markerboard Tiles

24" and 28" High and Markerboard Tray

description	height	width	pattern number	1 pack	2 pack	P1	P2	P3
 D3 24" Markerboard tile	24"	18"	DP3MB()2418	\$147.	\$254.			
	24"	24"	DP3MB()2424	183.	317.			
	24"	30"	DP3MB()2430	197.	341.			
	24"	36"	DP3MB()2436	221.	380.			
	24"	42"	DP3MB()2442	226.	394.			
	24"	48"	DP3MB()2448	232.	410.			
 D3 28" Markerboard tile	28"	18"	DP3MB()2818	160.	277.			
	28"	24"	DP3MB()2824	185.	323.			
	28"	30"	DP3MB()2830	198.	347.			
	28"	36"	DP3MB()2836	221.	387.			
	28"	42"	DP3MB()2842	226.	398.			
	28"	48"	DP3MB()2848	232.	412.			
 Markerboard Tray		24"	DP1MBT24			128.	135.	140.
		30"	DP1MBT30			131.	137.	143.
		36"	DP1MBT36			133.	140.	145.
		42"	DP1MBT42			136.	142.	148.
		48"	DP1MBT48			139.	144.	152.

Panels, Build-To-Spec

Ordering Information

Markerboard Tiles

1. Pattern Number

Markerboard Tray

1. Pattern Number
2. Paint Finish

Order Code

Markerboard Tiles

Example: **DP3MB(1) 1436**

DP3MB(1) Pattern Number
1436

Included with:

Markerboard Tiles

Options

Markerboard Tiles

(1) = 1 Pack
(2) = 2 Pack

Solid Steel Inserts

Solid steel tiles are painted solid steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Steel tiles are made of 20-gauge formed steel that is painted in any Dividends Horizon paint color.

Embossed Steel Inserts

Embossed steel tiles are painted embossed steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Embossed steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color

Perforated Steel Inserts

Perforated steel tiles are painted perforated steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Perforated steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color.

Available Sizes

- Height: 7", 10", 14", 21", 24" and 28"
- Widths: 15", 18", 24", 30", 36", 42" and 48"

Attachment

Steel tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.


One-sided Attachment

For applications with perforated inserts on one side of panel only, specify sound transmission septums.



Tile-to-Floor Option

14" and 28" high steel tiles are available to be specified Tile-to-Floor.

Solid Steel Tile Insert



Perforated and Embossed Steel Tile Inserts







DP8 Stack Frame/Steel Tile Planning Note

When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP8 SSTK (\$10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

Steel Insert Kits

7", 10", 14" and 21" High Solid Steel Insert

Dividends Horizon

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Solid Steel Insert 	15"	14 5/8"	7 3/16"	7/16"	DP3SS()715	\$63.	\$75.	\$87.	\$281.	\$325.	\$388.
	18"	17 5/8"	7 3/16"	7/16"	DP3SS()718	63.	75.	87.	281.	325.	388.
	24"	23 5/8"	7 3/16"	7/16"	DP3SS()724	67.	83.	89.	298.	369.	402.
	30"	29 5/8"	7 3/16"	7/16"	DP3SS()730	77.	91.	101.	334.	411.	446.
	36"	35 5/8"	7 3/16"	7/16"	DP3SS()736	88.	105.	111.	388.	446.	481.
	42"	41 5/8"	7 3/16"	7/16"	DP3SS()742	93.	109.	117.	411.	473.	514.
	48"	47 5/8"	7 3/16"	7/16"	DP3SS()748	98.	112.	119.	437.	501.	542.
D3 10" High Solid Steel Insert 	15"	14 5/8"	10 3/16"	7/16"	DP3SS()1015	88.	102.	106.	394.	446.	466.
	18"	17 5/8"	10 3/16"	7/16"	DP3SS()1018	88.	102.	106.	394.	446.	466.
	24"	23 5/8"	10 3/16"	7/16"	DP3SS()1024	93.	108.	111.	422.	481.	501.
	30"	29 5/8"	10 3/16"	7/16"	DP3SS()1030	94.	111.	115.	437.	507.	525.
	36"	35 5/8"	10 3/16"	7/16"	DP3SS()1036	106.	119.	128.	466.	534.	560.
	42"	41 5/8"	10 3/16"	7/16"	DP3SS()1042	110.	124.	139.	490.	560.	614.
	48"	47 5/8"	10 3/16"	7/16"	DP3SS()1048	115.	140.	144.	525.	630.	657.
D3 14" High Solid Steel Insert 	15"	14 5/8"	14 3/16"	7/16"	DP3SS()1415	88.	102.	106.	394.	446.	466.
	18"	17 5/8"	14 3/16"	7/16"	DP3SS()1418	88.	102.	106.	394.	446.	466.
	24"	23 5/8"	14 3/16"	7/16"	DP3SS()1424	93.	108.	111.	422.	481.	501.
	30"	29 5/8"	14 3/16"	7/16"	DP3SS()1430	94.	111.	115.	437.	507.	525.
	36"	35 5/8"	14 3/16"	7/16"	DP3SS()1436	106.	119.	128.	466.	534.	560.
	42"	41 5/8"	14 3/16"	7/16"	DP3SS()1442	110.	124.	139.	490.	560.	614.
	48"	47 5/8"	14 3/16"	7/16"	DP3SS()1448	115.	140.	144.	525.	630.	657.
D3 21" High Solid Steel Insert 	15	14 5/8"	21 3/16"	7/16"	DP3SS()2115	113.	136.	145.	588.	693.	754.
	18"	17 5/8"	21 3/16"	7/16"	DP3SS()2118	113.	136.	145.	588.	693.	754.
	24"	23 5/8"	21 3/16"	7/16"	DP3SS()2124	141.	161.	175.	735.	838.	919.
	30"	29 5/8"	21 3/16"	7/16"	DP3SS()2130	149.	174.	190.	788.	919.	990.
	36"	35 5/8"	21 3/16"	7/16"	DP3SS()2136	167.	191.	212.	875.	990.	1,105.
	42"	41 5/8"	21 3/16"	7/16"	DP3SS()2142	173.	192.	213.	911.	1,008.	1,121.
	48"	47 5/8"	21 3/16"	7/16"	DP3SS()2148	177.	203.	222.	946.	1,076.	1,173.

Panels, Build-To-Spec

Ordering Information

Solid Steel Insert

1. Pattern number
2. Paint finish

Order Code

Solid Steel Insert

Example: **DP3SS()1418 115**

DP3 Pattern number

SS21418

115 Medium Grey paint

Included with:

Solid Steel Insert


Options


Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Worksurface Height and 28" High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Solid Steel Insert 	15"	14 5/8"	22 1/2"	7/16"	DP3SS()WH15	\$113.	\$136.	\$145.	\$197.	\$231.	\$252.
	18"	17 5/8"	22 1/2"	7/16"	DP3SS()WH18	113.	136.	145.	197.	231.	252.
	24"	23 5/8"	22 1/2"	7/16"	DP3SS()WH24	141.	161.	175.	246.	281.	305.
	30"	29 5/8"	22 1/2"	7/16"	DP3SS()WH30	149.	174.	190.	261.	305.	332.
	36"	35 5/8"	22 1/2"	7/16"	DP3SS()WH36	167.	191.	212.	291.	332.	369.
	42"	41 5/8"	22 1/2"	7/16"	DP3SS()WH42	173.	192.	213.	303.	337.	373.
	48"	47 5/8"	22 1/2"	7/16"	DP3SS()WH48	177.	203.	222.	312.	359.	392.

D3 28" High Solid Steel Insert 	15"	14 5/8"	29"	7/16"	DP3SS()2815	122.	122.	144.	213.	233.	252.
	18"	17 5/8"	29"	7/16"	DP3SS()2818	122.	122.	144.	213.	233.	252.
	24"	23 5/8"	29"	7/16"	DP3SS()2824	142.	142.	175.	248.	283.	307.
	30"	29 5/8"	29"	7/16"	DP3SS()2830	152.	174.	191.	268.	307.	337.
	36"	35 5/8"	29"	7/16"	DP3SS()2836	167.	191.	212.	295.	337.	373.
	42"	41 5/8"	29"	7/16"	DP3SS()2842	173.	194.	212.	305.	339.	377.
	48"	47 5/8"	29"	7/16"	DP3SS()2848	177.	203.	223.	317.	361.	394.

Ordering Information

Solid Steel Insert

1. Pattern number
2. Paint finish

Order Code

Solid Steel Insert

Example: **DP3SS()2118 115**

DP3 Pattern number

SS22118

115 Medium Grey paint

Included with:

Solid Steel Insert

Options





Solid Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

7", 10", 14" and 21" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()715	\$94.	\$110.	\$133.	\$422.	\$490.	\$577.
	18"	17 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()718	94.	110.	133.	422.	490.	577.
	24"	23 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()724	102.	124.	137.	446.	551.	604.
	30"	29 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()730	112.	140.	148.	501.	623.	674.
	36"	35 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()736	136.	157.	166.	577.	674.	726.
	42"	41 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()742	143.	162.	177.	623.	709.	778.
	48"	47 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()748	147.	168.	183.	657.	754.	812.
D3 10" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1015	136.	152.	159.	595.	674.	700.
	18"	17 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1018	136.	152.	159.	595.	674.	700.
	24"	23 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1024	143.	161.	166.	630.	726.	754.
	30"	29 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1030	144.	166.	174.	657.	762.	788.
	36"	35 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1036	159.	183.	192.	700.	805.	838.
	42"	41 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1042	165.	190.	205.	735.	838.	919.
	48"	47 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1048	174.	207.	220.	788.	946.	990.
D3 14" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1415	136.	152.	159.	595.	674.	700.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1418	136.	152.	159.	595.	674.	700.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1424	143.	161.	166.	630.	726.	754.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1430	144.	166.	174.	657.	762.	788.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1436	159.	183.	192.	700.	805.	838.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1442	165.	190.	205.	735.	838.	919.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1448	174.	207.	220.	788.	946.	990.
D3 21" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2115	170.	202.	221.	884.	1,039.	1,131.
	18"	17 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2118	170.	202.	221.	884.	1,039.	1,131.
	24"	23 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2124	210.	242.	263.	1,105.	1,261.	1,382.
	30"	29 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2130	226.	261.	283.	1,180.	1,382.	1,490.
	36"	35 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2136	253.	285.	317.	1,312.	1,490.	1,655.
	42"	41 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2142	260.	288.	318.	1,368.	1,514.	1,681.
	48"	47 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2148	266.	304.	333.	1,419.	1,620.	1,761.

Panels, Build-To-Spec

Ordering Information

Perforated Steel Insert

1. Pattern number
2. Paint finish

Order Code

Perforated Steel Insert

Example: **DP3PBS21430 117**

DP3 Pattern number

PSB21430

117 Soft Grey paint

Included with:

Perforated Steel Insert

Options

Perforated Steel Insert




Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Tile to Floor Option not available on DP2 perforated steel tile insert.

14", Worksurface Height and 28" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Perforated Steel Insert 	15"	14 5/8"	22 1/2"	7/16"	DP3PSB()WH15	\$170.	\$202.	\$221.	\$295.	\$346.	\$377.
	18"	17 5/8"	22 1/2"	7/16"	DP3PSB()WH18	170.	202.	221.	295.	346.	377.
	24"	23 5/8"	22 1/2"	7/16"	DP3PSB()WH24	210.	242.	263.	369.	422.	462.
	30"	29 5/8"	22 1/2"	7/16"	DP3PSB()WH30	226.	261.	283.	394.	462.	498.
	36"	35 5/8"	22 1/2"	7/16"	DP3PSB()WH36	253.	285.	317.	437.	498.	551.
	42"	41 5/8"	22 1/2"	7/16"	DP3PSB()WH42	260.	288.	318.	456.	505.	560.
	48"	47 5/8"	22 1/2"	7/16"	DP3PSB()WH48	266.	304.	333.	473.	540.	588.
D3 28" High Perforated Steel Insert 	15"	14 5/8"	29"	7/16"	DP3PSB()2815	185.	185.	220.	319.	351.	377.
	18"	17 5/8"	29"	7/16"	DP3PSB()2818	185.	185.	220.	319.	351.	377.
	24"	24 5/8"	29"	7/16"	DP3PSB()2824	213.	213.	263.	373.	426.	466.
	30"	29 5/8"	29"	7/16"	DP3PSB()2830	227.	261.	285.	402.	466.	505.
	36"	35 5/8"	29"	7/16"	DP3PSB()2836	253.	285.	317.	444.	505.	560.
	42"	41 5/8"	29"	7/16"	DP3PSB()2842	260.	289.	317.	462.	507.	566.
	48"	47 5/8"	29"	7/16"	DP3PSB()2848	266.	304.	334.	478.	542.	592.
D2 14" High Perforated Steel Insert 	18"	17 5/8"	14 3/16"	7/16"	DP2PS()1418	117.	131.	137.	221.	240.	250.
	24"	23 5/8"	14 3/16"	7/16"	DP2PS()1424	157.	168.	180.	292.	325.	339.
	30"	29 5/8"	14 3/16"	7/16"	DP2PS()1430	159.	173.	183.	299.	328.	342.
	36"	35 5/8"	14 3/16"	7/16"	DP2PS()1436	161.	175.	187.	302.	333.	344.
	42"	41 5/8"	14 3/16"	7/16"	DP2PS()1442	161.	179.	187.	305.	338.	352.
	48"	47 5/8"	14 3/16"	7/16"	DP2PS()1448	165.	183.	191.	310.	342.	358.

Ordering Information

Perforated Steel Insert

1. Pattern number
2. Paint finish

Order Code

Perforated Steel Insert

Example: **DP3PSB21430 117**

DP3 Pattern number

PSB21430

117 Soft Grey paint

Included with:

Perforated Steel Insert

Options

Perforated Steel Insert





Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Tile to Floor Option not available on DP2 perforated steel tile insert.

7", 10", 14" and 21" High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
 <p>D3 7" High Embossed Steel Insert</p>	15"	14 5/8"	7 3/16"	7/16"	DP3ESB()715	\$94.	\$110.	\$133.	\$422.	\$490.	\$577.
	18"	17 5/8"	7 3/16"	7/16"	DP3ESB()718	94.	110.	133.	422.	490.	577.
	24"	23 5/8"	7 3/16"	7/16"	DP3ESB()724	102.	124.	137.	446.	551.	604.
	30"	30 5/8"	7 3/16"	7/16"	DP3ESB()730	112.	140.	148.	501.	623.	674.
	36"	35 5/8"	7 3/16"	7/16"	DP3ESB()736	136.	157.	166.	577.	674.	726.
	42"	41 5/8"	7 3/16"	7/16"	DP3ESB()742	143.	162.	177.	623.	709.	778.
	48"	47 5/8"	7 3/16"	7/16"	DP3ESB()748	147.	168.	183.	657.	754.	812.
 <p>D3 10" High Embossed Steel Insert</p>	15"	14 5/8"	10 3/16"	7/16"	DP3ESB()1015	136.	152.	159.	595.	674.	700.
	18"	17 5/8"	10 3/16"	7/16"	DP3ESB()1018	136.	152.	159.	595.	674.	700.
	24"	23 5/8"	10 3/16"	7/16"	DP3ESB()1024	143.	161.	166.	630.	726.	754.
	30"	29 5/8"	10 3/16"	7/16"	DP3ESB()1030	144.	166.	174.	657.	762.	788.
	36"	35 5/8"	10 3/16"	7/16"	DP3ESB()1036	159.	183.	192.	700.	805.	838.
	42"	41 5/8"	10 3/16"	7/16"	DP3ESB()1042	165.	190.	205.	735.	838.	919.
	48"	47 5/8"	10 3/16"	7/16"	DP3ESB()1048	174.	207.	220.	788.	946.	990.
 <p>D3 14" High Embossed Steel Insert</p>	15"	14 5/8"	14 3/16"	7/16"	DP3ESB()1415	136.	152.	159.	595.	674.	700.
	18"	17 5/8"	14 3/16"	7/16"	DP3ESB()1418	136.	152.	159.	595.	674.	700.
	24"	23 5/8"	14 3/16"	7/16"	DP3ESB()1424	143.	161.	166.	630.	726.	754.
	30"	29 5/8"	14 3/16"	7/16"	DP3ESB()1430	144.	166.	174.	657.	762.	788.
	36"	35 5/8"	14 3/16"	7/16"	DP3ESB()1436	159.	183.	192.	700.	805.	838.
	42"	41 5/8"	14 3/16"	7/16"	DP3ESB()1442	165.	190.	205.	735.	838.	919.
	48"	47 5/8"	14 3/16"	7/16"	DP3ESB()1448	174.	207.	220.	788.	946.	990.
 <p>D3 21" Embossed Steel Insert</p>	15"	14 5/8"	21"	7/16"	DP3ESB()2115	170.	202.	221.	884.	1,039.	1,131.
	18"	17 5/8"	21"	7/16"	DP3ESB()2118	170.	202.	221.	884.	1,039.	1,131.
	24"	23 5/8"	21"	7/16"	DP3ESB()2124	210.	242.	263.	1,105.	1,261.	1,382.
	30"	29 5/8"	21"	7/16"	DP3ESB()2130	226.	261.	283.	1,180.	1,382.	1,490.
	36"	35 5/8"	21"	7/16"	DP3ESB()2136	253.	285.	317.	1,312.	1,490.	1,655.
	42"	41 5/8"	21"	7/16"	DP3ESB()2142	260.	288.	318.	1,368.	1,514.	1,681.
	48"	47 5/8"	21"	7/16"	DP3ESB()2148	266.	304.	333.	1,419.	1,620.	1,761.

Panels, Build-To-Spec

Ordering Information

Embossed Steel Insert

1. Pattern number
2. Paint finish

Order Code

Embossed Steel Insert

Example: **DP3ESB21430 117**

DP3 Pattern number

ESB21430

117 Soft Grey paint

Included with:

Embossed Steel Insert

Options


Embossed Steel Insert


Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Worksurface Height and 28" High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
 D3 Worksurface Height Embossed Steel Insert	15"	14 5/8"	22 1/2"	7/16"	DP3ESB()WH15	\$170.	\$202.	\$221.	\$295.	\$346.	\$377.
	18"	17 5/8"	22 1/2"	7/16"	DP3ESB()WH18	170.	202.	221.	295.	346.	377.
	24"	23 5/8"	22 1/2"	7/16"	DP3ESB()WH24	210.	242.	263.	369.	422.	462.
	30"	39 5/8"	22 1/2"	7/16"	DP3ESB()WH30	226.	261.	283.	394.	462.	498.
	36"	35 5/8"	22 1/2"	7/16"	DP3ESB()WH36	253.	285.	317.	437.	498.	551.
	42"	41 5/8"	22 1/2"	7/16"	DP3ESB()WH42	260.	288.	318.	456.	505.	560.
	48"	47 5/8"	22 1/2"	7/16"	DP3ESB()WH48	266.	304.	333.	473.	540.	588.

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
 D3 28" High Embossed Steel Insert	15"	14 5/8"	29"	7/16"	DP3ESB()2815	185.	185.	220.	319.	351.	377.
	18"	17 5/8"	29"	7/16"	DP3ESB()2818	185.	185.	220.	319.	351.	377.
	24"	23 5/8"	29"	7/16"	DP3ESB()2824	213.	213.	263.	373.	426.	466.
	30"	29 5/8"	29"	7/16"	DP3ESB()2830	227.	261.	285.	402.	466.	505.
	36"	35 5/8"	29"	7/16"	DP3ESB()2836	253.	285.	317.	444.	505.	560.
	42"	41 5/8"	29"	7/16"	DP3ESB()2842	260.	289.	317.	462.	507.	566.
	48"	47 5/8"	29"	7/16"	DP3ESB()2848	266.	304.	334.	478.	542.	592.

Ordering Information

Embossed Steel Insert

1. Pattern number
2. Paint finish

Order Code

Embossed Steel Insert

Example: **DP3ESB22130 117**

DP3 Pattern number

ESB22130

117 Soft Grey paint

Included with:

Embossed Steel Insert

Options

Embossed Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

This page intentionally left blank

Slatwall Tiles

Slatwall tiles are designed to support KnollExtra Orchestra work tools. Slatwall tiles will support flat panel monitor arms with varying weight limitations based on mounting and application. Please refer to the KnollExtra price list for comprehensive mounting and weight limitation information by application. Slatwall kits include all mounting brackets and hardware for installation, and are fully assembled. SLATWALL TILES INCLUDE INTEGRAL TILE SUPPORT(S).

Slatwall tiles are field installed on Dividends Horizon DP8 panel frames or attached to wall mount tracks. To specify, select the slatwall width to match the width of the panel frame, in either top or middle position locations.

Specify slatwall tiles along with built-to-spec panel frames or wall mount tracks and other tiles for a complete installation. Slatwall tiles may not be specified directly above or below other slatwall tiles, beltway, stack frames, or stacking screens. Slatwall tiles may not be specified on stack frames.

Construction

Slatwall is constructed of heat treated extruded aluminum, powder coated in any Knoll Core paint color. 16 gauge steel reinforcements with integral hooks and tri-lobular screws on the back of slatwall provide reinforcement for heavy loads.

Note: Due to design improvements with the slatwall tile, monitor arm reinforcements are no longer required when hanging monitor arms from Dividends Horizon slatwall.

Note: When using stacking or add up components, slatwall must be installed first. It is not recommended to use stacking or add up components when slatwall is installed on both sides in the top position as this significantly limits the access to the fasteners needed to secure stacking or add up components.

Top Position Slatwall Tiles

Top position slatwall tiles may be installed at the top of any Dividends Horizon DP8 panel frame or attached to wall mount tracks, and includes all required hardware. Top position slatwall is available in heights of 7, 14, 21 and 28 inches.

TOP POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE BOTTOM, REPLACING THE SEPARATE D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.


Middle Position Slatwall Tiles

Middle position slatwall tiles may be installed at the middle of any Dividends Horizon DP8 panel frame or attached to wall mount tracks, and includes all necessary hardware. Middle position slatwall is available in heights of 7, 14 and 21 inches.


MIDDLE POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE TOP AND BOTTOM, REPLACING D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.

Note: due to the canted design of the slatwall tile, a variable reveal exists in applications where slatwall tiles meet in a corner of a 90 degree configuration.

Top Position Slatwall







Middle Position Slatwall



Slatwall Tiles

7", 14", 21" and 28" High

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
7" High Slatwall Tile 	24"	7"	7/16"	DP1SW0724()	\$237.	\$259.	\$270.
	30"	7"	7/16"	DP1SW0730()	252.	279.	290.
	36"	7"	7/16"	DP1SW0736()	270.	298.	308.
	42"	7"	7/16"	DP1SW0742()	286.	312.	328.
	48"	7"	7/16"	DP1SW0748()	302.	333.	345.
14" High Slatwall Tile 	24"	14"	7/16"	DP1SW1424()	316.	349.	383.
	30"	14"	7/16"	DP1SW1430()	373.	411.	446.
	36"	14"	7/16"	DP1SW1436()	427.	470.	513.
	42"	14"	7/16"	DP1SW1442()	467.	513.	558.
	48"	14"	7/16"	DP1SW1448()	506.	556.	610.
21" High Slatwall Tile 	24"	21"	7/16"	DP1SW2124()	420.	462.	504.
	30"	21"	7/16"	DP1SW2130()	505.	553.	604.
	36"	21"	7/16"	DP1SW2136()	589.	649.	706.
	42"	21"	7/16"	DP1SW2142()	651.	716.	780.
	48"	21"	7/16"	DP1SW2148()	710.	781.	854.
28" Top Position Slatwall Tile 	24"	28"	7/16"	DP1SW2824()	521.	575.	626.
	30"	28"	7/16"	DP1SW2830()	635.	698.	761.
	36"	28"	7/16"	DP1SW2836()	749.	821.	897.
	42"	28"	7/16"	DP1SW2842()	830.	912.	995.
	48"	28"	7/16"	DP1SW2848()	911.	1,002.	1,093.

Panels, Build-To-Spec

Ordering Information

Post Assemblies

1. Pattern Number
2. Paint Finish

Order Code

Post Assemblies

Example: **DP1 S2824T, 111**

DP1 S2824Pattern Number

T

111 Jet Black Paint

Included with:

Note: Middle position slatwall tiles are able to be used on topway or full view panels.

Options

Panel Options:

(T) = for topway panel top position
(F) = for full view panel top position
(M) = for middle position

Technology Tile

Dividends Horizon technology tiles are 14", worksurface height or 28" high fabric or painted steel tiles with a factory installed technology port for above worksurface power and/or data access. Technology ports may be specified on the left, right, or both sides of technology tiles.

Each technology port has two openings: duplex power receptacles are positioned to the outside of the panel, while data ports may be positioned in either of the two positions. For applications where only one of the two openings is used, a knockout filler is included with each data port to fill this opening.

Technology tiles with one port accommodate one power and one data or two data outlets. Technology tiles with two ports accommodate up to two power receptacles and two data outlets, or four data outlets.

Specify vertical power modules, power receptacles, and data components separately.

Construction

Steel inserts are made of 20-gauge formed painted steel. Fabric inserts are made with a roll-coat adhesive, heat-cured to $\frac{7}{16}$ " thick tackable acoustical board.


Available Sizes

Heights: 14", worksurface height, 28"
Widths: 18", 24", 30", 42", 48" and 60"


Note: Steel technology tiles are only available in Knoll Core finishes

Note: Technology tiles are not able to be specified in the top position of 36" high topway panel.


14" High Technology Tile






Worksurface Height Technology Tile



28" High Technology Tile



description	h	w	pattern no.	grade							
				10	15	20	25	30	35	40	45
14" High, Technology Tile Fabric 	14"	18"	DP6TF()1418	\$175.	\$180.	\$187.	\$189.	\$192.	\$196.	\$197.	\$201.
	14"	24"	DP6TF()1424	184.	187.	194.	196.	198.	203.	205.	212.
	14"	30"	DP6TF()1430	187.	190.	197.	201.	204.	207.	212.	216.
	14"	36"	DP6TF()1436	192.	197.	204.	205.	213.	216.	228.	231.
	14"	42"	DP6TF()1442	197.	201.	212.	213.	225.	231.	234.	239.
	14"	48"	DP6TF()1448	204.	205.	221.	228.	234.	235.	240.	246.
	14"	60"	DP6TF()1460	212.	214.	222.	223.	226.	228.	232.	235.
Worksurface Height, Technology Tile Fabric 	22 1/2"	18"	DP6TF()WH18	231.	239.	243.	251.	254.	260.	269.	276.
	22 1/2"	24"	DP6TF()WH24	252.	260.	276.	285.	295.	299.	305.	319.
	22 1/2"	30"	DP6TF()WH30	268.	276.	295.	302.	310.	319.	328.	341.
	22 1/2"	36"	DP6TF()WH36	283.	295.	310.	323.	338.	345.	352.	360.
	22 1/2"	42"	DP6TF()WH42	291.	300.	312.	325.	340.	347.	357.	371.
	22 1/2"	48"	DP6TF()WH48	300.	310.	328.	341.	349.	358.	372.	391.
	22 1/2"	60"	DP6TF()WH60	316.	329.	343.	358.	360.	373.	390.	421.
28" High, Technology Tile Fabric 	28"	18"	DP6TF()2818	231.	239.	243.	251.	254.	260.	269.	276.
	28"	24"	DP6TF()2824	252.	260.	276.	285.	295.	299.	305.	319.
	28"	30"	DP6TF()2830	268.	276.	295.	302.	310.	319.	328.	341.
	28"	36"	DP6TF()2836	283.	295.	310.	323.	338.	345.	352.	360.
	28"	42"	DP6TF()2842	291.	300.	312.	325.	340.	347.	357.	371.
	28"	48"	DP6TF()2848	300.	310.	328.	341.	349.	358.	372.	391.
	28"	60"	DP6TF()2860	338.	344.	356.	360.	369.	375.	381.	388.

Ordering Information
Technology Tile Fabric:

1. Pattern Number
2. Fabric
3. Bezel location

Order Code
Technology Tile Fabric

Example: **DP3TFL1418/ W352-4**

DP3TF Technology Tile Fabric

L Left Hand Bezel Location

14 Height

18 Width

W352-4 Labrynth Sage Fabric

Included with:
Technology Tile Fabric

- Fabric Technology Tile
- Bezel

Options
Technology Tile Fabric
Bezel Location Options:


- (L)** = Left Hand Bezel
- (R)** = Right Hand Bezel
- (D)** = Double Bezel - add \$45


Tile to Floor Options:


Tile to Floor available in heights of 14", Worksurface Height, and 28". To specify tile to floor, add an "F" suffix to the pattern number and add \$11 to the list price.

Technology Tiles Steel

Dividends Horizon

description	h	w	pattern no.	P1	P2	P3
14" High, Technology Tile Steel 	14"	18"	DP6TS()1418	\$155.	\$163.	\$166.
	14"	24"	DP6TS()1424	161.	168.	174.
	14"	30"	DP6TS()1430	162.	170.	175.
	14"	36"	DP6TS()1436	170.	182.	189.
	14"	42"	DP6TS()1442	174.	187.	192.
	14"	48"	DP6TS()1448	182.	195.	199.
	14"	60"	DP6TS()1460	194.	204.	208.

Worksurface Height, Technology Tile Steel	h	w	pattern no.	P1	P2	P3
	22 1/2"	18"	DP6TS()WH18	189.	199.	204.
	22 1/2"	24"	DP6TS()WH24	205.	222.	227.
	22 1/2"	30"	DP6TS()WH30	216.	231.	239.
	22 1/2"	36"	DP6TS()WH36	233.	251.	258.
	22 1/2"	42"	DP6TS()WH42	239.	255.	263.
	22 1/2"	48"	DP6TS()WH48	243.	259.	268.
	22 1/2"	60"	DP6TS()WH60	243.	259.	268.

28" High, Technology Tile Steel	h	w	pattern no.	P1	P2	P3
	28"	18"	DP6TS()2818	189.	199.	204.
	28"	24"	DP6TS()2824	205.	222.	227.
	28"	30"	DP6TS()2830	216.	231.	239.
	28"	36"	DP6TS()2836	233.	251.	258.
	28"	42"	DP6TS()2842	239.	255.	263.
	28"	48"	DP6TS()2848	243.	259.	268.

Ordering Information

Technology Tile Steel

1. Pattern Number
2. Paint
3. Bezel location

Order Code

Technology Tile Steel

Example: **DP3TSL1418/ 113**

DPSTS Technology Tile Steel

L Left Hand Bezel Location

14 Height

18 Width

113 Dark Grey Paint Finish

Included with:

Technology Tile Steel

- Steel Technology Tile
- Bezel

Note: Steel technology tiles are only available in Knoll core finishes.

Options

Technology Tile Steel

Bezel Location Options:

- (L)** = Left Hand Bezel
- (R)** = Right Hand Bezel
- (D)** = Double Bezel - add \$45

Tile to Floor Options:

Tile to Floor available in heights of 14", Worksurface Height, and 28". To specify tile to floor, add an "F" suffix to the pattern number and add \$17 to the list price.

This page intentionally left blank

Dividends Horizon rolling doors were developed for clients desiring increased privacy for focused work.

Rolling doors are available in 57, 64 and 78" overall heights, and widths to accommodate panel openings of 36, 42 and 48 inches.

Planning

Rolling doors must be mounted to the end of an equal height Dividends Horizon panel or run of panels of equal or greater width. Doors may not be mounted to Dividends Horizon screens or universal posts.

Door jamb may be mounted directly to DP8 series universal posts – specify jamb to post attachment kit separately.

When fully open, the door will extend 2" beyond the end of the panel end trim on a panel of corresponding width.

Thresholds are included with door pattern number, and are required in all installations. The Dividends Horizon rolling door meets ADA 5 lb pull test requirements when used with the supplied threshold.

42" and 48" wide meet ADA access requirements with openings of 36.4"W and 42.4"W respectively.

Specifying 57" and 64" Rolling Doors

57" and 64" rolling doors include:

- Rolling door
- Mounting brackets
- Door jamb (for door side opposite to mounting brackets)
- Panel end trim
- Threshold

To complete the specification, specify an end trim for the panel to which the door is mounted, and a jamb-compatible top cap for the panel to which the door jamb is attached.

Specifying 78" Rolling Doors

78" rolling doors include:

- Rolling door
- Header
- Mounting brackets,
- Door jamb (for door side opposite to mounting brackets)
- Panel end trim
- Threshold

78" high doors include a header, with vertical clearance of 76 1/2" from height of finished floor. Specify a top cap for the header separately. Extended length top caps are recommended in this application.

No additional end trim is required for 78" high doors, as it is included in the door pattern number.

Construction

Rolling door and door jamb are constructed of extruded aluminum, powder coated in any Knoll Core paint finish. Threshold is anodized extruded aluminum.

Door inserts are available in clear, powder or bronze frosted glass.

Locks are optional, and engage with door jamb. Standard KnollKey system keying guidelines apply.


Opening Clearance

36"W door = 30.4"W

42"W door = 36.4"W

48"W door = 42.4W


42"W and 48"W doors are ADA compliant.



Rolling Door

57", 64" and 78" High

Dividends Horizon

description	type	w	d	h	pattern no.	Temp	GL13	Metal P1	Metal P2	Metal P3	Plastic
							GL25 GL35				
 <p>right hand shown</p>	57" High with lock	36"	3"	57"	DPRD15736(L/R)L	\$2,817.	\$2,902.				
		42"	3"	57"	DPRD15742(L/R)L	3,060.	3,144.				
		48"	3"	57"	DPRD15748(L/R)L	3,368.	3,459.				
	57" High no lock	36"	3"	57"	DPRD15736(L/R)N	2,729.	2,813.				
		42"	3"	57"	DPRD15742(L/R)N	2,971.	3,056.				
		48"	3"	57"	DPRD15748(L/R)N	3,267.	3,361.				
	64" High with lock	36"	3"	64"	DPRD16436(L/R)L	2,931.	3,037.				
		42"	3"	64"	DPRD16442(L/R)L	3,175.	3,279.				
		48"	3"	64"	DPRD16448(L/R)L	3,492.	3,606.				
	64" High no lock	36"	3"	64"	DPRD16436(L/R)N	2,843.	2,949.				
		42"	3"	64"	DPRD16442(L/R)N	3,087.	3,189.				
		48"	3"	64"	DPRD16448(L/R)N	3,395.	3,510.				
	78" High with lock	36"	3"	78"	DPRD17836(L/R)L	3,409.	3,551.				
		42"	3"	78"	DPRD17842(L/R)L	3,651.	3,792.				
		48"	3"	78"	DPRD17848(L/R)L	4,017.	4,172.				
	78" High no lock	36"	3"	78"	DPRD17836(L/R)N	3,319.	3,462.				
		42"	3"	78"	DPRD17842(L/R)N	3,562.	3,705.				
		48"	3"	78"	DPRD17848(L/R)N	3,918.	4,075.				
Panel Top Caps for Jamb Side	18"			DP()PT18RD				71.	73.	75.	
	24"			DP()PT24RD				71.	73.	75.	
	30"			DP()PT30RD				71.	73.	75.	
	36"			DP()PT36RD				71.	73.	75.	
	42"			DP()PT42RD				71.	73.	75.	
	48"			DP()PT48RD				71.	73.	75.	
	54"			DP()PT54RD				75.	78.	80.	
	60"			DP()PT60RD				79.	81.	83.	
	66"			DP()PT66RD				83.	86.	89.	
72"			DP()PT72RD				88.	92.	98.		
78"			DP()PT78RD				96.	101.	105.		

Ordering Information

Rolling Door

1. Pattern Number
2. Glass type

Top Cap

1. Pattern Number
2. Paint finish

Application Notes:

Stacking screen header bracket is for use on 78" h doors (connection side) when connecting door header to top of 14" h stacking screen positioned on top of a 64" h panel.

Order Code

Rolling Door

Example: DPRD1 5736 RL

DPRD1 Rolling Door

57 Height

36 Width

R Right

L Lock

118T Bright White Textured

GL13 Frosted Glass

Included With:

Rolling Door

57" and 64" High

- Rolling Door
- Mounting Brackets
- Door jamb
- Threshold

78" High

- Rolling Door
- Header
- Mounting Brackets
- Door jamb
- Panel end trim
- Threshold

Top Cap

- Top Cap
- End Plug

Options

Rolling Door

Mounting Options:

- L** = Left Hand
- R** = Right Hand

Paint Finish:

All Core paint finishes

Glass Type:

- Temp** = Clear Glass
- GL13** = Frosted Glass
- GL25** = Bronze Glass
- GL35** = Grey Glass

Top Cap

Top Cap Options:

- (4)** = Radius Metal
- (5)** = Flat Metal

Rolling Door

57", 64" and 78" High

Dividends Horizon

description	type	w	d	h	pattern no.	Temp	GL13	Metal	Metal	Metal	Plastic
							GL25				
Panel Top Caps for Jamb Side		84"			DP()PT84RD			\$103.	\$108.	\$112.	
		90"			DP()PT90RD			111.	115.	118.	
		96"			DP()PT96RD			116.	121.	126.	
Door Jamb Kit to mount to DP8 Post					DPRD1JPM						26.
Stacking screen header bracket					DPRD1SSB						24.

Ordering Information

Rolling Door

1. Pattern Number
2. Glass type

Top Cap

1. Pattern Number
2. Paint finish

Application Notes:

Stacking screen header bracket is for use on 78"h doors (connection side) when connecting door header to top of 14"h stacking screen positioned on top of a 64"h panel.

Order Code

Rolling Door

Example: **DPRD1 5736 RL**

DPRD1 Rolling Door

57 Height

36 Width

R Right

L Lock

118T Bright White Textured

GL13 Frosted Glass

Included With:

Rolling Door

57" and 64" High

- Rolling Door
- Mounting Brackets
- Door jamb
- Threshold

78" High

- Rolling Door
- Header
- Mounting Brackets
- Door jamb
- Panel end trim
- Threshold

Top Cap

- Top Cap
- End Plug

Options

Rolling Door

Mounting Options:

- L** = Left Hand
- R** = Right Hand

Paint Finish:

All Core paint finishes

Glass Type:

- Temp** = Clear Glass
- GL13** = Frosted Glass
- GL25** = Bronze Glass
- GL35** = Grey Glass

Top Cap

Top Cap Options:

- (4)** = Radius Metal
- (5)** = Flat Metal

This page intentionally left blank

Open Weave Screens

Open Weave screens are designed to allow light and transparency into the workstation, while providing limited visual privacy.

When combined with Dividends Horizon freestanding components, open weave screen provide a layered aesthetic to the office.

Open Weave Screen Construction

Open weave screens feature Warp Net, a new open textile structure designed by Suzanne Tick. Warp net is constructed of 100% Earthtex, made from Olefin. Earthtex has passed the prestigious McDonough Braungart Design Chemistry Sustainability Protocol, and is fully recyclable.

Open weave screens have a triangular profile frame, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish.

Open Weave Screen Dimensions:

Widths: 24, 30, 36, 42, and 48 inches
Heights: 36, 42, 50, 57, and 64 inches
Thickness: 3 inches

Glass Screens

Glass Screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Glass Screen Construction

Glass screens are available in both triangular and rectangular frame profiles, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish. Glass is 4mm thick tempered glass.

Glass Screen Dimensions


Widths: 24, 30, 36, 42 and 48 inches
Heights: 42, 50, 57 and 64 inches
Thickness: 3 inches

Planning With Screens


Dividends Horizon open weave and glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components. Screens feature slots to allow use of a mid-span worksurface support at the standard 28 1/2" H worksurface height.

Screens attach to Dividends Horizon panels or connecting posts of the same or greater height, or other screens of the same height. In a "high/low" situation, screens do not attach to higher or lower screens, or lower panels. Screens ship with attachment hardware and topcap, if specified.

Open Weave Screen with Triangular Frame and Open Base Option



Glass Screen with Rectangular Frame and Open Base Option



Screen Base Options

Open weave screens are available with three base options: base raceway, open base, or frame to floor. Triangular frame glass screens are available with three base options: base raceway, open base, or frame to floor. Rectangular frame glass screens are available with two base options: base raceway or open base. All bases feature leveling glides with 2" of vertical travel. Raceway covers are standard without knockouts. Screens support electrical pass-thru's, but do not support power modules or electrical receptacles.

Note: 36"H screen may not be connected to a Legacy post.

Note: 64" open weave screen "L" or "U" configurations require minimum 36" wide panel return(s).

Note: Raceway covers are not available with knockouts.

Note: Screens are only available in Knoll core finishes.

Freestanding Open Weave Screen Kits

When used with Open Weave Screens with frame-to-floor (FF) option, new Freestanding Open Weave Screen kits allow open weave screens to be used in freestanding applications, creating a sense of enclosure without the need for conventional panel or screen planning.

Freestanding Open Weave Screen Kits may be used with open weave screens only, and are not compatible with panels or glass screens.

A single open weave screen of any height or width may become freestanding by specifying the appropriately sized freestanding open weave screen kit. Freestanding open weave screen kits for single screen applications include (2) flat steel feet and (1) ballast plate. The width of the screen determines which freestanding open weave screen kit is specified. For example, a 48" wide open weave screen would use DP7SWTFK48.

Two open weave screens of the same height and width may be attached together to create a double freestanding open weave screen. There is a single pattern number (DP7SWTFKD) for the freestanding open weave screen kit that should be specified to create a double freestanding open weave screen. The double freestanding open weave screen kit includes (3) flat steel feet.

Note: Freestanding open weave screen kits are finished with textured paint, including 613 silver.

Freestanding Open Weave Screen Kit Dimensions


Flat Steel Feet

Width: 4 inches

Thickness: 7/16 inches

Depth: 20 inches





Freestanding Open Weave Screen (Double Screen)



Open Weave and Glass Screens

Dividends Horizon

Open Weave Screens 36", 42", 50" and 57" High

description	h	w	t	pattern no.	P1	P2	P3
 36" High Open Weave Screen	36"	24"	3"	DP7SWT()3624	\$1,113.	\$1,132.	\$1,155.
	36"	30"	3"	DP7SWT()3630	1,220.	1,242.	1,267.
	36"	36"	3"	DP7SWT()3636	1,221.	1,243.	1,268.
	36"	42"	3"	DP7SWT()3642	1,276.	1,299.	1,324.
	36"	48"	3"	DP7SWT()3648	1,327.	1,354.	1,382.
 42" High Open Weave Screen	42"	24"	3"	DP7SWT()4224	1,198.	1,220.	1,242.
	42"	30"	3"	DP7SWT()4230	1,271.	1,297.	1,321.
	42"	30"	3"	DP7SWT()4236	1,349.	1,374.	1,401.
	42"	42"	3"	DP7SWT()4242	1,360.	1,388.	1,415.
	42"	48"	3"	DP7SWT()4248	1,373.	1,399.	1,425.
 50" High Open Weave Screen	50"	24"	3"	DP7SWT()5024	1,283.	1,306.	1,331.
	50"	30"	3"	DP7SWT()5030	1,324.	1,351.	1,379.
	50"	36"	3"	DP7SWT()5036	1,369.	1,394.	1,421.
	50"	42"	3"	DP7SWT()5042	1,448.	1,473.	1,503.
	50"	48"	3"	DP7SWT()5048	1,524.	1,553.	1,584.
 57" High Open Weave Screen	57"	24"	3"	DP7SWT()5724	1,306.	1,331.	1,355.
	57"	30"	3"	DP7SWT()5730	1,386.	1,415.	1,437.
	57"	36"	3"	DP7SWT()5736	1,465.	1,495.	1,523.
	57"	42"	3"	DP7SWT()5742	1,495.	1,524.	1,551.
	57"	48"	3"	DP7SWT()5748	1,524.	1,553.	1,584.

*Note: Frame to the floor shown

Ordering Information

Open Weave Screen:

1. Pattern number
2. Frame finish
3. Top cap style
4. Top cap finish
5. Base finish
6. Fabric finish

Order Code

Open Weave Screen:

Example: **DP7SWTFF3636**
117/4/117/117/W1113-1

DP7SWT	Triangular open weave screen
FF	Screen to Floor
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish
W1113-1	Warp Net White

Included with:

Open Weave Screen

Note: 36" h screens are not compatible with Legacy post connectors.

Note: Screens are only available in Knoll core finishes.

Options

Open Weave Screen



Top Cap Options:
No Top Cap - Deduct \$40
Radius and Flat Metal P1 as standard P2 \$2, P3 \$4

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base

Note: Raceway covers are not available with knockouts.

Open Weave Screens

64" High and Freestanding Open Weave Screen Kits

description	type	h	w	d	pattern no.	P1	P2	P3
 <p>64" High Open Weave Screen</p>		64"	24"	3"	DP7SWT()6424	\$1,327.	\$1,354.	\$1,382.
		64"	30"	3"	DP7SWT()6430	1,449.	1,474.	1,504.
		64"	36"	3"	DP7SWT()6436	1,523.	1,551.	1,582.
		64"	42"	3"	DP7SWT()6442	1,542.	1,572.	1,603.
		64"	48"	3"	DP7SWT()6448	1,562.	1,595.	1,623.
 <p>Freestanding Open Weave Screen Kit</p> <p>(single screen kit shown)</p>	For use with 2 open weave screens				DP7SWTFKD	499.	548.	571.
	For use with 24" wide open weave screen				DP7SWTFK24	466.	512.	532.
	For use with 30" wide open weave screen				DP7SWTFK30	472.	519.	538.
	For use with 36" wide open weave screen				DP7SWTFK36	485.	532.	552.
	For use with 42" wide open weave screen				DP7SWTFK42	499.	548.	571.
	For use with 48" wide open weave screen				DP7SWTFK48	499.	548.	571.

Panels, Build-To-Spec

Ordering Information

Open Weave Screen:

1. Pattern number
2. Frame finish
3. Top cap style
4. Top cap finish
5. Base finish
6. Fabric finish

Freestanding Open Weave Screen Kits

1. Pattern number
2. Paint finish

Order Code

Open Weave Screen:

Example: **DP7SWTFF3636**
117/4/117/117/W1113-1

DP7SWT	Triangular open weave screen
FF	Screen to Floor
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish
W1113-1	Warp Net White

Included with:

Open Weave Screen

Note: Freestanding open weave screen kits are finished with textured paint, including 613 Silver.

Note: Freestanding open weave screen kits only work with open weave screens with frame-to-floor (FF) base option.

Options:

Open Weave Screen

Top Cap Options:
No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Type:
(FF) = Frame to the Floor both sides
(RR) = Raceway covers no knockouts
(LL) = Open base


Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens


Triangular Frame Screen with Glass

42" and 50" High

description	h	w	t	pattern no.	P1	P2	P3
42" High Triangular Frame Screen with Glass	42"	24"	3"	DP7S()T()4224	\$1,145.	\$1,169.	\$1,190.
	42"	30"	3"	DP7S()T()4230	1,210.	1,235.	1,256.
	42"	36"	3"	DP7S()T()4236	1,279.	1,302.	1,326.
	42"	42"	3"	DP7S()T()4242	1,303.	1,329.	1,354.
	42"	48"	3"	DP7S()T()4248	1,329.	1,354.	1,379.



50" High Triangular Frame Screen with Glass	50"	24"	3"	DP7S()T()5024	1,228.	1,252.	1,278.
	50"	30"	3"	DP7S()T()5030	1,258.	1,284.	1,307.
	50"	36"	3"	DP7S()T()5036	1,289.	1,314.	1,338.
	50"	42"	3"	DP7S()T()5042	1,395.	1,419.	1,446.
	50"	48"	3"	DP7S()T()5048	1,493.	1,524.	1,553.



*Note: Frame with raceway covers shown


Ordering Information	Order Code	Included with:	Options
Triangular Frame Screen with Glass: 1. Pattern number 2. Frame finish 3. Glass type 4. Top cap style 5. Top cap finish 6. Raceway finish	Triangular Frame with Glass: <i>Example:</i> DP7SGTRR4236 117/4/117/117 <hr/> DP7SGT Triangular frame with clear glass <hr/> RR Raceway type <hr/> 117 Frame finish <hr/> 4 Radius metal top cap <hr/> 117 Top cap finish <hr/> 117 Raceway finish	Triangular Frame with Glass <ul style="list-style-type: none"> • Topcap (when specified) • Connecting hardware Note: Screens are only available in Knoll core finishes.	Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Type: (FF) = Frame to the Floor both sides (RR) = Raceway covers no knockouts (LL) = Open base Frame to floor option not available on Triangular glass screens. Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens


Triangular Frame Screen with Glass

57" and 64" High

description	h	w	t	pattern no.	P1	P2	P3
57" High Triangular Frame Screen with Glass	57"	24"	3"	DP7S()T()5724	\$1,258.	\$1,284.	\$1,307.
	57"	30"	3"	DP7S()T()5730	1,326.	1,351.	1,376.
	57"	36"	3"	DP7S()T()5736	1,396.	1,421.	1,448.
	57"	42"	3"	DP7S()T()5742	1,448.	1,477.	1,503.
	57"	48"	3"	DP7S()T()5748	1,499.	1,530.	1,559.



64" High Triangular Frame Screen with Glass	64"	24"	3"	DP7S()T()6424	1,288.	1,313.	1,337.
	64"	30"	3"	DP7S()T()6430	1,395.	1,419.	1,446.
	64"	36"	3"	DP7S()T()6436	1,495.	1,527.	1,556.
	64"	42"	3"	DP7S()T()6442	1,501.	1,531.	1,561.
	64"	48"	3"	DP7S()T()6448	1,507.	1,535.	1,566.



*Note: Frame to the floor shown

Ordering Information

Triangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Triangular Frame with Glass:

Example: **DP7SGTRR5736**
117/4/117/117

DP7SGT Triangular frame with clear glass

RR Raceway type

117 Frame finish

4 Radius metal top cap

117 Top cap finish

117 Raceway finish

Included with:

Triangular Frame with Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:

- (G)** = Clear Tempered Glass
- (F)** = Powder Glass

Top Cap Options:

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Type:

- (FF)** = Frame to the Floor both sides
- (RR)** = Raceway covers no knockouts
- (LL)** = Open base


Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens


Rectangular Frame Screen with Glass

42" and 50" High

description	h	w	t	pattern no.	P1	P2	P3
42" High Rectangular Frame Screen with Glass	42"	24"	3"	DP7S()R()4224	\$1,151.	\$1,174.	\$1,198.
	42"	30"	3"	DP7S()R()4230	1,219.	1,242.	1,266.
	42"	36"	3"	DP7S()R()4236	1,287.	1,312.	1,336.
	42"	42"	3"	DP7S()R()4242	1,313.	1,337.	1,362.
	42"	48"	3"	DP7S()R()4248	1,338.	1,365.	1,394.



50" High Rectangular Frame Screen with Glass	50"	24"	3"	DP7S()R()5024	1,238.	1,261.	1,287.
	50"	30"	3"	DP7S()R()5030	1,269.	1,295.	1,320.
	50"	36"	3"	DP7S()R()5036	1,301.	1,326.	1,351.
	50"	42"	3"	DP7S()R()5042	1,405.	1,434.	1,457.
	50"	48"	3"	DP7S()R()5048	1,509.	1,538.	1,568.



Ordering Information

Rectangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Rectangular Frame with Glass:

Example: **DP7SGRRR4236**
117/4/117/117

DP7SGR Rectangular frame screen with clear glass

RR Raceway type

117 Frame finish

4 Radius metal top cap

117 Top cap finish

117 Raceway finish

Included with:

Rectangular Frame Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:

(G)= Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Type:

(RR) = Raceway covers no knockouts
(LL) = Open base

Frame to floor option not available on Rectangular glass screens.


Note: Raceway covers are not available with knockouts.

Open Weave and Glass Screens


Rectangular Frame Screen with Glass

57" and 64" High

description	h	w	t	pattern no.	P1	P2	P3
57" High Rectangular Frame Screen with Glass	57"	24"	3"	DP7S()R()5724	\$1,267.	\$1,292.	\$1,317.
	57"	30"	3"	DP7S()R()5730	1,337.	1,364.	1,393.
	57"	36"	3"	DP7S()R()5736	1,406.	1,436.	1,458.
	57"	42"	3"	DP7S()R()5742	1,458.	1,488.	1,520.
	57"	48"	3"	DP7S()R()5748	1,517.	1,542.	1,574.



64" High Rectangular Frame Screen with Glass	64"	24"	3"	DP7S()R()6424	1,296.	1,322.	1,344.
	64"	30"	3"	DP7S()R()6430	1,404.	1,433.	1,456.
	64"	36"	3"	DP7S()R()6436	1,510.	1,539.	1,569.
	64"	42"	3"	DP7S()R()6442	1,517.	1,542.	1,574.
	64"	48"	3"	DP7S()R()6448	1,521.	1,549.	1,578.



Ordering Information

Rectangular Frame Screen with Glass:

1. Pattern number
2. Frame finish
3. Glass type
4. Top cap style
5. Top cap finish
6. Raceway finish

Order Code

Rectangular Frame with Glass:

Example: **DP7SGRRR5736**
117/4/117/117

DP7SGR	Rectangular frame screen with clear glass
RR	Raceway type
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish

Included with:

Rectangular Frame Glass

- Topcap (when specified)
- Connecting hardware

Note: Screens are only available in Knoll core finishes.

Options

Glass Options:

(G)= Clear Tempered Glass
(F) = Powder Glass

Top Cap Options:

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Type:

(RR) = Raceway covers no knockouts
(LL) = Open base

Frame to floor option not available on Rectangular glass screens.

Note: Raceway covers are not available with knockouts.

Stacking Open Weave Screens

Stacking open weave screens are designed to allow light and transparency into the workstation, while providing limited visual privacy. When combined with Dividends Horizon freestanding components, open weave screens provide a layered aesthetic to the office.

Stacking Open Weave Screen Construction

Open weave screens feature Warp Net, a new open textile structure designed by Suzanne Tick. Warp Net is constructed of 100% Earthtex, made from Olefin. Earthtex has passed the prestigious McDonough Braungart Design Chemistry Sustainability Protocol, and is fully recyclable.

Open weave screens have a triangular profile frame, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish.

Stacking Glass Screens

Stacking glass screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Stacking Glass Screen Construction

Stacking glass screens are constructed of extruded aluminum frame members, powder coated in any Knoll Core paint finish. Clear glass is 4mm tempered glass.

Stacking Screen Dimensions:

Widths: 24, 30, 36, 42, and 48 inches

Heights: 14, 21 and 28 inches

Thickness: 3 inches

Planning With Stacking Screens

Dividends Horizon open weave and glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components.

Stacking screens attach to any Dividends Horizon DP8 series full view panel frame, and may be stacked one tier high. Stacking screens do not stack on topway panel frames.

Stacking screens attach to Dividends Horizon DP8 panels or connecting posts of the same or greater height, or other screens of the same height.


Note: Stacking screens may be used with DP8 full view panel frames only.

Note: Screens are only available in Knoll core finishes.


Note: Knoll's three window types are aesthetically and functionally different, and are not designed to be mixed together within a single installation.

Note: Reveal strips for stacking screens 60" or wider must be specified separately to ensure the correct length of reveal strip is provided.

Triangular Stack Panel Screen with Open Weave Fabric insert






Rectangular Stack Panel Screen with Glass insert



Open Weave and Glass Stacking Screens

Triangular Frame Stacking Screen with Open Weave Fabric

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
14" High Triangular Frame Stacking Screen with Open Weave Fabric 	14"	24"	3"	DP7SSWT1424	\$629.	\$640.	\$654.
	14"	30"	3"	DP7SSWT1430	666.	679.	691.
	14"	36"	3"	DP7SSWT1436	703.	716.	729.
	14"	42"	3"	DP7SSWT1442	729.	745.	758.
	14"	48"	3"	DP7SSWT1448	755.	771.	786.
21" High Triangular Frame Stacking Screen with Open Weave Fabric 	21"	24"	3"	DP7SSWT2124	674.	688.	702.
	21"	30"	3"	DP7SSWT2130	717.	730.	746.
	21"	36"	3"	DP7SSWT2136	762.	776.	791.
	21"	42"	3"	DP7SSWT2142	791.	809.	823.
	21"	48"	3"	DP7SSWT2148	820.	835.	855.
28" High Triangular Frame Stacking Screen with Open Weave Fabric 	28"	24"	3"	DP7SSWT2824	718.	732.	748.
	28"	30"	3"	DP7SSWT2830	770.	784.	799.
	28"	36"	3"	DP7SSWT2836	820.	835.	855.
	28"	42"	3"	DP7SSWT2842	855.	871.	887.
	28"	48"	3"	DP7SSWT2848	885.	903.	921.

Panels, Build-To-Spec

Ordering Information

Triangular Frame Stacking Screen with Open Weave Fabric:

1. Pattern number
2. Frame finish
3. Fabric finish

Order Code

Triangular Frame Stacking Screen with Open Weave Fabric:

Example: **DP7SSWT1436**
117/W1113-1

DP7SSWT Stack, triangular frame, open weave

117 Frame finish

W1113-1 Fabric finish

Included with:

Triangular Frame Stacking Screen with Open Weave Fabric

- Attachment hardware




Note: Screens are only available in Knoll core finishes.

NOTE: Stacking screens are compatible with DP8 Full View panels only.

Open Weave and Glass Stacking Screens

Triangular Frame Stacking Screen with Glass

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
14" High Triangular Frame Stacking Screen with Glass 	14"	24"	3"	DP7SS()T1424	\$677.	\$689.	\$703.
	14"	30"	3"	DP7SS()T1430	710.	723.	737.
	14"	36"	3"	DP7SS()T1436	743.	760.	776.
	14"	42"	3"	DP7SS()T1442	779.	793.	810.
	14"	48"	3"	DP7SS()T1448	812.	826.	845.
	14"	54"	3"	DP7SS()T1454	853.	879.	904.
	14"	60"	3"	DP7SS()T1460	896.	922.	948.
	14"	66"	3"	DP7SS()T1466	944.	969.	1,001.
	14"	72"	3"	DP7SS()T1472	988.	1,017.	1,047.
	14"	78"	3"	DP7SS()T1478	1,039.	1,069.	1,100.
	14"	84"	3"	DP7SS()T1484	1,091.	1,124.	1,155.
14"	90"	3"	DP7SS()T1490	1,145.	1,180.	1,214.	
14"	96"	3"	DP7SS()T1496	1,203.	1,239.	1,275.	
21" High Triangular Frame Stacking Screen with Glass 	21"	24"	3"	DP7SS()T2124	680.	693.	709.
	21"	30"	3"	DP7SS()T2130	718.	733.	748.
	21"	36"	3"	DP7SS()T2136	755.	770.	786.
	21"	42"	3"	DP7SS()T2142	793.	809.	824.
	21"	48"	3"	DP7SS()T2148	830.	851.	866.
	21"	54"	3"	DP7SS()T2154	873.	898.	922.
	21"	60"	3"	DP7SS()T2160	915.	942.	970.
	21"	66"	3"	DP7SS()T2166	961.	989.	1,019.
	21"	72"	3"	DP7SS()T2172	1,009.	1,038.	1,070.
	21"	78"	3"	DP7SS()T2178	1,059.	1,092.	1,123.
	21"	84"	3"	DP7SS()T2184	1,111.	1,146.	1,179.
21"	90"	3"	DP7SS()T2190	1,168.	1,203.	1,238.	
21"	96"	3"	DP7SS()T2196	1,226.	1,264.	1,299.	
28" High Triangular Frame Stacking Screen with Glass 	28"	24"	3"	DP7SS()T2824	730.	745.	760.
	28"	30"	3"	DP7SS()T2830	774.	791.	804.
	28"	36"	3"	DP7SS()T2836	818.	831.	853.
	28"	42"	3"	DP7SS()T2842	864.	881.	899.
	28"	48"	3"	DP7SS()T2848	907.	926.	943.
	28"	54"	3"	DP7SS()T2854	952.	982.	1,010.
	28"	60"	3"	DP7SS()T2860	1,000.	1,029.	1,061.
	28"	66"	3"	DP7SS()T2866	1,050.	1,081.	1,112.
	28"	72"	3"	DP7SS()T2872	1,103.	1,135.	1,169.
	28"	78"	3"	DP7SS()T2878	1,157.	1,192.	1,227.
	28"	84"	3"	DP7SS()T2884	1,215.	1,250.	1,289.
28"	90"	3"	DP7SS()T2890	1,277.	1,316.	1,353.	
28"	96"	3"	DP7SS()T2896	1,340.	1,380.	1,422.	

Ordering Information

Triangular Frame Stacking Screen

1. Pattern number
2. Frame finish
3. Glass

Order Code

Triangular Frame Stacking Screen

Example: DP7SSGT1424 / 117
DP7SSGT Stack, Triangular Frame, w/ clear tempered glass
117 Frame finish

Included with:

Triangular Frame Stacking Screen

- Attachment hardware
- Note:** Screens are only available in Knoll core finishes.
- Note:** Reveal strips for stacking screens 60" or wider must be specified separately.

Options

NOTE: Stacking screens are compatible with DP8 Full View panels only.

Glass Options:

- (G)**= Clear Tempered Glass
(F) = Powder Glass

Open Weave and Glass Stacking Screens

Glass Stacking Screen Reveal Filler Strips

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
Stacking Screen Reveal Filler	2"	24"	2"	DP8PRFN24	n/c	n/c	n/c
	2"	30"	2"	DP8PRFN30	n/c	n/c	n/c
	2"	36"	2"	DP8PRFN36	n/c	n/c	n/c
	2"	42"	2"	DP8PRFN42	n/c	n/c	n/c
	2"	48"	2"	DP8PRFN48	n/c	n/c	n/c
	2"	60"	2"	DP8PRFN60	n/c	n/c	n/c




Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Triangular Frame Stacking Screen 1. Pattern number 2. Frame finish 3. Glass	Triangular Frame Stacking Screen <i>Example:</i> DP7SSGT1424 / 117 DP7SSGT Stack, Triangular Frame, w/ clear tempered glass 117 Frame finish	Triangular Frame Stacking Screen <ul style="list-style-type: none"> Attachment hardware Note: Screens are only available in Knoll core finishes. Note: Reveal strips for stacking screens 60" or wider must be specified separately.	NOTE: Stacking screens are compatible with DP8 Full View panels only. Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass

Open Weave and Glass Stacking Screens

Rectangular Frame Stacking Screen with Glass

Dividends Horizon

description	h*	w	t	pattern no.	P1	P2	P3
14" High Rectangular Frame Stacking Screen with Glass 	14"	24"	3"	DP7SS()R1424	\$620.	\$631.	\$644.
	14"	30"	3"	DP7SS()R1430	653.	667.	679.
	14"	36"	3"	DP7SS()R1436	685.	696.	713.
	14"	42"	3"	DP7SS()R1442	717.	732.	746.
	14"	48"	3"	DP7SS()R1448	750.	764.	780.
	14"	54"	3"	DP7SS()R1454	789.	811.	835.
	14"	60"	3"	DP7SS()R1460	828.	851.	877.
	14"	66"	3"	DP7SS()R1466	868.	895.	920.
	14"	72"	3"	DP7SS()R1472	911.	939.	967.
	14"	78"	3"	DP7SS()R1478	957.	987.	1,016.
	14"	84"	3"	DP7SS()R1484	1,005.	1,035.	1,067.
	14"	90"	3"	DP7SS()R1490	1,056.	1,088.	1,119.
	14"	96"	3"	DP7SS()R1496	1,108.	1,141.	1,176.
21" High Rectangular Frame Stacking Screen with Glass 	21"	24"	3"	DP7SS()R2124	752.	768.	781.
	21"	30"	3"	DP7SS()R2130	797.	813.	826.
	21"	36"	3"	DP7SS()R2136	839.	856.	874.
	21"	42"	3"	DP7SS()R2142	884.	900.	919.
	21"	48"	3"	DP7SS()R2148	924.	943.	965.
	21"	54"	3"	DP7SS()R2154	970.	1,000.	1,029.
	21"	60"	3"	DP7SS()R2160	1,019.	1,050.	1,081.
	21"	66"	3"	DP7SS()R2166	1,070.	1,102.	1,136.
	21"	72"	3"	DP7SS()R2172	1,123.	1,156.	1,191.
	21"	78"	3"	DP7SS()R2178	1,180.	1,216.	1,249.
	21"	84"	3"	DP7SS()R2184	1,239.	1,277.	1,314.
	21"	90"	3"	DP7SS()R2190	1,301.	1,340.	1,379.
	21"	96"	3"	DP7SS()R2196	1,366.	1,407.	1,447.
28" High Rectangular Frame Stacking Screen with Glass 	28"	24"	3"	DP7SS()R2824	723.	736.	752.
	28"	30"	3"	DP7SS()R2830	767.	782.	796.
	28"	36"	3"	DP7SS()R2836	811.	825.	846.
	28"	42"	3"	DP7SS()R2842	859.	875.	894.
	28"	48"	3"	DP7SS()R2848	903.	921.	937.
	28"	54"	3"	DP7SS()R2854	947.	977.	1,005.
	28"	60"	3"	DP7SS()R2860	994.	1,025.	1,054.
	28"	66"	3"	DP7SS()R2866	1,045.	1,076.	1,107.
	28"	72"	3"	DP7SS()R2872	1,098.	1,130.	1,163.
	28"	78"	3"	DP7SS()R2878	1,151.	1,187.	1,220.
	28"	84"	3"	DP7SS()R2884	1,210.	1,245.	1,282.
	28"	90"	3"	DP7SS()R2890	1,271.	1,309.	1,347.
	28"	96"	3"	DP7SS()R2896	1,332.	1,373.	1,412.

Ordering Information

Rectangular Frame Stacking Screen:

1. Pattern number
2. Frame finish
3. Glass

Order Code

Rectangular Frame Stacking Screen:

Example: DP7SSGR1424/117

DP7SSGR Stack, Rectangular Frame, w/clear tempered glass

117 Raceway finish

Included with:

Rectangular Frame Stacking Screen:

- Attachment hardware

Note: Screens are only available in Knoll core finishes.

Note: Reveal strips for stacking screens 60" or wider must be specified separately.

Options

NOTE: Stacking screens are compatible with DP8 Full View panels only.

Glass Options:

(G)= Clear Tempered Glass
(F) = Powder Glass

This page intentionally left blank

Frameless Add Up

Frameless add ups provide additional privacy between workstations, while creating a lighter and more transparent space. Combining frameless glass add ups with Dividends Horizon panels provides a clean, light aesthetic.

Frameless add ups are available in clear or powder glass. 7" and 14" heights are available, which is consistent with Dividends Horizon panel frame height increments.

Frameless add ups replace flat top caps on panels, bolting onto the panel frame. Add ups are not available in radius profile.

Frameless Glass Add Up Construction

Frameless glass add ups feature an extruded aluminum base and are available in any Knoll Core paint finish. Legacy finishes are not available.

Clear tempered or powder glass is ½" thick with polished edge.

Frameless Glass Add Up Dimensions

- Widths: 15, 18, 24, 30, 36, 42, 48, 54, 60, 66, and 72 inches
- Heights: 7 and 14 inches
- Thickness: 3 inches

Planning with Frameless Add Ups

Frameless add ups attach to the top of any height Dividends or Dividends Horizon topway or full view panel frame or stack frame, regardless of production date.

Frameless add ups replace the panel top cap and can span over one or more panels up to 72" wide.

Dividends Horizon frameless add ups are designed for use in same-height panel applications, and also support change of height applications involving a post connection.

Use shortened frameless add ups in change of height applications with DP5 end trims. Frameless add ups are not compatible with DP6 thin profile end trims.


End caps are specified for each end of a run of add ups. End caps must be specified separately and are available in packages of ten.

Note: Frameless add ups should not be used with worksurface height panels in a high-low condition. The glass will not line up with the higher panel.


Frameless Add Up Alignment Clip

A clear polycarbonate alignment clip maintains alignment between frameless add up inserts. One alignment clip is included with every frameless add up. Alignment clips do not need to be specified separately.


14" High Frameless Add Up



7" High Frameless Add Up




Frameless Add Up End Cap




Frameless Add Up

Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
Frameless Add Up, 7" High 	15"	1/2"	7"	DP1AU0715()G		\$237.	\$253.
	18"	1/2"	7"	DP1AU0718()G		262.	285.
	24"	1/2"	7"	DP1AU0724()G		289.	317.
	30"	1/2"	7"	DP1AU0730()G		314.	349.
	36"	1/2"	7"	DP1AU0736()G		356.	396.
	42"	1/2"	7"	DP1AU0742()G		396.	445.
	48"	1/2"	7"	DP1AU0748()G		438.	492.
	54"	1/2"	7"	DP1AU0754()G		475.	538.
	60"	1/2"	7"	DP1AU0760()G		514.	581.
	66"	1/2"	7"	DP1AU0766()G		552.	626.
	72"	1/2"	7"	DP1AU0772()G		590.	672.
	78"	1/2"	7"	DP1AU0778()G		638.	725.
	84"	1/2"	7"	DP1AU0784()G		687.	783.
	90"	1/2"	7"	DP1AU0790()G		743.	847.
	96"	1/2"	7"	DP1AU0796()G		803.	915.

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
Shortened Frameless Add Up, 7" High 	14"	1/2"	7"	DP1AU0714()G		237.	253.
	17"	1/2"	7"	DP1AU0717()G		262.	285.
	23"	1/2"	7"	DP1AU0723()G		289.	317.
	29"	1/2"	7"	DP1AU0729()G		314.	349.
	35"	1/2"	7"	DP1AU0735()G		356.	396.
	41"	1/2"	7"	DP1AU0741()G		396.	445.
	47"	1/2"	7"	DP1AU0747()G		438.	492.
	53"	1/2"	7"	DP1AU0753()G		475.	538.
	59"	1/2"	7"	DP1AU0759()G		514.	581.
	65"	1/2"	7"	DP1AU0765()G		552.	626.
	71"	1/2"	7"	DP1AU0771()G		590.	672.
	77"	1/2"	7"	DP1AU0777()G		638.	725.
	83"	1/2"	7"	DP1AU0783()G		687.	783.
	89"	1/2"	7"	DP1AU0789()G		743.	847.
	95"	1/2"	7"	DP1AU0795()G		803.	915.

Panels, Build-To-Spec

Ordering Information

Frameless Add Up with Clear Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Clear Glass

Example: **DP1AU0736VG**

DP1AU Frameless Add Up

07 7" High

36 36" Wide

V Full view

G Glass

117 Frame finish

TEMP Clear glass finish

Included with:

Frameless Add Up with Clear Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Alignment Clip

Options



Frame Options:
(V) = Full view
(C) = Topway

Glass Options:
(TEMP) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Frameless Add Up

Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
 Frameless Add Up, 14" High	15"	1/2"	14"	DP1AU1415()G		\$292.	\$325.
	18"	1/2"	14"	DP1AU1418()G		338.	383.
	24"	1/2"	14"	DP1AU1424()G		384.	438.
	30"	1/2"	14"	DP1AU1430()G		427.	496.
	36"	1/2"	14"	DP1AU1436()G		491.	570.
	42"	1/2"	14"	DP1AU1442()G		552.	646.
	48"	1/2"	14"	DP1AU1448()G		617.	723.
	54"	1/2"	14"	DP1AU1454()G		677.	797.
	60"	1/2"	14"	DP1AU1460()G		736.	871.
	66"	1/2"	14"	DP1AU1466()G		798.	945.
	72"	1/2"	14"	DP1AU1472()G		859.	1,019.
	78"	1/2"	14"	DP1AU1478()G		927.	1,100.
	84"	1/2"	14"	DP1AU1484()G		1,002.	1,188.
	90"	1/2"	14"	DP1AU1490()G		1,082.	1,284.
96"	1/2"	14"	DP1AU1496()G		1,169.	1,385.	
 Shortened Frameless Add Up, 14" High	14"	1/2"	14"	DP1AU1414()G		292.	325.
	17"	1/2"	14"	DP1AU1417()G		338.	383.
	23"	1/2"	14"	DP1AU1423()G		384.	438.
	29"	1/2"	14"	DP1AU1429()G		427.	496.
	35"	1/2"	14"	DP1AU1435()G		491.	570.
	41"	1/2"	14"	DP1AU1441()G		552.	646.
	47"	1/2"	14"	DP1AU1447()G		617.	723.
	53"	1/2"	14"	DP1AU1453()G		677.	797.
	59"	1/2"	14"	DP1AU1459()G		736.	871.
	65"	1/2"	14"	DP1AU1465()G		798.	945.
	71"	1/2"	14"	DP1AU1471()G		859.	1,019.
	77"	1/2"	14"	DP1AU1477()G		927.	1,100.
	83"	1/2"	14"	DP1AU1483()G		1,002.	1,188.
	89"	1/2"	14"	DP1AU1489()G		1,082.	1,284.
95"	1/2"	14"	DP1AU1495()G		1,169.	1,385.	
End Cap				DP1AUECTP	41.		



Ordering Information

Frameless Add Up with Clear Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Clear Glass

Example: **DP1AU0736VG**

DP1AU Frameless Add Up

07 7" High

36 36" Wide

V Full view

G Glass

117 Frame finish

TEMP Clear glass finish

Included with:

Frameless Add Up with Clear Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Alignment Clip

Options

Frame Options:
(V) = Full view
(C) = Topway

Glass Options:
(TEMP) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

This page intentionally left blank

Dividends Horizon DP8 Post Assemblies

Post assemblies are required for all "L", "T", and "X" applications involving same-height panels. Included with post assemblies are the appropriate post, post cover, top cap and inside corner raceway filler.

Posts use the universal panel connection hardware, which is included with the post, for attachment.

For high-low and post-to-panel applications, posts and covers must be ordered separately by component.

Dividends Horizon Post and Trim Construction

Posts are 3" square extruded aluminum construction. Post covers are powder-coated 20 gauge steel.

Posts have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway. Refer to the Beltway Electrical Specification page for cable routing information.

The illustrations that follow are common same-height post assembly configurations. Choose the post assembly that matches the required application.

Note: Worksurface height panels do not attach to any other panel height.

Post "L" Configuration

"L" post assembly includes:

- Universal post
- Two-way top cap
- Corner post cover
- Inside corner raceway filler
- "L" Post/Panel Top Connector

Post "T" Configuration

"T" post assembly includes:

- Universal post
- Three-way top cap
- Straight post cover
- Inside corner raceway filler
- T Post/Panel Top Connector

Post "X" Configuration

"X" post assembly includes:


- Universal post
- Four-way top cap
- Inside corner raceway filler
- X Post/Panel Top Connector

Post "X" Configuration


Trim options available:

- Radius
- Flat


Two-way Post Connection




Post and Cover Plan Views




Post "L" Configuration



Post "T" Configuration




Post "X" Configuration





Dividends Horizon DP8 Post Assemblies

L, T and X Configurations

Dividends Horizon

description	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
 Dividends Horizon Two-Way Post Assembly ("L")	28 1/2"	3"	3"	DP8(C/V/U)PAWH2()	\$167.	\$176.	\$186.	\$534.
	36"	3"	3"	DP8(C/V/U)PA362()	167.	176.	186.	536.
	42"	3"	3"	DP8(C/V/U)PA422()	167.	176.	186.	552.
	50"	3"	3"	DP8(C/V/U)PA502()	181.	193.	201.	602.
	57"	3"	3"	DP8(C/V/U)PA572()	214.	227.	235.	699.
	64"	3"	3"	DP8(C/V/U)PA642()	214.	227.	235.	726.
	78"	3"	3"	DP8(C/V/U)PA782()	309.	329.	343.	872.

 Dividends Horizon Three-Way Post Assembly ("T")	28 1/2"	3"	3"	DP8(C/V/U)PAWH3()	174.	184.	193.	507.
	36"	3"	3"	DP8(C/V/U)PA363()	174.	184.	193.	539.
	42"	3"	3"	DP8(C/V/U)PA423()	174.	184.	193.	550.
	50"	3"	3"	DP8(C/V/U)PA503()	186.	196.	204.	575.
	57"	3"	3"	DP8(C/V/U)PA573()	214.	228.	235.	621.
	64"	3"	3"	DP8(C/V/U)PA643()	214.	228.	235.	679.
	78"	3"	3"	DP8(C/V/U)PA783()	307.	321.	341.	780.

 Dividends Horizon Four-Way Post Assembly ("X")	28 1/2"	3"	3"	DP8(C/V/U)PAWH4()	162.	169.	177.	297.
	36"	3"	3"	DP8(C/V/U)PA364()	162.	169.	177.	301.
	42"	3"	3"	DP8(C/V/U)PA424()	162.	169.	177.	302.
	50"	3"	3"	DP8(C/V/U)PA504()	169.	180.	191.	314.
	57"	3"	3"	DP8(C/V/U)PA574()	196.	205.	215.	332.
	64"	3"	3"	DP8(C/V/U)PA644()	196.	205.	215.	343.
	78"	3"	3"	DP8(C/V/U)PA784()	282.	295.	309.	399.

Post Connectors/End Trim

Ordering Information

Post Assemblies

1. Pattern Number
2. Finish

Order Code

Post Assemblies

Example: **DP8A362,5,113**
613 Silver Paint Finish

Included with:

Post Assemblies

- Post
- Post top cap
- Post cover
- Connecting hardware

Options

Post Assemblies

- (4) = Radius Metal
- (5) = Flat Metal
- (V4) = Radius Veneer
- (V5) = Flat Veneer

Note: Plastic versions not available.

High-Low Post Components

High-Low panel-to-post configurations require ordering the post covers by components.

Shown are common high-low panel-to-post configurations. Choose the high-low panel-to-post configuration that matches the required application.

Posts use the universal panel connection hardware for attachment, which is included with the post.

Change of height kit is required for every WH panel connecting to taller panel or taller post.

NOTE: 28½"H panels do not attach to 36"H posts in a high-low application.

Panel-to-panel high-low applications require DP8HLCWH Change of Height Kit.

High-Low "L" Post Connector Configuration (see Figure 1)

High-Low "L" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "one-way" post top cap DP8PT1(5)
- 3 One corner post covers that match height of tallest panel. DP8PC(64)2
- 4 One, high-low right hand post cover that matches high-low panel-to-post dimension. DP8PC(14)(R)H - Mirrored configuration would require left hand cover DP8PC(14)(L)H

High-Low "T" Post Connector Configuration A (see Figure 2)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "two-way" top cap DP8PT2(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 One, high-low right hand post cover that matches high-low panel-to-post dimension DP8PC(14)(R)H - Mirrored configuration would require a left hand cover DP8PC(14)(L)H

High-Low "T" Post Connector Configuration B (see Figure 3)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "in-line" top cap DP8PTS(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 One, high-low straight post cover that matches high-low panel-to-post dimension DP8PC(14)H

Hi-Low "T" Post Connector Configuration C (see Figure 4)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PC(64)
- 2 One, "one-way" top cap DP8PT1(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 Two, high-low right hand post covers that match high-low panel-to-post dimension DP8PC(14)(R)H - Mirrored configuration would require left hand covers DP8PC(14)(L)H

Figure 1




Figure 2




Figure 3







Figure 4



Post Top Caps




One-Way




Two-Way



Three-Way



Four-Way



Inline

High-Low "X" Post Connector Configuration A (see Figure 5)

High-Low "X" components required (best method of various options):

- 1 One universal post that matches height of tallest panel DP8PO(64)
- 2 One, "one-way" top cap assembly DP8(C/V/U)PT1(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimensions DP8PC(14)H
- 4 Two, high-low right hand post covers that match high-low panel-to-post dimensions DP8PC(14)(R)H - Mirrored configuration would require left hand covers DP8PC(14)(L)H

High-Low "X" Post Connector Configuration B (see Figure 6)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "in-line" top cap assembly DP8(C/V/U)PTS(5)
- 3 Two, high-low straight post covers assemblies that match high-low panel-to-post dimensions DP8PC(14)H

High-Low "X" Post Connector Configuration C (see Figure 7)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "two-way" top cap assembly DP8(C/V/U)PT2(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimension. DP8PC(14)H
- 4 One, high-low right hand post cover assembly that matches high-low panel-to-post dimension. DP8PC(14)(R)H - Mirrored configuration would require left hand cover DP8PC(14)(L)H

High-Low "X" Post Connector Configuration D (see Figure 8)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "three-way" top cap assembly DP8(C/V/U)PT3(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimension DP8PC(14)H

Note: Change of height kit is required for every WH panel connecting to a taller panel or taller post.

Figure 5




Figure 6




Figure 7







Figure 8





Post Plan View





Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
Dividends Horizon Universal Post 		28 1/2"	3"	3"	DP8POWH	\$88.				
		36"	3"	3"	DP8PO36	88.				
		42"	3"	3"	DP8PO42	88.				
		42"	3"	3"	DP8PO50	102.				
		57"	3"	3"	DP8PO57	122.				
		64"	3"	3"	DP8PO64	122.				
		78"	3"	3"	DP8PO78	210.				

Dividends Horizon Universal Post-Four-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH4	96.				
		36"	3"	3"	DP8(C/V/U)PO364	96.				
		42"	3"	3"	DP8(C/V/U)PO424	98.				
		50"	3"	3"	DP8(C/V/U)PO504	111.				
		57"	3"	3"	DP8(C/V/U)PO574	131.				
		64"	3"	3"	DP8(C/V/U)PO644	131.				
		78"	3"	3"	DP8(C/V/U)PO784	218.				

Dividends Horizon Universal Post-Three-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH3	96.				
		36"	3"	3"	DP8(C/V/U)PO363	96.				
		42"	3"	3"	DP8(C/V/U)PO423	98.				
		50"	3"	3"	DP8(C/V/U)PO503	111.				
		57"	3"	3"	DP8(C/V/U)PO573	131.				
		64"	3"	3"	DP8(C/V/U)PO643	131.				
		78"	3"	3"	DP8(C/V/U)PO783	218.				

Dividends Horizon Universal Post-Two-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH2	96.				
		36"	3"	3"	DP8(C/V/U)PO362	96.				
		42"	3"	3"	DP8(C/V/U)PO422	98.				
		50"	3"	3"	DP8(C/V/U)PO502	111.				
		57"	3"	3"	DP8(C/V/U)PO572	131.				
		64"	3"	3"	DP8(C/V/U)PO642	131.				
		78"	3"	3"	DP8(C/V/U)PO782	218.				

Dividends Horizon Universal Post-Straight High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWHS	96.				
		36"	3"	3"	DP8(C/V/U)PO36S	96.				
		42"	3"	3"	DP8(C/V/U)PO42S	98.				
		42"	3"	3"	DP8(C/V/U)PO50S	111.				
		57"	3"	3"	DP8(C/V/U)PO57S	131.				
		64"	3"	3"	DP8(C/V/U)PO64S	131.				
		78"	3"	3"	DP8(C/V/U)PO78S	218.				

Ordering Information

Post Top Cap

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example: **DP8PT45**
 013 Silver Paint Finish

Included with:

Options

Post Top Caps Options










- (4)** = Radius Metal
- (5)** = Flat Metal
- (V4)** = Radius Veneer
- (V5)** = Flat Veneer

An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.

Dividends Horizon DP8 Post Components

Dividends Horizon

Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
14" High Dividends Horizon Stack Panel Post 		14 3/8"	3"	3"	DP8SPO14	\$91.				
21" High Dividends Horizon Stack Panel Post 		21 15/16"	3"	3"	DP8SPO21	92.				
28" High Dividends Horizon Stack Panel Post 		29 1/4"	3"	3"	DP8SPO28	106.				
Worksurface Height Panel Change of Height Kit					DP7HLCWH	68.				
Dividends Horizon Post Top Cap Assemblies     	Four-Way In-line Straght One-Way Three-Way Two-Way	1/2" 1/2" 1/2" 1/2" 1/2"	3" 3" 3" 3" 3"	3" 3" 3" 3" 3"	DP8(C/V/U)PT4() DP8(C/V/U)PTS() DP8(C/V/U)PT1() DP8(C/V/U)PT3() DP8(C/V/U)PT2()	8. 8. 8. 8. 8.	9. 9. 9. 9. 9.	9. 9. 9. 9. 9.	116. 112. 100. 113. 114.	
Inside Corner Raceway Filler 					DP7BF	10.				
Panel to Panel Connectors	High-low (10 qty) In Line (10 qty)	1 1/2" 6 1/2"	1/2" 3/4"	1/2" 1/4"	DP8HLC DP8PPC	27. 21.				

Post Connectors/End Trim

Ordering Information

Post Top Cap

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example: **DP8PT45**
013 Silver Paint Finish

Included with:

Options

Post Top Caps Options

- (4) = Radius Metal
- (5) = Flat Metal
- (V4) = Radius Veneer
- (V5) = Flat Veneer

An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.

Dividends Horizon DP8 Post Components

Post Covers and High Low Post Covers

Dividends Horizon

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon	28 1/2" + 14"	DP8PCWHS14	\$117.	\$131.	\$136.	n/a
Post Covers Full Height "T"	28 1/2" + 21"	DP8PCWHS21	130.	143.	149.	n/a
	28 1/2" + 28"	DP8PCWHS28	137.	151.	157.	n/a
	28 1/2"	DP8PCWH	51.	54.	71.	204.
	36"	DP8PC36	51.	54.	71.	233.
	42"	DP8PC42	51.	54.	71.	243.
	50"	DP8PC50	52.	57.	61.	253.
	57"	DP8PC57	60.	63.	67.	284.
	64"	DP8PC64	60.	63.	67.	328.
	78"	DP8PC78	67.	74.	77.	372.
Dividends Horizon	28 1/2" + 14"	DP8PCWHS142	123.	136.	141.	n/a
Post Covers Full Height "L"	28 1/2" + 21"	DP8PCWHS212	132.	145.	152.	n/a
	28 1/2" + 28"	DP8PCWHS282	139.	152.	158.	n/a
	28 1/2"	DP8PCWH2	80.	83.	86.	281.
	36"	DP8PC362	80.	83.	86.	279.
	42"	DP8PC422	80.	83.	86.	294.
	50"	DP8PC502	83.	87.	91.	330.
	57"	DP8PC572	89.	94.	103.	411.
	64"	DP8PC642	89.	94.	103.	424.
	78"	DP8PC782	103.	109.	112.	511.
Dividends Horizon	28 1/2" - 36"	DP8PCWH36()	97.	107.	110.	n/a
High Low Post Covers	28 1/2" - 42"	DP8PCWH42()	101.	111.	115.	n/a
	28 1/2" - 50"	DP8PCWH50()	115.	129.	133.	n/a
	28 1/2" - 57"	DP8PCWH57()	116.	130.	135.	n/a
	28 1/2" - 64"	DP8PCWH64()	117.	131.	136.	n/a
	28 1/2" - 78"	DP8PCWH78()	122.	135.	140.	n/a
	36" - 42"	DP8PC07()	9.	11.	11.	159.
	36" - 50"	DP8PC14()	16.	24.	27.	180.
	36" - 57"	DP8PC21()	28.	29.	30.	196.
	36" - 64"	DP8PC28()	41.	45.	46.	214.
	36" - 78"	DP8PC42()	61.	66.	68.	279.
	42" - 50"	DP8PC07()	9.	11.	11.	159.
	42" - 57"	DP8PC14()	16.	24.	27.	180.
	42" - 64"	DP8PC21()	28.	29.	30.	196.
	42" - 78"	DP8PC36()	54.	60.	63.	255.
	50" - 57"	DP8PC07()	9.	11.	11.	159.
	50" - 64"	DP8PC14()	16.	24.	27.	180.
	50" - 78"	DP8PC28()	41.	45.	46.	214.

Ordering Information

Post Covers

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example: **DP8PT45**
613 Silver Paint Finish

Included with:

Options

Post Covers

Add a "V" suffix to the base pattern number for a veneer finish.

High Low Post Covers Options

(H) = Straight Condition
(RH) = Right Hand Condition
(LH) = Left Hand Condition

Dividends Horizon DP8 Post Components

Post Covers and High Low Post Covers

Dividends Horizon

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon	57" - 64"	DP8PC07()	\$9.	\$11.	\$11.	\$159.
High Low Post Covers	57" - 78"	DP8PC21()	28.	29.	30.	196.
	64" - 78"	DP8PC14()	16.	24.	27.	180.
<hr/>						
Dividends Horizon Post	28 1/2"	DP8PCWHU	130.	143.	149.	263.
Covers Full Height	36"	DP8PC36U	136.	149.	156.	286.
Double Underlap	42"	DP8PC42U	140.	153.	159.	310.
	50"	DP8PC50U	155.	168.	177.	353.
	57"	DP8PC57U	156.	170.	179.	383.
	64"	DP8PC64U	168.	187.	195.	425.
	78"	DP8PC78U	233.	255.	265.	543.
<hr/>						
Dividends Horizon High Low Post Covers Double Underlap	36"-42"	DP8PC07UH	101.	111.	115.	206.
	36"-50"	DP8PC14UH	106.	116.	122.	237.
	36"-57"	DP8PC21UH	105.	115.	119.	248.
	36"-64"	DP8PC28UH	113.	124.	130.	273.
	42"-50"	DP8PC07UH	101.	111.	115.	206.
	42"-57"	DP8PC14UH	106.	116.	122.	237.
	42"-64"	DP8PC28UH	113.	124.	130.	273.
	42"-78"	DP8PC36UH	123.	136.	141.	298.
	50"-57"	DP8PC07UH	101.	111.	115.	206.
	50"-64"	DP8PC14UH	106.	116.	122.	237.
	50"-78"	DP8PC28UH	113.	124.	130.	273.
	57"-64"	DP8PC07UH	101.	111.	115.	206.
	57"-78"	DP8PC21UH	105.	115.	119.	248.
	64"-78"	DP8PC14UH	106.	116.	122.	237.

Post Connectors/End Trim

Ordering Information

Post Covers

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example: **DP8PT45**
613 Silver Paint Finish

Included with:

Options

Post Covers

Add a "V" suffix to the base pattern number for a veneer finish.

High Low Post Covers Options

(H) = Straight Condition
(RH) = Right Hand Condition
(LH) = Left Hand Condition

Panel End Trim

Panel end trim in one of three trim types ends a panel run.

Trim options available:

- Metal Radius
- Metal Flat

Metal trim is constructed of extruded aluminum, powder coated.

End trim includes the appropriate attachment hardware and the panel end cap for transition to panel top trim.

Thin Profile Panel End Trim

The thin profile panel end trim is an extruded aluminum end cover that is designed to attach to panel ends to provide a smooth end condition for the end of panel runs. The thin profile end trim and high low end trims are constructed of extruded aluminum with a powder coated finish. Thin profile panel end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

High-Low Panel-to-Panel End Trim

High-low panel-to-panel end trim is used to complete straight, high-low panel-to-panel connections.

Construction and attachment is identical to panel end trim and includes attachment hardware and top/bottom end caps.

Up to ten, category 5 cables can be laid-in to carry data from the upper panel topway to the lower panel topway.

High-Low Thin Profile End Trim

High-low panel to panel end trim is used to complete straight, high-low panel to panel connections. Construction and attachment is identical to the thin profile panel end trim and includes attachment hardware. High-low thin profile end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

Note: When using the high-low thin profile end trim, the higher and lower panels continue to use the standard full-width top cap.

Panel Top Caps

Radius and flat metal top caps are available in all panel widths.

Construction: All panel top caps are powder coated metal.


Top caps with retainer clips must be ordered when using top caps on full view panels.

Shortened High-Low Panel Top Caps


When specifying the enhanced smooth or metal panel trim for a high-low panel end trim condition, the top cap on the lower panel must be shortened by 1 inch. Panel top caps can be field cut to the new length, or shortened top caps may be ordered separately.

Note: Thin profile end trim and high low end trim are available in Knoll core finishes only.


Panel End Trim



Enhanced High-Low Panel End Trim





Thin Profile End Trim



Panel End Trim and Panel Top Caps

Panel End and High-Low Panel End

Dividends Horizon



description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
 Panel End	28 1/2"	28 1/2"	3"	3/8"	DP()PEWH	\$68.	\$75.	\$78.	\$235.
	28 1/2" + 14"	42 1/2"	3"	3/8"	DP()PEWHS14	78.	84.	87.	210.
	28 1/2" + 21"	49 1/2"	3"	3/8"	DP()PEWHS21	81.	88.	91.	223.
	28 1/2" + 28"	56 1/2"	3"	3/8"	DP()PEWHS28	83.	90.	93.	233.
	36"	36"	3"	3/8"	DP()PE36F	68.	75.	78.	247.
	42"	42"	3"	3/8"	DP()PE42	71.	77.	79.	263.
	50"	50"	3"	3/8"	DP()PE50	74.	78.	80.	297.
	57"	57"	3"	3/8"	DP()PE57	77.	80.	82.	332.
	64"	64"	3"	3/8"	DP()PE64	77.	80.	82.	358.
	78"	78"	3"	3/8"	DP()PE78	82.	86.	89.	391.
 Panel End, High-Low	28 1/2" - 36"	7 1/2"	3"	3/8"	DP()PEWH36	55.	63.	66.	247.
	28 1/2" - 42"	13 1/2"	3"	3/8"	DP()PEWH42	60.	67.	69.	263.
	28 1/2" - 50"	21 1/2"	3"	3/8"	DP()PEWH50	65.	71.	74.	297.
	28 1/2" - 57"	28 1/2"	3"	3/8"	DP()PEWH57	68.	77.	79.	332.
	28 1/2" - 64"	35 1/2"	3"	3/8"	DP()PEWH64	71.	79.	82.	359.
	28 1/2" - 78"	49 1/2"	3"	3/8"	DP()PEWH78	79.	85.	88.	391.
	36" - 42"	6"	3"	3/8"	DP()PE08	41.	45.	46.	183.
	36" - 50"	14"	3"	3/8"	DP()PE14	45.	47.	48.	210.
	36" - 57"	21"	3"	3/8"	DP()PE22	47.	50.	52.	223.
	36" - 64"	28"	3"	3/8"	DP()PE28	57.	61.	66.	233.
	36" - 78"	42"	3"	3/8"	DP()PE42H	71.	77.	79.	268.
	42" - 50"	8"	3"	3/8"	DP()PE08	41.	45.	46.	183.
	42" - 57"	15"	3"	3/8"	DP()PE14	45.	47.	48.	210.
	42" - 64"	22"	3"	3/8"	DP()PE22	47.	50.	52.	223.
	42" - 78"	36"	3"	3/8"	DP()PE36	68.	75.	78.	250.
	50" - 57"	7"	3"	3/8"	DP()PE08	41.	45.	46.	183.
	50" - 64"	14"	3"	3/8"	DP()PE14	45.	47.	48.	210.
	50" - 78"	28"	3"	3/8"	DP()PE28	57.	61.	66.	233.
	57" - 64"	7"	3"	3/8"	DP()PE08	41.	45.	46.	183.
	57" - 78"	21"	3"	3/8"	DP()PE22	47.	50.	52.	223.
64" - 78"	14"	3"	3/8"	DP()PE14	45.	47.	48.	210.	

h* = Nominal height
 Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel End 1. Pattern Number 2. Trim Finish	Panel End <i>Example:</i> DP2A PE42, 117 DP2A Pattern Number PE42 117 Soft grey	Panel End <ul style="list-style-type: none"> Panel end cover Connecting hardware High-Low Panel End <ul style="list-style-type: none"> Panel end cover Connecting hardware Lower transition cap 	Panel End, High-Low Panel End and Top Caps Trim options (4) = Radius Metal (5) = Flat Metal (V5) = Flat Veneer
High-Low Panel End 1. Pattern Number 2. Trim Finish	High-Low Panel End <i>Example:</i> DP2A PE42 117 DP2A Pattern Number PE42 117 Soft Grey		

Post Connectors/End Trim

Thin Profile Panel End Trim and High-Low Panel End

description	type	h*	w	d	pattern no.	P1	P2	P3
Thin Profile Panel End 	28 1/2"	28 1/2"	3"	5/8"	DP6PEWH	\$106.	\$106.	\$106.
	28 1/2" + 14"	42 1/2"	3"	5/8"	DP6PEWHS14	124.	137.	142.
	28 1/2" + 21"	49 1/2"	3"	5/8"	DP6PEWHS21	135.	148.	155.
	28 1/2" + 28"	56 1/2"	3"	5/8"	DP6PEWHS28	144.	159.	164.
	36"	36"	3"	5/8"	DP6PE36F	106.	106.	106.
	42"	42"	3"	5/8"	DP6PE42	114.	114.	114.
	50"	50"	3"	5/8"	DP6PE50	126.	126.	126.
	57"	57"	3"	5/8"	DP6PE57	137.	137.	137.
	64"	64"	3"	5/8"	DP6PE64	148.	148.	148.
	78"	78"	3"	5/8"	DP6PE78	172.	172.	172.
Thin Profile Panel End High-Low 	28 1/2"-36"	36"	3"	5/8"	DP6PEWH36	76.	82.	85.
	28 1/2"-42"	42"	3"	5/8"	DP6PEWH42	84.	92.	95.
	28 1/2"-50"	50"	3"	5/8"	DP6PEWH50	92.	103.	107.
	28 1/2"-57"	57"	3"	5/8"	DP6PEWH57	102.	112.	116.
	28 1/2"-64"	64"	3"	5/8"	DP6PEWH64	113.	125.	130.
	28 1/2"-78"	78"	3"	5/8"	DP6PEWH78	135.	150.	156.
	36"-42"	6"	3"	5/8"	DP6PE08	53.	55.	55.
	36"-50"	14"	3"	5/8"	DP6PE14	69.	73.	73.
	36"-57"	21"	3"	5/8"	DP6PE22	82.	86.	86.
	36"-64"	28"	3"	5/8"	DP6PE28	94.	100.	100.
	36"-78"	42"	3"	5/8"	DP6PE42H	116.	125.	125.
	42"-50"	8"	3"	5/8"	DP6PE08	53.	55.	55.
	42"-57"	15"	3"	5/8"	DP6PE14	69.	73.	73.
	42"-64"	22"	3"	5/8"	DP6PE22	82.	86.	86.
	42"-78"	36"	3"	5/8"	DP6PE36	108.	113.	113.
	50"-57"	7"	3"	5/8"	DP6PE08	53.	55.	55.
	50"-64"	14"	3"	5/8"	DP6PE14	69.	73.	73.
	50"-78"	28"	3"	5/8"	DP6PE28	94.	100.	100.
	57"-64"	7"	3"	5/8"	DP6PE08	53.	55.	55.
	57"-78"	21"	3"	5/8"	DP6PE22	82.	86.	86.
64"-78"	14"	3"	5/8"	DP6PE14	69.	73.	73.	

h* = Nominal height
 Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information

Thin Profile End Trim
 1. Pattern Number
 2. Finish

Order Code

Thin Profile End Trim	
<i>Example:</i> DP6PE42 117	
DP	Dividends Panel
6	Thin Profile
PE	Panel End
42	Height
117	Finish

Included with:

Thin Panel End Trim

Attachment hardware

Note: Thin profile end trim is only available in Knoll core paint finishes.


Options

Panel End Trim and Panel Top Caps

Topway and Full View Frame Top Caps

Dividends Horizon

description	w	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Panel Top Caps	15"	DP()PT15	\$46.	\$48.	\$50.	\$94.
	18"	DP()PT18	46.	48.	50.	105.
	24"	DP()PT24	46.	48.	50.	119.
	30"	DP()PT30	46.	48.	50.	136.
	36"	DP()PT36	46.	48.	50.	153.
	42"	DP()PT42	46.	48.	50.	170.
	48"	DP()PT48	46.	48.	50.	194.
	54"	DP()PT54	50.	52.	54.	215.
	60"	DP()PT60	53.	55.	59.	242.
	66"	DP()PT66	59.	63.	67.	265.
	72"	DP()PT72	66.	71.	75.	281.
	78"	DP()PT78	74.	78.	81.	297.
	84"	DP()PT84	80.	83.	87.	311.
	90"	DP()PT90	86.	90.	93.	332.
	96"	DP()PT96	91.	98.	103.	351.



Post Connectors/End Trim

Ordering Information

Panel Top Cap

1. Pattern Number
2. Trim Finish

Order Code

Panel Top Cap

Example: **DP5PT18, 117**

DP5PT18 Pattern number

117 Soft Grey trim finish

Included with:

Panel Top Cap

- Panel Top Cap

Options

Panel Top Caps

Trim options


- (4) = Radius Metal
- (5) = Flat Metal
- (V4) = Radius Veneer
- (V5) = Flat Veneer

Panel End Trim and Panel Top Caps

Shortened Panel Top Caps

Dividends Horizon

description	w	pattern no.	Metal P1	Metal P2	Metal P3
Shortened Panel Top Caps (for lower panel on high-low panel to panel application) Not for use with DP6 Thin profile panel ends	14"	DP()PT14	\$46.	\$48.	\$50.
	17"	DP()PT17	46.	48.	50.
	23"	DP()PT23	46.	48.	50.
	29"	DP()PT29	46.	48.	50.
	35"	DP()PT35	46.	48.	50.
	41"	DP()PT41	46.	48.	50.
	47"	DP()PT47	46.	48.	50.
	53"	DP()PT53	50.	52.	54.
	59"	DP()PT59	53.	55.	59.
	65"	DP()PT65	59.	63.	67.
	71"	DP()PT71	66.	71.	75.
	77"	DP()PT77	74.	78.	81.
	83"	DP()PT83	80.	83.	87.
	89"	DP()PT89	86.	90.	93.
	95"	DP()PT95	91.	98.	103.



h* = Nominal height
 Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Top Cap 1. Pattern Number 2. Trim Finish	Panel Top Cap <hr/> <i>Example:</i> DP5PT18, 117 <hr/> DP5PT18 Pattern number <hr/> 117 Soft Grey trim finish	Panel Top Cap • Panel Top Cap	Panel Top Caps Trim options (4) = Radius Metal (5) = Flat Metal (V4) = Radius Veneer (V5) = Flat Veneer
Panel-to-Panel Top Cap Transition 1. Pattern Number 2. Trim Finish			

This page intentionally left blank

Panel Wall Starter, Panel-to-Panel Top Cap Transition

Off-Module Panel Connector

Specifications

Panel Wall Starter

Panel wall starters mount to reinforced building walls to begin a perpendicular topway or full view panel run. Wall starters consist of a wall bracket and upper and lower panel-mounting brackets. Wall fasteners are not included or supplied by Knoll. Choice of wall fasteners is critical and must be selected to match the wall construction, wall surface and loading conditions.

Wall starters are available in all Dividends Horizon panel heights. Black finish only.

NOTE: KNOLL, INC. ASSUMES NO RESPONSIBILITY FOR WALL CONSTRUCTION OR PERFORMANCE OF FASTENERS USED.

Off-Module Panel Connector

The off-module connector allows for panel attachment anywhere along the width of the perpendicular panel. The off-module connector can be used with same height topway or full view panels only. The connector consists of a height specific connector and attaching hardware. The 3-way (DP1PT3) or 4-way (DP1PT4) post top cap must be ordered separately when radius metal top caps are being used. Specify connector height to match panel height. Black finish only.

When using the off-module panel connector, the attached connector will deface the perpendicular fabric panel insert.

Electrical components and data cables cannot be routed through the off-module panel.


Panel-to-Panel Top Cap Transition

Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.


- Construction: Trim-colored, softly-radiused molded plastic
- Size: 1" wide by 3" deep
- Attachment: Snaps between top cap sections in straight, same-height panel configurations

NOTE: PANEL-TO-PANEL TOP CAP TRANSITIONS ARE ORDERED SEPARATELY FROM PANELS.


Panel Wall Starter Connection



Off-Module Panel Connector





Panel-To-Panel Transition for Enhanced Smooth Panel Trim



Panel Wall Starter, Panel-to-Panel Top Cap Transition and Off-Module Panel Connector

Dividends Horizon

description	type	h *	h	w	d	pattern no.	Single pack list	10 pack list
 Panel/Screen Wall Starter		36"	28"	2"	3/4"	DP3PWS36	\$109.	n/a
		42"	35 3/8"	2"	3/4"	DP3PWS42	113.	n/a
		50"	42 11/16"	2"	3/4"	DP3PWS50	117.	n/a
		57"	50"	2"	3/4"	DP3PWS57	120.	n/a
		64"	57 1/4"	2"	3/4"	DP3PWS64	128.	n/a
		78"	71 7/8"	2"	3/4"	DP3PWS78	133.	n/a
Panel-to-Panel Top Cap Transition		3/4"	1"	3"		DP() TCT()	7.	67.
 Off-Module Panel Connector		36"	28"	2"	3/4"	DP2PMS36	71.	n/a
		42"	35 3/8"	2"	3/4"	DP2PMS42	71.	n/a
		50"	42 11/16"	2"	3/4"	DP2PMS50	80.	n/a
		57"	50"	2"	3/4"	DP2PMS57	83.	n/a
		64"	57 1/4"	2"	3/4"	DP2PMS64	85.	n/a
		78"	71 7/8"	2"	3/4"	DP2PMS78	102.	n/a
Radius Post Top Cap (for use with off-module panel connector when radius metal top caps are used)	three-way		1/2"	3"	3"	DP1PT3	5.	n/a
	four-way		1/2"	3"	3"	DP1PT4	5.	n/a

Post Connectors/End Trim

h* = nominal height
Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Wall Starter	Panel Wall Starter	Panel Wall Starter	Panel Wall Starter
1. Pattern Number	<i>Example:</i> DP1 PWS 64	Off-Module Panel Connector	Off-Module Panel Connector
Off-Module Panel Connector	DP1 PW Pattern Number	Panel-to-Panel Top Cap Transition	Panel-to-Panel Top Cap Transition
1. Pattern Number	64	Note: Three-way or four-way post top cap must be ordered separately when radius metal panel top caps are being used.	Trim Option: (4) = Radius Metal (5) = Flat Metal (V4) = Radius Veneer (V5) = Flat Veneer
Panel-to-Panel Top Cap Transition	Off-Module Panel Connector		Panel-to-Panel Top Cap Transition
1. Pattern Number	<i>Example:</i> DP1 PMS50		
2. Trim Finish	DP1 Pattern Number PMS50		
	Panel-to-Panel Top Cap Transition		
	<i>Example:</i> DP1 TCT, 117		
	DP1 TCT Pattern Number		
	117 Soft Grey		

Add an 'SP' suffix to the base pattern number for single pack or 'TP' suffix for a 10 pack.

Dividends Horizon Wall System

The Dividends Horizon Wall System allows designers to transform the aesthetic and function of private offices.

With the use of vertical wall tracks, building walls can support worksurfaces and storage, while fabric, slatwall, and marker board tiles improve aesthetic and function.

Wall System Dimensions

The Dividends Horizon wall system is available in heights of 57, 64, 71 and 78" from the finished floor. Wall tracks are designed to be positioned 5" from top of finished floor to accommodate building base molding and uneven floors.

Horizontal elements like bottom trim channels and top trims are available on 6" increments, from 24" to 48" wide. The maximum distance between wall tracks is 48".

Wall Tracks

Wall tracks work like the vertical elements of a Dividends Horizon panel frame, and are shipped in pairs which include a left and right track. Tracks feature slotted standards on the standard Dividends Horizon 1 1/2" increment.

Wall tracks are attached to building walls at 7" height increments. Available in all Knoll Core paint finishes.

End Trim


While wall tracks are painted, end trims are available for applications where a finished end is desired. Match end trim height to wall track height.

Top Cap

Top caps are available for applications with a lower horizon height, and are optional. Top caps conceal the space between tiles and the finished wall, and the top of the wall tracks.

Bottom Channel

The bottom channel is a "J" shaped channel that supports the bottom of the lowest tile. Bottom channels are also used during the installation process to accurately set the width between left and right wall tracks.



Tile Supports

Tile supports are specified in the same manner as with Dividends Horizon panels, and are not required at the top or bottom of wall tracks, or with Slatwall. Specify Wall Track tile support mounting brackets for each tile support.

Tiles

Standard Dividends Horizon tiles are specified with Wall Tracks.

Wall tracks support monolithic or tiled applications, using standard fabric, steel, or Slatwall tiles. Specify bottom channels at the bottom of the lowest tile.

Unlike panels, Wall Tracks accommodate tile supports at 7" inch increments, increasing design flexibility. Both D1 and D2 tile supports may be used with Wall Tracks.

For tiled applications, specify standard tile supports, and DP1WTTSB tile support mounting brackets for D2 tile supports.

Worksurface Planning


Dividends Horizon worksurfaces up to 24" deep may be mounted to wall tracks, using the same cantilevers, end supports and end panels used in panel planning, and follow the same planning rules.

Wall Track Planning


Wall tracks may be positioned on 6" width increments, from 24" to a maximum of 48".

Worksurfaces are supported with standard supports, including cantilevers, end supports, and end panels. Maximum worksurface depth when cantilever supported is 24".

One overhead may be mounted on each wall track section or multiple wall mount frames can be used to support shelves and overheads exceeding 48" w.







Post Connectors/End Trim



Wall Mount Tracks and Components

57", 64", 71" and 78" High

Dividends Horizon

description	w	h	d	pattern no.	NA Black	P1	P2	P3
 Wall Mount Tracks (pair)	1 1/2"	57"	1 1/2"	DP1WT57	\$245.	\$245.	\$269.	\$281.
	1 1/2"	64"	1 1/2"	DP1WT64	254.	254.	281.	291.
	1 1/2"	71"	1 1/2"	DP1WT71	263.	263.	291.	303.
	1 1/2"	78"	1 1/2"	DP1WT78	274.	274.	302.	312.
 End Trim for Wall Mount Tracks	1 1/2"	57"	5/8"	DP1WTET57	n/a	89.	98.	102.
	1 1/2"	64"	5/8"	DP1WTET64	n/a	98.	109.	113.
	1 1/2"	71"	5/8"	DP1WTET71	n/a	98.	109.	113.
	1 1/2"	78"	5/8"	DP1WTET78	n/a	98.	109.	113.
 Top Cap for Wall Mount Tracks	15"	3/4"	1 1/2"	DP1WTTC15	n/a	72.	80.	83.
	18"	3/4"	1 1/2"	DP1WTTC18	n/a	77.	83.	86.
	24"	3/4"	1 1/2"	DP1WTTC24	n/a	80.	87.	90.
	30"	3/4"	1 1/2"	DP1WTTC30	n/a	88.	96.	101.
	36"	3/4"	1 1/2"	DP1WTTC36	n/a	100.	110.	114.
	42"	3/4"	1 1/2"	DP1WTTC42	n/a	109.	118.	124.
	48"	3/4"	1 1/2"	DP1WTTC48	n/a	109.	118.	124.
	54"	3/4"	1 1/2"	DP1WTTC54	n/a	129.	142.	148.
	60"	3/4"	1 1/2"	DP1WTTC60	n/a	130.	143.	149.
	66"	3/4"	1 1/2"	DP1WTTC66	n/a	130.	143.	149.
	72"	3/4"	1 1/2"	DP1WTTC72	n/a	130.	143.	149.
	78"	3/4"	1 1/2"	DP1WTTC78	n/a	136.	149.	156.
	84"	3/4"	1 1/2"	DP1WTTC84	n/a	183.	200.	207.
90"	3/4"	1 1/2"	DP1WTTC90	n/a	187.	204.	213.	
96"	3/4"	1 1/2"	DP1WTTC96	n/a	192.	210.	220.	
 Bottom Tile Channel for Wall Mount Tracks	15"			DP1WTBTC15	n/a	51.	55.	59.
	18"			DP1WTBTC18	n/a	52.	57.	60.
	24"			DP1WTBTC24	n/a	55.	63.	66.
	30"			DP1WTBTC30	n/a	59.	66.	68.
	36"			DP1WTBTC36	n/a	72.	80.	83.
	42"			DP1WTBTC42	n/a	82.	89.	92.
48"			DP1WTBTC48	n/a	92.	103.	108.	

Ordering Information

Wall Mount Tracks

1. Pattern Number
2. Paint Finish

End Trim for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Top Cap for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Bottom Tile Channel for Wall Mount Tracks

1. Pattern Number
2. Paint Finish

Tile Support Brackets

1. Pattern Number

Order Code

Wall Mount Tracks

Example: **DP1WT57613**

DP1WT57 Pattern Number

613 Paint Finish

Tile Support Brackets

Example: **DP1WTTSB**

DP1WT Pattern Number

TSB

Included with:

Wall Mount Tracks

Wall fasteners are not included or supplied by Knoll.

Bottom Tile Channel for Wall Mount Tracks

- Hardware

Tile Support Brackets for Wall Mount Tracks

- Hardware

Options

Wall Mount Tracks and Components

57", 64", 71" and 78" High

Dividends Horizon

description	w	h	d	pattern no.	NA Black	P1	P2	P3
Tile Support Brackets for Wall Mount Tracks (pair)				DP1WTTSB	\$11.	n/a	n/a	n/a



Post Connectors/End Trim

Ordering Information	Order Code	Included with:	Options
Wall Mount Tracks 1. Pattern Number 2. Paint Finish	Wall Mount Tracks <i>Example:</i> DP1WT57613 DP1WT57 Pattern Number	Wall Mount Tracks Wall fasteners are not included or supplied by Knoll.	
End Trim for Wall Mount Tracks 1. Pattern Number 2. Paint Finish	613 Paint Finish Tile Support Brackets <i>Example:</i> DP1WTTSB	Bottom Tile Channel for Wall Mount Tracks • Hardware	
Top Cap for Wall Mount Tracks 1. Pattern Number 2. Paint Finish	DP1WT Pattern Number TSB	Tile Support Brackets for Wall Mount Tracks • Hardware	
Bottom Tile Channel for Wall Mount Tracks 1. Pattern Number 2. Paint Finish			
Tile Support Brackets 1. Pattern Number			

Carpet Grippers

Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Available in black finish only.

Panel-Mounted Coat Hook

The Dividends Horizon panel-mounted coat hook is made of extruded aluminum and is available in an anodized black finish or matte aluminum finish. The coat hook attaches to any Dividends Horizon panel by connecting over the top of the Dividends Horizon metal panel top caps only.

Slotted Standard Coat Hook

Independent of the top cap, the slotted standard coat hook attaches to the left or right vertical slotted standard of any Dividends Horizon panel. The die cast slotted standard coat hook is available in any of the Knoll Core paint finishes. The slotted standard coat hook is sold in packages of ten and is not compatible with laminate tiles or screens.

Panel Reveal Fillers

Panel reveal filler strips are used to cover unused vertical panel slots. Panel reveal fillers are designed to only be used with Legacy post panel applications. Panel reveal fillers should not be used with panel applications that are using DP8 posts. Panel reveal fillers are available in two thickness:

- 1/2" for panel-to-panel and panel to end trim attachment.
- 1/4" for panel-to-post attachment.


Panel reveal fillers are offered in a 74" length and are field cut to install into any Dividends Horizon panel height.

To determine the correct amount of reveal fillers to be specified, use the following formulas: For panels and end trim-2 x the number of straight panel connections plus the number of panel end trims. For panel to post connections, 4x the number of posts.


Carpet Gripper




Panel-Mounted Coat Hook
(for radius plastic and metal trim only)




Slotted Standard Coat Hook



Panel Reveal Fillers









Slotted Standard Coat Hook Application



Coat Hooks and Reveal Fillers

Carpet Grippers

Dividends Horizon

description	type	h	w	d	pattern no.	list	P1	P2	P3
Carpet Grippers 	Package of 10				DP1 CG	\$14.			
Coat Hook (For Panel Slotted Standard) 	Package of 10				DP2CHTP		160.	160.	160.
Coat Hook (For radius metal and plastic trim only) (Package of 4) 	Anodized Black Finish				DP1 CHB	139.			
	Matte Aluminum Finish				DP1 CHP	132.			
Panel Reveal Filler (for panel-to-post attachment) for pre-DP7 panels/posts 	15 Fillers	74"			DP1PRFN15 ()	50.			
	70 Fillers	74"			DP1PRFN70 ()	133.			
Wide Panel Reveal Filler (for panel-to-panel, panel-to-DP2/4/5 end trim or between laminate inserts) 	15 Fillers	74"			DP2PRFW15 ()	66.			
	70 Fillers	74"			DP2PRFW70 ()	190.			
Narrow Panel Reveal Filler (for panel-to-post attachment and panel-to-DP6 end trim) 	15 Fillers	74"			DP2PRFN15 ()	50.			
	70 Fillers	74"			DP2PRFN70 ()	133.			

Post Connectors/End Trim

Ordering Information

Panel Rigidizer Bracket

1. Pattern Number

Panel Reveal Filler

1. Pattern Number

Slotted Standard Coat Hook

1. Pattern Number

2. Paint Finish

Order Code

Panel Rigidizer Bracket

Example: **DP1 PRBL**

Panel Reveal Filler

Example: **DP1PRF N15**

Slotted Standard Coat Hook

Example: **DP2CH**

118 Bright White

Included with:

Panel Rigidizer Bracket

- Rigidizer Bracket
- Set Screws

Panel Reveal Filler

- Reveal Fillers (15 qty)

Options

Panel Rigidizer Bracket

Panel Reveal Filler

Note: Two narrow panel reveal fillers are required for inside corner on DP2/4/5 posts. They are used only on the outside of DP8 posts.

Panel Reveal Option:


(B) = Black
(W) = White
(G) = Grey

Coat Hooks and Reveal Fillers

Carpet Grippers

Dividends Horizon

description	type	h	w	d	pattern no.	list	P1	P2	P3
Corner Panel Reveal Filler (for inside corner of DP8 post)	15 Fillers	74"			DP2PRFIC15	\$190.			
	70 Fillers	74"			DP2PRFIC70	849.			



Ordering Information

Panel Rigidizer Bracket

1. Pattern Number

Panel Reveal Filler

1. Pattern Number

Slotted Standard Coat Hook

1. Pattern Number
2. Paint Finish

Order Code

Panel Rigidizer Bracket

Example: **DP1 PRBL**

Panel Reveal Filler

Example: **DP1PRF N15**

Slotted Standard Coat Hook

Example: **DP2CH**

118 Bright White

Included with:

Panel Rigidizer Bracket

- Rigidizer Bracket
- Set Screws

Panel Reveal Filler

- Reveal Fillers (15 qty)

Options

Panel Rigidizer Bracket

Panel Reveal Filler

Note: Two narrow panel reveal fillers are required for inside corner on DP2/4/5 posts. They are used only on the outside of DP8 posts.

Panel Reveal Option:

(B) = Black
(W) = White
(G) = Grey

This page intentionally left blank

Concealed Post Planning Guidelines Specifications

Concealed Post

Concealed posts eliminate visible post covers, creating a seamless aesthetic at three-way post connections. Larger widths of fabric or laminate tile-to-floor tiles are used to hide the concealed post. Panel top caps, up to 99" long, span concealed posts, which eliminate the need for post top caps. Concealed post applications are specified by individual components through "Build-to-Spec".

Planning with Concealed Posts

Concealed posts are to be used in three-way post conditions where straight post covers want to be eliminated. The concealed post should be specified in place of a standard Dividends Horizon DP8 post. Concealed post fabric or laminate tiles must be specified in the tile location that is covering the post. (See illustration below) Concealed post, half post or centered fabric and laminate tiles are designed to cover the concealed post with the edge

of the tile ending in the center of the concealed post. Only concealed post fabric and laminate tile sizes are compatible with concealed posts.


A high low condition may be created by having a perpendicular panel at a lower height than the concealed post. Specify the height of the concealed post to be at the same height as the higher panels. A concealed post high low top cap must be specified in this situation. Panel top caps that span concealed posts are not designed for use in high-low concealed post applications, standard width panel top caps and a concealed post high low top cap should be used instead. A DP8 straight high low post cover should be specified in a concealed post high low application.

The two panels on the straight side of the three-way concealed post intersection must always be the same height. The concealed post is not designed to change height on the concealed post side of the three-way connection.


Concealed post panel top caps and frameless add ups are 3" wider than standard sizes, for applications that span the concealed post. Panel top caps are available in lengths up to 99". Any concealed post application requiring panel top caps longer than 99" must specify panel top caps equal to the width of a panel or combination of panels and a concealed post same height top cap. Concealed post fabric and laminate tiles, post top caps, panel top caps, and frameless add ups are designed for use with the concealed post only.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP8 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.

Concealed Post Connection Plan View



Concealed Post Application



Concealed Post Construction

Concealed posts are a square extruded aluminum construction. They have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway.

Concealed Post Same Height Top Cap

When all three panels in a concealed post application are the same height and standard length panel top caps are used, a concealed post same height top cap must be specified. A concealed post same height top cap covers the top of a concealed post and connects three panel top caps at the same height. (See illustration below)

Concealed Post High Low Top Cap

When the perpendicular panel in a three-way concealed post application is a lower height than the concealed post, a concealed post high low top cap must be specified. A concealed post high low top

cap covers the top of the concealed post and connects the two same height panel top caps. (See illustration below) A DP8 high low straight post cover should be specified in a concealed post high low application.

Concealed Post Top Cap Construction

Concealed post flat and radius profile top caps are constructed of cast aluminum and powder coated in all core paint finishes.

Concealed Post Panel Top Caps


Concealed post panel top caps are 3" longer than standard panel top cap widths, so they can span over a concealed post. Concealed post panel top caps are available in flat profile metal. Concealed post panel top caps that span a concealed post must be used in same height applications only. High low concealed post conditions must use concealed post high low top caps. (See illustration below)

Concealed Post Shortened Panel Top Caps

Concealed post shortened panel tops are 3" longer than standard shortened panel top cap widths, so they can span over a concealed post. A concealed post shortened panel top cap must be specified for the lower panel in a high low panel-to-panel condition when the panel top cap of the lower panel is spanning over the concealed post. (See illustration below) When the lower panel top cap is not spanning over the concealed post because a concealed post top cap is being used, specify standard shortened panel top cap widths. Standard DP5 high low panel end trim should be specified with concealed post shortened panel top caps in high low panel-to-panel applications.

Concealed Post Panel Top Cap Construction




Concealed post panel top caps are constructed of roll-formed steel.



Concealed Post

Post Components

Post and Post Top Caps Assemblies

description	w	h	d	pattern no.	list	P1	P2	P3
Concealed Post 	3"	28 1/2"	3"	DP8POWHCPF	\$145.			
	3"	36"	3"	DP8PO36CPF	165.			
	3"	42"	3"	DP8PO42CPF	177.			
	3"	50"	3"	DP8PO50CPF	193.			
	3"	57"	3"	DP8PO57CPF	207.			
	3"	64"	3"	DP8PO64CPF	231.			
Concealed Post Same Height Top Caps 	3"	1/2"	3"	DP8(C/V/U)PTCP()		12.	14.	15.
Concealed Post High Low Top Caps 	3"	1/2"	3"	DP8(C/V/U)PTCPH()		12.	14.	15.

Ordering Information

Concealed Post

1. Pattern Number
2. Paint Finish Code

Concealed Post Top Caps

1. Pattern Number
2. Paint Finish Code

Order Code

Concealed Post

Example: **DP8PO42CPF**
DP8PO42 Pattern Number
CPF

Concealed Post Top Caps

Example: **DP8PTCP5**
DP8PTCP Pattern Number
5 Flat profile
613 Silver paint finish



Included with:

- Concealed Post**
- Tile to floor filler
- Concealed Post Top Caps**

Options:

- Post Top Cap Option:**
- (4)** = Radius Profile
(5) = Flat Profile

Concealed Post
 Post Components
 Panel Top Caps

description	w	h	d	pattern no.	P1	P2	P3
Concealed Post Panel Top Caps 	33"	1/2"	3"	DP5PT30CP	\$71.	\$79.	\$82.
	39"	1/2"	3"	DP5PT36CP	72.	80.	83.
	51"	1/2"	3"	DP5PT48CP	74.	81.	84.
	63"	1/2"	3"	DP5PT60CP	75.	82.	85.
	75"	1/2"	3"	DP5PT72CP	78.	84.	87.
	87"	1/2"	3"	DP5PT84CP	80.	87.	90.
	99"	1/2"	3"	DP5PT96CP	81.	88.	91.
Concealed Post Shortened Panel Top Caps 	32"	1/2"	3"	DP5PT29CP	71.	79.	82.
	38"	1/2"	3"	DP5PT35CP	72.	80.	83.
	50"	1/2"	3"	DP5PT47CP	74.	81.	84.
	62"	1/2"	3"	DP5PT59CP	75.	82.	85.
	74"	1/2"	3"	DP5PT71CP	78.	84.	87.
	86"	1/2"	3"	DP5PT83CP	80.	87.	90.
	98"	1/2"	3"	DP5PT95CP	81.	88.	91.

Ordering Information	Order Code	Included with:	Options:
Concealed Post Panel Top Caps 1. Pattern Number 2. Paint Finish Code	Concealed Post Panel Top Caps <i>Example:</i> DP5PT48CP DP5PT48 Pattern Number CP 117 Soft Grey paint finish	Concealed Post Panel Top Caps • Panel Top Caps	Trim Option: (5) = Metal, Flat

Concealed Post Monolithic Panel Inserts Specifications

Concealed Post Monolithic Inserts

Concealed post monolithic inserts are designed to cover a concealed post and eliminate the need for a post cover. Concealed post monolithic tile-to-floor fabric inserts create a seamless aesthetic at a three-way connection. There are three types of concealed post monolithic tiles: half post, centered, and double with post. Concealed post monolithic inserts can be fabric or laminate and are only available tile-to-floor. Concealed post applications are specified by individual components through "Build-to-Spec".

Concealed Post Monolithic Insert Construction

Fabric Tiles

Fabric laminated with adhesive and heat-cured to 7/18" thick acoustical board.

Laminate Tiles

The surface material is laminate on the front and back of a particle board core. Overall thickness is 7/16" with a 0.5 edgeband.

Concealed Post Monolithic Insert Attachment

Fabric Tiles

Panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting clips are attached to panel inserts for connection to the vertical frame for additional support. No tools are required for insert attachment.

Laminate Tiles

Laminate tiles are installed one side or both sides of a panel frame. Mounting clips are attached to laminate inserts for connection to the panel frame.


Planning with Concealed Post Half Post Tiles

Half post tiles attach to a panel frame or combination of panel frames that are connected to a concealed post. This type of tile covers the entire width of the panel frame(s) and half of the concealed post. Half post tiles are 1-1/2" wider than standard tile widths


to cover half of the concealed post. Half post tiles are handed, either left or right.

The left edge of a left half post tile ends in the middle of a concealed post and the right edge of the tile ends on the furthest right edge of the panel(s). The right edge of a right half post tile ends in the middle of a concealed post and the left edge of the tile ends on the left side of the panel(s). (See illustration below) A half post tile must be used with either another half post tile or a centered tile, so the other half of the post is concealed by a tile.

Half Post Tile Application



Half Post Tile Plan View



Concealed Post Monolithic Panel Inserts and Frameless Add Ups Specifications

Planning with Concealed Post Centered Tiles

Centered tiles attach to a panel frame or combination of panel frames that are connected to concealed posts. Centered tiles are centered on a panel frame(s) between two concealed posts. The left and right edge of the tile ends in the center of a concealed post. A centered tile is 3" wider than standard tile widths. Centered tiles must be centered on the panel frame(s) between the concealed posts. Neither the right nor left edge of a centered tile is able to end anywhere other than the center of a concealed post. (See illustration below) A centered tile must be used with either a half post tile or another centered tile, so the other half of the post is concealed by a tile.

Planning with Concealed Post Double with Post Tiles


A double with post tile attaches to two panel frames that are connected by a concealed post. The tile attaches to the panels and hides the concealed post connection. The concealed post must be between the panel frames. Double with post tiles are 3" wider than standard tile widths, so that they are able to cover a concealed post. (See illustration below) Neither the right nor left edge of a double with post tile is able to end anywhere other than the right or left edge of a panel frame.

Concealed Post Frameless Add Ups


Concealed post frameless add ups are 3" longer than standard frameless add up lengths, so they can span over a concealed post. Concealed post frameless add ups are not compatible with Dividends Horizon DP8 or Legacy posts.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP8 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.


Double With Post Tile Application




Centered Tile Application



Double With Post Tile Plan View



Centered Tile Plan View






Concealed Post

Monolithic Panel Half Post Fabric Inserts

Worksurface Height, 28" and 42" High

Dividends Horizon




description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	27 1/4"	7/16"	DP1SOWH15()F	\$114.	\$117.	\$123.	\$128.	\$129.	\$132.	\$133.	\$137.
	18"	19 1/2"	27 1/4"	7/16"	DP1SOWH18()F	129.	132.	139.	142.	143.	147.	149.	153.
	24"	25 1/2"	27 1/4"	7/16"	DP1SOWH24()F	141.	145.	152.	156.	159.	162.	163.	167.
	30"	31 1/2"	27 1/4"	7/16"	DP1SOWH30()F	155.	159.	165.	168.	173.	177.	180.	185.
	36"	37 1/2"	27 1/4"	7/16"	DP1SOWH36()F	166.	172.	182.	185.	189.	192.	196.	200.
	42"	43 1/2"	27 1/4"	7/16"	DP1SOWH42()F	180.	186.	195.	198.	203.	206.	208.	215.
	48"	49 1/2"	27 1/4"	7/16"	DP1SOWH48()F	194.	199.	207.	212.	218.	222.	225.	232.
60"	61 1/2"	27 1/4"	7/16"	DP1SOWH60()F	203.	208.	220.	224.	231.	234.	239.	244.	
28" High Concealed Post Monolithic Panel Half Post Fabric Inserts (For 36"H Panel Frame) 	15"	16 1/2"	33 13/16"	7/16"	DP1SO2815()F	115.	118.	100.	102.	106.	109.	109.	111.
	18"	19 1/2"	33 13/16"	7/16"	DP1SO2818()F	132.	137.	126.	130.	133.	136.	137.	141.
	24"	25 1/2"	33 13/16"	7/16"	DP1SO2824()F	149.	153.	153.	156.	160.	163.	164.	167.
	30"	31 1/2"	33 13/16"	7/16"	DP1SO2830()F	164.	168.	179.	183.	187.	191.	194.	198.
	36"	37 1/2"	33 13/16"	7/16"	DP1SO2836()F	182.	187.	203.	207.	213.	216.	221.	226.
	42"	43 1/2"	33 13/16"	7/16"	DP1SO2842()F	198.	202.	231.	234.	241.	245.	248.	254.
	48"	49 1/2"	33 13/16"	7/16"	DP1SO2848()F	213.	220.	231.	235.	242.	245.	250.	255.
60"	61 1/2"	33 13/16"	7/16"	DP1SO2860()F	226.	233.	245.	248.	255.	260.	263.	272.	
42" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	41 3/16"	7/16"	DP1SO4215()F	118.	122.	130.	130.	136.	139.	141.	143.
	18"	19 1/2"	41 3/16"	7/16"	DP1SO4218()F	140.	143.	151.	152.	158.	160.	163.	165.
	24"	25 1/2"	41 3/16"	7/16"	DP1SO4224()F	159.	162.	172.	173.	180.	184.	186.	191.
	30"	31 1/2"	41 3/16"	7/16"	DP1SO4230()F	179.	184.	194.	196.	201.	204.	207.	213.
	36"	37 1/2"	41 3/16"	7/16"	DP1SO4236()F	198.	203.	213.	216.	223.	226.	232.	237.
	42"	43 1/2"	41 3/16"	7/16"	DP1SO4242()F	216.	223.	235.	240.	245.	250.	253.	260.
	48"	49 1/2"	41 3/16"	7/16"	DP1SO4248()F	237.	244.	255.	260.	266.	272.	276.	284.
60"	61 1/2"	41 3/16"	7/16"	DP1SO4260()F	252.	260.	273.	277.	285.	291.	297.	303.	

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts 1. Pattern Number 2. Fabric	Concealed Post Monolithic Panel Fabric Inserts <i>Example:</i> DP1SO2818CEF <hr/> DP1SO Pattern Number <hr/> 2818 <hr/> CE Center left, End Right <hr/> F Tile to Floor <hr/> W351-3 Foundation Corn Silk Fabric	Concealed Post Monolithic Panel Fabric Inserts • Attachment Clips	Concealed Post Monolithic Panel Fabric Inserts Configuration: (CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame. (EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post Monolithic Panel Half Post Fabric Inserts 50", 57" and 64" High

description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	48 1/2"	7/16"	DP1SO5015()F	\$123.	\$126.	\$132.	\$135.	\$139.	\$141.	\$143.	\$147.
	18"	19 1/2"	48 1/2"	7/16"	DP1SO5018()F	147.	149.	157.	160.	163.	166.	168.	174.
	24"	25 1/2"	48 1/2"	7/16"	DP1SO5024()F	167.	173.	183.	185.	191.	194.	197.	201.
	30"	31 1/2"	48 1/2"	7/16"	DP1SO5030()F	192.	197.	205.	208.	215.	220.	223.	228.
	36"	37 1/2"	48 1/2"	7/16"	DP1SO5036()F	214.	220.	231.	235.	242.	246.	250.	257.
	42"	43 1/2"	48 1/2"	7/16"	DP1SO5042()F	237.	244.	255.	259.	268.	272.	276.	284.
	48"	49 1/2"	48 1/2"	7/16"	DP1SO5048()F	259.	266.	281.	285.	294.	299.	303.	310.
	60"	61 1/2"	48 1/2"	7/16"	DP1SO5060()F	279.	286.	301.	305.	312.	319.	325.	334.
57" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	55 3/8"	7/16"	DP1SO5715()F	128.	131.	137.	139.	142.	145.	148.	152.
	18"	19 1/2"	55 3/8"	7/16"	DP1SO5718()F	153.	158.	164.	166.	170.	175.	179.	184.
	24"	25 1/2"	55 3/8"	7/16"	DP1SO5724()F	180.	185.	194.	196.	201.	204.	207.	213.
	30"	31 1/2"	55 3/8"	7/16"	DP1SO5730()F	204.	210.	221.	224.	231.	235.	240.	245.
	36"	37 1/2"	55 3/8"	7/16"	DP1SO5736()F	231.	239.	248.	253.	259.	265.	269.	276.
	42"	43 1/2"	55 3/8"	7/16"	DP1SO5742()F	257.	263.	276.	282.	290.	295.	300.	306.
	48"	49 1/2"	55 3/8"	7/16"	DP1SO5748()F	283.	291.	304.	309.	318.	325.	330.	339.
	60"	61 1/2"	55 3/8"	7/16"	DP1SO5760()F	304.	311.	329.	335.	343.	349.	354.	367.
64" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	63 1/16"	7/16"	DP1SO6415()F	129.	131.	139.	142.	144.	148.	149.	156.
	18"	19 1/2"	63 1/16"	7/16"	DP1SO6418()F	158.	161.	168.	174.	179.	183.	185.	191.
	24"	25 1/2"	63 1/16"	7/16"	DP1SO6424()F	189.	194.	202.	205.	210.	215.	218.	225.
	30"	31 1/2"	63 1/16"	7/16"	DP1SO6430()F	216.	223.	234.	240.	245.	250.	253.	260.
	36"	37 1/2"	63 1/16"	7/16"	DP1SO6436()F	246.	253.	265.	272.	279.	284.	289.	297.
	42"	43 1/2"	63 1/16"	7/16"	DP1SO6442()F	276.	285.	299.	303.	310.	317.	323.	332.
	48"	49 1/2"	63 1/16"	7/16"	DP1SO6448()F	305.	314.	330.	337.	345.	351.	357.	368.
	60"	61 1/2"	63 1/16"	7/16"	DP1SO6460()F	332.	341.	356.	362.	375.	381.	388.	396.




w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts 1. Pattern Number 2. Fabric	Concealed Post Monolithic Panel Fabric Inserts <i>Example:</i> DP1SO5718CEF	Concealed Post Monolithic Panel Fabric Inserts • Attachment Clips	Concealed Post Monolithic Panel Fabric Inserts Configuration: (CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame. (EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.
	DP1SO 5718 Pattern Number		
	CE Center left, End Right		
	F Tile to Floor		
	W351-3 Foundation Corn Silk Fabric		

Concealed Post

Monolithic Panel Half Post Laminate Inserts



Worksurface Height, 28" and 42" High

description	w*	w	h	d	pattern no.	list
Worksurface Height Concealed Post	15"	16 1/2"	27 1/4"	7/16"	DP3L1WH15()F	\$195.
Monolithic Panel Half Post	18"	19 1/2"	27 1/4"	7/16"	DP3L1WH18()F	222.
Laminate Inserts	24"	25 1/2"	27 1/4"	7/16"	DP3L1WH24()F	259.
	30"	31 1/2"	27 1/4"	7/16"	DP3L1WH30()F	281.
	36"	37 1/2"	27 1/4"	7/16"	DP3L1WH36()F	335.
	42"	43 1/2"	27 1/4"	7/16"	DP3L1WH42()F	340.
	48"	49 1/2"	27 1/4"	7/16"	DP3L1WH48()F	448.
<hr/>						
28" High Concealed Post	15"	16 1/2"	33 13/16"	7/16"	DP3L12815()F	195.
Monolithic Panel Half Post	18"	19 1/2"	33 13/16"	7/16"	DP3L12818()F	222.
Laminate Inserts	24"	25 1/2"	33 13/16"	7/16"	DP3L12824()F	259.
(For 36"H Panel Frame)	30"	31 1/2"	33 13/16"	7/16"	DP3L12830()F	281.
	36"	37 1/2"	33 13/16"	7/16"	DP3L12836()F	335.
	42"	43 1/2"	33 13/16"	7/16"	DP3L12842()F	340.
	48"	49 1/2"	33 13/16"	7/16"	DP3L12848()F	448.
<hr/>						
42" High Concealed Post	15"	16 1/2"	41 3/16"	7/16"	DP3L14215()F	259.
Monolithic Panel Half Post	18"	19 1/2"	41 3/16"	7/16"	DP3L14218()F	290.
Laminate Inserts	24"	25 1/2"	41 3/16"	7/16"	DP3L14224()F	335.
	30"	31 1/2"	41 3/16"	7/16"	DP3L14230()F	453.
	36"	37 1/2"	41 3/16"	7/16"	DP3L14236()F	476.
	42"	43 1/2"	41 3/16"	7/16"	DP3L14242()F	481.
	48"	49 1/2"	41 3/16"	7/16"	DP3L14248()F	529.

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts
1. Pattern Number	<i>Example:</i> DP3L14236CEF	• Attachment Clips	Finish Options:
2. Laminate Finish	DP3L1 Pattern Number		114 Folkstone Grey
3. Edgeband Finish	4236		117 Soft Grey
	CE Center left, End Right		118 Bright White
	F Tile to Floor		119 Pumice
	118 Bright White Laminate		
	118 Bright White Edgeband		
			Configuration:
			(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
			(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post Monolithic Panel Half Post Laminate Inserts 50" and 57" High




description	w*	w	h	d	pattern no.	list
 50" High Concealed Post Monolithic Panel Half Post Laminate Inserts	15"	16 1/2"	48 1/2"	7/16"	DP3L15015()F	\$282.
	18"	19 1/2"	48 1/2"	7/16"	DP3L15018()F	337.
	24"	25 1/2"	48 1/2"	7/16"	DP3L15024()F	422.
	30"	31 1/2"	48 1/2"	7/16"	DP3L15030()F	458.
	36"	37 1/2"	48 1/2"	7/16"	DP3L15036()F	560.
	42"	43 1/2"	48 1/2"	7/16"	DP3L15042()F	565.
	48"	49 1/2"	48 1/2"	7/16"	DP3L15048()F	730.
 57" High Concealed Post Monolithic Panel Half Post Laminate Inserts	15"	16 1/2"	55 3/8"	7/16"	DP3L15715()F	288.
	18"	19 1/2"	55 3/8"	7/16"	DP3L15718()F	342.
	24"	25 1/2"	55 3/8"	7/16"	DP3L15724()F	427.
	30"	31 1/2"	55 3/8"	7/16"	DP3L15730()F	465.
	36"	37 1/2"	55 3/8"	7/16"	DP3L15736()F	566.
	42"	43 1/2"	55 3/8"	7/16"	DP3L15742()F	570.
	48"	49 1/2"	55 3/8"	7/16"	DP3L15748()F	735.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L15736CEF DP3L1 Pattern Number 5736 CE Center left, End Right F Tile to Floor 118 Bright White Laminate 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts <ul style="list-style-type: none"> Attachment Clips 	Concealed Post Monolithic Panel Fabric Inserts Finish Options: 114 Folkstone Grey 117 Soft Grey 118 Bright White 119 Pumice Configuration: (CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame. (EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Concealed Post
Monolithic Panel Centered Fabric Inserts
Worksurface Height, 28" and 42" High

Dividends Horizon

description	w*	w	d	h	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post	15"	18"	7/16"	27 1/4"	DP1SOWH15CCF	\$160.	\$163.	\$173.	\$174.	\$183.	\$185.	\$189.	\$194.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	27 1/4"	DP1SOWH18CCF	164.	168.	180.	182.	189.	191.	195.	199.
	24"	27"	7/16"	27 1/4"	DP1SOWH24CCF	170.	174.	185.	187.	194.	197.	200.	204.
	30"	33"	7/16"	27 1/4"	DP1SOWH30CCF	175.	182.	191.	194.	199.	202.	205.	210.
	36"	39"	7/16"	27 1/4"	DP1SOWH36CCF	182.	187.	197.	199.	204.	207.	212.	216.
	42"	45"	7/16"	27 1/4"	DP1SOWH42CCF	187.	192.	201.	204.	208.	214.	218.	223.
	48"	51"	7/16"	27 1/4"	DP1SOWH48CCF	192.	198.	206.	210.	215.	221.	224.	228.
	60"	63"	7/16"	27 1/4"	DP1SOWH60CCF	202.	207.	218.	223.	228.	233.	237.	243.
28" High Concealed Post	15"	18"	7/16"	33 13/16"	DP1SO2815CCF	172.	179.	189.	191.	197.	199.	202.	207.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	33 13/16"	DP1SO2818CCF	180.	186.	196.	198.	203.	205.	208.	215.
(For 36"H Panel Frame)	24"	27"	7/16"	33 13/16"	DP1SO2824CCF	186.	192.	201.	204.	210.	214.	218.	224.
	30"	33"	7/16"	33 13/16"	DP1SO2830CCF	194.	199.	207.	212.	218.	222.	225.	232.
	36"	39"	7/16"	33 13/16"	DP1SO2836CCF	200.	205.	215.	220.	225.	228.	233.	240.
	42"	45"	7/16"	33 13/16"	DP1SO2842CCF	205.	212.	222.	226.	233.	239.	242.	247.
	48"	51"	7/16"	33 13/16"	DP1SO2848CCF	213.	220.	228.	234.	241.	245.	248.	254.
	60"	63"	7/16"	33 13/16"	DP1SO2860CCF	225.	233.	244.	248.	254.	259.	263.	270.
42" High Concealed Post	15"	18"	7/16"	41 3/16"	DP1SO4215CCF	189.	194.	202.	204.	210.	215.	218.	225.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	41 3/16"	DP1SO4218CCF	197.	201.	210.	214.	221.	225.	227.	235.
	24"	27"	7/16"	41 3/16"	DP1SO4224CCF	203.	208.	221.	223.	228.	234.	239.	245.
	30"	33"	7/16"	41 3/16"	DP1SO4230CCF	212.	218.	228.	233.	240.	244.	247.	254.
	36"	39"	7/16"	41 3/16"	DP1SO4236CCF	221.	226.	239.	243.	248.	253.	257.	263.
	42"	45"	7/16"	41 3/16"	DP1SO4242CCF	227.	235.	247.	251.	257.	261.	266.	274.
	48"	51"	7/16"	41 3/16"	DP1SO4248CCF	237.	244.	255.	260.	266.	272.	276.	284.
	60"	63"	7/16"	41 3/16"	DP1SO4260CCF	252.	260.	273.	277.	285.	291.	297.	303.




w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO2818CCF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	2818		
	CC Center Left, Center Right		
	F Tile to Floor		
	W351-3 Foundation Corn Silk Fabric		

Concealed Post

Monolithic Panel Centered Fabric Inserts

50", 57" and 64" High

description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50" High Concealed Post	15"	18"	48 1/2"	7/16"	DP1SO5015CCF	\$203.	\$206.	\$220.	\$223.	\$227.	\$233.	\$237.	\$244.
Monolithic Panel Centered Fabric Insert	18"	21"	48 1/2"	7/16"	DP1SO5018CCF	213.	216.	228.	234.	240.	244.	247.	254.
	24"	27"	48 1/2"	7/16"	DP1SO5024CCF	222.	227.	241.	244.	250.	254.	259.	266.
	30"	33"	48 1/2"	7/16"	DP1SO5030CCF	232.	239.	250.	254.	260.	265.	270.	277.
	36"	39"	48 1/2"	7/16"	DP1SO5036CCF	242.	247.	259.	265.	272.	276.	282.	289.
	42"	45"	48 1/2"	7/16"	DP1SO5042CCF	250.	258.	270.	275.	283.	288.	294.	310.
	48"	45"	48 1/2"	7/16"	DP1SO5048CCF	259.	268.	281.	286.	294.	299.	304.	310.
	60"	63"	48 1/2"	7/16"	DP1SO5060CCF	279.	288.	301.	306.	314.	319.	327.	335.
57" High Concealed Post	15"	18"	55 3/8"	7/16"	DP1SO5715CCF	215.	223.	235.	240.	245.	250.	253.	259.
Monolithic Panel Centered Fabric Insert	18"	21"	55 3/8"	7/16"	DP1SO5718CCF	226.	234.	247.	251.	257.	261.	266.	273.
	24"	27"	55 3/8"	7/16"	DP1SO5724CCF	240.	246.	258.	262.	270.	275.	279.	286.
	30"	33"	55 3/8"	7/16"	DP1SO5730CCF	250.	257.	270.	275.	283.	288.	292.	300.
	36"	39"	55 3/8"	7/16"	DP1SO5736CCF	260.	268.	283.	288.	295.	300.	305.	311.
	42"	45"	55 3/8"	7/16"	DP1SO5742CCF	273.	281.	294.	300.	307.	311.	317.	327.
	48"	51"	55 3/8"	7/16"	DP1SO5748CCF	284.	291.	305.	310.	319.	325.	332.	340.
	60"	63"	55 3/8"	7/16"	DP1SO5760CCF	305.	312.	330.	337.	344.	350.	356.	368.
64" High Concealed Post	15"	18"	63 1/16"	7/16"	DP1SO6415CCF	234.	240.	251.	257.	261.	268.	272.	281.
Monolithic Panel Centered Fabric Insert	18"	21"	63 1/16"	7/16"	DP1SO6418CCF	246.	252.	263.	270.	276.	283.	286.	295.
	24"	27"	63 1/16"	7/16"	DP1SO6424CCF	258.	263.	277.	284.	290.	297.	301.	308.
	30"	33"	63 1/16"	7/16"	DP1SO6430CCF	270.	277.	291.	298.	304.	309.	314.	324.
	36"	39"	63 1/16"	7/16"	DP1SO6436CCF	283.	291.	304.	309.	318.	325.	330.	339.
	42"	45"	63 1/16"	7/16"	DP1SO6442CCF	295.	303.	317.	324.	333.	339.	344.	352.
	48"	51"	63 1/16"	7/16"	DP1SO6448CCF	306.	316.	332.	338.	346.	352.	358.	369.
	60"	63"	63 1/16"	7/16"	DP1SO6460CCF	332.	342.	357.	367.	377.	383.	389.	398.




w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO5718CCF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	5718		
	CC Center Left, Center Right		
	F Tile to Floor		
	W351-3 Foundation Corn Silk Fabric		

Concealed Post

Monolithic Panel Centered Laminate Inserts

Worksurface Height, 28" and 42" High

description	w*	w	h	d	pattern no.	list
Worksurface Height Concealed Post	15"	18"	27 1/4"	7/16"	DP3L1WH15CCF	\$195.
Monolithic Panel Centered Laminate Insert	18"	21"	27 1/4"	7/16"	DP3L1WH18CCF	222.
	24"	27"	27 1/4"	7/16"	DP3L1WH24CCF	259.
	30"	33"	27 1/4"	7/16"	DP3L1WH30CCF	281.
	36"	39"	27 1/4"	7/16"	DP3L1WH36CCF	335.
	42"	45"	27 1/4"	7/16"	DP3L1WH42CCF	340.
	48"	51"	27 1/4"	7/16"	DP3L1WH48CCF	448.
28" High Concealed Post	15"	18"	33 13/16"	7/16"	DP3L12815CCF	195.
Monolithic Panel Centered Laminate Insert	18"	21"	33 13/16"	7/16"	DP3L12818CCF	222.
(For 36"H Panel Frame)	24"	27"	33 13/16"	7/16"	DP3L12824CCF	259.
	30"	33"	33 13/16"	7/16"	DP3L12830CCF	281.
	36"	39"	33 13/16"	7/16"	DP3L12836CCF	335.
	42"	45"	33 13/16"	7/16"	DP3L12842CCF	340.
	48"	51"	33 13/16"	7/16"	DP3L12848CCF	448.
42" High Concealed Post	15"	18"	41 3/16"	7/16"	DP3L14215CCF	259.
Monolithic Panel Centered Laminate Insert	18"	21"	41 3/16"	7/16"	DP3L14218CCF	290.
	24"	27"	41 3/16"	7/16"	DP3L14224CCF	335.
	30"	33"	41 3/16"	7/16"	DP3L14230CCF	453.
	36"	39"	41 3/16"	7/16"	DP3L14236CCF	476.
	42"	45"	41 3/16"	7/16"	DP3L14242CCF	481.
	48"	51"	41 3/16"	7/16"	DP3L14248CCF	529.



w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts
1. Pattern Number	<i>Example:</i> DP3L14236CCF	• Attachment Clips	Finish Options:
2. Laminate Finish	DP3L1 Pattern Number		114 Folkstone Grey
3. Edgeband Finish	4236		117 Soft Grey
	CC Center Left, Center Right		118 Bright White
	F Tile to Floor		119 Pumice
	118 Bright White Laminate		
	118 Bright White Edgeband		

Concealed Post

Monolithic Panel Centered Laminate Inserts

50" and 57" High

description	w *	w	h	d	pattern no.	list
50" High Concealed Post Monolithic Panel Centered Laminate Insert 	15"	18"	48 1/2"	7/16"	DP3L15015CCF	\$282.
	18"	21"	48 1/2"	7/16"	DP3L15018CCF	337.
	24"	27"	48 1/2"	7/16"	DP3L15024CCF	422.
	30"	33"	48 1/2"	7/16"	DP3L15030CCF	458.
	36"	39"	48 1/2"	7/16"	DP3L15036CCF	560.
	42"	45"	48 1/2"	7/16"	DP3L15042CCF	565.
	48"	51"	48 1/2"	7/16"	DP3L15048CCF	730.
57" High Concealed Post Monolithic Panel Centered Laminate Insert 	15"	18"	55 3/8"	7/16"	DP3L15715CCF	288.
	18"	21"	55 3/8"	7/16"	DP3L15718CCF	342.
	24"	27"	55 3/8"	7/16"	DP3L15724CCF	427.
	30"	33"	55 3/8"	7/16"	DP3L15730CCF	465.
	36"	39"	55 3/8"	7/16"	DP3L15736CCF	566.
	42"	45"	55 3/8"	7/16"	DP3L15742CCF	570.
	48"	51"	55 3/8"	7/16"	DP3L15748CCF	735.

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L15736CCF DP3L1 Pattern Number 5736 CC Center Left, Center Right F Tile to Floor 118 Bright White Laminate 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts • Attachment Clips	Concealed Post Monolithic Panel Laminate Inserts Finish Options: 114 Folkstone Grey 117 Soft Grey 118 Bright White 119 Pumice

Monolithic Panel Double with Post Fabric Inserts
Worksurface Height, 28" and 42" High

description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
Worksurface Height Concealed Post	30"	33"	27 1/4"	7/16"	DP1SOWH30EPEF	\$160.	\$165.	\$173.	\$175.	\$183.	\$185.	\$187.	\$192.
Monolithic Panel Double with	36"	39"	27 1/4"	7/16"	DP1SOWH36EPEF	179.	185.	194.	196.	201.	204.	206.	213.
Post Fabric Insert	48"	51"	27 1/4"	7/16"	DP1SOWH48EPEF	196.	201.	210.	214.	221.	224.	227.	234.
	60"	63"	27 1/4"	7/16"	DP1SOWH60EPEF	213.	220.	231.	234.	241.	245.	248.	255.



28" High Concealed Post	30"	33"	33 13/16"	7/16"	DP1SO2830EPEF	126.	129.	136.	140.	142.	145.	147.	151.
Monolithic Panel Double with	36"	39"	33 13/16"	7/16"	DP1SO2836EPEF	170.	174.	185.	189.	194.	197.	199.	203.
Post Fabric Insert	48"	51"	33 13/16"	7/16"	DP1SO2848EPEF	214.	221.	232.	237.	243.	247.	251.	257.
(For 36" h panel frame)	60"	63"	33 13/16"	7/16"	DP1SO2860EPEF	259.	266.	281.	285.	294.	299.	303.	309.



42" High Concealed Post	30"	33"	41 3/16"	7/16"	DP1SO4230EPEF	157.	161.	168.	173.	175.	180.	183.	187.
Monolithic Panel Double with	36"	39"	41 3/16"	7/16"	DP1SO4236EPEF	199.	204.	214.	220.	223.	227.	232.	239.
Post Fabric Insert	48"	51"	41 3/16"	7/16"	DP1SO4248EPEF	241.	247.	259.	263.	270.	275.	281.	288.
	60"	63"	41 3/16"	7/16"	DP1SO4260EPEF	283.	291.	304.	309.	317.	324.	330.	339.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO2836EPEF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	2836		
	EPE End, Post, End		
	F Tile to Floor		
	W351-3 Foundation Corn Silk Fabric		

Concealed Post

Monolithic Panel Double with Post Fabric Inserts

50", 57" and 64" High

description	w*	w	h	d	pattern no.	10	15	20	25	30	35	40	45
50" High Concealed Post	30"	33"	48 1/2"	7/16"	DP1SO5030EPEF	\$186.	\$190.	\$199.	\$204.	\$207.	\$212.	\$216.	\$222.
Monolithic Panel Double with	36"	39"	48 1/2"	7/16"	DP1SO5036EPEF	224.	231.	242.	247.	253.	257.	262.	269.
Post Fabric Insert	48"	51"	48 1/2"	7/16"	DP1SO5048EPEF	262.	270.	284.	290.	298.	302.	307.	314.
	60"	63"	48 1/2"	7/16"	DP1SO5060EPEF	302.	310.	327.	333.	342.	346.	353.	361.



57" High Concealed Post	30"	33"	55 3/8"	7/16"	DP1SO5730EPEF	214.	221.	232.	237.	243.	245.	251.	257.
Monolithic Panel Double with	36"	39"	55 3/8"	7/16"	DP1SO5736EPEF	251.	258.	270.	276.	284.	288.	294.	301.
Post Fabric Insert	48"	51"	55 3/8"	7/16"	DP1SO5748EPEF	286.	295.	308.	314.	324.	329.	335.	343.
	60"	63"	55 3/8"	7/16"	DP1SO5760EPEF	323.	333.	347.	354.	367.	372.	379.	388.



64" High Concealed Post	30"	33"	63 1/16"	7/16"	DP1SO6430EPEF	273.	281.	295.	300.	307.	311.	318.	327.
Monolithic Panel Double with	36"	39"	63 1/16"	7/16"	DP1SO6436EPEF	291.	300.	314.	319.	330.	335.	341.	349.
Post Fabric Insert	48"	51"	63 1/16"	7/16"	DP1SO6448EPEF	308.	318.	335.	341.	350.	356.	361.	372.





w* = nominal width


Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO5736EPEF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	5736		
	EPE End, Post, End		
	F Tile to Floor		
	W351-3 Foundation Corn Silk Fabric		

Monolithic Panel Double with Post Laminate Inserts
Worksurface Height, 28" and 42" High

description	w*	w	h	d	pattern no.	list
Worksurface Height Concealed Post	30"	33"	27 1/4"	7/16"	DP3L1WH30EPEF	\$281.
Monolithic Panel Double with Post Laminate Insert 	36"	39"	27 1/4"	7/16"	DP3L1WH36EPEF	335.
	48"	51"	27 1/4"	7/16"	DP3L1WH48EPEF	344.
	60"	63"	27 1/4"	7/16"	DP3L1WH60EPEF	452.
	72"	75"	27 1/4"	7/16"	DP3L1WH72EPEF	462.
	84"	87"	27 1/4"	7/16"	DP3L1WH84EPEF	470.

28" High Concealed Post	30"	33"	33 13/16"	7/16"	DP3L12830EPEF	419.
Monolithic Panel Double with Post Laminate Insert (For 36" h panel frame) 	36"	39"	33 13/16"	7/16"	DP3L12836EPEF	423.
	48"	51"	33 13/16"	7/16"	DP3L12848EPEF	448.
	60"	63"	33 13/16"	7/16"	DP3L12860EPEF	727.
	72"	75"	33 13/16"	7/16"	DP3L12872EPEF	737.
	84"	87"	33 13/16"	7/16"	DP3L12884EPEF	747.

42" High Concealed Post	30"	33"	41 3/16"	7/16"	DP3L14230EPEF	453.
Monolithic Panel Double with Post Laminate Insert 	36"	39"	41 3/16"	7/16"	DP3L14236EPEF	476.
	48"	51"	41 3/16"	7/16"	DP3L14248EPEF	495.
	60"	63"	41 3/16"	7/16"	DP3L14260EPEF	734.
	72"	75"	41 3/16"	7/16"	DP3L14272EPEF	743.
	84"	87"	41 3/16"	7/16"	DP3L14284EPEF	753.

w* = nominal width


Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L14236EPEF <hr/> DP3L1 Pattern Number <hr/> 4236 <hr/> EPE End, Post, End <hr/> F Tile to Floor <hr/> 118 Bright White Laminate <hr/> 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts • Attachment Clips	Concealed Post Monolithic Panel Laminate Inserts Finish Options: 114 Folkstone Grey 117 Soft Grey 118 Bright White 119 Pumice

Concealed Post

Monolithic Panel Double with Post Laminate Inserts

50" and 57" High

description	w *	w	h	d	pattern no.	list
50" High Concealed Post Monolithic Panel Double with Post Laminate Insert 	30"	33"	48 1/2"	7/16"	DP3L15030EPEF	\$458.
	36"	39"	48 1/2"	7/16"	DP3L15036EPEF	560.
	48"	51"	48 1/2"	7/16"	DP3L15048EPEF	730.
	60"	63"	48 1/2"	7/16"	DP3L15060EPEF	740.
	72"	75"	48 1/2"	7/16"	DP3L15072EPEF	749.
	84"	87"	48 1/2"	7/16"	DP3L15084EPEF	758.




57" High Concealed Post Monolithic Panel Double with Post Laminate Insert 	30"	33"	55 3/8"	7/16"	DP3L15730EPEF	465.
	36"	39"	55 3/8"	7/16"	DP3L15736EPEF	566.
	48"	51"	55 3/8"	7/16"	DP3L15748EPEF	735.
	60"	63"	55 3/8"	7/16"	DP3L15760EPEF	745.
	72"	75"	55 3/8"	7/16"	DP3L15772EPEF	754.
	84"	87"	55 3/8"	7/16"	DP3L15784EPEF	763.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L15736EPEF <hr/> DP3L1 Pattern Number <hr/> 5736 <hr/> EPE End, Post, End <hr/> F Tile to Floor <hr/> 118 Bright White Laminate <hr/> 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts • Attachment Clips	Concealed Post Monolithic Panel Laminate Inserts Finish Options: 114 Folkstone Grey 117 Soft Grey 118 Bright White 119 Pumice

Concealed Post
 Frameless Add Up
 Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
Frameless Add Up, 7" High (For use with concealed post only) 	51"	3/4"	7"	DP1AU0751()G		\$458.	\$513.
	57"	3/4"	7"	DP1AU0757()G		497.	558.
	63"	3/4"	7"	DP1AU0763()G		533.	603.
	69"	3/4"	7"	DP1AU0769()G		573.	647.
	75"	3/4"	7"	DP1AU0775()G		612.	694.
	81"	3/4"	7"	DP1AU0781()G		662.	755.
	87"	3/4"	7"	DP1AU0787()G		716.	814.
	93"	3/4"	7"	DP1AU0793()G		772.	882.
	99"	3/4"	7"	DP1AU0799()G		834.	952.
	Shortened Frameless Add Up, 7" High (For use with concealed post only) 	50"	3/4"	7"	DP1AU0750()G		458.
56"		3/4"	7"	DP1AU0756()G		497.	558.
62"		3/4"	7"	DP1AU0762()G		533.	603.
68"		3/4"	7"	DP1AU0768()G		573.	647.
74"		3/4"	7"	DP1AU0774()G		612.	694.
80"		3/4"	7"	DP1AU0780()G		662.	755.
86"		3/4"	7"	DP1AU0786()G		716.	814.
92"		3/4"	7"	DP1AU0792()G		772.	882.
98"		3/4"	7"	DP1AU0798()G		834.	952.
Frameless Add Up, 14" High (For use with concealed post only) 		51"	3/4"	14"	DP1AU1451()G		646.
	57"	3/4"	14"	DP1AU1457()G		706.	833.
	63"	3/4"	14"	DP1AU1463()G		767.	909.
	69"	3/4"	14"	DP1AU1469()G		827.	981.
	75"	3/4"	14"	DP1AU1475()G		888.	1,056.
	81"	3/4"	14"	DP1AU1481()G		965.	1,143.
	87"	3/4"	14"	DP1AU1487()G		1,041.	1,235.
	93"	3/4"	14"	DP1AU1493()G		1,125.	1,335.
	99"	3/4"	14"	DP1AU1499()G		1,216.	1,441.

Ordering Information

Frameless Add Up with Glass

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code

Frameless Add Up with Glass

Example: **DP1AU0757VG**

DP1AU Frameless Add Up

07 7" High

57 57" Wide

V Full view

G Glass

117 Frame finish

TEMP Clear glass finish

Included with:

Frameless Add Up with Glass

- Attachment hardware
- Topway Trough Spacer (Topway only)
- Alignment Clip

Options

Frame Options:


- (V)**= Full view
(C) = Topway

Glass Options:

- (TEMP)**= Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Concealed Post
 Frameless Add Up
 Clear, Powder, Bronze and Grey Glass

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
Shortened Frameless Add Up, 14" High (For use with concealed post only)	50"	3/4"	14"	DP1AU1450()G		\$646.	\$760.
	56"	3/4"	14"	DP1AU1456()G		706.	833.
	62"	3/4"	14"	DP1AU1462()G		767.	909.
	68"	3/4"	14"	DP1AU1468()G		827.	981.
	74"	3/4"	14"	DP1AU1474()G		888.	1,056.
	80"	3/4"	14"	DP1AU1480()G		965.	1,143.
	86"	3/4"	14"	DP1AU1486()G		1,041.	1,235.
	92"	3/4"	14"	DP1AU1492()G		1,125.	1,335.
	98"	3/4"	14"	DP1AU1498()G		1,216.	1,441.




End Cap	DP1AUECTP	41.
---------	------------------	-----




Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Paint finish	Frameless Add Up with Glass <i>Example:</i> DP1AU0757VG DP1AU Frameless Add Up 07 7" High 57 57" Wide V Full view G Glass 117 Frame finish TEMP Clear glass finish	Frameless Add Up with Glass <ul style="list-style-type: none"> Attachment hardware Topway Trough Spacer (Topway only) Alignment Clip 	Frame Options: (V) = Full view (C) = Topway Glass Options: (TEMP) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey


The 120-degree planning model provides comparable or greater square footage per workstation than typical cubicle layouts (comparisons are illustrated on this page). At the same time, Dividends Horizon 120° allows for a more natural space, creating a more comfortable place to work. Maintaining a consistent 48" module promotes improved asset management and a reduction of reconfiguration costs.




Big House
Sq. Feet = 69.8'
7 Panels




8' x 8'
Sq. Feet = 64'
7 Panels




Full House
Sq. Feet = 42.1'
5 Panels



6' x 7'
Sq. Feet = 42'
7 Panels




Open House
Sq. Feet = 35.5'
4 Panels




6' x 6'
Sq. Feet = 36'
6 Panels




Townhouse
Sq. Feet = 34.1'
3 Panels




6' x 6'
Sq. Feet = 36'
6 Panels




Apartment
Sq. Feet = 32.1'
2 Panels



4' x 6'
Sq. Feet = 24'
4 Panels



8 Open House Stations
Sq. Feet = 284'
19 Panels




8 Station Cluster
Each station 6' x 6'
Sq. Feet = 288'
28 Panels


These worksurfaces are designed specifically for Dividends Horizon 120. The (L/R) suffix at the end of a pattern number indicates a defined pedestal location. If the worksurface has no defined pedestal location, the (L/R) represents the curved side of the top. All tops and tables are available with 2mm edge band or a 1" ergonomic edge.

Worksurface: W3


This worksurface, combined with the T3 Transition top, works best with the "apartment" layout. This application allows for stations on both sides of the spine, and is ideal for high density layouts. Available in extended versions for placement directly next to another worksurface.



Worksurface: W3



Worksurface: W4



Worksurface: W5 (L/R)

Worksurface: W4


This top works well in the "open house," "full house," and "big house" layouts for call center, professional, and managerial applications.

Worksurface: W5 (L/R)


With transition top T5 and this worksurface, teaming is made easy using the "townhouse" or "open house" layout. The shared space allows for call center, professional, or technical applications.

Worksurface: W6 (L/R)


In the "big house," "full house" or "open house", this worksurface allows for a pedestal on one side (determined by the L/R). Applications for this top include a call center with the "open house," technical applications with the "full house," and managerial layouts with the "big house."



Worksurface: W6 (L/R)



Worksurface: W7 (L/R)



Worksurface: W11 / W1118 (L/R)

Worksurface: W7 (L/R)

Used in conjunction with a T4 transition top, the W7 worksurface provides a great teaming space when the "townhouse" layout is used. The "open house" layout incorporates the T2 transition top for professional or technical stations with shared space for conferencing. Available in extended versions for placement directly next to another worksurface.

Worksurface: W11 / W1118 (L/R)

This top is a spacious option for a technical station in the "open house" layout. Adding a T2 transition top provides additional teaming space. The W11 surface also fits nicely in a private managerial office or a "full house" professional application.

Worksurface: W12 / W1218 (L/R)

This top, with the T5/T518 transition top provides a technical office with shared conferencing space in the “open house” layout. The 18” return allows ample space in the supervisory application of the “full house.”

Worksurface: W13 / W1318 (L/R)

This surface provides a teaming space with the T2/T218 transition in the “open house” layout. The W13/W1318 creates generous worksurface space in the “full house” as well as the management layout of the “big house.”


Transition Tops

Transition tops require columns (not included) for support. Flat brackets (not included) are required to attach transition tops to adjacent worksurfaces.

Application Notes


Dividends Horizon 120° worksurfaces use cantilevers as their main form of support. A cantilever must be used at each post location to support worksurfaces properly. A pedestal may be used for support, where applicable, in conjunction with cantilevers.

Worksurface: W12 / W1218 (L/R)




left

right




Worksurface: W13 / W1318 (L/R)




left

right




Transition Tops



Transition top: T2



Transition top: T218



Transition top: T3



Transition top: T4



Transition top: T5








Transition top: T518

120° Planning

120° Post Assemblies

Dividends Horizon

description	h*	w	d	pattern no.	Black	Metal P1	Metal P2	Metal P3
 120° Two-Way Post Assembly	36"	3"	3"	DP8(C/V/U)120PA362()		\$299.	\$307.	\$317.
	42"	3"	3"	DP8(C/V/U)120PA422()		299.	307.	317.
	50"	3"	3"	DP8(C/V/U)120PA502()		311.	323.	333.
	57"	3"	3"	DP8(C/V/U)120PA572()		345.	357.	368.
	64"	3"	3"	DP8(C/V/U)120PA642()		345.	357.	368.
	78"	3"	3"	DP8(C/V/U)120PA782()		440.	459.	473.
 120° Three-Way Post Assembly	36"	3"	3"	DP8(C/V/U)120PA363()		305.	314.	323.
	42"	3"	3"	DP8(C/V/U)120PA423()		305.	314.	323.
	50"	3"	3"	DP8(C/V/U)120PA503()		317.	327.	337.
	57"	3"	3"	DP8(C/V/U)120PA573()		345.	357.	368.
	64"	3"	3"	DP8(C/V/U)120PA643()		345.	357.	368.
	78"	3"	3"	DP8(C/V/U)120PA783()		437.	455.	470.
 14" High 120° Stack Panel Posts	14 ⁵ / ₈ "	3"	3"	DP8120SPO 14	120.			
 21" High 120° Stack Panel Posts	21 ¹⁵ / ₁₆ "	3"	3"	DP8120SPO 21	135.			
 28" High 120° Stack Panel Posts	29 ¹ / ₄ "	3"	3"	DP8120SPO 28	140.			

Alternative Planning

h = nominal height

Ordering Information

- Post Assemblies**
1. Pattern Number
 2. Trim Finish

Order Code

Post Assemblies
Example: **DP(4)120PA 642, 113**
DP(4)120 Pattern Number
PA 642
113 Dark grey trim finish

Included with:

- Post Assemblies**
- Post assemblies
 - Post top cap
 - Post cover
 - Connecting hardware





Options

Post assembly trim options
(4) = Metal, Radius
(5) = Metal, Flat

120° Planning

120° High Low Planning












Dividends Horizon

description	type	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Post Covers (Straight) High-Low Connection 	36" - 42"	8"			DP8120PC08S	\$9.	\$11.	\$11.
	36" - 50"	14"			DP8120PC14S	16.	24.	27.
	36" - 64"	28"			DP8120PC28S	41.	45.	46.
	36" - 78"	42"			DP8120PC42SH	61.	66.	68.
	42" - 50"	8"			DP8120PC08S	9.	11.	11.
	42" - 64"	22"			DP8120PC22S	28.	29.	30.
	42" - 78"	36"			DP8120PC36S	54.	60.	63.
	50" - 64"	14"			DP8120PC14S	16.	24.	27.
	50" - 78"	28"			DP8120PC28S	41.	45.	46.
64" - 78"	14"			DP8120PC14S	16.	24.	27.	
Post Top Caps 	One-Way	1/2"	3"	3"	DP8(C/V/U)120PT1	8.	9.	9.
	Three-Way	1/2"	3"	3"	DP8(C/V/U)120PT3	8.	9.	9.
	Two-Way	1/2"	3"	3"	DP8(C/V/U)120PT2	8.	9.	9.
Post Covers (Straight) 		36"			DP8120PC36SF	51.	54.	60.
		42"			DP8120PC42S	51.	54.	60.
		50"			DP8120PC50S	52.	57.	61.
		57"			DP8120PC57S	60.	63.	67.
		64"			DP8120PC64S	60.	63.	67.
		78"			DP8120PC78S	67.	74.	77.
Universal Post (Post Only) 		36"	3"	3"	DP8120PO36	223.		
		42"	3"	3"	DP8120PO42	223.		
		50"	3"	3"	DP8120PO50	235.		
		57"	3"	3"	DP820PO57	255.		
		64"	3"	3"	DP8120PO64	255.		
		78"	3"	3"	DP8120PO78	344.		

Ordering Information	Order Code	Included with:	Options
Universal Post 1. Pattern Number	Universal Post <i>Example:</i> DP2A P050	Universal Post Connecting hardware	120° Post Panel Top Cap and Post Covers
Panel Top Cap 1. Pattern Number 2. Trim finish	DP2A Pattern Number P050	Panel Top Cap Post Covers	(4) = Metal, Radius (5) = Metal, Flat
Post Covers 1. Pattern Number 2. Trim finish	<i>Example:</i> DPV1 PT4, V04 DPV1 PT4 Pattern Number V04 Maple trim finish		
	Post Covers <i>Example:</i> DP2A PC50S, 117 DP(2A) Pattern Number PC50S 117 Soft grey trim finish		

This page intentionally left blank

Grain Direction



120° Planning

120° Worksurface and Transition Tops

Dividends Horizon

description	top name	w	return depth	d	pattern no.	2 mm	woodgrain edge	metal edge
Worksurface	W11L	48"	18"L-24"R		D1WW11481824	\$1,188.	\$1,305.	\$1,424.
	W11R	48"	24"L-18"R		D1WW11482418	1,188.	1,305.	1,424.
	W12L	48"	24"		D1WW124824L	1,239.	1,368.	1,490.
	W12R	48"	24"		D1WW124824R	1,239.	1,368.	1,490.
	W1318L	48"	24"L-18"R		D1WW13482418	1,188.	1,305.	1,424.
	W1318R	48"	18"L-24"R		D1WW13481824	1,188.	1,305.	1,424.
	W13L	48"	24"		D1WW134824L	1,188.	1,305.	1,424.
	W13R	48"	24"		D1WW134824R	1,188.	1,305.	1,424.
	W218L	48"	24"L-18"R		D1WW12482418	1,239.	1,368.	1,490.
	W218R	48"	18"L-24"R		D1WW12481824	1,239.	1,368.	1,490.
	W3	48"	24"		D1WW34824	907.	995.	1,082.
	W4	48"	24"		D1WW44824	930.	1,025.	1,117.
	W5L	48"	24"		D1WW54824L	749.	825.	903.
	W5R	48"	24"		D1WW54824R	749.	825.	903.
	W6L	48"	24"		D1WW64824L	1,006.	1,107.	1,207.
	W6R	48"	24"		D1WW64824R	1,006.	1,107.	1,207.
	W7L	48"	24"		D1WW74824L	1,002.	1,105.	1,203.
W7R	48"	24"		D1WW74824R	1,002.	1,105.	1,203.	
Transition tops	T2	50"	24"		D1WT224	603.	665.	725.
	T218	37 1/2"	18"		D1WT218	565.	624.	678.
	T3	26"	24"		D1WT324	575.	635.	694.
	T4	26"	24"		D1WT424	693.	761.	829.
	T5	50"	24"		D1WT524	700.	771.	837.
	T518	37 1/2"	18"		D1WT518	628.	689.	751.

Alternative Planning

Ordering Information

Worksurface

1. Pattern number
2. Finish

Order Code

Example:	D1WW134824L, 118, 118
D1W	Dividends 120 w/s 2mm edge
W13	Worksurface #13
4824	Side width/return depth
L	Pedestal on left side
118	Bright White laminate
118	Bright White edge

Included with:

Worksurface

- Worksurface

Worksurface supports must be ordered separately.

For all tops, specify laminate and edge color.

Transition and peninsula tops require a column base for support.

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Refer to the worksurface planning page for worksurface drawings and applications.

Note: W3 worksurfaces have a grain direction option. Specify left, right or diagonal. Add \$26 to the list price when specifying diagonal.

3+1 Circuit Electrical

The Dividends Horizon 3+1 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring a single isolated circuit is required.

The wire configuration of the 8-wire/4 circuit electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Hot "C" (blue)
- Shared neutral "N1" (white/black) for circuits #1, 2 and 3
- Shared ground "G1" (green) for circuits #1, 2 and 3
- Hot "X" (pink)
- Isolated neutral "N2" (white/red) for circuit 4
- Isolated ground "G2" (green/yellow) for circuit 4

Circuits 1, 2 and 3 have shared neutral and grounds for convenience power while circuit 4 has a separate ground and neutral for designated/isolated power or to support uninterrupted power supply (UPS).

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+1 components can be connected to 3+3 wire systems, however only 3+1 will function.

3+1 Duplex Receptacles

Duplex receptacles used in 3+1 electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)

Isolated duplex receptacle number 4 has an orange-colored triangle on black background to identify an isolated duplex.

An optional orange-colored isolated duplex is also available. It has the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)

3+1 Electrical System Technical Specifications

The 3+1 electrical system consists of four 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric Code (NEC) limits continuous loads to 80% of capacity or 16 amps.

Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 8-wire (4-circuit) system can supply a cluster of 6 - 10 workstations from each infeed.

Independent Neutral Electrical Systems

Dividends Horizon offers a 2+1 electrical system with independent neutrals as a standard special. It is our belief that independent neutrals are not required. However, if a customer desires an independent neutral electrical system, a Dividends Horizon solution can be provided. For further information, list pricing and schematic drawings, contact Knoll Customer Service.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.


Power Connector

Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (3+1)



2+2 Electrical System

The Dividends Horizon 2+2 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring two isolated circuits are required.

The wiring configuration of the (2+2) electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Shared neutral "N1" (white/black) for circuits #1 and 2
- Shared ground "G1" (green) for circuits #1 and 2
- Hot "Y" (tan)
- Hot "X" (pink)
- Isolated Shared Neutral "N2" (white/red) for circuits #4 and 5
- Isolated Shared ground "G2" (green/yellow) for circuits #4 and 5

Circuits 1 and 2 share common neutral and ground. Circuits 4 and 5 share a separate common neutral and ground.

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable.

2+2 Duplex Receptacles

Duplex receptacles used in 8-wire (2+2) electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)

2+2 Electrical System Technical Specifications

The 2+2 electrical system consists of four 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase, and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric Code (NEC) limits continuous loads up to 80% of capacity or 16 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.


Power Connector

Specify one power connector (with or without post) to connect power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (2+2)



3+3 Electrical System

The Dividends Horizon 3+3 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring multiple isolated circuits is required.

The wiring configuration of the 3+3 electrical system is (see chart):


- Hot "A" (black)
- Hot "B" (red)
- Hot "C" (blue)
- Shared neutral "N1" (white/black) for circuits #1, 2 and 3
- Shared ground "G1" (green) for circuits #1, 2 and 3
- Hot "Z" (orange)
- Hot "X" (pink)
- Hot "Y" (tan)
- Isolated neutral "N2" (white/ red for circuits 4, 5 and 6
- Isolated ground "G2" (green/yellow) for circuits 4, 5 and 6

Circuits 1, 2 and 3 are for convenience power while circuits 4, 5 and 6 are for designated/ isolated power or for supporting uninterrupted power supply (UPS).

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+3 components can be connected to 3+1 systems, however only 8-wires will function.

Wiring Diagram (3+3)



3+3 Duplex Receptacles

Duplex receptacles used in 3+3 electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)
- Isolated duplex circuit number 6 (pattern number DE1DR6)

Isolated duplex receptacles number 4, 5 and 6 have an orange-colored triangle on black background to signify as an isolated duplex.

Optional orange-colored isolated duplexes are also available. They have the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)
- Isolated orange-colored duplex circuit number 5 (pattern number DE1DOR5)
- Isolated orange-colored duplex circuit number 6 (pattern number DE1DOR6)

3+3 Electrical System Technical Specifications

The 3+3 electrical system consists of six 20 amp, 120 volt, 60-Hertz circuits. The circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. System components are 20 amp capacity. The National Electric Code (NEC) limits continuous loads to 80% of capacity or 16 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 10-wire (6-circuit) system can supply a cluster of 9 - 15 workstations from each infeed.

Surge Suppressors

Dividends Horizon surge suppressors (pattern number DE1SS) plug into any terminal block position to provide surge protection for all duplexes on that circuit.

Note: When connected, surge suppressors take the place of a duplex receptacle resulting in the elimination of one duplex position from the circuit.

Independent Neutral Electrical Systems

Dividends Horizon offers a 10-wire/2+2 electrical system with independent neutrals as a standard special. It is our belief that independent neutrals are not required. However, if a customer desires an independent neutral electrical system, a Dividends Horizon solution can be provided. For further information, list pricing and schematic drawings, contact Knoll Customer Service.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.

Power Connector

Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Base Raceway Electrical

Power Modules, Power Jumpers

Specifications

Base Raceway Electrical

Power can be distributed through the base raceway.

Three systems are available:

- 3 + 1
- 2 + 2
- 3 + 3

Modular components are used to distribute power through the base raceway and consist of:

- Power modules
- Power connectors
- Power jumpers
- Duplex receptacles
- Power infeeds

All electrical components and data cables are field-installed.

CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Power Modules

Power modules are the primary electrical components for distributing electrical within panels. They are also the only components that accept duplex receptacles and power infeeds for access.

Panels 24" and wider can accept power modules. 18" wide panels only accept power jumpers.

Power modules consist of terminal blocks at each end connected by a hard-wired metal conduit. The terminal blocks accept duplex receptacles or power infeeds. Power modules snap into integral channels in base raceways and can be accessed on one or both panel sides.

Power Jumpers

Power jumpers connect between power modules in non-adjacent panels. Power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:


- Single panel power jumpers
- Single panel power jumpers with post
- Multiple panel power jumpers

Single panel power jumpers carry power from a panel with a power module through a single non-electrified panel to an adjacent panel with a power module when a post connector is not involved.

Single panel power jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a power module.

Multiple panel power jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available power module.

Base Raceway Electrical



Base Raceway Electrical 3+1, 2+2 and 3+3 Systems Specifications

Power Connectors

Power connectors carry power from power module to power module in adjacent panels.

Two versions are available:

- 12" no post
- 15" with post

12" power connectors connect adjacent power modules in straight configurations when no post connector is involved.

15" power connectors are used in applications involving adjacent power modules separated by post connectors.

Duplex Receptacles

Duplex receptacles provide access to power along the base raceway.

Two duplex receptacles can be installed per panel side in base raceways 24" and wider. 18" wide panels cannot accept duplex receptacles.

Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.

Duplexes are available in (3+1), (2+2) and (3+3) systems. Each system engages a different combination of circuit wiring within the power module. For detailed wiring diagrams, refer to the electrical system required:

- 3 + 1
- 2 + 2
- 3 + 3

3+1, 2+2 and 3+3 Electrical Systems

Each electrical system is designed for different usage.

The (2+2) electrical system is for areas requiring 2 circuits for standard power usage and 2 circuits for isolated power usage.

The (3+1) electrical system is for areas requiring significant power usage and an isolated circuit.


The (3+3) electrical system is for areas with significant power usage and a need for multiple isolated circuits.

Base Power Infeeds


Base power infeeds route power from the building's electrical source to the panel base raceway.

Power infeeds plug into any terminal block position on panel power modules.


Power Connector



Duplex Receptacle



Base Infeed








Legend



- Power Module
- ⋯ Power Jumper
- Power Connector

Note: Power connectors or power jumpers can only plug into power modules


Power Connectors




Single Panel Power Jumpers



Multiple Panel Power Jumpers



Multiple Panel Power Jumper and Power Connector








Base Raceway Electrical

Power Modules, Connectors and Jumpers

(3+1), (2+2) and (3+3)

Dividends Horizon

description	type	pattern no.	E	8	T
Power Module - Double sided for raceway on both sides 	24"W Panel	DE1(E,8,T) PM24	\$123.	\$137.	\$141.
	30"W Panel	DE1(E,8,T) PM30	132.	145.	145.
	36"W Panel	DE1(E,8,T) PM36	137.	149.	153.
	42"W Panel	DE1(E,8,T) PM42	147.	161.	160.
	48"W Panel	DE1(E,8,T) PM48	156.	168.	167.
	60"W Panel	DE1(E,8,T) PM60	173.	191.	191.
Power Module - Single sided for raceway on one side 	24"W Panel	DE1(E,8,T) PMS24	123.	137.	141.
	30"W Panel	DE1(E,8,T) PMS30	132.	145.	145.
	36"W Panel	DE1(E,8,T) PMS36	137.	149.	153.
	42"W Panel	DE1(E,8,T) PMS42	147.	161.	160.
	48"W Panel	DE1(E,8,T) PMS48	156.	168.	167.
	60"W Panel	DE1(E,8,T) PMS60	173.	191.	191.
Power Connector - (power module-to-power module) 	12" no post	DE1(E,8,T) PCNP	81.	87.	98.
	15" with post	DE1(E,8,T) PCWP	83.	89.	106.
	21" Mesh with post	DE1(E,8,T) PC21M	89.	95.	105.
Power Jumper 	15" Panel	DE1(E,8,T) PJ15NP	92.	109.	137.
	18" Panel	DE1(E,8,T) PJ18NP	92.	109.	137.
	24" Panel	DE1(E,8,T) PJ24NP	108.	114.	143.
	30" Panel	DE1(E,8,T) PJ30NP	111.	119.	148.
	36" Panel	DE1(E,8,T) PJ36NP	114.	124.	157.
	42" Panel	DE1(E,8,T) PJ42NP	119.	133.	161.
	48" Panel	DE1(E,8,T) PJ48NP	128.	142.	167.
Power Jumper (with post) 	15" Panel + Post	DE1(E,8,T) PJ15WP	103.	112.	141.
	18" Panel + Post	DE1(E,8,T) PJ18WP	103.	112.	141.
	24" Panel + Post	DE1(E,8,T) PJ24WP	109.	117.	147.
	30" Panel + Post	DE1(E,8,T) PJ30WP	112.	122.	152.
	36" Panel + Post	DE1(E,8,T) PJ36WP	117.	131.	160.
	42" Panel + Post	DE1(E,8,T) PJ42WP	123.	137.	163.
	48" Panel + Post	DE1(E,8,T) PJ48WP	132.	145.	172.

Ordering Information

Power Jumper
1. Pattern Number

Order Code

Power Jumper
Example: **DE1E PJ42NP**
DE1E Pattern Number
PJ42NP

Included with:

Power Jumper

Options


Power Jumper

Options
(E) = 3+1
(8) = 2+2
(T) = 3+3

Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

Base Raceway Electrical
Power Modules, Connectors and Jumpers
(3+1), (2+2) and (3+3)

Dividends Horizon

description	type	pattern no.	E	8	T
Multiple Panel Power Jumper (with or without post) 	54" Panel Run	DE1(E,8,T) PJ54WP	\$139.	\$152.	\$179.
	60" Panel Run	DE1(E,8,T) PJ60WP	142.	157.	179.
	66" Panel Run	DE1(E,8,T) PJ66WP	149.	163.	192.
	72" Panel Run	DE1(E,8,T) PJ72WP	153.	167.	198.
	78" Panel Run	DE1(E,8,T) PJ78WP	160.	175.	202.
	84" Panel Run	DE1(E,8,T) PJ84WP	165.	185.	206.
	96" Panel Run	DE1(E,8,T) PJ96WP	174.	194.	222.

Ordering Information

Power Jumper

1. Pattern Number

Order Code

Power Jumper

Example: **DE1E PJ42NP**

DE1E Pattern Number

PJ42NP

Included with:

Power Jumper

Options

Power Jumper

Options

(E) = 3+1

(8) = 2+2

(T) = 3+3

Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

This page intentionally left blank

Duplex Receptacles

Duplexes are field-installed into power modules within beltway and base raceways. Duplex receptacles insert into panel power module terminal block positions and attach with a single screw.

Identification of Duplexes

Duplexes are clearly marked to indicate which circuits they access. Convenience duplex receptacles are black or white in color with the circuit identification in white.

Isolated duplexes are black or white in color with the circuit identification in white and an orange triangle located in the lower right corner.

Orange isolated duplexes are also available for ease of identification. In orange-colored duplexes the identifying triangle is outlined in black.

Types of Duplex Receptacles

Several types of duplex outlets are available. Each is specific to the circuit it accesses and is listed by power system.

Specify the duplex receptacle related to the power system being used (example: 8-wire) and circuit accessed (example: circuit 4). Black, white or orange finish.

3+1 Duplex Receptacles

Receptacles in a 3+1 electrical system can access circuits 1, 2 and 3 (convenience power) and circuit 4 (isolated power)

2+2 Duplex Receptacles

Receptacles in a 2+2 electrical system can access circuits 1 and 2 (convenience power) and circuits 4 and 5 (isolated power)

Please note that circuit 3 is not available in a 2+2 electrical system.

3+3 Duplex Receptacles

Receptacles in a 3+3 electrical system can access circuits 1, 2 and 3 (convenience power) and circuits 4, 5 and 6 (isolated power)

Power Capacity

Each duplex circuit has a capacity of 20 amps. The National Electrical Code (NEC) requires that each circuit does not exceed 80% of capacity or 16 amps continuous use on each 20 amp circuit.

Duplex Receptacle Dimensions

- Overall dimensions: 4 ⁵/₈" wide, 2 ¹/₁₆" high, 1" deep
- Face dimensions: 2 ⁵/₈" wide, 1 ¹/₄" high

Access


Non-electrified panels can accept data ports in any raceway cover knockout. Panels with power modules can only accept data ports in the center knockout due to the location of the terminal block.

Typical Power Requirements of Various Equipment


Equipment	Amp (approx.)
Calculator	.25
Coffee maker*	8.5-15
Desktop copier*	10-15
Fan	1
Fax (plain paper)	5-8
Heater*	8.5-15
Laser printer	6-10
Lighting	.5-1.5
Microwave*	10-20
PC	4-8
Refrigerator*	10-15
Terminal	1-3
Typewriter	1-2
Scanner	.25-.5

*Requires separate circuit


Note: The above amperage chart is based on the estimated average amount of power required and is intended as a general guide only. For precise amperage requirements, refer to the equipment manufacturer's amperage specifications and compare to the available amperage on each circuit.



Base Raceway Covers (knockout locations)









Beltway Covers (knockout locations)



Receptacles

Knockout Replacement Covers



Dividends Horizon

description	type	pattern no.	Single pack list	Ten pack list
Receptacle, (3+1) 	Duplex circuit 1	DE1DR1 ()	\$43.	\$342.
	Duplex circuit 2	DE1DR2 ()	43.	342.
	Duplex circuit 3	DE1DR3 ()	43.	342.
	Duplex circuit 4	DE1DR4 ()	43.	342.
Receptacle, (2+2) 	Duplex circuit 1	DE1DR1 ()	43.	342.
	Duplex circuit 2	DE1DR2 ()	43.	342.
	Duplex circuit 4	DE1DR4 ()	43.	342.
	Duplex circuit 5	DE1DR5 ()	43.	342.
Receptacle, (3+3) 	Duplex circuit 1	DE1DR1 ()	43.	342.
	Duplex circuit 2	DE1DR2 ()	43.	342.
	Duplex circuit 3	DE1DR3 ()	43.	342.
	Duplex circuit 4	DE1DR4 ()	43.	342.
	Duplex circuit 5	DE1DR5 ()	43.	342.
	Duplex circuit 6	DE1DR6 ()	43.	342.
Receptacle, (Orange) 	Duplex circuit 4	DE1DOR4()	43.	342.
	Duplex circuit 5	DE1DOR5()	43.	342.
	Duplex circuit 6	DE1DOR6()	43.	342.
Receptacle, (With Controlled Symbol) 	Duplex circuit 1	DE1DR1C ()	43.	342.
	Duplex circuit 2	DE1DR2C ()	43.	342.
	Duplex circuit 3	DE1DR3C ()	43.	342.
	Duplex circuit 4	DE1DR4C ()	43.	342.
	Duplex circuit 5	DE1DR5C ()	43.	342.
	Duplex circuit 6	DE1DR6C ()	43.	342.
Base Raceway Knockout Replacement Cover (for electrical or data) 	Package of 10	DE2KC10	n/a	78.

Electrical/Data Components

Ordering Information	Order Code	Included with:	Options
Receptacle 1. Pattern Number	Receptacle <i>Example:</i> DE1 DR4 DE1 DR4 Pattern Number	Receptacle	Receptacle Quantity Option: (SP) = Single Pack (TP) = Ten Pack Color Option: Black = B White = W

Receptacles USB

description	type	pattern no.	Single pack list	Ten pack list
 USB Receptacle Vertical	Circuit 1	DE1USB1V()	\$120.	\$1,140.
	Circuit 2	DE1USB2V()	120.	1,140.
	Circuit 3	DE1USB3V()	120.	1,140.
	Circuit 4	DE1USB4V()	120.	1,140.
	Circuit 5	DE1USB5V()	120.	1,140.
	Circuit 6	DE1USB6V()	120.	1,140.
 USB Receptacle Horizontal	Circuit 1	DE1USB1H()	120.	1,140.
	Circuit 2	DE1USB2H()	120.	1,140.
	Circuit 3	DE1USB3H()	120.	1,140.
	Circuit 4	DE1USB4H()	120.	1,140.
	Circuit 5	DE1USB5H()	120.	1,140.
	Circuit 6	DE1USB6H()	120.	1,140.

Ordering Information

Vertical Power Module

1. Pattern Number

Order Code

Vertical Power Module

Example: **DE1 USB 1V10W**

DE1USB Pattern Number
1V10W

Included with:

Vertical Power Module

- USB Receptacle

Options

Vertical Power Module

Quantity Option:

(V) = Vertical Single Pack
(V10) = Vertical Ten Pack
(H) = Horizontal Single Pack
(H10) = Horizontal Ten Pack

Color Option:

(B) = Black
(W) = White

This page intentionally left blank

Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate Specifications

Vertical Power Module

A vertical power module is an alternative to using beltway electrical. The use of a vertical power module allows for electrical access within a panel without having to order a beltway panel. Vertical power modules can be installed below a worksurface, at desk height or even within a panel-mounted overhead cabinet.

A panel's left-hand or right-hand vertical rail (see below) allows for installation of a vertical power module. Vertical power modules may be installed with 1-sided or 2-sided access, allowing users of both panel faces access to an electrical receptacle.

Base Power Jumpers

Base raceway power jumpers are used to connect the adjacent panel's base power module to the vertical power module.

Additional vertical power modules may be "daisy-chained" together with base power jumpers. If one vertical power module is installed, an additional vertical power module may be added within the same panel. A base power jumper connects between the two vertical power modules.

Vertical power modules can also be daisy-chained in adjacent panels. A base power jumper passes through the beltway panel frame opening to connect to the additional vertical power module.

Vertical Electrical Receptacle

Please note that base raceway receptacles are not compatible with vertical power modules.

Vertical electrical receptacles must be ordered separately from the vertical power module. Vertical electrical receptacles consist of one vertical receptacle. One vertical power module can also accommodate back-to-back vertical electrical receptacles.

To provide back-to-back vertical electrical power, two vertical receptacles must be specified. Vertical electrical receptacles must be ordered separately.

Specify the vertical receptacle that relates to the circuit specified.

Desktop Power module

Desktop power modules (DE3WSME) provide two low-profile outlets at worksurface height. The desktop power module also helps meet ADA requirements regarding power access at worksurface height.

A mounting bracket and attachment screw allow the desktop power module to be installed at any point along the rear of a worksurface without tools or the removal of the worksurface. An 8 1/2" power cord plugs into any duplex receptacle in the base raceway and accesses the circuit it is connected to. Desktop power module dimensions are 3 3/4" wide and 4 1/2" high.

Base Raceway Power Jumpers

To specify a base power jumper that connects a desk height vertical power module to an adjacent panel's base power module, specify a 48" base power jumper for panel widths of 36" or less. Use a 54" base power jumper for panel widths of 42" or 48". If a vertical power module is to be installed higher than worksurface height within a 64" high panel, a 66" base power jumper is required and an 84" base power jumper is required for 78" high panels.


To specify a base power jumper to span the width of two vertical power modules within two adjacent panels, identify the base power jumper length by combining the panel widths and height differences between the two vertical power modules.

Note: The base power jumper passes through the panel's beltway opening that is at a height of 33".



The panel's beltway opening (at 33" high) must not be obstructed as to allow for the base power jumper to pass through.

Note: 36" high panel frames do not have beltway openings and do not support horizontal power pass through at 33".

Note: Vertical electrical components can be used with a technology tile or field installed into a fabric tile.



Vertical Electrical Power Jumpers



Vertical Power Module and Electrical Receptacle

Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate Specifications

Communications and Data Distribution

Dividends Horizon panels can accommodate communications and data cables horizontally in three ways:

- Along the top cableway
- Along the beltway (with optional cable tray)
- Along the base raceway (with optional cable tray)

Vertical cable distribution is through the panel's internal panel cavity which is accessed by cable slots located in both the upper and lower horizontal panel frame. Since cables are distributed internally within Dividends Horizon panels, no external cable managers are required.

Raceway cover data knockouts have an opening of 1³/₈" high x 2¹¹/₁₆" wide. Data port covers are no longer available from Knoll and must be supplied from a communications vendor.

Data Port Access

Non-electrified panels can accept data ports in any raceway cover knockout.

Panels with power modules can only accept data ports in the center knockout due to the location of the terminal blocks.

Single Floating Data Port

Dividends Horizon floating data ports allow data and communications to be mounted in any location on the panel surface.

Floating data ports include front and back mounting plates and attachment screws. All data port kits must be specified separately for floating data ports. Floating data ports involve field-cutting the panel insert for installation.


Includes front and back mounting plates and two mounting screws. Data ports kits or data port components must be specified separately from a communications vendor. Black finish.

Desktop Modules




The desktop data module provides up to two data/communication ports at worksurface height. The desktop power module provides two convenient electrical outlets at worksurface height. The desktop power and data module includes two data/communication ports and two electrical outlets at worksurface height. The thumbscrew on the bracket allows user adjustability if desired. Black finish.

Data modules do not include data jacks. Data jacks need to be purchased separately. This data module has two openings that can accept most standard jack sizes. The data module comes with adapter pieces that can accommodate most standard data jacks.


Topway Panel Cable Routing




Floating Data Port




Desktop Power and Data Module



Desktop Data Module



Desktop Power Module







Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate

Double and Single Ports

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	3+3
Vertical Power Module	Vertical Power Module	DE6 VPM	\$223.	n/a			
Vertical Electrical Receptacle (3+1)	Duplex circuit 1	DE6 VDR1()	43.	342.			
	Duplex circuit 2	DE6 VDR2()	43.	342.			
	Duplex circuit 3	DE6 VDR3()	43.	342.			
	Duplex circuit 4	DE6 VDR4()	43.	342.			
Vertical Electrical Receptacle (2+2)	Duplex circuit 1	DE6 VDR1()	43.	342.			
	Duplex circuit 2	DE6 VDR2()	43.	342.			
	Duplex circuit 4	DE6 VDR4()	43.	342.			
	Duplex circuit 5	DE6 VDR5()	43.	342.			
Vertical Electrical Receptacle (3+3)	Duplex circuit 1	DE6 VDR1()	43.	342.			
	Duplex circuit 2	DE6 VDR2()	43.	342.			
	Duplex circuit 3	DE6 VDR3()	43.	342.			
	Duplex circuit 4	DE6 VDR4()	43.	342.			
	Duplex circuit 5	DE6 VDR5()	43.	342.			
	Duplex circuit 6	DE6 VDR6()	43.	342.			




Ordering Information	Order Code	Included with:	Options
Vertical Power Module	Vertical Power Module	Vertical Power Module	Vertical Power Module
1. Pattern Number	<i>Example:</i> DE5 VPM	Base Raceway Power Jumper	Base Raceway Power Jumper
Base Raceway Power Jumper	DE5 VPM Pattern Number		Insert appropriate letter for type of wiring required within the parentheses of the pattern number.
1. Pattern Number	Base Raceway Power Jumper		(E) = 3+1
	<i>Example:</i> DE1(E) BPJ30		(8) = 2+2
	DE1(E) Pattern Number		(T) = 3+3
	BPJ30		Receptacle Quantity Option:
			(SP) = Single Pack
			(TP) = Ten Pack
			Note: Trim plate filler for use with technology tile trim plate only.
			Color Option:
			Black = B
			White = W

Vertical Electrical


Power Module, Electrical Receptacle and Trim Plate

Double and Single Ports


description	type	pattern no.	Single pack	Ten pack	3+1	2+2	3+3
Vertical Electrical Receptacle (With Controlled Symbol)	Duplex circuit 1	DE6 VDR1C()	\$43.	\$342.			
	Duplex circuit 2	DE6 VDR2C()	43.	342.			
	Duplex circuit 3	DE6 VDR3C()	43.	342.			
	Duplex circuit 4	DE6 VDR4C()	43.	342.			
	Duplex circuit 5	DE6 VDR5C()	43.	342.			
	Duplex circuit 6	DE6 VDR6C()	43.	342.			



Trim Plate Filler	Package of 10	DE6 FDPF	n/a	45.			
-------------------	---------------	-----------------	-----	-----	--	--	--



Single Floating Data Port Trim Plate (field install kit)	Faceplate, backplate and hardware	DE1 FDP	52.	n/a			
---	--------------------------------------	----------------	-----	-----	--	--	--



Ordering Information	Order Code	Included with:	Options
Vertical Power Module 1. Pattern Number	Vertical Power Module <i>Example:</i> DE5 VPM	Vertical Power Module	Vertical Power Module
Base Raceway Power Jumper 1. Pattern Number	DE5 VPM Pattern Number Base Raceway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30	Base Raceway Power Jumper	Base Raceway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. (E) = 3+1 (8) = 2+2 (T) = 3+3 Receptacle Quantity Option: (SP) = Single Pack (TP) = Ten Pack Note: Trim plate filler for use with technology tile trim plate only. Color Option: Black = B White = W


Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate

Double and Single Ports

Dividends Horizon

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	3+3
Technology Tile Trim Plate (field install kit)	Faceplate, backplate filler and hardware	DE6 FDP	\$57.	n/a			







Base Raceway Power Jumpers							
	48" Jumper	DE1(E,8,T) PJ48WP			132.	145.	172.
	54" Jumper	DE1(E,8,T) PJ54WP			139.	152.	179.
	60" Jumper	DE1(E,8,T) PJ60WP			142.	157.	179.
	66" Jumper	DE1(E,8,T) PJ66WP			149.	163.	192.
	72" Jumper	DE1(E,8,T) PJ72WP			153.	167.	198.
	78" Jumper	DE1(E,8,T) PJ78WP			160.	175.	202.
	84" Jumper	DE1(E,8,T) PJ84WP			165.	185.	206.

Ordering Information	Order Code	Included with:	Options
Vertical Power Module	Vertical Power Module	Vertical Power Module	Vertical Power Module
1. Pattern Number	<i>Example:</i> DE5 VPM	Base Raceway Power Jumper	Base Raceway Power Jumper
Base Raceway Power Jumper	DE5 VPM Pattern Number		Insert appropriate letter for type of wiring required within the parentheses of the pattern number.
1. Pattern Number	Base Raceway Power Jumper		(E) = 3+1
	<i>Example:</i> DE1(E) BPJ30		(8) = 2+2
	DE1(E) Pattern Number		(T) = 3+3
	BPJ30		Receptacle Quantity Option:
			(SP) = Single Pack
			(TP) = Ten Pack
			Note: Trim plate filler for use with technology tile trim plate only.
			Color Option:
			Black = B
			White = W

Desktop Power and Data Modules





Table Undermount Outlet

description	type	pattern no.	list
Electrical Outlet for Table Undermount 210, 2 power + 1 dual USB + 0 data 	120" cordset	DE4TU210120(BB/WW/WS)	\$545.
	72" cordset	DE4TU21072(BB/WW/WS)	528.
	72" hardwire	DE4TU210H(BB/WW/WS)	588.
Electrical Outlet for Table Undermount 202, 2 power + 0 dual USB + 2 data 	120" cordset	DE4TU202120(BB/WW/WS)	496.
	72" cordset	DE4TU20272(BB/WW/WS)	455.
	72" hardwire	DE4TU202H(BB/WW/WS)	569.
Electrical Outlet for Table Undermount 311, 3 power + 1 dual USB + 1 data 	120" cordset	DE4TU311120(BB/WW/WS)	657.
	72" cordset	DE4TU31172(BB/WW/WS)	638.
	72" hardwire	DE4TU311H(BB/WW/WS)	722.
Electrical Outlet for Table Undermount 412, 4 power + 1 dual USB + 2 data 	120" cordset	DE4TU412120(BB/WW/WS)	729.
	72" cordset	DE4TU41272(BB/WW/WS)	711.
	72" hardwire	DE4TU412H(BB/WW/WS)	796.

Order Code	Specification Information	Application Notes
Example: DE4TU21072 (BB)	<i>To order please specify pattern number including:</i>	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet		
TU Table Undermount		Refer to planning guide pages for complete description.
210 2 Power, 1 USB, 0 Data	1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
72 72" cordset, 120=120" cord, H=72" Hardwire		Simplex receptacles and USB charging ports are wired together and on the same circuit.
() Color Option		

Desktop Power and Data Modules





Clamp-on

description	type	pattern no.	list
Clamp-on Electrical Outlet 210, 2 power + 1 dual USB + 0 data 	120" cordset	DE4CL210120(BB/WW/WS)	\$585.
	72" cordset	DE4CL21072(BB/WW/WS)	569.
	72" hardwire	DE4CL210H(BB/WW/WS)	628.
Clamp-on Electrical Outlet 202, 2 power + 0 dual USB + 2 data 	120" cordset	DE4CL202120(BB/WW/WS)	491.
	72" cordset	DE4CL20272(BB/WW/WS)	471.
	72" hardwire	DE4CL202H(BB/WW/WS)	556.
Clamp-on Electrical Outlet 311, 3 power + 1 dual USB + 1 data 	120" cordset	DE4CL311120(BB/WW/WS)	646.
	72" cordset	DE4CL31172(BB/WW/WS)	627.
	72" hardwire	DE4CL311H(BB/WW/WS)	712.
Clamp-on Electrical Outlet 412, 4 power + 1 dual USB + 2 data 	120" cordset	DE4CL412120(BB/WW/WS)	722.
	72" cordset	DE4CL41272(BB/WW/WS)	704.
	72" hardwire	DE4CL412H(BB/WW/WS)	788.

Order Code	Specification Information	Application Notes
Example: DE4CL21072 (BB)	<i>To order please specify pattern number including:</i>	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet	1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	Refer to planning guide pages for complete description.
CL Clamp-on		USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
210 2 Power, 1 USB, 0 Data		Simplex receptacles and USB charging ports are wired together and on the same circuit.
72 72" cordset, 120=120" cord, H=72" Hardwire		
() Color Option		

Desktop Power and Data Modules

Offset Clamp-on

description	type	pattern no.	list
Offset Clamp-on Electrical Outlet 202, 2 power + 0 dual USB + 2 data 	72" cordset	DE4OC20272 (BB/WW/WS)	\$471.
	120" cordset	DE4OC202120 (BB/WW/WS)	491.
	72" hardwire	DE4OC202H (BB/WW/WS)	556.
Offset Clamp-on Electrical Outlet 210, 2 power + 1 dual USB + 0 data 	72" cordset	DE4OC21072 (BB/WW/WS)	569.
	120" cordset	DE4OC210120 (BB/WW/WS)	585.
	72" hardwire	DE4OC210H (BB/WW/WS)	628.
Offset Clamp-on Electrical Outlet 311, 3 power + 1 dual USB + 1 data 	72" cordset	DE4OC31172 (BB/WW/WS)	627.
	120" cordset	DE4OC311120 (BB/WW/WS)	646.
	72" hardwire	DE4OC311H (BB/WW/WS)	712.
Offset Clamp-on Electrical Outlet 412, 4 power + 1 dual USB + 2 data 	72" cordset	DE4OC41272 (BB/WW/WS)	704.
	120" cordset	DE4OC412120 (BB/WW/WS)	722.
	72" hardwire	DE4OC412H (BB/WW/WS)	788.

Order Code	Specification Information	Application Notes
Example: DE4OC21072 (BB)	<i>To order please specify pattern number including:</i>	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet	1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	Refer to planning guide pages for complete description.
OC Offset Clamp-on		USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
210 2 Power, 1 USB, 0 Data		Simplex receptacles and USB charging ports are wired together and on the same circuit.
72 72" cordset, 120=120" cord, H=72" Hardwire		
() Color Option		

Desktop Power and Data Modules

Clamp mount

description	type	w	d	h	pattern no.	list
Desktop Power Module, clamp mount	With 108" Cord	3 3/4"	4 1/2"	2 1/2"	DE4WSME108	\$156.
	With 72" Cord	3 3/4"	4 1/2"	2 1/2"	DE4WSME72	124.



Desktop Power + Data Module, clamp mount	With 108" Cord	6 1/8"	4 1/2"	2 1/2"	DE4WSMED108	333.
	With 72" Cord	6 1/8"	4 1/2"	2 1/2"	DE4WSMED72	301.



Desktop Data Module, clamp mount		3 3/4"	4 1/2"	2 1/2"	DE4WSMC	110.
-------------------------------------	--	--------	--------	--------	----------------	------



Ordering Information	Order Code	Included with	Options
Desktop Power Module	Desktop Power Module		
1. Pattern Number	<i>Example:</i> DE4 WSME108		

This page intentionally left blank

Beltway Electrical

Power can be distributed through the beltway

Three systems are available:

- 3+1
- 2+2
- 3+3

Modular components are used to distribute power within beltways and consist of:

- Beltway power modules
- Beltway power connectors
- Beltway power jumpers
- Beltway vertical power jumpers
- Duplex receptacles

All electrical components and data cables are field-installed.

WARNING: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTING TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Beltway modules accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway. Another alternative for desk height electrical is a vertical power module.

Depending on the number of desk height receptacles required in each panel, consider the list price of both beltway electrical and vertical power module in each application.

Beltway Power Modules

Power modules are the primary electrical components for distributing power within beltways. Beltway power modules are also components that accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway.

Beltway raceways 30" and wider can accept beltway power modules while 18" and 24" wide panels can accept power jumpers for pass-through power only.

Beltway power modules screw into the vertical channels of panel frames and include a steel horizontal mounting support.

Specify one beltway power module per panel that matches the width of the panel where duplexes are required. Available one- or two-sided.

Just like base raceway power modules, beltway power modules consist of a terminal block at each end connected by a hard-wired metal conduit.

Beltway power modules are one- or two-sided. This allows planning options such as beltway one side and monolithic or tiled inserts on the other, or beltway one side and no inserts on the other for against-the-wall applications. The terminal blocks accept either duplex receptacles or vertical power jumpers.

Beltway Power Connectors

Beltway power connectors carry power from power module to power module in adjacent panels.

Two versions are available:


- no post
- with post.

Beltway power connectors, no post, connect adjacent power modules in straight configurations when a post connector is not involved.

Beltway power connectors, with post, are used in applications involving adjacent power modules separated by post connectors in straight through post configurations only.

Specify one beltway power connector (with or without post) to connect beltway power module or beltway power jumper in adjacent panels. In straight line configurations only.

Beltway Electrical



Beltway Profiles

Beltway Power Jumpers

Beltway power jumpers connect between power modules in nonadjacent panels. Beltway power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:

- Single panel jumpers
- Single panel jumpers with post
- Multiple panel jumpers

Single panel beltway jumpers carry power from a panel with a beltway power module through a single non-electrified panel to an adjacent panel with a beltway power module when a post is not involved in straight line configurations only.

Single beltway panel jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a beltway power module in straight through post configurations only.

Multiple beltway panel jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available beltway power module in straight line configurations only.

Specify one beltway power jumper per panel that matches the width of the panel for pass-through electrical where duplexes are not required for straight line configurations only.

90° Beltway Power Jumper

A 90° beltway power jumper connects adjacent beltway power modules at a 90° “L” panel connection.

The following illustrations outline the various components required for beltway applications with a post.

Note: A 90° beltway power jumper can only be used with adjacent panels in a “X”, “T” or “L” conditions. The 90° jumper cannot be used to span multiple panels.

To specify correct jumper length, determine the largest panel width between the two adjacent corner panels in which jumper is to be installed.

Vertical Power Jumpers

To carry power from the base raceway to the beltway located in the same panel requires a vertical power jumper. Vertical power jumpers function as an extension of the base raceway power system.

Attachment is from any unused outlet position in the base raceway to the end terminal block connection in the beltway power module. The vertical power jumper cable is concealed in the cavity of the panel frame.

Power can also be carried to a beltway run from the base raceway of an adjacent panel with a power module. This is accomplished by using a panel power jumper.

Specify one vertical power jumper per beltway electrical run not to exceed the electrical systems capacity. See the technical specifications for the electrical system being utilized.

Note: Length of power jumper allows for connections with or without post conditions.

Power Infeeds


A ceiling infeed may also be used to bring power directly to the beltway power module without having to go directly to a base raceway power module.

Duplex Receptacles

Duplex receptacles provide access to power along the beltway. Duplexes used in the beltway are the same as the duplexes used in the base raceway.

Two duplex receptacles can be installed per panel side in beltway raceways 30" and wider. 24"W panels will accept beltway power jumpers for pass-through power only.







Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.



Beltway Electrical

Power Modules, Power Connectors and Power Jumpers

Dividends Horizon

description	type	length	pattern no.	list	3+1	2+2	3+3
 Beltway Power Module - 1-Side		30"	DE1() BPM301	\$172.	\$190.	\$190.	
		36"	DE1() BPM361	181.	198.	194.	
		42"	DE1() BPM421	190.	204.	202.	
		48"	DE1() BPM481	198.	220.	211.	
		60"	DE1() BPM601	223.	229.	229.	
 Beltway Power Module - 2-Side		30"	DE1() BPM302	172.	190.	190.	
		36"	DE1() BPM362	181.	198.	194.	
		42"	DE1() BPM422	190.	204.	202.	
		48"	DE1() BPM482	198.	220.	211.	
		60"	DE1() BPM602	223.	229.	229.	
 Beltway Power Connector	17" No Post		DE2() BPCNP	85.	91.	107.	
	20" With Post		DE2() BPCWP	87.	101.	110.	
	21" Mesh with post		DE1(E,8,T) PC21M	89.	95.	105.	
Intermediate Connector	Independent Neutral		DE1IPA	25.			
	Shared Neutral		DE1SPA	25.			
 Beltway Power Jumper (No post)		18"	DE2() BPJ18NP	107.	113.	141.	
		24"	DE2() BPJ24NP	110.	118.	146.	
		30"	DE2() BPJ30NP	113.	123.	156.	
		36"	DE2() BPJ36NP	118.	131.	160.	
		42"	DE2() BPJ42NP	126.	140.	166.	
		48"	DE2() BPJ48NP	130.	143.	171.	
 Beltway Power Jumper (With post)		18"	DE2() BPJ18WP	108.	116.	145.	
		24"	DE2() BPJ24WP	111.	121.	150.	
		30"	DE2() BPJ30WP	116.	129.	159.	
		36"	DE2() BPJ36WP	122.	137.	162.	
		42"	DE2() BPJ42WP	130.	143.	171.	
		48"	DE2() BPJ48WP	140.	146.	173.	
 Multiple Panel Power Jumper (with or without post)		54" Panel Run	DE2() BPJ54WP	140.	156.	177.	
		60" Panel Run	DE2() BPJ60WP	147.	162.	190.	
		66" Panel Run	DE2() BPJ66WP	152.	165.	196.	
		72" Panel Run	DE2() BPJ72WP	159.	173.	200.	
		78" Panel Run	DE2() BPJ78WP	164.	181.	204.	
		84" Panel Run	DE2() BPJ84WP	173.	194.	220.	
		96" Panel Run	DE2() BPJ96WP	187.	201.	228.	

Ordering Information

Beltway Power Jumper

1. Pattern Number

Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

Order Code

Beltway Power Jumper

Example: **DE1(E) BPJ30**

DE1(E) Pattern Number

BPJ30

Included with:

Beltway Power Jumper

Options

Beltway Power Jumper



Insert appropriate letter for type of wiring required within the parentheses of the pattern number.

- E= 3+1
- 8= 2+2
- T= 3+3

Beltway Electrical

Power Modules, Power Connectors and Power Jumpers

Dividends Horizon

description	type	length	pattern no.	list	3+1	2+2	3+3
90° Beltway Power Jumper 		30" Beltway Panel	DE1() PJ120WP		\$225.	\$247.	\$283.
		36" Beltway Panel	DE1() PJ126WP		232.	257.	295.
		42" Beltway Panel	DE1() PJ138WP		243.	268.	304.
		48" Beltway Panel	DE1() PJ144WP		251.	278.	315.
Vertical Power Jumper (Within Same Panel)			DE1() VPJ		194.	211.	200.
Vertical Power Jumper (From Adjacent Panel) 		30" Beltway Panel	DE1(E,8,T) PJ48WP		132.	145.	172.
		36" Beltway Panel	DE1(E,8,T) PJ54WP		139.	152.	179.
		42" Beltway Panel	DE1(E,8,T) PJ54WP		139.	152.	179.
		48" Beltway Panel	DE1(E,8,T) PJ60WP		142.	157.	179.

Ordering Information	Order Code	Included with:	Options
Beltway Power Jumper 1. Pattern Number Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.	Beltway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30	Beltway Power Jumper	Beltway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. <ul style="list-style-type: none"> • E= 3+1 • 8= 2+2 • T= 3+3

Power Infeeds

Power infeeds carry power from the building's electrical source to the panel system's base raceway. Two styles are available:

- Base power infeeds
- Ceiling infeeds

Base Power Infeed

Dividends Horizon base power infeeds route power from floor monuments or electrical boxes to any terminal block duplex position on base raceway power modules. Two screws secure the base power infeed to the power module.

Note: When connected, a base power infeed takes the place of one duplex outlet.

Base power infeeds have a 56" long liquid tight conduit and pigtail for connection to the building's power supply.

Infeeds are specified either right- or left-handed. This allows the conduit to enter the outlet position from either the left or right side.

In addition to right- or left handed base power infeeds is a reversible base power infeed with a 56" long liquid tight conduit. The reversible infeed rotates to provide either a right- or left-hand power entry.

Specify the base infeed that matches the power system accessed and left or right cable entry (example: (3+1), left-hand entry).

Ceiling Infeeds

Raceway-to-ceiling infeeds route power from a ceiling-located power source to the panel system's base raceway. Unlike base infeeds which plug into any terminal block outlet position, ceiling infeeds must plug into the end of a base raceway power module. Ceiling infeeds have a 19 1/2" long metal conduit and pigtail. Two components are required for installation:

- Raceway to ceiling infeed
- Power pole

Ceiling infeed may be installed directly into a beltway power module for beltway electrical only.

Specify the ceiling infeed that matches the power system accessed.

Power Poles

Power poles can accommodate one raceway-to-ceiling infeed along with data cables. The power pole can also be used to route data cables only, if required. Cable capacity for power poles with the electrical conduit installed is 30, category 5 cables and without an electrical conduit is 40, category 5 cables.


Power poles integrate within the panel system footprint by mounting atop existing post connectors in "L", "T" or "X" configurations.

Power poles are available in three lengths in order to accommodate all three heights of post connectors. All power poles measure 126" or 144" when added to the height of the post connector. For ceilings less than 126" or 144" high, field-cut the power pole to the required height. Power poles include ceiling trim plate, connecting hardware and post/power pole trim covers.

Dividends Horizon DP8 Power Pole Construction

Power pole is extruded aluminum, with removable cover, powder coated in any Knoll Core or Dividends Horizon Legacy finish. One side of the power pole is open, allowing cables to be inserted or removed when the cover is removed.




CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.



Electrical Infeeds and Power Poles

Base Power and Raceway-to-Ceiling Infeeds

Dividends Horizon

description	type	length	pattern no.	list
Base Power Infeed (specify left or right) (right shown) 	2+2	56"	DE18 BI56(L/R)	\$244.
	3+1	56"	DE1E BI56(L/R)	222.
	3+3	56"	DE1T BI56(L/R)	286.
Base Power Infeed (reversible) 	2+2	56"	DE18 RBI56	295.
	3+1	56"	DE1E RBI56	269.
	3+3	56"	DE1T RBI56	353.
Raceway-to-Ceiling Infeed 	2+2	19 1/2'	DE18 CI144	357.
	3+1	19 1/2'	DE1E CI144	324.
	3+3	19 1/2'	DE1T CI144	412.

Ordering Information	Order Code	Included with:	Options
Base Power Infeed (L/R) 1. Pattern Number Power Pole 1. Pattern Number 2. Trim Finish Note: Power poles mount atop existing post connectors in "L", "T" and "X" configurations	Base Power Infeed (L/R) <i>Example:</i> DE18 BI56(L) <hr/> DE18 Pattern Number (left entry) BI56(L) <hr/> Power Pole <hr/> <i>Example:</i> DE(1) PP64S, 117 DE(1) Pattern Number PP64S <hr/> 117 Soft Grey trim finish	Base Power Infeed (L/R) Power Pole <ul style="list-style-type: none"> Power pole Ceiling trim plate Connecting hardware Post/power pole trim cover Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.	Base Power Infeed (L/R) <ul style="list-style-type: none"> To specify direction of entry, add either an "L" or "R" suffix to the pattern number. Insert appropriate number for post cover option within the parentheses of the pattern number Dividends Horizon Power Pole <ul style="list-style-type: none"> Post cover

Electrical Infeeds and Power Poles

DP7 and DP8 Power Poles

Dividends Horizon

description	type	length	pattern no.	P1	P2	P3
Dividends Horizon Power Pole for use with DP7 & DP8 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 126" ceiling height	For 36"H DP7 Post	90"	DP7PP36S	\$459.	\$482.	\$505.
	For 42"H DP7 Post	84"	DP7PP42S	422.	442.	465.
	For 50"H DP7 Post	76"	DP7PP50S	389.	408.	426.
	For 57"H DP7 Post	69"	DP7PP57S	343.	360.	379.
	For 64"H DP7 Post	62"	DP7PP64S	338.	353.	372.
	For 78"H DP7 Post	48"	DP7PP78S	338.	353.	372.
Dividends Horizon Power Pole for use with DP7 & DP8 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 144" ceiling height	For 36"H DP7 Post	108"	DP7PP36T	468.	492.	513.
	For 42"H DP7 Post	102"	DP7PP42T	428.	452.	473.
	For 50"H DP7 Post	94"	DP7PP50T	389.	408.	426.
	For 57"H DP7 Post	86"	DP7PP57T	343.	360.	379.
	For 64"H DP7 Post	80"	DP7PP64T	338.	353.	372.
	For 78"H DP7 Post	66"	DP7PP78T	338.	353.	372.

Ordering Information

Power Pole

1. Pattern Number
2. Trim Finish

Order Code

Power Pole

Example: **DE(2) PP64S, 117**

DE(2) Pattern Number

PP64S

117 Soft Grey trim finish

Included With

Power Pole

- Power pole
- Ceiling trim plate
- Connecting hardware
- Post/power pole trim cover

Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.

Note: Power poles mount atop existing post connectors in "L", "T" and "X" configurations.

This page intentionally left blank

New York City Hardwire Infeeds

The New York City hardwire infeed is comprised of a junction box and a power connector exiting from one side.

New York City infeeds are available in one size which mount within any base raceway 24" or wider.

The New York City infeed takes the place of a power module and prevents the installation of duplex receptacles in the panel housing the infeed. The hardwire infeed's power connector plugs into a power module which must be located in the adjacent panel.

The New York City infeed can be rotated to either the right or left side of the base raceway to provide power to either the adjacent left or right panel.

If power is required in both directions, specify a separate power jumper the length of the panel containing the infeed. The power jumper connects panel power modules located at either side of the panel containing the NYC hardwire infeed and is routed within the same raceway as the NYC hardwire infeed.

The power jumper is then routed in the opposite direction and connects to a power module located in the adjacent panel on the panel's other side (refer to the diagram below).

The panel containing the NYC hardwire infeed must be specified without base raceway cover knockouts.

A template for drilling the base raceway cover to accept the NYC hardwire infeed conduit is included.

Chicago Hardwire

Pre-wired modular electrical systems are not permitted in the City of Chicago. All electrical must be hard-wired by a qualified electrician.

In order to conform to City of Chicago electrical codes, a hardwire receptacle raceway kit(s) must be installed in all panel base raceways that require duplex receptacles. In order to conform to the City of Chicago electrical code for base power infeed, the hardwire infeed raceway kit must be installed within the panel base raceway. Hardwire receptacle raceway kit(s) and hardwire infeed raceway kit(s) mount in the base raceway between the panel feet and are available in 24" to 48" widths.

Hardwire receptacle raceway kits are secured by four screws. In addition, the base raceway covers on both sides of a panel with hardwire receptacle raceway kits must be secured with two screws each. A template for drilling attachment holes in base raceway covers is included with the hardwire receptacle raceway kit.



Optional Chicago base raceway covers can be ordered separately to replace existing covers if pre-drilled covers are desired.

When passing (jumping) hardwired power through panels, panels must be specified without knockouts in the base raceway to conform to the City of Chicago electrical code. All panels containing hardwire receptacle raceway kits must be specified with base raceway knockouts.


Note: Dividends Horizon beltway electrical is not available with Chicago hardware.

New York Electrical Configurations


NYC Infeeds are reversible and one direction



New York Electrical






Chicago Electrical



New York City, San Francisco and Chicago Electrical Infeeds and Retrofit Kit




Dividends Horizon

description	type	l	pattern no.	list
 Hardwire Infeed (NYC) - 1 Direction	2+2		DE18 B1NY1	\$673.
	3+1		DE1E B1NY1	584.
	3+3		DE1T B1NY1	753.
 Base Power Infeed (San Francisco)	2+2	56"	DE18 BI56()SF	231.
	3+1	56"	DE1E BI56()SF	208.
	3+3	56"	DE1T BI56()SF	272.
 Reversible Base Power Infeed (San Francisco)	2+2	56"	DE18 RBI56SF	281.
	3+1	56"	DE1E RBI56SF	255.
	3+3	56"	DE1T RBI56SF	337.
Electrical Retrofit Kit (Chicago) (for electrical on new panel base raceway)			DP7CERK	74.

Ordering Information	Order Code	Included with:	Options
Hardwire Infeed (NYC) 1. Pattern Number	Hardwire Infeed (NYC) Example: DE1E B1NY1 DE1E Pattern Number B1NY1	Hardwire Infeed (NYC) <ul style="list-style-type: none"> • Junction box with power connector and infeed • Ceiling trim plate • Attachment screws 	Hardwire Infeed (NYC) Power System <ul style="list-style-type: none"> • 3+1 • 2+2 • 3+3 San Francisco Infeed direction option (L) = Left (R) = Right Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP8 panel base raceways.

New York City, San Francisco and Chicago Electrical Infeeds, Receptacle Kits and Replacement Kits

Dividends Horizon

description	type	l	pattern no.	list
 Hardwire Infeed Raceway Kit (Chicago)	Double Sided	24"	DP7HIRKD24	\$413.
	Double Sided	30"	DP7HIRKD30	700.
	Double Sided	36"	DP7HIRKD36	706.
	Double Sided	42"	DP7HIRKD42	712.
	Double Sided	48"	DP7HIRKD48	716.
	Double Sided	60"	DP7HIRKD60	727.
	Single Sided	24"	DP7HIRKS24	581.
	Single Sided	30"	DP7HIRKS30	826.
	Single Sided	36"	DP7HIRKS36	831.
	Single Sided	42"	DP7HIRKS42	834.
	Single Sided	48"	DP7HIRKS48	839.
Single Sided	60"	DP7HIRKS60	854.	
 Hardwire Receptacle Raceway Kit (Chicago)	Double Sided	24"	DP7HRRKD24	317.
	Double Sided	30"	DP7HRRKD30	532.
	Double Sided	36"	DP7HRRKD36	539.
	Double Sided	42"	DP7HRRKD42	542.
	Double Sided	48"	DP7HRRKD48	548.
	Double Sided	60"	DP7HRRKD60	561.
	Single Sided	24"	DP7HRRKS24	368.
	Single Sided	30"	DP7HRRKS30	518.
	Single Sided	36"	DP7HRRKS36	524.
	Single Sided	42"	DP7HRRKS42	524.
	Single Sided	48"	DP7HRRKS48	529.
Single Sided	60"	DP7HRRKS60	541.	
 Pre-Drilled Replacement Covers, Pair (Chicago)	24" Wide Panel	24"	DP7RCCH24	45.
	30" Wide Panel	30"	DP7RCCH30	49.
	36" Wide Panel	36"	DP7RCCH36	52.
	42" Wide Panel	42"	DP7RCCH42	60.
	48" Wide Panel	48"	DP7RCCH48	63.
	60" Wide Panel	60"	DP7RCCH60	74.

Ordering Information

Hardwire Infeed (NYC)

1. Pattern Number

Order Code

Hardwire Infeed (NYC)

Example: DE1E B1NY1

DE1E Pattern Number
B1NY1

Included with:

Hardwire Infeed (NYC)

- Junction box with power connector and infeed
- Ceiling trim plate
- Attachment screws

Options

Hardwire Infeed (NYC)

Power System

- 3+1
- 2+2
- 3+3

San Francisco Infeed direction option

(L) = Left
(R) = Right

Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP8 panel base raceways.

This page intentionally left blank

Base Raceway Cable Tray

Optional steel cable trays are available for installations requiring the use of data and communications cables within the base raceway. The cable tray mounts between the panel feet.

Cable trays are field-installed and accessible from either side of the base raceway. A single sided base raceway cable tray should be specified when attaching to a tile-to-floor panel base.

Note: Cables should not be installed in base raceways without cable trays.

Beltway Cable Tray

An optional cable tray is available for data and communications cables within the beltway. Beltway cable trays should be used when wires are being routed horizontally from panel-to-panel at the beltway. The cable tray mounts into slots located on the vertical panel frame.

Cable trays are 1¹/₄" high, 1⁵/₁₆" deep and are field-installed. Construction is 20-gauge steel with black finish.

Note: Beltway cable trays can be installed in monolithic panels to provide additional mid span insert support when required.

Worksurface Cable Management Basket

Constructed of black finished steel wire, the worksurface cable management basket mounts to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable management basket slides forward to a position abutting the panel face to allow the passage of cords and cables.

Specify by width available between worksurface supports. Black finish.

Worksurface cable management baskets are 1¹/₂" high, 3¹/₂" deep and 19¹/₂" to 41¹/₂" wide.

Vertical Wire Pathway Grommet

An optional plastic grommet that snaps into the vertical wire pathway on the horizontal panel frame to separate cables from the panel frame. Located in center of topway and base raceway.

Topway Cable Grommet

The primary location for cable management for Dividends Horizon is in the topway. In order to utilize the topway channel effectively, the outside knockouts must be removed by using pliers. When the knockouts are removed the cables can be easily managed in the channel.


If required, a topway knockout grommet may be installed inside of the topway channel. Four grommets would be required per panel topway.

Worksurface Cable Management Clip

An optional cable management clip. 3/4" x 1/2" (internal dimension) plastic clip manages cables on the underside of worksurfaces.






Data Shield

If separation of cabling and electrical wires is required within the base raceway, a data shield can be attached below a base raceway power module at either end. Data shields are field-installed. The data shield should be used with base raceway panels or tile to floor panels only.



Cable Management Accessories

Dividends Horizon

description	type	pattern no.	list
	19 1/2" wide	D1WB20	\$46.
	25 1/2" wide	D1WB26	48.
	31 1/2" wide	D1WB32	60.
	35" wide	D1WB36	67.
	41" wide	D1WB42	71.
Vertical Wire Pathway Grommet (optional)	Package of 10	DP1 VWG	196.
			
Topway Cable Grommet	Package of 40	DP1 TKC	68.
			
Worksurface Cable Management Clip	Package of 10	D1WC	44.
			
Data Shield	1 Pair for use with base raceway	DE1DATSHD	45.
	1 Pair for use with tile to floor	DE1DATSHDF	60.
			

Ordering Information

Base Raceway Cable Tray

1. Pattern Number

Order Code

Base Raceway Cable Tray

Example: **DP1 RCT24**

DP1 Pattern Number
RCT24

Included with:

Base Raceway Cable Tray

Options




Base Raceway Cable Tray

Note: Cable trays are for use with all DP7 and DP8 series panels and all panels produced prior to November 2007.

Note: Data Shield is not compatible with open base panels.

Cable Management

Base Raceway and Beltway Cable Trays

description	type	pattern no.	list
Base Raceway Cable Tray - double sided for use with raceway on both sides (optional) 	18" Panel Width	DP72RCT18	\$29.
	24" Panel Width	DP72RCT24	31.
	30" Panel Width	DP72RCT30	35.
	36" Panel Width	DP72RCT36	37.
	42" Panel Width	DP72RCT42	39.
	48" Panel Width	DP72RCT48	44.
	60" Panel Width	DP72RCT60	47.
Base Raceway Cable Tray - single sided for use with raceway on one side (optional) 	18" Panel Width	DP71RCT18	29.
	24" Panel Width	DP71RCT24	31.
	30" Panel Width	DP71RCT30	35.
	36" Panel Width	DP71RCT36	37.
	42" Panel Width	DP71RCT42	39.
	48" Panel Width	DP71RCT48	44.
	60" Panel Width	DP71RCT60	47.
Beltway Cable Tray (optional) 	18" Panel Width	DP1BCT18	31.
	24" Panel Width	DP1BCT24	32.
	30" Panel Width	DP1BCT30	36.
	36" Panel Width	DP1BCT36	38.
	42" Panel Width	DP1BCT42	41.
	48" Panel Width	DP1BCT48	45.
	60" Panel Width	DP1BCT60	66.

Ordering Information

Base Raceway Cable Tray

1. Pattern Number

Order Code

Base Raceway Cable Tray

Example: **DP1 RCT24**
DP1 Pattern Number
RCT24

Included with:

Base Raceway Cable Tray

Options

Base Raceway Cable Tray

Note: Cable trays are for use with all DP7 and DP8 series panels and all panels produced prior to November 2007.

This page intentionally left blank

Flip-Up Door Overheads

Panel- and Wall-Mounted

Dividends Series 1, Series 2 and Series 3 Overheads - Specifications

Flip-Up Door Overheads

Flip-up overheads mount to the integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Flip-up overhead cabinets consist of a top, shelf, end panels, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.


Series 1 Flip-up Door Overhead

Series 1 flip-up overhead cabinets match the aesthetics of the original Dividends Horizon system. The radiused fronts and molded plastic end trim match the radiused profile trim used on panel topcaps and end trim. Series 1 cabinets are offered with steel doors.

Series 2 Flip-up Door Overhead

Series 2 overhead cabinets offer an alternative aesthetic to the original Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below). The Series 2 overhead offers a painted steel or veneer overhead door front.

Flip-up Door Overhead Configurations



Series 3 Flip-up Door Overhead

Series 3 cabinets offer a third aesthetic choice for flip-up overhead cabinets. The series 3 door profile is similar to the rectilinear door of the Series 2 cabinet, but the corners have a sharper radius to complement Dividends Horizon flat profile trim. Series 3 cabinets are offered with steel, laminate or veneer doors.

Note: Horizon Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes

- Height: 15"
- Depth: 14¹/₈"
- Widths: 24", 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:

- **Horizontal top and shelf:** 18-gauge painted roll-formed steel
- **Overhead door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Overhead door end trim:** Color injected, molded plastic (on Series 1 only)
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Overhead door suspension:** Steel ball bearing

Interior Dimensions

The interior dimensions of overhead cabinets and shelves are:

- Depth: 12"
- Usable interior height: 12⁵/₈"
- Width: 1/8" shorter than the exterior width

Cabinet Door Clearance

Cabinet doors open over the tops of cabinets. Required clearance is 16¹/₄" total height (height of cabinet plus top clearance required).

Touchdown Overhead Cabinets

Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allow the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Task Lights


All Dividends cabinets and shelves will accept task lights. Task lights must be specified separately.

Locks


Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required. When locks are not specified on Series 1 and Series 2 overheads, a plug is located in the lock position. Lock retrofit kits are available for field installation at a later date for Series 1 and Series 2 overheads only.

Note: Horizon Series 3 flip-up overheads are only available in Knoll Core finishes.


Interior Dimensions



Cabinet Door Clearance



Flip-up Door Overhead Profiles





Flip-Up Door Overheads

Panel- and Wall-Mounted


Dividends Series 1, Series 2 and Horizon Series 3

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Dividends Series 1 Flip-Up Overhead w/Steel Door 	24"	23 7/8"	14 1/8"	15"	DS1O24L	\$423.	\$465.	\$483.	n/a	n/a	n/a
	30"	29 7/8"	14 1/8"	15"	DS1O30L	423.	465.	483.	n/a	n/a	n/a
	36"	35 7/8"	14 1/8"	15"	DS1O36L	446.	489.	511.	n/a	n/a	n/a
	42"	41 7/8"	14 1/8"	15"	DS1O42L	471.	520.	543.	n/a	n/a	n/a
	48"	47 7/8"	14 1/8"	15"	DS1O48L	487.	540.	561.	n/a	n/a	n/a
	54"	53 7/8"	14 1/8"	15"	DS1O54L	719.	788.	826.	n/a	n/a	n/a
	60"	59 7/8"	14 1/8"	15"	DS1O60L	719.	788.	826.	n/a	n/a	n/a
	66"	65 7/8"	14 1/8"	15"	DS1O66L	742.	817.	854.	n/a	n/a	n/a
72"	71 7/8"	14 1/8"	15"	DS1O72L	742.	817.	854.	n/a	n/a	n/a	

Series 2 Flip-Up Overhead w/ Steel or Veneer Door 	24"	23 7/8"	14 1/8"	15"	DS2PM24L	548.	633.	661.	860.	945.	969.
	30"	29 7/8"	14 1/8"	15"	DS2PM30L	548.	633.	661.	860.	945.	969.
	36"	35 7/8"	14 1/8"	15"	DS2PM36L	596.	686.	716.	869.	957.	988.
	42"	41 7/8"	14 1/8"	15"	DS2PM42L	652.	748.	778.	889.	990.	1,022.
	48"	47 7/8"	14 1/8"	15"	DS2PM48L	716.	821.	860.	955.	1,062.	1,100.
	54"	53 7/8"	14 1/8"	15"	DS2PM54L	849.	978.	1,022.	1,362.	1,487.	1,531.
	60"	59 7/8"	14 1/8"	15"	DS2PM60L	849.	978.	1,022.	1,362.	1,487.	1,531.
	66"	65 7/8"	14 1/8"	15"	DS2PM66L	948.	1,088.	1,137.	1,423.	1,566.	1,615.
72"	71 7/8"	14 1/8"	15"	DS2PM72L	948.	1,088.	1,137.	1,423.	1,566.	1,615.	

Dividends "touchdown" retro-fit (two kits required for 54"w - 72"w)	DS1EAKIT	290.
---	-----------------	------

Series 3 Flip-Up Overhead w/ Steel Door 	30"	29 7/8"	14 1/2"	15"	DS3PMS30L	541.	596.	624.
	36"	35 7/8"	14 1/2"	15"	DS3PMS36L	557.	614.	641.
	42"	41 7/8"	14 1/2"	15"	DS3PMS42L	574.	633.	662.
	48"	47 7/8"	14 1/2"	15"	DS3PMS48L	594.	653.	681.
	60"	59 7/8"	14 1/2"	15"	DS3PMS60L	748.	824.	863.
	66"	65 7/8"	14 1/2"	15"	DS3PMS66L	814.	896.	938.
	72"	71 7/8"	14 1/2"	15"	DS3PMS72L	814.	896.	938.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"



Ordering Information	Order Code	Included with:	Options
Dividends Series 1 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish Series 2 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door Finish (veneer door only) Series 3 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish case 3. Door Finish (laminated and veneer door only) 4. Door Edge Finish (laminated door only)	Dividends Series 1 Flip-Up Door Overhead <i>Example:</i> DS1O 30L, 113, 113 DS1O 30L Pattern Number 113 Dark grey paint finish 113 Dark grey End cap finish Series 2 Flip-Up Overhead w/ Steel Door <i>Example:</i> DS2PM 30L, 115 DS2PM Pattern Number 30L 115 Medium grey paint finish	Dividends Series 1 Flip-Up Door Overhead Series 2 Flip-Up Overhead Series 3 Flip-Up Overhead Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads. Note: Series 3 Horizon overheads are only available in Knoll core finishes. Wallmount bracket specified separately.	Flip-Up Door Door Overhead To specify overhead cabinet without locks replace the "L" suffix from the pattern number with "N" Deduct \$20. For 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater). Series 2 and Series 3 Flip-Up Door Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Flip-Up Door Overheads

Panel- and Wall-Mounted

Dividends Series 1, Series 2 and Horizon Series 3

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Series 3 Flip-Up Overhead w/ Laminate Door 	30"	29 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML30L	\$817.	\$912.	\$951.			
	36"	35 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML36L	855.	935.	977.			
	42"	41 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML42L	880.	963.	1,006.			
	48"	47 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML48L	932.	1,023.	1,068.			
	60"	59 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML60L	1,395.	1,530.	1,596.			
	66"	65 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML66L	1,416.	1,554.	1,635.			
	72"	71 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PML72L	1,457.	1,602.	1,673.			
Series 3 Flip-Up Overhead w/ Veneer Door 	30"	29 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV30L	1,130.	1,237.	1,293.			
	36"	35 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV36L	1,155.	1,267.	1,325.			
	42"	41 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV42L	1,182.	1,298.	1,357.			
	48"	47 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV48L	1,234.	1,341.	1,403.			
	60"	59 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV60L	1,989.	2,184.	2,282.			
	66"	65 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV66L	2,043.	2,247.	2,359.			
	72"	71 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV72L	2,060.	2,260.	2,364.			

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Dividends Series 1 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish Series 2 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door Finish (veneer door only) Series 3 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish case 3. Door Finish (laminated and veneer door only) 4. Door Edge Finish (laminated door only)	Dividends Series 1 Flip-Up Door Overhead <i>Example:</i> DS10 30L, 113, 113 DS10 30L Pattern Number 113 Dark grey paint finish 113 Dark grey End cap finish Series 2 Flip-Up Overhead w/ Steel Door <i>Example:</i> DS2PM 30L, 115 DS2PM Pattern Number 30L 115 Medium grey paint finish	Dividends Series 1 Flip-Up Door Overhead Series 2 Flip-Up Overhead Series 3 Flip-Up Overhead Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads. Note: Series 3 Horizon overheads are only available in Knoll core finishes. Wallmount bracket specified separately.	Flip-Up Door Door Overhead To specify overhead cabinet without locks replace the "L" suffix from the pattern number with "N" Deduct \$20. For 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater). Series 2 and Series 3 Flip-Up Door Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

This page intentionally left blank

Sliding Door Overheads

Panel-, Center- and Wall-Mounted Specifications

Sliding Door Overheads

Sliding door overheads complement the aesthetic of the Dividends Horizon system. The rectilinear door profile was designed to match Dividends Horizon flat profile trim details.

Dividends Horizon sliding door overhead cabinets mount to integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Sliding door overhead cabinets consist of a top, shelf, mid cabinet septum, end panels and a door with handle. Units are available with or without locks.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.

Note: Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes

- Height: 14" and 21"
- Depth: 13 $\frac{1}{2}$ "
- Widths: 30", 36", 42", 48", 54", 60", 66" and 72"

Construction:

- **Horizontal top and shelf:** 18-gauge painted roll-formed steel
- **Sliding door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Fixed shelf:** 16-gauge painted steel
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Sliding door mechanism:** Integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Door handle:** painted aluminum (same color as case)

Interior Dimensions

The interior dimensions of overhead cabinets and shelves are:

- Depth: 12 $\frac{1}{4}$ "
- Usable interior height: 12 $\frac{5}{8}$ "
- Width: $\frac{1}{8}$ " shorter than the exterior width

Task Lights


All Dividends Horizon cabinets and shelves will accept task lights. Task lights must be ordered separately. Please see individual price list pages to determine which task lights are compatible.

Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.


Note: Horizon sliding door overheads are only available in Knoll Core finishes.

Sliding Door Overhead Configurations




Interior Dimensions for 14"H Overhead

Front View, Interior Height




Top View, Interior Height




Interior Dimensions for 21"H Overhead

Front View, Interior Height



Top View, Interior Height




Sliding Door Overheads

14" High Panel-Mounted


Dividends Horizon and Template Doors

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door	29 ⁷ / ₈ "	30"	12 ¹ / ₂ "	14"	DS3PMNS3014	\$322.	\$353.	\$371.
	35 ⁷ / ₈ "	36"	12 ¹ / ₂ "	14"	DS3PMNS3614	335.	369.	387.
	41 ⁷ / ₈ "	42"	12 ¹ / ₂ "	14"	DS3PMNS4214	344.	380.	396.
	47 ⁷ / ₈ "	48"	12 ¹ / ₂ "	14"	DS3PMNS4814	357.	393.	410.
	59 ⁷ / ₈ "	60"	12 ¹ / ₂ "	14"	DS3PMNS6014	408.	448.	469.
	65 ⁷ / ₈ "	66"	12 ¹ / ₂ "	14"	DS3PMNS6614	421.	462.	482.
	71 ⁷ / ₈ "	72"	12 ¹ / ₂ "	14"	DS3PMNS7214	430.	474.	497.




Template Panel-Mounted Sliding Door Overhead with Steel Doors	35 ⁷ / ₈ "	36"	15"	14"	DS3PMT(S/G)3614L	699.	769.	804.
	41 ⁷ / ₈ "	42"	15"	14"	DS3PMT(S/G)4214L	724.	798.	832.
	47 ⁷ / ₈ "	48"	15"	14"	DS3PMT(S/G)4814L	747.	820.	859.
	59 ⁷ / ₈ "	60"	15"	14"	DS3PMT(S/G)6014L	1,065.	1,173.	1,225.
	71 ⁷ / ₈ "	72"	15"	14"	DS3PMT(S/G)7214L	1,127.	1,239.	1,297.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/Steel Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	14"	DS3PMSS3014L	532.	587.	613.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	14"	DS3PMSS3614L	547.	602.	632.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	14"	DS3PMSS4214L	565.	623.	649.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	14"	DS3PMSS4814L	574.	633.	662.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	14"	DS3PMSS6014L	649.	716.	747.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	14"	DS3PMSS6614L	667.	734.	767.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	14"	DS3PMSS7214L	677.	745.	778.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	14"	DS3PMSL3014L	919.	1,010.	1,056.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	14"	DS3PMSL3614L	946.	1,036.	1,082.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	14"	DS3PMSL4214L	972.	1,065.	1,115.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	14"	DS3PMSL4814L	997.	1,093.	1,142.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	14"	DS3PMSL6014L	1,023.	1,123.	1,172.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	14"	DS3PMSL6614L	1,049.	1,152.	1,201.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	14"	DS3PMSL7214L	1,074.	1,177.	1,230.



w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads: 1. Pattern number 2. Paint finish case 3. Door finish (laminated and veneer door only) 4. Door edge finish (laminated door only)	Sliding Door Overhead w/ Steel Door <i>Example:</i> DS3PMSS3014L /117/117 DS3PMSS Pattern Number 3014L 117 Dark grey paint finish case	Sliding Door Overhead Note: Sliding door overheads are only available in Knoll core finishes. Specify one of the following for Template Glass door option: (Temp) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey	Sliding Door Overhead Lock/No lock For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Overheads with Template style doors only accept LED task light. T5 task light mounting brackets are not compatible.


Sliding Door Overheads

14" High Panel-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	14"	DS3PMSV3014L	\$1,016.	\$1,115.	\$1,165.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	14"	DS3PMSV3614L	1,049.	1,151.	1,201.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	14"	DS3PMSV4214L	1,079.	1,186.	1,237.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	14"	DS3PMSV4814L	1,114.	1,222.	1,276.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	14"	DS3PMSV6014L	1,146.	1,258.	1,313.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	14"	DS3PMSV6614L	1,177.	1,293.	1,350.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	14"	DS3PMSV7214L	1,211.	1,330.	1,389.





w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included With	Options
Sliding Door Overheads: 1. Pattern number 2. Paint finish case 3. Door finish (laminated and veneer door only) 4. Door edge finish (laminated door only)	Sliding Door Overhead w/ Steel Door <i>Example:</i> DS3PMSS3014L /117/117 DS3PMSS Pattern Number 3014L 117 Dark grey paint finish case	Sliding Door Overhead Note: Sliding door overheads are only available in Knoll core finishes. Specify one of the following for Template Glass door option: (Temp) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey	Sliding Door Overhead Lock/No lock For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes. Overheads with Template style doors only accept LED task light. T5 task light mounting brackets are not compatible.


Sliding Door Overheads 21" High Panel-Mounted Dividends Horizon Full Height Door

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door 	29 ⁷ / ₈ "	30"	12 ¹ / ₂ "	21"	DS3PMNS3021	\$445.	\$490.	\$511.
	35 ⁷ / ₈ "	36"	12 ¹ / ₂ "	21"	DS3PMNS3621	464.	508.	532.
	41 ⁷ / ₈ "	42"	12 ¹ / ₂ "	21"	DS3PMNS4221	478.	526.	549.
	47 ⁷ / ₈ "	48"	12 ¹ / ₂ "	21"	DS3PMNS4821	497.	545.	569.
	59 ⁷ / ₈ "	60"	12 ¹ / ₂ "	21"	DS3PMNS6021	565.	623.	649.
	65 ⁷ / ₈ "	66"	12 ¹ / ₂ "	21"	DS3PMNS6621	462.	507.	530.
	71 ⁷ / ₈ "	72"	12 ¹ / ₂ "	21"	DS3PMNS7221	598.	660.	687.

Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door 	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSS3021FL	693.	762.	797.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSS3621FL	716.	787.	821.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSS4221FL	740.	811.	849.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSS4821FL	759.	832.	872.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSS6021FL	869.	955.	1,000.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSS6621FL	893.	981.	1,027.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSS7221FL	911.	1,001.	1,046.

Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door 	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSL3021FL	1,146.	1,258.	1,312.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSL3621FL	1,179.	1,294.	1,353.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSL4221FL	1,215.	1,332.	1,393.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSL4821FL	1,251.	1,372.	1,429.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSL6021FL	1,283.	1,410.	1,470.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSL6621FL	1,315.	1,447.	1,510.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSL7221FL	1,350.	1,483.	1,548.

Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door 	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSV3021FL	1,248.	1,370.	1,428.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSV3621FL	1,292.	1,420.	1,482.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSV4221FL	1,340.	1,470.	1,537.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSV4821FL	1,386.	1,523.	1,591.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSV6021FL	1,431.	1,574.	1,645.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSV6621FL	1,480.	1,627.	1,698.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSV7221FL	1,529.	1,678.	1,752.


w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads: 1. Pattern number 2. Paint finish case 3. Door finish (laminated and veneer door only) 4. Door edge finish (laminated door only)	Sliding Door Overhead w/ Steel Door <i>Example:</i> DS3PMSS3021FL /117/117 DS3PMSS Pattern Number 3021FL 117 Dark grey paint finish case	Sliding Door Overhead Note: Sliding door overheads are only available in Knoll core finishes.	Sliding Door Overhead Lock/No lock For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.


Sliding Door Overheads 21" High Panel-Mounted Dividends Horizon Partial Height Door

Dividends Horizon


description	w*	w	d	h	pattern number	P1	P2	P3
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSS3021PL	\$687.	\$759.	\$791.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSS3621PL	712.	780.	817.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSS4221PL	733.	805.	839.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSS4821PL	751.	826.	865.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSS6021PL	831.	915.	957.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSS6621PL	859.	942.	984.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSS7221PL	873.	959.	1,003.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSL3021PL	1,137.	1,248.	1,302.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSL3621PL	1,170.	1,284.	1,340.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSL4221PL	1,203.	1,319.	1,380.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSL4821PL	1,236.	1,358.	1,419.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSL6021PL	1,271.	1,395.	1,457.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSL6621PL	1,304.	1,430.	1,497.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSL7221PL	1,337.	1,468.	1,536.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSV3021PL	1,248.	1,370.	1,427.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSV3621PL	1,284.	1,411.	1,471.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSV4221PL	1,322.	1,452.	1,515.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSV4821PL	1,363.	1,494.	1,560.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSV6021PL	1,398.	1,536.	1,603.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSV6621PL	1,432.	1,576.	1,647.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSV7221PL	1,472.	1,620.	1,690.



w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead w/ Steel Door	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3PMSS3021PL	Note: Sliding door overheads are only available in Knoll core finishes.	Lock/No lock
2. Paint finish case	/117/117		For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish (laminated and veneer door only)	DS3PMSS Pattern Number		Paint Configuration Option:
4. Door edge finish (laminated door only)	3021PL		Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	117 Dark grey paint finish case		


Sliding Door Overheads


14" High Wall-Mounted


Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
 Dividends Horizon Wall-Mounted Sliding Door Overhead without Door	35 ⁷ / ₈ "	36"	14"	14"	DS3WMN3614	\$777.	\$856.	\$894.
	42 ⁷ / ₈ "	42"	14"	14"	DS3WMN4214	821.	907.	946.
	47 ⁷ / ₈ "	48"	14"	14"	DS3WMN4814	864.	948.	991.
	59 ⁷ / ₈ "	60"	14"	14"	DS3WMN6014	1,179.	1,297.	1,357.
	71 ⁷ / ₈ "	72"	14"	14"	DS3WMN7214	1,278.	1,409.	1,470.

 Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Steel Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSS3614L	977.	1,074.	1,123.
	42 ⁷ / ₈ "	42"	15"	14"	DS3WMSS4214L	1,026.	1,130.	1,180.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSS4814L	1,068.	1,175.	1,227.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSS6014L	1,393.	1,533.	1,603.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSS7214L	1,499.	1,648.	1,724.

 Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Laminate Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSL3614L	n/a	n/a	1,304.
	42 ⁷ / ₈ "	42"	15"	14"	DS3WMSL4214L	n/a	n/a	1,353.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSL4814L	n/a	n/a	1,398.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSL6014L	n/a	n/a	1,737.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSL7214L	n/a	n/a	1,850.

 Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Veneer Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSV3614L	n/a	n/a	1,513.
	41 ⁷ / ₈ "	42"	15"	14"	DS3WMSV4214L	n/a	n/a	1,567.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSV4814L	n/a	n/a	1,633.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSV6014L	n/a	n/a	1,976.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSV7214L	n/a	n/a	2,110.

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish
(laminated and veneer door only)
4. Door edge finish
(laminated door only)

Order Code

Sliding Door Overhead

Example: **DS3WMSS4214N**
/118/118

DS3WM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Wall mount cleat
Hardware
Specify one of the following for Template Glass door option:
(Temp) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Wall-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
Template Wall-Mounted	35 ⁷ / ₈ "	36"	15"	14"	DS3WMT(S/G)3614L	\$959.	\$1,057.	\$1,106.
Sliding Door Overhead w/Steel or Glass Doors	42 ⁷ / ₈ "	42"	15"	14"	DS3WMT(S/G)4214L	1,013.	1,115.	1,165.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMT(S/G)4814L	1,057.	1,161.	1,215.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMT(S/G)6014L	1,389.	1,529.	1,598.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMT(S/G)7214L	1,503.	1,654.	1,729.



Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Paint finish case
3. Door finish
(laminated and veneer door only)
4. Door edge finish
(laminated door only)

Order Code

Sliding Door Overhead

Example: **DS3WMSS4214N**
/118/118

DS3WMM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Wall mount cleat
Hardware

Specify one of the following for Template Glass door option:
(Temp) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Options

Sliding Door Overhead

Lock Option:
For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.


Note: Sliding door overheads are only available in Knoll core finishes.


Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads


14" High Shared Center-Mounted Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
 Dividends Horizon Shared Top-Mounted Sliding Door Overhead without Door	35 7/8"	36"	14"	14"	DS3SMN3614	\$1,041.	\$1,148.	\$1,200.
	42 7/8"	42"	14"	14"	DS3SMN4214	1,086.	1,197.	1,252.
	47 7/8"	48"	14"	14"	DS3SMN4814	1,120.	1,231.	1,288.
	59 7/8"	60"	14"	14"	DS3SMN6014	1,327.	1,459.	1,527.
	71 7/8"	72"	14"	14"	DS3SMN7214	1,384.	1,523.	1,592.

 Template Shared Top-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3SMT(S/G)3614L	1,232.	1,358.	1,419.
	42 7/8"	42"	15"	14"	DS3SMT(S/G)4214L	1,284.	1,413.	1,475.
	47 7/8"	47"	15"	14"	DS3SMT(S/G)4814L	1,313.	1,447.	1,510.
	59 7/8"	60"	15"	14"	DS3SMT(S/G)6014L	1,533.	1,687.	1,762.
	71 7/8"	72"	15"	14"	DS3SMT(S/G)7214L	1,621.	1,784.	1,864.

 Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Steel Door	35 7/8"	36"	15"	14"	DS3SMSS3614L	1,302.	1,430.	1,498.
	42 7/8"	42"	15"	14"	DS3SMSS4214L	1,354.	1,489.	1,554.
	47 7/8"	48"	15"	14"	DS3SMSS4814L	1,384.	1,523.	1,592.
	59 7/8"	60"	15"	14"	DS3SMSS6014L	1,599.	1,760.	1,840.
	71 7/8"	72"	15"	14"	DS3SMSS7214L	1,687.	1,854.	1,939.

 Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Laminate Door	35 7/8"	36"	15"	14"	DS3SMSL3614L	n/a	n/a	1,998.
	42 7/8"	42"	15"	14"	DS3SMSL4214L	n/a	n/a	2,045.
	47 7/8"	48"	15"	14"	DS3SMSL4814L	n/a	n/a	2,084.
	59 7/8"	60"	15"	14"	DS3SMSL6014L	n/a	n/a	2,304.
	71 7/8"	72"	15"	14"	DS3SMSL7214L	n/a	n/a	2,405.

Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish
(laminated and veneer door only)
4. Door edge finish
(laminated door only)

Order Code

Sliding Door Overhead

Example: **DS3SMSS4214N**
/118/118

DS3SM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Specify one of the following for Template Glass door option:

- (Temp)** = Clear
- (GL13)** = Powder
- (GL25)** = Bronze
- (GL35)** = Grey

Options

Sliding Door Overhead

Lock Option:

For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Deduct \$40.00 for shared overheads.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Shared Center-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Veneer Door	35 ⁷ / ₈ "	36"	15"	14"	DS3SMSV3614L	n/a	n/a	\$2,417.
	42 ⁷ / ₈ "	42"	15"	14"	DS3SMSV4214L	n/a	n/a	2,478.
	47 ⁷ / ₈ "	48"	15"	14"	DS3SMSV4814L	n/a	n/a	2,548.
	59 ⁷ / ₈ "	60"	15"	14"	DS3SMSV6014L	n/a	n/a	2,784.
	71 ⁷ / ₈ "	72"	15"	14"	DS3SMSV7214L	n/a	n/a	2,924.



Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish
(laminated and veneer door only)
4. Door edge finish
(laminated door only)

Order Code

Sliding Door Overhead

Example: **DS3SMSS4214N**
/118/118

DS3SM	Pattern Number
SS	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Specify one of the following for Template Glass door option:

(Temp) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Options

Sliding Door Overhead

Lock Option:

For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Deduct \$40.00 for shared overheads.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Individual Center-Mounted


Dividends Horizon Doors / Template Doors

Dividends Horizon


description	w*	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Overhead without Door	35 7/8"	36"	14"	14"	DS3CMN3614	\$834.	\$918.	\$959.		
	41 7/8"	42"	14"	14"	DS3CMN4214	871.	958.	1,002.		
	47 7/8"	48"	14"	14"	DS3CMN4814	893.	981.	1,027.		
	59 7/8"	60"	14"	14"	DS3CMN6014	1,245.	1,369.	1,428.		
	71 7/8"	72"	14"	14"	DS3CMN7214	1,309.	1,443.	1,505.		



Template Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3CMT(S/G)3614L	999.	1,100.	1,149.		
	42 7/8"	42"	15"	14"	DS3CMT(S/G)4214L	1,040.	1,146.	1,199.		
	47 7/8"	48"	15"	14"	DS3CMT(S/G)4814L	1,068.	1,175.	1,227.		
	59 7/8"	60"	15"	14"	DS3CMT(S/G)6014L	1,452.	1,598.	1,670.		
	71 7/8"	72"	15"	14"	DS3CMT(S/G)7214L	1,535.	1,688.	1,764.		



Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3CMSS3614L	1,103.	1,213.	1,267.		
	41 7/8"	42"	15"	14"	DS3CMSS4214L	1,144.	1,259.	1,316.		
	47 7/8"	48"	15"	14"	DS3CMSS4814L	1,175.	1,292.	1,353.		
	59 7/8"	60"	15"	14"	DS3CMSS6014L	1,409.	1,547.	1,619.		
	71 7/8"	72"	15"	14"	DS3CMSS7214L	1,488.	1,637.	1,711.		



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3CMTS4214N	Hardware	Lock Option:
2. Case paint finish	/118/118	Specify one of the following for Template Glass door option:	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish	DS3CM Pattern Number	(Temp) = Clear	Paint Configuration Option:
4. Door edge finish (laminated door only)	T Template Style Door	(GL13) = Powder	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	S Steel Door	(GL25) = Bronze	Note: Sliding door overheads are only available in Knoll core finishes.
	42 Width	(GL35) = Grey	Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.
	14 Height		
	N No lock		
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Individual Center-Mounted


Dividends Horizon Doors / Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Laminate Doors	35 ⁷ / ₈ "	36"	15"	14"	DS3CMSL3614L	n/a	n/a	n/a	\$1,432.	n/a
	41 ⁷ / ₈ "	42"	15"	14"	DS3CMSL4214L	n/a	n/a	n/a	1,476.	n/a
	47 ⁷ / ₈ "	48"	15"	14"	DS3CMSL4814L	n/a	n/a	n/a	1,510.	n/a
	59 ⁷ / ₈ "	60"	15"	14"	DS3CMSL6014L	n/a	n/a	n/a	1,754.	n/a
	71 ⁷ / ₈ "	72"	15"	14"	DS3CMSL7214L	n/a	n/a	n/a	1,840.	n/a



Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Veneer Doors	35 ⁷ / ₈ "	36"	15"	14"	DS3CMSV3614L	n/a	n/a	n/a	n/a	1,642.
	41 ⁷ / ₈ "	42"	15"	14"	DS3CMSV4214L	n/a	n/a	n/a	n/a	1,691.
	47 ⁷ / ₈ "	48"	15"	14"	DS3CMSV4814L	n/a	n/a	n/a	n/a	1,745.
	59 ⁷ / ₈ "	60"	15"	14"	DS3CMSV6014L	n/a	n/a	n/a	n/a	1,990.
	71 ⁷ / ₈ "	72"	15"	14"	DS3CMSV7214L	n/a	n/a	n/a	n/a	2,099.



Ordering Information

Sliding Door Overheads:

1. Pattern number
2. Case paint finish
3. Door finish
4. Door edge finish (laminated door only)

Order Code

Sliding Door Overhead

Example: **DS3CMTS4214N /118/118**

DS3CM	Pattern Number
T	Template Style Door
S	Steel Door
42	Width
14	Height
N	No lock
118	Bright White Paint Finish
118	Bright White Paint Finish

Included With

Sliding Door Overhead

Hardware

Specify one of the following for Template Glass door option:

(Temp) = Clear
(GL13) = Powder
(GL25) = Bronze
(GL35) = Grey

Options

Sliding Door Overhead

Lock Option:

For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.

Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.

This page intentionally left blank

Panel Up Mounted Overhead Cabinets

Up mounted cabinets mount to 50" or 57" high panels only to provide overhead storage within workstations and are an alternative to overheads panel-mounted on 64" high panels. Up mounted cabinets have full finished backs and require up mount brackets for mounting.

When installed on 50" high panels, up mounted cabinets match up to the overall 64" height of panel-mounted overhead cabinets and freestanding overdesks to provide a consistent height within the facility.

Overhead cabinets consist of a top, shelf, end panels, enclosed back, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Up mounted cabinets are shipped knocked-down.

Up mounted overheads must match the width of single or multiple panels and cannot be mounted off module.

Series 1 Flip-up Overhead Cabinets

Series 1 flip-up overhead cabinets match the aesthetics of the original Dividends Horizon system. The radiused fronts and molded plastic end trim match the radiused profile trim used on panel topcaps and end trim. Series 1 cabinets are offered with steel doors.

Series 2 Flip-up Overhead Cabinets

Series 2 overhead cabinets offer an alternative aesthetic to the Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below). The Series 2 overhead offers a painted steel or veneer overhead door front.

Available Sizes

- Height: 15"
- Depth: 13¹/₂"
- Widths: 30", 36", 42", 48", 54", 60", 66" and 72"

Construction:

- Horizontal top and shelf: 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- Overhead door: 20-gauge painted
- Overhead door suspension: Steel ball-bearing
- Overhead door end trim: Color injected, molded plastic (Series 1 only)
- End panels: 16-gauge painted steel with integral mounting hooks
- Up mount brackets: 14-gauge steel

Interior Dimensions

Up mounted cabinet interiors measure:

- Depth 12"
- Usable interior height: 12⁵/₈"
- Width: 1/8" shorter than the exterior width.

Cabinet Door Clearance

Cabinet doors open over the tops of cabinets. Required clearance is: 16¹/₄" total height (height of cabinet plus top clearance required).

Panel Up Mounted Overhead for Stack Frames

Dividends Horizon non-load bearing stacking frames do not allow for panel-mount hanging components. To provide overhead storage, a panel up mounted overhead cabinet with enclosed back can be utilized.

Up mount brackets

Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Touchdown Overhead Cabinets

Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.


When locks are not specified a plug is located in the lock position.

Optional lock retrofit kits are available for field-installation at a later date if required.


Task Lights

All Dividends up mounted cabinets will accept task lights. Task lights must be ordered separately.


Panel Up Mounted Cabinet




Up Mount Brackets



Interior Dimensions




Front View, Interior Height



Top View, Interior Depth



Cabinet Door Clearance



Up Mounted Overheads

Dividends and Series 2

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Dividends Overhead Cabinet with Enclosed Back and Lock 	30"	29 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E30L	\$561.	\$620.	\$646.	n/a	n/a	n/a
	36"	35 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E36L	583.	643.	671.	n/a	n/a	n/a
	42"	41 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E42L	630.	694.	724.	n/a	n/a	n/a
	48"	47 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E48L	659.	724.	757.	n/a	n/a	n/a
	54"	53 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E54L	863.	946.	988.	n/a	n/a	n/a
	60"	59 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E60L	863.	946.	988.	n/a	n/a	n/a
	66"	65 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E66L	888.	978.	1,023.	n/a	n/a	n/a
	72"	71 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS1E72L	888.	978.	1,023.	n/a	n/a	n/a
Series 2 Overhead Cabinet With Enclosed Back and Lock 	30"	29 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM30L	747.	860.	895.	1,009.	1,120.	1,160.
	36"	35 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM36L	770.	887.	925.	1,038.	1,158.	1,197.
	42"	41 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM42L	797.	914.	955.	1,079.	1,201.	1,237.
	48"	47 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM48L	810.	931.	971.	1,138.	1,260.	1,299.
	54"	53 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM54L	1,088.	1,253.	1,305.	1,591.	1,756.	1,806.
	60"	59 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM60L	1,088.	1,253.	1,305.	1,591.	1,756.	1,806.
	66"	65 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM66L	1,138.	1,308.	1,367.	1,662.	1,836.	1,889.
	72"	71 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM72L	1,138.	1,308.	1,367.	1,662.	1,836.	1,889.
Overhead Upmount Brackets (Pair)		⁷ / ₈ "	12 ³ / ₁₆ "	11 ³ / ₄ "	DB1U18	82.	88.	93.	82.	88.	93.
Reuter Upmount Brackets (Pair)		⁷ / ₈ "	12 ³ / ₁₆ "	11 ³ / ₄ "	DB1RU18	111.	118.	126.	n/a	n/a	n/a

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Upmount Overhead Cabinet 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish	Upmount Overhead Cabinet <i>Example:</i> DS1E 30L, 113, 113 DS1E 30L Pattern Number 113 Dark grey paint finish 113 Dark grey end cap finish	Upmount Overhead Cabinet Series 2 Overhead Cabinet Up Mount overheads include an enclosed back. Up Mount brackets are required and must be ordered separately.	Upmount Overhead Cabinet To specify overhead cabinet without locks, replace the "L" suffix from the pattern number with "N" Deduct \$20 for 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater).
Series 2 Overhead Cabinet 1. Pattern Number 2. Paint Finish	Series 2 Overhead Cabinet <i>Example:</i> DS2UM 30L, 115 DS2UM Pattern Number 30L 115 Medium grey paint finish		Series 2 Up Mount Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a front color that is different than the case color. Use P3 pricing for this dual finish option.

Overhead Book Shelves

Dividends Horizon bookshelves mount to the integral vertical channels on Dividends Horizon panels or to wall mount tracks to provide overhead storage within workstations or private offices.

Bookshelves include a shelf, end panels, open back and required assembly screws.

Shelves must match the width of single or multiple panels and cannot be mounted off-module.

All book shelves are shipped knocked-down.

Available Sizes

- Height: shelf 8"
- Depth: 14¹/₈"
- Widths: 24", 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:

- Horizontal shelf: 18-gauge (24" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- End panels: 16-gauge painted steel with integral mounting hooks

Corner Shelf

Dividends Horizon corner shelves mount to the integral vertical channels of Dividends Horizon panels to provide overhead storage in corner applications. Panels supporting the corner shelf must be of the same width. Corner shelf consists of shelf, end panels and rear corner support bracket.

Note: Corner shelves do not accept task lights.

Note: Corner shelves may not be mounted on load bearing stack frames.

Available Sizes

- Height: 8"
- Depth: 12"
- Widths: 36", 42", and 48"


Construction:

- Shelf: ⁷/₈" wood core construction with laminate on both sides and t-mold edge
- End panels: 16-gauge painted steel with integral mounting hooks


Task Lights

All Dividends Horizon shelves will accept task lights. Task lights must be ordered separately.

Bookshelf





Corner Shelf



Overhead Bookshelf and Corner Shelf

7 1/4" High

description	w *	w	d	h	pattern no.	P1	P2	P3
 Overhead Bookshelf	24"	23 7/8"	14 1/8"	7 1/4"	DS1S 24	\$170.	\$190.	\$198.
	30"	29 7/8"	14 1/8"	7 1/4"	DS1S 30	170.	190.	198.
	36"	35 7/8"	14 1/8"	7 1/4"	DS1S 36	180.	190.	199.
	42"	41 7/8"	14 1/8"	7 1/4"	DS1S 42	189.	199.	206.
	48"	47 7/8"	14 1/8"	7 1/4"	DS1S 48	197.	205.	215.
	54"	53 7/8"	14 1/8"	7 1/4"	DS1S 54	210.	223.	234.
	60"	59 7/8"	14 1/8"	7 1/4"	DS1S 60	210.	223.	234.
	66"	65 7/8"	14 1/8"	7 1/4"	DS1S 66	228.	242.	254.
	72"	71 7/8"	14 1/8"	7 1/4"	DS1S 72	228.	242.	254.
 Overhead Corner Shelf	36"	35 7/8"	12"	7 1/4"	DS1CS 36	562.	596.	617.
	42"	41 7/8"	12"	7 1/4"	DS1CS 42	611.	645.	676.
	48"	47 7/8"	12"	7 1/4"	DS1CS 48	666.	703.	737.

w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Overhead Bookshelf

1. Pattern Number
2. Paint Finish

Overhead Corner Shelf

1. Pattern Number
2. Laminate Finish
3. Edge Band Finish
4. Paint Finish

Order Code

Overhead Bookshelf

Example: **DS1S 60, 113**

DS1S 60 Pattern Number

113 Dark Grey Finish

Overhead Corner Shelf

Example: **DS1CS36, M42, 117, 117**

DS1CS36 Pattern Number

M42 Soft Grey Laminate

117 Soft Grey Edge Band

117 Soft Grey Paint

Included with:

Overhead Bookshelf

Overhead Corner Shelf

- Rear Corner Support Bracket

Note: An upcharge applies when specifying a Legacy laminate. See Legacy finish page for more information.

Mounting Brackets and Accessories

Backstop, Wall-Mount and Panel Mount Specifications

Optional Overhead Back Stop

Panel-mounted overhead cabinet and bookshelf backs are open and use the panel face as the back. When required, an optional field-installed back stop is available. Attachment can be made to an assembled unit. Construction is dark grey extruded plastic.

Specify the overhead back stop width to match the width of the shelf or overhead cabinet.

Overhead Cabinet Wall-Mount Brackets

Wall-mount brackets allow Dividends Horizon panel-mounted overheads to be wall-mounted to dry-wall construction. Wall-mounting brackets are available in sizes 30", 36", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead cabinet.

If a 60" cabinet is desired, two (2) 30" wide wall-mount brackets may be installed side-by-side to support the overhead cabinet. When a 72" cabinet is used, two (2) 36" wall-mount brackets may be used.

Shelf Wall-Mount Brackets

Wall-mount brackets allow Dividends Horizon panel-mounted shelves to be wall-mounted to dry-wall construction. Wallmounting brackets are painted black, and are available in sizes 30", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead shelf. Specify paint finish to match the shelf paint finish.

A metal shelf back will ship with the wall-mount bracket, which is painted to match the shelf color. Overhead shelves larger than 48" wide cannot be wall mounted using the Dividends Horizon wall-mount bracket.

NOTE: WALL-MOUNT BRACKETS MUST ONLY BE USED WITH STRUCTURAL WALLS. TO ENSURE PROPER INSTALLATION, PLEASE FOLLOW THE INSTALLATION INSTRUCTIONS ENCLOSED WITH THE BRACKETS.

Up mount brackets

Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Currents Downmount Bracket

This downmount bracket allows for Dividends Horizon or Series 2 panel mounted overhead cabinets to be mounted into Currents spine wall. This downmount bracket can only be used with Currents 64"H spine wall only.

Specify to match the overhead cabinet width. Specify paint finish to match the overhead cabinet finish.

Reuter Panel-Mount Brackets








Reuter panel-mount brackets are available to allow Reuter overheads and shelves to be panel-mounted on Dividends Horizon 57" or 64" high panels. Reuter overhead panel-mount brackets allow overhead sizes up to 72" to be panel-mounted. Reuter shelf panel-mount brackets allow shelves up to 48" to be panel-mounted. Finish black.

Vertical Dividers

Optional vertical dividers attach to the shelves within overhead cabinets and bookshelves to provide inner cabinet organization. Construction is 18-gauge steel with dark grey finish.





Overhead Cabinet Lock Retrofit Kit

The overhead cabinet lock retrofit kit allows non-locking Series 1 and Series 2 flip-up overhead cabinets to be converted to locking overhead cabinets.



Mounting Brackets and Accessories

Overhead Backstop, Wall-mount Brackets and Currents Downmount Brackets

description	w *	w	d	h	pattern no.	black	P1	P2	P3
Overhead Back Stop (Dark Grey Only) 	24"	23 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 24		\$4.	n/a	n/a
	30"	29 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 30		4.	n/a	n/a
	36"	35 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 36		4.	n/a	n/a
	42"	41 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 42		7.	n/a	n/a
	48"	47 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 48		7.	n/a	n/a
	54"	53 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 54		10.	n/a	n/a
	60"	59 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 60		10.	n/a	n/a
	66"	65 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 66		10.	n/a	n/a
	72"	71 ^{11/16} "	5/8"	1 ^{7/16} "	DS1BS 72		10.	n/a	n/a
14" H Overhead Wall-Mount Bracket 	24"	24"	1/2"	1 4 1/4"	DS1WM 24	83.	86.	90.	93.
	30"	30"	1/2"	1 4 1/4"	DS1WM 30	83.	86.	90.	93.
	36"	36"	1/2"	1 4 1/4"	DS1WM 36	87.	91.	94.	101.
	42"	42"	1/2"	1 4 1/4"	DS1WM 42	96.	102.	108.	112.
	48"	48"	1/2"	1 4 1/4"	DS1WM 48	105.	111.	115.	119.
Overhead Shelf-Mount Bracket 	30"	30"	1/2"	7"	DS1SWM 30		145.	156.	169.
	36"	36"	1/2"	7"	DS1SWM 36		152.	172.	180.
	42"	42"	1/2"	7"	DS1SWM 42		169.	189.	195.
	48"	48"	1/2"	7"	DS1SWM 48		184.	200.	206.
Dividends Series 2 Downmount Brackets (For Currents spine use) 	24"				DSCSWDB24		273.	n/a	n/a
	30"				DSCSWDB30		282.	n/a	n/a
	36"				DSCSWDB36		289.	n/a	n/a
	42"				DSCSWDB42		298.	n/a	n/a
	48"				DSCSWDB48		303.	n/a	n/a







w* = nominal width
 Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket
1. Pattern Number	<i>Example:</i> DS1WM 30	Overhead Back Stop	Overhead Back Stop
Overhead Back Stop	DS1WM Pattern Number		
1. Pattern Number	30		
	Overhead Back Stop		
	<i>Example:</i> DB1BS 30		
	DB1BS 30 Pattern Number		

Mounting Brackets and Accessories

Upmount Brackets, Vertical Dividers and Lock Retrofit Kit

Dividends Horizon

description	pattern no.	black	P1	P2	P3
Vertical Dividers (for flip-up overheads and open shelves) Package of 4 	DS1 VD	\$108.	\$112.	\$117.	\$123.
Overhead Cabinet Lock Retrofit Kit 	DS1 OHL	65.	n/a	n/a	n/a
Overhead Upmount Brackets (Pair) 	DB1U18	n/a	82.	88.	93.
Reuter Upmount Brackets (Pair) 	DB1RU18	n/a	111.	118.	126.
Reuter Overhead Panel Bracket (pair) 	RO1-DPB	71.	n/a	n/a	n/a
Reuter Shelf Panel-Mount Bracket (pair) 	RS1-DPB	71.	n/a	n/a	n/a

Ordering Information

Vertical Dividers

1. Pattern Number

Reuter Overhead Panel-Mount Bracket

1. Pattern Number

Order Code

Vertical Dividers

Example: **DS1 VD**

Reuter Overhead Panel-Mount Bracket

Example: **RO1 DPB**

Included with:

Vertical Dividers
(4) Vertical dividers

Reuter Overhead Panel-Mount Bracket
Brackets (pair)

Options

Vertical Dividers

Reuter Overhead Panel-Mount Bracket

Overhead cabinet lock retrofit kit is for Dividends Series 1 and Series 2 Flip-up Overhead only.

This page intentionally left blank

Task Lights

Dividends Horizon offers T5 and LED task lights. T5 task lights are available in standard and advanced models. Task lights must be ordered separately from shelves, overhead cabinets, and overdesk units.

Task lights are TCLP compliant and meet requirements of California Title 20 and Title 24. T5 advanced task lights are fitted with ballasts and lamps compliant with LEED requirements. All task lights are approved for New York City installations.

T5 Task Lights

T5 task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9 foot grounded cordset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware. T5 task light housings are painted black.

The T5 task light cordset is a center exit. On smaller units the cord exit is off-center, but still not handed, allowing the cordset to be positioned either to the right or left of the task light for easy access to the closest available duplex.

All T5 task lights include mounting hardware for attachment to overhead cabinets, shelves, up mounted cabinets and freestanding overdesks. Specify task lights one size or less than the overall cabinet or overdesk width. T5 task lights have adjustable mounting brackets that lock into integral channels in the underside of the cabinet's lower shelf. The spring steel adjustable mounting brackets flex to install without requiring tools and allow the light to be positioned at any position side-to-side and front-to-back.

City of Chicago T5 task lights have a 9 foot power cord with a resettable circuit breaker built into the plug.

LED Task Lights

LED task lights include LED's, a power supply with 9'-12' cord and mounting hardware. Housings are clear anodized aluminum with white color end-caps. Cord management clips must be ordered separately. The power supply cord attaches to either end of the fixture, allowing for easier access to the closest available duplex.

LED task lights mount into the recess in the underside of overhead cabinets and shelves at least 5" wider than the task light width..


Cord Management Clips

Cord management clips attach to the integral slotted channels on panel frames to manage task light cordsets. Clips are 3/8" high black molded plastic construction.


Task Light Specifications

Model Number	Fixture Length	Lamp Length	Lamp Part Number	Lamp Watts	Input Watts
T5 Standard Task Lights					
DL3T5E19S	19"	12"	FULHAM F8T5/CW	8	8
DL3T5E25S	25"	21.6"	FULHAM F14T5/41K	14	15
DL3T5E37S	37"	33.4"	FULHAM F21T5/41K	21	24
DL3T5E49S	49"	45.2"	FULHAM F28T5/41K	28	31
T5 Advanced Task Lights					
DL3T5E25A	25"	22.2"	PHILIPS F14T5/841/ALTO	14	18
DL3T5E37A	37"	33.98"	PHILIPS F21T5/841/ALTO	21	24
DL3T5E49A	49"	45.8"	PHILIPS F28T5/841/ALTO	28	31
LED Task Lights					
DL4L17	17"	16.4"	N/A	6.6	7.8
DL4L31	31"	30.1"	N/A	14.8	17.6
DL4L44	44"	43.7"	N/A	21.8	25.9
DL4L58	58"	57.4"	N/A	28.2	33.6


T5 Task Light



LED Task Light






Cord Management Clip Attachment



Task Lights

Cord Management Clip

description	type	w	d	h	pattern no.	list
 T5 Standard Task Light	Use with 24" and wider overhead	19"	4"	1 1/2"	DL3T5E19S	\$206.
	Use with 30" and wider overhead	25"	4"	1 1/2"	DL3T5E25S	223.
	Use with 42" and wider overhead	37"	4"	1 1/2"	DL3T5E37S	227.
	Use with 60" and wider overhead	49"	4"	1 1/2"	DL3T5E49S	259.
 T5 Advanced Task Light	Use with 30" and wider overhead	25"	4"	1 1/2"	DL3T5E25A	524.
	Use with 42" and wider overhead	37"	4"	1 1/2"	DL3T5E37A	551.
	Use with 60" and wider overhead	49"	4"	1 1/2"	DL3T5E49A	573.
 LED Task Light	Use with 24" and wider overhead (24 LED's)	17"	2"	1/2"	DL4L17	530.
	Use with 36" and wider overhead (48 LED's)	31"	2"	1/2"	DL4L31	884.
	Use with 44" and wider overhead (72 LED's)	44"	2"	1/2"	DL4L44	1,153.
	Use with 66" and wider overhead (96 LED's)	58"	2"	1/2"	DL4L58	1,447.
Cord management clip	(package of 50)				DL3TC	51.

Ordering Information

Task Lights

1. Pattern Number

Cord Management Clip

1. Pattern Number

Order Code

T5 Standard Task Light

Example: **DL3T5E25S**

DL3 Task Light

T5 T5 lamp

E Electronic ballast

25 Width

S Standard

LED Task Light

Example: **DL4L17**

DL4 Task Light

L LED

17 Width

Included with:

T5 Task Lights:

120v and includes T5 cool white (4100K) fluorescent lamp, electronic ballast, 9' grounded cordset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware. Housings are black.

LED Task Lights:

Includes LED's, power supply with 9-12' cord and mounting hardware. Housings are clear anodized aluminum with white color end-caps.

Cord Management Clips:

Additional clips must be ordered separately.

Options

T5 Task Lights:

Specify suffix -CH and add \$45 list for City of Chicago installations. Example: DL3T5E25S-CH

Cordset is center exit. On smaller units cord exit is off-center, but still not handed.

T5 advanced task lights are fitted with ballasts and lamps compliant with LEED requirements, meeting the LEED EB standard for mercury content.

LED Task Lights:

Power cord is able to attach to either end of fixture.

Notes:

All task lights mount into the recess in the underside of overhead cabinets and shelves at least 6" wider than task light width.

All task lights are TCLP compliant and meet requirements of California Title 20 and Title 24.

Dividends Floorstanding, Doublewide and Mobile Specifications

Floorstanding Pedestals

Dividends Series 1 floorstanding pedestals are used to support worksurfaces in both panel-wrap and freestanding desk applications. No cantilevers or other supports are required at the end of the worksurface supported by a pedestal.

For panel-wrap applications, three depths are available in order to mount beneath 18", 24" and 30" deep worksurfaces.

In floorstanding desks, pedestals can either be specified "Preconfigured" with floorstanding desks or ordered by component for "Build-to-Spec" applications.

Two drawer configurations are available: box/box/file and file/file. Pedestals can be specified with or without locks.

Mobile Pedestals

Dividends Series 1 mobile pedestals provide moveable storage within workstations and tuck beneath worksurfaces when not in use. Available drawer configurations are box/box/file, box/file, and file/file.

Mobile pedestals roll on four corner-mounted swivel casters and one bottom drawer-mounted caster for stability when the lower drawer is in the open position. The front corner casters are locking.

Mobile pedestals may be specified with an optional handle allowing easy mobility. All mobile pedestals include 13-gauge finished tops. All other construction and drawer dimensions are the same as freestanding pedestals.

Mobile pedestals measure 20⁵/₈" and 26⁵/₈" high, 15" wide and 18" or 24" deep. All mobile pedestals include locks.

Available Sizes

Depths: 18", 24" and 30"
Width: 15"
Height: 20⁵/₈" and 26⁷/₈"

Doublewide Pedestals

The doublewide pedestal incorporates two 12" high drawers in a 30" width (18³/₄" depth) and is intended for below worksurface applications only. The doublewide's design allows for side-to-side letter or legal filing and front-to-back letter filing.

Doublewide pedestal can be used below 19", 24", or 36" deep worksurfaces, not 18" deep worksurfaces.

Available Size

Depth: 18³/₄" (floorstanding pedestal only)
Width: 30"
Height: 26⁷/₈"

Construction

Floorstanding mobile and doublewide pedestals match the aesthetics and dimensions of Dividends Horizon panel components.

- Outer wrapper: 20-gauge seamless steel wrapper, includes finished back and full dust pan
- Inner frame: 20-gauge steel uprights and 16-gauge cross rails
- Drawer front: 20-gauge steel, gently radiused (double wide front: 18-gauge)
- Drawer top cap trim: Color injected, molded plastic
- Box drawer suspension (floorstanding pedestal only): 3/4" extension, ball-bearing slides

- File drawer suspension: Full extension, ball-bearing slides
- Drawer pulls: Color injected, molded plastic
- Leveling glides: 3/8" diameter steel stem with 1 1/2" of height adjustment (double wide pedestal: 5/16" diameter steel stem with a 1 9/16" of height adjustment)

Internal Drawer Dimensions (DS1)

Box drawer

- Internal height: 4⁵/₁₆"
- Internal width: 12⁹/₁₆"
- Internal depths: 18" = 15¹⁵/₁₆", 24" = 21¹/₄", 30" = 27¹/₄"

File drawer

- Internal height: 9¹/₄"
- Internal width: 12¹/₈"
- Internal depths: 18" = 15¹⁵/₁₆", 24" = 21¹/₄", 30" = 27¹/₄"

File drawer (doublewide pedestal)

- Internal height: 9³/₄"
- Internal width: 26³/₄"
- Internal depth: 15³/₄"


Locks

Pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field installation of locks at a later date if required.


Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All random keyed locks are factory-installed and have a black finish.

Pedestal Accessories


A hanging file bar for front-to-back or side-to-side filing is included with Series 1 pedestals.



Pedestal Filing Configurations






Doublewide Pedestal Filing Configurations



Doublewide Pedestal

Mobile Pedestal

*Dividends Floorstanding, Doublewide and Mobile
18", 24" and 30" Depths*

description	type	d*	d	w	h	pattern no.	P1	P2	P3	
	Floorstanding Pedestals with Locks	6/6/12	18"	17 1/2"	14 7/8"	26 7/8"	DS1PF L18A	\$663.	\$727.	\$762.
		12/12	18"	17 1/2"	14 7/8"	26 7/8"	DS1PF L18B	638.	700.	733.
		6/6/12	24"	23 1/2"	14 7/8"	26 7/8"	DS1PF L24A	727.	801.	837.
		12/12	24"	23 1/2"	14 7/8"	26 7/8"	DS1PF L24B	699.	770.	802.
		6/6/12	30"	29 1/2"	14 7/8"	26 7/8"	DS1PF L30A	764.	839.	880.
		12/12	30"	29 1/2"	14 7/8"	26 7/8"	DS1PF L30B	732.	802.	838.
	Mobile Pedestals with Locks	6/6/12	18"	17 1/2"	14 7/8"	26 3/8"	DS1PM L18A	1,094.	1,125.	1,258.
		12/12	18"	17 1/2"	14 7/8"	26 3/8"	DS1PM L18B	1,061.	1,169.	1,222.
		6/12	18"	17 1/2"	14 7/8"	20 5/8"	DS1PM L18F	973.	1,070.	1,120.
		6/6/12	24"	22 3/4"	14 7/8"	26 3/8"	DS1PM L24A	1,177.	1,297.	1,356.
		12/12	24"	22 3/4"	14 7/8"	26 3/8"	DS1PM L24B	1,145.	1,258.	1,315.
		6/12	24"	22 3/4"	14 7/8"	20 5/8"	DS1PM L24F	1,055.	1,160.	1,211.
	Doublewide Pedestals with Locks	12/12	19"	18 3/4"	30"	26 7/8"	DS1DW 30L	1,006.	1,109.	1,158.

d* = nominal depth

Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Floorstanding Pedestals 1. Pattern Number 2. Paint Finish 3. Pull Finish 4. Drawer Top Cap Finish Mobile Pedestals 1. Pattern Number 2. Paint Finish 3. Pull Finish 4. Drawer Top Cap Finish Doublewide Pedestals 1. Pattern Number 2. Paint Finish 3. Pull Finish 4. Drawer Top Cap Finish	Floorstanding Pedestals <i>Example:</i> DS1PF L24A, 117, 117, 117 <hr/> DS1PF Pattern Number 24A <hr/> 117 Soft Grey paint finish <hr/> 117 Soft Grey pull finish <hr/> 117 Soft Grey top cap finish <hr/> Doublewide Pedestals <i>Example:</i> DS1DW 30L, 117, 117, 117 <hr/> DS1DW Pattern Number 30L <hr/> 117 Soft Grey paint finish <hr/> 117 Soft Grey pull finish <hr/> 117 Soft Grey top cap finish <hr/> Mobile Pedestals <i>Example:</i> DS1PM L24A, 117, 117, 117 <hr/> DS1PM Pattern Number L24A <hr/> 117 Soft Grey paint finish <hr/> 117 Soft Grey pull finish <hr/> 117 Soft Grey drawer top cap finish	Floorstanding Pedestals <ul style="list-style-type: none"> Hanging file bar (file drawer) Mobile Pedestals <ul style="list-style-type: none"> Hanging file bar (file drawer) Doublewide Pedestals <ul style="list-style-type: none"> Hanging file bar (front-to-back) Hanging file rail (side-to-side) Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface	Floorstanding Pedestals <ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" (6th character) in the pattern number with an "N". Deduct \$20 Doublewide Pedestals <ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" (6th character) in the pattern number with an "N". Deduct \$20 Mobile Pedestals Mobile pedestals are available with lock only. To specify a Dividends mobile pedestal with a handle, add "P" as the 7th character of the pattern number ie. DS1PML(P)24 add \$55 Full Extension Drawer Slide Option To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add \$25 to the list price.

Series 2 Floorstanding, Doublewide and Mobile Specifications

Series 2 Floorstanding Pedestals

Series 2 floorstanding pedestals are used to support worksurfaces in both panel wrapped and freestanding applications. No cantilevers or other supports are required at the end of the worksurface supported by a pedestal.

Two drawer configurations are available: box/box/file and file/ file. Mobile pedestals are not available without locks.

The Series 2 24" deep pedestal design offers case without a back. In panel applications or in freestanding desking applications where the desk is against the wall, a back is not necessary.

In desking applications where the back of the case is exposed, an optional back is used to conceal the pedestals contents.

The 18" and 30" deep Series 2 pedestals include a back with each case.

Mobile Pedestals

Series 2 mobile pedestals provide moveable storage within a workstation and tuck beneath worksurfaces when not in use. Available drawer configurations are box/file, box/box/file and file/file.

Mobile pedestals roll on four corner-mounted swivel casters and one bottom drawer-mounted caster for stability when the lower drawer is in the open position. The front corner casters are locking.

Mobile pedestals may be specified with an optional handle allowing easy mobility.

All mobile pedestals include 13-gauge finished tops. A back is included with all Series 2 mobile pedestals.

Pedestals may be specified without the top for attachment of a pedestal cushion. Pedestal cushion may be ordered through the Knoll Currents product line.

Available Sizes

Depths: 18", 24" and 30" (Floorstanding pedestal only)

Width: 15"

Height: 26 $\frac{7}{8}$ "

Series 2 Doublewide Pedestals

The doublewide pedestal incorporates two 12" high drawers in a 30" or 36" width (18 $\frac{3}{4}$ " depth) and is intended for below worksurface applications only. The doublewide's design allows for side-to-side letter or legal filing and front-to-back letter filing.

Doublewide pedestals can be used below 19", 24", 30" or 36" deep worksurfaces, not 18" deep worksurfaces.

Available Sizes

Depth: 18 $\frac{3}{4}$ " (floorstanding pedestal only)

Width: 30" and 36"

Height: 26 $\frac{7}{8}$ "

Construction:

- Outer wrapper: 20-gauge steel
- Drawer front: 20-gauge steel (double wide front: 18-gauge)
- Pedestal back: 20-gauge
- $\frac{3}{4}$ " extension ball bearing slides on 6" box drawers

- Full extension ball bearing slides on 12" file drawers
- Leveling glides: $\frac{3}{8}$ " diameter steel stem with 1 $\frac{1}{2}$ " of height adjustment (double wide ped: $\frac{5}{16}$ " diameter steel stem with a 1 $\frac{9}{16}$ " of height adjustment

Internal Drawer Dimensions (DS2, 24"d) Box drawer

- Internal height: 4 $\frac{5}{16}$ "
- Internal width: 12 $\frac{1}{16}$ "
- Internal depths: 18 $\frac{3}{8}$ "

File drawer

- Internal height: 9 $\frac{1}{4}$ "
- Internal width: 12 $\frac{1}{8}$ "
- Internal depths: 18 $\frac{3}{8}$ "

File drawer (doublewide pedestal)

- Internal height: 9 $\frac{3}{4}$ "
- Internal width: 26 $\frac{3}{4}$ " and 32 $\frac{3}{4}$ "
- Internal depth: 15 $\frac{3}{4}$ "

Locks


Series 2 mobile pedestals are available not available without locks. Series 2 doublewide pedestals can be ordered with or without locks.

Locks are randomly keyed unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and have a black finish.

Pedestal Accessories

All Series 2 freestanding pedestal accessories including the hanging file bar must be specified separately. Series 2 double wide pedestals are shipped with hanging file bars.

Interior drawer dimensions for DS2 are 18" deep and 30" deep. Pedestals are the same as DS1 dimensions listed on page 228.




Mobile Pedestal


Pedestals


Series 2 Floorstanding, Doublewide and Mobile

18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
	6/6/12 w/back	18"	17 1/2"	14 7/8"	26 7/8"	DS2PF L18A	\$668.	\$769.	\$801.
	12/12 w/back	18"	17 1/2"	14 7/8"	26 7/8"	DS2PF L18B	642.	740.	771.
	6/6/12 no back	24"	23 1/2"	14 7/8"	26 7/8"	DS2PF L24A	573.	660.	686.
	12/12 no back	24"	23 1/2"	14 7/8"	26 7/8"	DS2PF L24B	542.	625.	651.
	6/6/12 w/back	30"	24 1/2"	14 7/8"	26 7/8"	DS2PF L30A	771.	887.	929.
	12/12 w/back	30"	29 1/2"	14 7/8"	26 7/8"	DS2PF L30B	737.	845.	883.

Series 2 Floorstanding Case Back (For 24" deep units only)				14 7/8"	26 7/8"	DS2XPB	98.	111.	114.
--	--	--	--	---------	---------	---------------	-----	------	------



	6/6/12	18"	16 3/4"	14 7/8"	26 3/8"	DS2PM L18A	1,078.	1,236.	1,290.
	12/12	18"	16 3/4"	14 7/8"	26 3/8"	DS2PM L18B	1,042.	1,201.	1,253.
	6/12	18"	16 3/4"	14 7/8"	20 5/8"	DS2PM L18F	957.	1,103.	1,149.
	6/6/12	24"	22 3/4"	14 7/8"	26 3/8"	DS2PM L24A	782.	904.	942.
	12/12	24"	22 3/4"	14 7/8"	26 3/8"	DS2PM L24B	782.	904.	942.
	6/12	24"	22 3/4"	14 7/8"	20 3/8"	DS2PM L24F	702.	807.	840.

d* = nominal depth
 Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestals 1. Pattern Number 2. Paint Finish	Floorstanding Pedestals <i>Example:</i> DS2PF L24A, 117 DS2PF Pattern Number L24A 117 Soft Grey paint finish Doublewide Pedestals <i>Example:</i> DS2DW 30L, 113 DS2DW Pattern Number 30L 113 Dark grey paint finish	Floorstanding Pedestals <ul style="list-style-type: none"> Hanging file bar not included Note: 24" deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18" and 30" deep floorstanding pedestals have backs. Mobile Pedestals <ul style="list-style-type: none"> Hanging file bar not included Doublewide Pedestals <ul style="list-style-type: none"> Hanging File Bar (front-to-back) Hanging file rail (side-to-side) Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.	Floorstanding Pedestals <ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$15 Doublewide Pedestals <ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$20 Mobile Pedestals <ul style="list-style-type: none"> To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A Deduct \$35 Add \$55 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A) Finish Option: Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option. Full Extension Drawer Slide Option To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add \$25 to the list price.

Pedestals

Series 2 Floorstanding, Doublewide and Mobile

18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Series 2 Doublewide Pedestals with Locks	12/12	19"	18 ³ / ₄ "	30"	26 ⁷ / ₈ "	DS2DW 30L	\$1,013.	\$1,166.	\$1,216.
	12/12	19"	18 ³ / ₄ "	36"	26 ⁷ / ₈ "	DS2DW 36L	1,070.	1,231.	1,285.



d* = nominal depth
 Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestals	Floorstanding Pedestals	Floorstanding Pedestals	Floorstanding Pedestals
1. Pattern Number	<i>Example:</i> DS2PF L24A, 117	<ul style="list-style-type: none"> Hanging file bar not included 	<ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$15
2. Paint Finish	DS2PF Pattern Number	Note: 24" deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18" and 30" deep floorstanding pedestals have backs.	Doublewide Pedestals
	L24A		<ul style="list-style-type: none"> To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$20
	117 Soft Grey paint finish	Mobile Pedestals	Mobile Pedestals
	Doublewide Pedestals	<ul style="list-style-type: none"> Hanging file bar not included 	<ul style="list-style-type: none"> To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A Deduct \$35 Add \$55 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A)
	<i>Example:</i> DS2DW 30L, 113	Doublewide Pedestals	Finish Option:
	DS2DW Pattern Number	<ul style="list-style-type: none"> Hanging File Bar (front-to-back) Hanging file rail (side-to-side) 	Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.
	30L	Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.	Full Extension Drawer Slide Option
	113 Dark grey paint finish		To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add \$25 to the list price.

This page intentionally left blank

Pencil Tray

Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13¹/₄" wide, 5⁷/₁₆" deep and 7/8" high. Black or clear finish available.

Hanging File Bar

Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.

A hanging file bar is included with each file drawer when ordering Series 1 desks or pedestals. Hanging file bars are not included with Series 2 pedestals or desks - order separately.

Drawer Dividers

Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.

Stationery Inserts

Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.

Pencil Drawer

For use with freestanding desks or panel-mounted worksurfaces with depths of 24" or more. 24" wide, 17 5/8" deep and 2" high. Black finish.


Attachment: Mounts on underside of worksurface with included mounting hardware

Pedestal Lock Retrofit Kit


Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core and lock rod assembly (must be specified box/box/file or file/file).

Worksurface Edge Grommet


Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.




Pencil Tray




Stationery Inserts




Hanging File Bar




Pencil Drawer



Worksurface Edge Grommet










Drawer Divider, Box



Drawer Divider, File Drawer

Accessories

Drawer Organizers, Grommet Kits and Lock Retrofit Kits

description	type	w	d	h	pattern no.	list
Pencil Tray 	Black finish	13 1/4"	5 7/8"	7/8"	DS2PPTN	\$43.
	Clear finish	13 1/4"	5 7/8"	7/8"	DS2PPTC	50.
Hanging File Bar 		12 3/16"	2 15/16"	1/2"	DS1PFS	37.
Drawer Divider, Box 		12 3/8"	3"	3 1/8"	DS1PBD	37.
Drawer Divider, File 		10	3 5/8"	6 3/8"	DS1PFD	37.
Stationary Inserts, box (4 trays) 		13	15 1/16"	8 7/8"	DS1PST	196.
Pencil Drawer 		24"	17 5/8"	2"	DS1PCD	265.
Worksurface Grommet Kit (Dark Grey) 		2 3/16"	2 5/16"	1 3/8"	D1WSG	27.
Dividends Floorstanding Pedestal Lock Retrofit Kit					DS1LKKT	82.
Series 2 Floorstanding Pedestal Lock Retrofit Kit	24" ped only				DS2LKKT	67.
Dividends Doublewide Pedestal Lock Retrofit Kit					DS1DWDPL	74.
Series 2 Doublewide Pedestal Lock Retrofit Kit		30"			DS2DWDPL30	71.
		36"			DS2DWDPL36	74.

Ordering Information

Pencil Tray
1. Pattern Number

Order Code

Pencil Tray
Example: **DS2PPT**
DS2PPT Pattern Number

Included with:

Pencil Tray

Options

Single Depth Credenzas

Dividends Horizon single depth credenzas increase planning and design options by blending residential furniture attributes within systems furniture applications. Credenzas offer a practical solution for functional under worksurface storage, while increasing the overall aesthetics of an office.

Credenzas consist of a metal, laminate, or veneer top option with a shelf and binder storage area. Single depth credenzas have four configuration options: sliding door only, drawer only, sliding door and drawer combination, and open shelves without a sliding door or a drawer.

The sliding door is a single steel, laminate, or veneer door with a handle that conceals half the width of the binder storage area. A single drawer may be specified for the location above the shelf. The drawer may be installed in either the right or left location, the drawer location does not need to be specified when ordered. When a drawer is specified along with a sliding door, the drawer front and sliding door finishes are the same. Units that include a drawer have a full back and those without a drawer have a partial back that encloses the binder storage area below the shelf.

Shorter width credenzas, 24, 30, and 36 inches wide, are available with a laminate or veneer top only. 24 inch wide credenzas do not include a center vertical septum and are only available as open shelf units, without a sliding door or drawer. Units are shipped knocked down and may be specified with or without locks. Dividends Horizon credenzas are available in all Knoll Core finishes. Legacy finishes are not available.

Available Sizes

Heights: 24 inches
Depth: 13-5/16 inches
Widths: 24 – 72 inches

Construction

- **Top:**
 - Steel: 16-gauge painted steel
 - Laminate: 1-1/4 inch thick particle board with laminate on top and a paper backer on the underside with 2mm edgeband
 - Veneer: 1-1/4 inch thick particle board with 0.6mm veneer on top and edge.
- **End Panels:** 16-gauge painted steel
- **Back Panel:** 20-gauge painted steel

• **Door:**

- Steel: 20-gauge panted steel
- Laminate: 3/4 inch thick particle board with laminate on the outside and a paper backer on the inside with 1mm edgeband
- Veneer 3/4 inch thick particle board with 0.6mm thick veneer on top and edge

• **Fixed Shelf:** 16-gauge painted steel

• **Door Handle:** painted aluminum (same color as case)


Interior Dimensions

Heights: 12-1/2 inches for the lower section, 5-7/8 inches for the upper section
Depth: 12-1/16 inches


Locks

Locks are standard on credenzas with doors and/or drawers and are keyed randomly unless otherwise specified. All locks are factory installed and have a black finish. Credenzas can also be specified without locks if required.


Single Depth Credenza with Open Shelves




Single Depth Credenza with a Drawer



Single Depth Credenza with a Sliding Door







Single Depth Credenza with a Drawer and a Sliding Door



Credenzas

Single Depth with Steel Top




With or Without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS42N	\$734.	\$806.	\$843.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS48N	753.	827.	866.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS54N	838.	924.	967.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS60N	848.	934.	976.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS66N	873.	959.	1,003.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS72N	909.	999.	1,041.
 Credenza with Steel Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS42L	908.	997.	1,039.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS48L	925.	1,019.	1,064.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS54L	1,029.	1,133.	1,182.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS60L	1,034.	1,140.	1,190.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS66L	1,067.	1,174.	1,227.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS72L	1,104.	1,210.	1,266.
 Credenza with Laminate Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS42L	1,471.	1,619.	1,689.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS48L	1,508.	1,656.	1,730.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS54L	1,542.	1,695.	1,770.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS60L	1,578.	1,733.	1,809.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS66L	1,615.	1,772.	1,851.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS72L	1,650.	1,809.	1,892.
 Credenza with Veneer Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS42L	1,570.	1,724.	1,802.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS48L	1,615.	1,772.	1,850.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS54L	1,658.	1,820.	1,901.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS60L	1,701.	1,868.	1,952.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS66L	1,744.	1,917.	2,001.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS72L	1,788.	1,962.	2,052.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Door finish (laminite and veneer only) 4. Door edge finish (laminite only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BSS42L/117 DS4LC1B Pattern Number SS42L 117 Dark grey paint	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without Sliding Door: 1. Pattern number 2. Paint finish	<i>Example:</i> DS4LC1ANS42N/117 DS4LC1A Pattern Number NS42N 117 Dark grey paint		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas
Single Depth with Steel Top
Without a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Steel Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS42L	\$1,102.	\$1,172.	\$1,210.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS48L	1,118.	1,192.	1,229.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS54L	1,206.	1,289.	1,331.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS60L	1,215.	1,299.	1,341.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS66L	1,237.	1,326.	1,370.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS72L	1,272.	1,366.	1,411.
 Credenza with Laminate Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS42L	1,304.	1,376.	1,415.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS48L	1,323.	1,397.	1,432.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS54L	1,411.	1,495.	1,536.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS60L	1,419.	1,503.	1,544.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS66L	1,445.	1,530.	1,573.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS72L	1,476.	1,569.	1,615.
 Credenza with Veneer Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS42L	1,347.	1,420.	1,458.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS48L	1,368.	1,443.	1,479.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS54L	1,454.	1,538.	1,579.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS60L	1,462.	1,547.	1,590.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS66L	1,488.	1,573.	1,618.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS72L	1,522.	1,614.	1,658.

Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Drawer front finish (laminite and veneer only) 4. Drawer front edge finish (laminite only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CLS42L /117/118/118 DS4LC1C Pattern Number LS42L 117 Dark grey paint 118 Bright white drawer front 118 Bright white drawer front edge	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
			Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas


Single Depth with Steel Top

With a Sliding Door and with a Drawer


description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS42L	\$1,271.	\$1,365.	\$1,409.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS48L	1,291.	1,383.	1,428.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS54L	1,394.	1,498.	1,547.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS60L	1,403.	1,505.	1,556.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS66L	1,430.	1,539.	1,593.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS72L	1,467.	1,574.	1,633.



Credenza with Laminate Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS42L	1,839.	1,983.	2,054.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS48L	1,875.	2,022.	2,096.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS54L	1,908.	2,058.	2,137.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS60L	1,943.	2,099.	2,177.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS66L	1,979.	2,139.	2,219.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS72L	2,015.	2,177.	2,257.



Credenza with Veneer Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS42L	1,935.	2,091.	2,170.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS48L	1,979.	2,139.	2,217.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS54L	2,023.	2,185.	2,267.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS60L	2,064.	2,232.	2,317.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS66L	2,107.	2,282.	2,367.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS72L	2,152.	2,330.	2,417.



Dimensions listed under w h d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Drawer/Door finish (laminated and veneer only) 4. Drawer/Door edge finish (laminated only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1DSS42L/117 DS4LC1D Pattern Number SS42L 117 Dark grey paint	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Laminate Top

With or without a Sliding Door

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL24N	\$987.	\$1,082.	\$1,136.
	30"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL30N	987.	1,082.	1,136.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL36N	987.	1,082.	1,136.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL42N	987.	1,082.	1,136.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL48N	1,015.	1,116.	1,168.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL54N	1,093.	1,204.	1,259.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL60N	1,094.	1,206.	1,260.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL72N	1,171.	1,288.	1,344.
 Credenza with Steel Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL30L	1,148.	1,262.	1,319.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL36L	1,148.	1,262.	1,319.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL42L	1,148.	1,262.	1,319.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL48L	1,176.	1,294.	1,354.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL54L	1,277.	1,407.	1,467.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL60L	1,278.	1,409.	1,470.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL66L	1,319.	1,452.	1,516.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL72L	1,357.	1,494.	1,560.
 Credenza with Laminate Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL30L	1,599.	1,757.	1,837.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL36L	1,599.	1,757.	1,837.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL42L	1,599.	1,757.	1,837.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL48L	1,650.	1,809.	1,894.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL54L	1,700.	1,867.	1,949.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL60L	1,750.	1,922.	2,007.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL66L	1,800.	1,977.	2,063.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL72L	1,849.	2,033.	2,125.

Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminated and veneer only) 6. Door edge finish (laminated only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BLL42L /117/118/117/118/118 DS4LC1B Pattern Number LL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge 118 Bright white door 118 Bright white door edge	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$20. from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANL42N/117 DS4LC1A Pattern Number NL42N 117 Dark grey paint 118 Bright white top 117 Dark grey top edge		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Laminate Top

With or without a Sliding Door




Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Veneer Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL30L	\$1,700.	\$1,867.	\$1,952.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL36L	1,700.	1,867.	1,952.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL42L	1,700.	1,867.	1,952.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL48L	1,758.	1,931.	2,017.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL54L	1,814.	1,995.	2,085.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL60L	1,874.	2,057.	2,150.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL66L	1,931.	2,121.	2,219.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL72L	1,988.	2,185.	2,284.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminated and veneer only) 6. Door edge finish (laminated only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BLL42L /117/118/117/118/118 DS4LC1B Pattern Number LL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge 118 Bright white door 118 Bright white door edge	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$20. from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANL42N/117 DS4LC1A Pattern Number NL42N 117 Dark grey paint 118 Bright white top 117 Dark grey top edge		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

*Single Depth with Laminate Top
Without a Sliding Door and with a Drawer*


description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Steel Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL30L	\$1,354.	\$1,450.	\$1,500.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL36L	1,354.	1,450.	1,500.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL42L	1,354.	1,450.	1,500.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL48L	1,380.	1,481.	1,532.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL54L	1,459.	1,569.	1,624.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL60L	1,460.	1,570.	1,625.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL66L	1,498.	1,613.	1,668.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CSL72L	1,536.	1,654.	1,710.
 Credenza with Laminate Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL30L	1,558.	1,654.	1,705.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL36L	1,558.	1,654.	1,705.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL42L	1,558.	1,654.	1,705.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL48L	1,585.	1,686.	1,737.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL54L	1,664.	1,772.	1,831.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL60L	1,666.	1,773.	1,832.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL66L	1,702.	1,814.	1,872.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CLL72L	1,740.	1,858.	1,916.
 Credenza with Veneer Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL30L	1,602.	1,698.	1,749.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL36L	1,602.	1,698.	1,749.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL42L	1,602.	1,698.	1,749.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL48L	1,628.	1,729.	1,782.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL54L	1,707.	1,815.	1,874.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL60L	1,709.	1,816.	1,875.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL66L	1,747.	1,859.	1,917.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CVL72L	1,785.	1,901.	1,958.


Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer finish (laminated and veneer only) 6. Drawer edge finish (laminated only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CSL42L /117/118/117 DS4LC1C Pattern Number SL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Laminate Top With a Sliding Door and with a Drawer

description	w	d	h	pattern no.	P1	P2	P3
 Credenza with Steel Sliding Door and Drawer	30"	13 ³ / ₁₆ "	24"	DS4LC1DSL30L	\$1,512.	\$1,628.	\$1,686.
	36"	13 ³ / ₁₆ "	24"	DS4LC1DSL36L	1,512.	1,628.	1,686.
	42"	13 ³ / ₁₆ "	24"	DS4LC1DSL42L	1,512.	1,628.	1,686.
	48"	13 ³ / ₁₆ "	24"	DS4LC1DSL48L	1,541.	1,661.	1,719.
	54"	13 ³ / ₁₆ "	24"	DS4LC1DSL54L	1,643.	1,770.	1,835.
	60"	13 ³ / ₁₆ "	24"	DS4LC1DSL60L	1,644.	1,771.	1,838.
	66"	13 ³ / ₁₆ "	24"	DS4LC1DSL66L	1,686.	1,815.	1,884.
	72"	13 ³ / ₁₆ "	24"	DS4LC1DSL72L	1,722.	1,858.	1,926.

 Credenza with Laminate Sliding Door and Drawer	30"	13 ³ / ₁₆ "	24"	DS4LC1DLL30L	1,964.	2,125.	2,201.
	36"	13 ³ / ₁₆ "	24"	DS4LC1DLL36L	1,964.	2,125.	2,201.
	42"	13 ³ / ₁₆ "	24"	DS4LC1DLL42L	1,964.	2,125.	2,201.
	48"	13 ³ / ₁₆ "	24"	DS4LC1DLL48L	2,015.	2,177.	2,258.
	54"	13 ³ / ₁₆ "	24"	DS4LC1DLL54L	2,063.	2,231.	2,316.
	60"	13 ³ / ₁₆ "	24"	DS4LC1DLL60L	2,115.	2,287.	2,374.
	66"	13 ³ / ₁₆ "	24"	DS4LC1DLL66L	2,166.	2,342.	2,432.
	72"	13 ³ / ₁₆ "	24"	DS4LC1DLL72L	2,214.	2,398.	2,487.

 Credenza with Veneer Sliding Door and Drawer	30"	13 ³ / ₁₆ "	24"	DS4LC1DVL30L	2,063.	2,231.	2,317.
	36"	13 ³ / ₁₆ "	24"	DS4LC1DVL36L	2,063.	2,231.	2,317.
	42"	13 ³ / ₁₆ "	24"	DS4LC1DVL42L	2,063.	2,231.	2,317.
	48"	13 ³ / ₁₆ "	24"	DS4LC1DVL48L	2,126.	2,296.	2,384.
	54"	13 ³ / ₁₆ "	24"	DS4LC1DVL54L	2,181.	2,359.	2,449.
	60"	13 ³ / ₁₆ "	24"	DS4LC1DVL60L	2,239.	2,425.	2,516.
	66"	13 ³ / ₁₆ "	24"	DS4LC1DVL66L	2,296.	2,485.	2,585.
	72"	13 ³ / ₁₆ "	24"	DS4LC1DVL72L	2,355.	2,552.	2,648.

Dimensions listed under w h d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer/Door finish (laminated and veneer only) 6. Drawer/Door edge finish (laminated only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1DSL42L /117/118/117 DS4LC1D Pattern Number SL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Veneer Top

With or without a Sliding Door


Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV24N	\$1,510.	\$1,663.	\$1,738.
	30"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV30N	1,510.	1,663.	1,738.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV36N	1,510.	1,663.	1,738.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV42N	1,510.	1,663.	1,738.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV48N	1,545.	1,702.	1,781.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV54N	1,584.	1,743.	1,821.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV60N	1,621.	1,783.	1,863.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV66N	1,656.	1,821.	1,905.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1ANV72N	1,694.	1,862.	1,946.
 Credenza with Steel Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV30L	1,594.	1,751.	1,831.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV36L	1,594.	1,751.	1,831.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV42L	1,594.	1,751.	1,831.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV48L	1,634.	1,794.	1,874.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV54L	1,672.	1,837.	1,919.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV60L	1,710.	1,880.	1,962.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV66L	1,749.	1,921.	2,006.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BSV72L	1,788.	1,962.	2,052.
 Credenza with Laminate Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV30L	1,937.	2,129.	2,223.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV36L	1,937.	2,129.	2,223.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV42L	1,937.	2,129.	2,223.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV48L	1,976.	2,172.	2,267.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV54L	2,015.	2,213.	2,311.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV60L	2,054.	2,256.	2,359.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV66L	2,093.	2,300.	2,403.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BLV72L	2,134.	2,343.	2,449.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminare and veneer) 5. Door edge finish (laminare only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BSV42L /117/Y319 DS4LC1B Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANV42N /117/Y319 DS4LC1A Pattern Number NV42N 117 Dark grey paint Y319 Cherry Techwood top		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.




Credenzas
Single Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Veneer Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV30L	\$2,038.	\$2,236.	\$2,340.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV36L	2,038.	2,236.	2,340.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV42L	2,038.	2,236.	2,340.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV48L	2,085.	2,290.	2,394.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV54L	2,133.	2,342.	2,448.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV60L	2,179.	2,394.	2,500.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV66L	2,225.	2,445.	2,556.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV72L	2,274.	2,496.	2,609.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer) 5. Door edge finish (laminate only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BSV42L /117/Y319 <hr/> DS4LC1B Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top <hr/>	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANV42N /117/Y319 <hr/> DS4LC1A Pattern Number NV42N <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top <hr/>		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Credenzas
Single Depth with Veneer Top
Without a Sliding Door and with a Drawer


description	w	h	d	pattern no.	P1	P2	P3
	30"	24"	13 5/16"	DS4LC1CSV30L	\$1,878.	\$2,027.	\$2,102.
	36"	24"	13 5/16"	DS4LC1CSV36L	1,878.	2,027.	2,102.
	42"	24"	13 5/16"	DS4LC1CSV42L	1,878.	2,027.	2,102.
	48"	24"	13 5/16"	DS4LC1CSV48L	1,914.	2,066.	2,144.
	54"	24"	13 5/16"	DS4LC1CSV54L	1,948.	2,106.	2,188.
	60"	24"	13 5/16"	DS4LC1CSV60L	1,985.	2,146.	2,228.
	66"	24"	13 5/16"	DS4LC1CSV66L	2,022.	2,188.	2,272.
	72"	24"	13 5/16"	DS4LC1CSV72L	2,057.	2,226.	2,310.
	30"	24"	13 5/16"	DS4LC1CLV30L	2,083.	2,232.	2,307.
	36"	24"	13 5/16"	DS4LC1CLV36L	2,083.	2,232.	2,307.
	42"	24"	13 5/16"	DS4LC1CLV42L	2,083.	2,232.	2,307.
	48"	24"	13 5/16"	DS4LC1CLV48L	2,117.	2,273.	2,349.
	54"	24"	13 5/16"	DS4LC1CLV54L	2,152.	2,310.	2,393.
	60"	24"	13 5/16"	DS4LC1CLV60L	2,191.	2,351.	2,433.
	66"	24"	13 5/16"	DS4LC1CLV66L	2,226.	2,393.	2,477.
	72"	24"	13 5/16"	DS4LC1CLV72L	2,261.	2,432.	2,516.
	30"	24"	13 5/16"	DS4LC1CVV30L	2,127.	2,276.	2,351.
	36"	24"	13 5/16"	DS4LC1CVV36L	2,127.	2,276.	2,351.
	42"	24"	13 5/16"	DS4LC1CVV42L	2,127.	2,276.	2,351.
	48"	24"	13 5/16"	DS4LC1CVV48L	2,160.	2,317.	2,394.
	54"	24"	13 5/16"	DS4LC1CVV54L	2,197.	2,356.	2,436.
	60"	24"	13 5/16"	DS4LC1CVV60L	2,234.	2,396.	2,477.
	66"	24"	13 5/16"	DS4LC1CVV66L	2,270.	2,436.	2,519.
	72"	24"	13 5/16"	DS4LC1CVV72L	2,306.	2,476.	2,561.


Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminated and veneer only) 5. Door edge finish (laminated only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CSV42L /117/ Y319 <hr/> DS4LC1C Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Single Depth with Veneer Top
With a Sliding Door and with a Drawer

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Steel Sliding Door and Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV30L	\$1,959.	\$2,117.	\$2,194.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV36L	1,959.	2,117.	2,194.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV42L	1,959.	2,117.	2,194.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV48L	1,999.	2,158.	2,239.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV54L	2,038.	2,201.	2,284.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV60L	2,077.	2,245.	2,330.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV66L	2,114.	2,286.	2,373.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV72L	2,152.	2,330.	2,417.

 Credenza with Laminate Sliding Door and Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV30L	2,301.	2,492.	2,589.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV36L	2,301.	2,492.	2,589.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV42L	2,301.	2,492.	2,589.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV48L	2,341.	2,535.	2,634.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV54L	2,381.	2,580.	2,678.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV60L	2,419.	2,623.	2,724.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV66L	2,456.	2,667.	2,768.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV72L	2,497.	2,709.	2,815.

 Credenza with Veneer Sliding Door and Drawer	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV30L	2,402.	2,602.	2,706.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV36L	2,402.	2,602.	2,706.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV42L	2,402.	2,602.	2,706.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV48L	2,449.	2,656.	2,758.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV54L	2,496.	2,708.	2,814.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV60L	2,543.	2,758.	2,868.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV66L	2,591.	2,811.	2,921.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV72L	2,640.	2,863.	2,973.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Drawer/Door finish (laminated and veneer only) 5. Drawer/Door edge finish (laminated only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1SV42L /117/Y319 DS4LC1 Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
			Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Double Depth Credenzas

Dividends Horizon double depth credenzas are designed for use in various applications, including personal storage in shared workstations, space division in the open plan, and impromptu collaboration areas. Double depth credenzas offer a more unified aesthetic option, with the seamless top and end panels, when back-to-back credenzas are required.

Double depth credenzas consist of a seamless laminate or veneer top option with a shelf and binder storage area. Credenzas have four configuration options: sliding door only, drawer only, sliding door and drawer combination, and open shelves without a sliding door or a drawer. Double depth credenzas have the same configuration on both sides.

The sliding door is a single steel, laminate, or veneer door with a handle that conceals half the width of the binder storage area. A single drawer may be specified for the location above the shelf. The drawer may be installed in either the right or left location, the drawer location does not need to be specified when ordered. When a drawer is specified along with a sliding door, the drawer front and sliding door finishes are the same. A single full back panel divides the front and back sections of the credenza.

24 inch wide credenzas do not include a center vertical septum and are only available as open shelf units, without a sliding door or drawer. Units are shipped knocked down and may be specified with or without locks. Dividends Horizon credenzas are available in all Knoll Core finishes. Legacy finishes are not available.

Available Sizes

Heights: 24 inches
 Depth: 26-5/8 inches
 Widths: 24 – 72 inches

Construction

- **Top:**
 - Laminate: 1-1/4 inch thick particle board with laminate on top and a paper backer on the underside with 2mm edgeband
 - Veneer: 1-1/4 inch thick particle board with 0.6mm veneer on top and edge.
- **End Panels:** 16-gauge painted steel
- **Back Panel:** 20-gauge painted steel

• **Door:**

- Steel: 20-gauge panted steel
- Laminate: 3/4 inch thick particle board with high laminate on the outside and a paper backer on the inside with 1mm edgeband
- Veneer 3/4 inch thick particle board with 0.6mm thick veneer on top and edge

• **Fixed Shelf:** 16-gauge painted steel

• **Door Handle:** painted aluminum (same color as case)


Interior Dimensions

Heights: 12-1/2 inches for the lower section, 5-7/8 inches for the upper section
 Depth: 12-1/16 inches


Locks

Locks are standard on credenzas with doors and/or drawers and are keyed randomly unless otherwise specified. All locks are factory installed and have a black finish. Credenzas can also be specified without locks if required.


Double Depth Credenza with Open Shelves




Double Depth Credenza with a Drawer



Double Depth Credenza with a Sliding Door






Double Depth Credenza with a Drawer and a Sliding Door



Credenzas

Double Depth with Laminate Top


With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	26 ⁵ / ₈ "	DS4LC2ANL24N	\$1,976.	\$2,170.	\$2,270.
	30"	24"	26 ⁵ / ₈ "	DS4LC2ANL30N	1,976.	2,170.	2,270.
	36"	24"	26 ⁵ / ₈ "	DS4LC2ANL36N	1,976.	2,170.	2,270.
	42"	24"	26 ⁵ / ₈ "	DS4LC2ANL42N	1,976.	2,170.	2,270.
	48"	24"	26 ⁵ / ₈ "	DS4LC2ANL48N	2,029.	2,231.	2,334.
	54"	24"	26 ⁵ / ₈ "	DS4LC2ANL54N	2,188.	2,406.	2,518.
	60"	24"	26 ⁵ / ₈ "	DS4LC2ANL60N	2,190.	2,408.	2,520.
	66"	24"	26 ⁵ / ₈ "	DS4LC2ANL66N	2,264.	2,491.	2,603.
	72"	24"	26 ⁵ / ₈ "	DS4LC2ANL72N	2,341.	2,577.	2,688.
 Credenza with Steel Sliding Door	30"	24"	26 ⁵ / ₈ "	DS4LC2BSL30L	2,294.	2,526.	2,641.
	36"	24"	26 ⁵ / ₈ "	DS4LC2BSL36L	2,294.	2,526.	2,641.
	42"	24"	26 ⁵ / ₈ "	DS4LC2BSL42L	2,294.	2,526.	2,641.
	48"	24"	26 ⁵ / ₈ "	DS4LC2BSL48L	2,353.	2,590.	2,707.
	54"	24"	26 ⁵ / ₈ "	DS4LC2BSL54L	2,555.	2,811.	2,934.
	60"	24"	26 ⁵ / ₈ "	DS4LC2BSL60L	2,559.	2,814.	2,943.
	66"	24"	26 ⁵ / ₈ "	DS4LC2BSL66L	2,641.	2,904.	3,035.
	72"	24"	26 ⁵ / ₈ "	DS4LC2BSL72L	2,713.	2,986.	3,121.
 Credenza with Laminate Sliding Door	30"	24"	26 ⁵ / ₈ "	DS4LC2BLL30L	3,200.	3,514.	3,671.
	36"	24"	26 ⁵ / ₈ "	DS4LC2BLL36L	3,200.	3,514.	3,671.
	42"	24"	26 ⁵ / ₈ "	DS4LC2BLL42L	3,200.	3,514.	3,671.
	48"	24"	26 ⁵ / ₈ "	DS4LC2BLL48L	3,301.	3,623.	3,788.
	54"	24"	26 ⁵ / ₈ "	DS4LC2BLL54L	3,400.	3,732.	3,899.
	60"	24"	26 ⁵ / ₈ "	DS4LC2BLL60L	3,501.	3,844.	4,016.
	66"	24"	26 ⁵ / ₈ "	DS4LC2BLL66L	3,600.	3,953.	4,131.
	72"	24"	26 ⁵ / ₈ "	DS4LC2BLL72L	3,700.	4,065.	4,245.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminite and veneer only) 6. Door edge finish (laminite only)	Credenza with a Sliding Door: Example: DS4LC2BSL42L /117/118/117 <hr/> DS4LC2B Pattern Number LL42L <hr/> 117 Dark grey paint <hr/> 118 Bright white top <hr/> 117 Dark grey top edge	Credenza with a Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: Example: DS4LC2ANL42N /117/118/117 <hr/> DS4LC2A Pattern Number NL42N <hr/> 117 Dark grey paint <hr/> 118 Bright white top <hr/> 117 Dark grey top edge		




Credenzas
Double Depth with Laminate Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
	30"	24"	26 ⁵ / ₈ "	DS4LC2BVL30L	\$3,400.	\$3,732.	\$3,902.
	36"	24"	26 ⁵ / ₈ "	DS4LC2BVL36L	3,400.	3,732.	3,902.
	42"	24"	26 ⁵ / ₈ "	DS4LC2BVL42L	3,400.	3,732.	3,902.
	48"	24"	26 ⁵ / ₈ "	DS4LC2BVL48L	3,516.	3,863.	4,036.
	54"	24"	26 ⁵ / ₈ "	DS4LC2BVL54L	3,632.	3,986.	4,169.
	60"	24"	26 ⁵ / ₈ "	DS4LC2BVL60L	3,745.	4,117.	4,300.
	66"	24"	26 ⁵ / ₈ "	DS4LC2BVL66L	3,863.	4,240.	4,435.
	72"	24"	26 ⁵ / ₈ "	DS4LC2BVL72L	3,978.	4,373.	4,568.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminated and veneer only) 6. Door edge finish (laminated only)	Credenza with a Sliding Door: <i>Example:</i> DS4LC2BSL42L /117/118/117 <hr/> DS4LC2B Pattern Number LL42L <hr/> 117 Dark grey paint <hr/> 118 Bright white top <hr/> 117 Dark grey top edge	Credenza with a Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC2ANL42N /117/118/117 <hr/> DS4LC2A Pattern Number NL42N <hr/> 117 Dark grey paint <hr/> 118 Bright white top <hr/> 117 Dark grey top edge		


*Double Depth with Laminate Top
Without a Sliding Door and with a Drawer*


description	w	h	d	pattern no.	P1	P2	P3
 <p>Credenza with Steel Drawer</p>	30"	24"	26 ⁵ / ₈ "	DS4LC2CSL30L	\$2,707.	\$2,900.	\$3,001.
	36"	24"	26 ⁵ / ₈ "	DS4LC2CSL36L	2,707.	2,900.	3,001.
	42"	24"	26 ⁵ / ₈ "	DS4LC2CSL42L	2,707.	2,900.	3,001.
	48"	24"	26 ⁵ / ₈ "	DS4LC2CSL48L	2,759.	2,961.	3,065.
	54"	24"	26 ⁵ / ₈ "	DS4LC2CSL54L	2,918.	3,138.	3,250.
	60"	24"	26 ⁵ / ₈ "	DS4LC2CSL60L	2,920.	3,140.	3,253.
	66"	24"	26 ⁵ / ₈ "	DS4LC2CSL66L	2,997.	3,222.	3,335.
	72"	24"	26 ⁵ / ₈ "	DS4LC2CSL72L	3,071.	3,308.	3,420.
 <p>Credenza with Laminate Drawer</p>	30"	24"	26 ⁵ / ₈ "	DS4LC2CLL30L	3,116.	3,308.	3,411.
	36"	24"	26 ⁵ / ₈ "	DS4LC2CLL36L	3,116.	3,308.	3,411.
	42"	24"	26 ⁵ / ₈ "	DS4LC2CLL42L	3,116.	3,308.	3,411.
	48"	24"	26 ⁵ / ₈ "	DS4LC2CLL48L	3,169.	3,372.	3,473.
	54"	24"	26 ⁵ / ₈ "	DS4LC2CLL54L	3,327.	3,548.	3,658.
	60"	24"	26 ⁵ / ₈ "	DS4LC2CLL60L	3,329.	3,550.	3,661.
	66"	24"	26 ⁵ / ₈ "	DS4LC2CLL66L	3,404.	3,632.	3,743.
	72"	24"	26 ⁵ / ₈ "	DS4LC2CLL72L	3,479.	3,716.	3,829.
 <p>Credenza with Veneer Drawer</p>	30"	24"	26 ⁵ / ₈ "	DS4LC2CVL30L	3,204.	3,396.	3,499.
	36"	24"	26 ⁵ / ₈ "	DS4LC2CVL36L	3,204.	3,396.	3,499.
	42"	24"	26 ⁵ / ₈ "	DS4LC2CVL42L	3,204.	3,396.	3,499.
	48"	24"	26 ⁵ / ₈ "	DS4LC2CVL48L	3,257.	3,459.	3,561.
	54"	24"	26 ⁵ / ₈ "	DS4LC2CVL54L	3,416.	3,634.	3,745.
	60"	24"	26 ⁵ / ₈ "	DS4LC2CVL60L	3,418.	3,637.	3,749.
	66"	24"	26 ⁵ / ₈ "	DS4LC2CVL66L	3,492.	3,718.	3,832.
	72"	24"	26 ⁵ / ₈ "	DS4LC2CVL72L	3,568.	3,806.	3,916.


Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
<p>Credenza with a Drawer:</p> <ol style="list-style-type: none"> 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer finish (laminated and veneer only) 6. Drawer edge finish (laminated only) 	<p>Credenza with a Drawer:</p> <p><i>Example:</i> DS4LC2CSL42L /117/118/117</p> <hr/> <p>DS4LC2C Pattern Number</p> <hr/> <p>SL42L</p> <hr/> <p>117 Dark grey paint</p> <hr/> <p>118 Bright white top</p> <hr/> <p>117 Dark grey top edge</p>	<p>Credenza with a Drawer:</p> <p>Note: Credenzas are only available in Knoll core finishes.</p>	<p>Credenza with a Drawer:</p> <p>Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price.</p> <p>Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.</p>

*Double Depth with Laminate Top
With a Sliding Door and with a Drawer*

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer 	30"	24"	26 ⁵ / ₈ "	DS4LC2DSL30L	\$3,025.	\$3,257.	\$3,372.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DSL36L	3,025.	3,257.	3,372.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DSL42L	3,025.	3,257.	3,372.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DSL48L	3,084.	3,319.	3,436.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DSL54L	3,285.	3,543.	3,667.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DSL60L	3,290.	3,546.	3,673.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DSL66L	3,372.	3,634.	3,765.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DSL72L	3,444.	3,716.	3,852.

Credenza with Laminate Sliding Door and Drawer 	30"	24"	26 ⁵ / ₈ "	DS4LC2DLL30L	3,930.	4,245.	4,401.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DLL36L	3,930.	4,245.	4,401.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DLL42L	3,930.	4,245.	4,401.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DLL48L	4,031.	4,352.	4,519.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DLL54L	4,131.	4,463.	4,630.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DLL60L	4,231.	4,575.	4,745.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DLL66L	4,331.	4,683.	4,860.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DLL72L	4,430.	4,796.	4,976.

Credenza with Veneer Sliding Door and Drawer 	30"	24"	26 ⁵ / ₈ "	DS4LC2DVL30L	4,131.	4,463.	4,633.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DVL36L	4,131.	4,463.	4,633.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DVL42L	4,131.	4,463.	4,633.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DVL48L	4,247.	4,594.	4,767.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DVL54L	4,364.	4,718.	4,898.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DVL60L	4,477.	4,848.	5,033.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DVL66L	4,594.	4,970.	5,166.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DVL72L	4,708.	5,102.	5,298.

Dimensions listed under w h d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer/Door finish (laminated and veneer only) 6. Drawer/Door edge finish (laminated only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC2DSL42L /117/118/117 DS4LC2D Pattern Number SL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$80 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Double Depth with Veneer Top

With or without a Sliding Door

Dividends Horizon


description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	26 ³ / ₈ "	DS4LC2ANV24N	\$3,022.	\$3,325.	\$3,475.
	30"	24"	26 ³ / ₈ "	DS4LC2ANV30N	3,022.	3,325.	3,475.
	36"	24"	26 ³ / ₈ "	DS4LC2ANV36N	3,022.	3,325.	3,475.
	42"	24"	26 ³ / ₈ "	DS4LC2ANV42N	3,022.	3,325.	3,475.
	48"	24"	26 ³ / ₈ "	DS4LC2ANV48N	3,095.	3,404.	3,559.
	54"	24"	26 ³ / ₈ "	DS4LC2ANV54N	3,167.	3,482.	3,643.
	60"	24"	26 ³ / ₈ "	DS4LC2ANV60N	3,243.	3,563.	3,723.
	66"	24"	26 ³ / ₈ "	DS4LC2ANV66N	3,313.	3,643.	3,813.
	72"	24"	26 ³ / ₈ "	DS4LC2ANV72N	3,387.	3,721.	3,893.
 Credenza with Steel Sliding Door	30"	24"	26 ³ / ₈ "	DS4LC2BSV30L	3,186.	3,504.	3,658.
	36"	24"	26 ³ / ₈ "	DS4LC2BSV36L	3,186.	3,504.	3,658.
	42"	24"	26 ³ / ₈ "	DS4LC2BSV42L	3,186.	3,504.	3,658.
	48"	24"	26 ³ / ₈ "	DS4LC2BSV48L	3,265.	3,589.	3,745.
	54"	24"	26 ³ / ₈ "	DS4LC2BSV54L	3,345.	3,671.	3,837.
	60"	24"	26 ³ / ₈ "	DS4LC2BSV60L	3,420.	3,758.	3,928.
	66"	24"	26 ³ / ₈ "	DS4LC2BSV66L	3,499.	3,841.	4,014.
	72"	24"	26 ³ / ₈ "	DS4LC2BSV72L	3,574.	3,928.	4,103.
 Credenza with Laminate Sliding Door	30"	24"	26 ³ / ₈ "	DS4LC2BLV30L	3,873.	4,254.	4,445.
	36"	24"	26 ³ / ₈ "	DS4LC2BLV36L	3,873.	4,254.	4,445.
	42"	24"	26 ³ / ₈ "	DS4LC2BLV42L	3,873.	4,254.	4,445.
	48"	24"	26 ³ / ₈ "	DS4LC2BLV48L	3,949.	4,340.	4,536.
	54"	24"	26 ³ / ₈ "	DS4LC2BLV54L	4,031.	4,428.	4,626.
	60"	24"	26 ³ / ₈ "	DS4LC2BLV60L	4,108.	4,515.	4,718.
	66"	24"	26 ³ / ₈ "	DS4LC2BLV66L	4,184.	4,600.	4,809.
	72"	24"	26 ³ / ₁₆ "	DS4LC2BLV72L	4,266.	4,685.	4,898.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer) 5. Door edge finish (laminate only)	Credenza with a Sliding Door: <i>Example:</i> DS4LC2BSV42L /117/Y319 <hr/> DS4LC2B Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC2ASV42L /117/Y319 <hr/> DS4LC2A Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top		

Storage Components




Credenzas
Double Depth with Veneer Top
With or without a Sliding Door

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Veneer Sliding Door	30"	24"	26 5/8"	DS4LC2BVV30L	\$4,075.	\$4,475.	\$4,679.
	36"	24"	26 5/8"	DS4LC2BVV36L	4,075.	4,475.	4,679.
	42"	24"	26 5/8"	DS4LC2BVV42L	4,075.	4,475.	4,679.
	48"	24"	26 5/8"	DS4LC2BVV48L	4,169.	4,582.	4,786.
	54"	24"	26 5/8"	DS4LC2BVV54L	4,263.	4,683.	4,896.
	60"	24"	26 5/8"	DS4LC2BVV60L	4,357.	4,786.	5,005.
	66"	24"	26 5/8"	DS4LC2BVV66L	4,449.	4,891.	5,113.
	72"	24"	26 5/8"	DS4LC2BVV72L	4,547.	4,995.	5,216.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer) 5. Door edge finish (laminate only)	Credenza with a Sliding Door: <i>Example:</i> DS4LC2BSV42L /117/Y319 <hr/> DS4LC2B Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC2ASV42L /117/Y319 <hr/> DS4LC2A Pattern Number SV42L <hr/> 117 Dark grey paint <hr/> Y319 Cherry Techwood top		


*Double Depth with Veneer Top
Without a Sliding Door and with a Drawer*


description	w	h	d	pattern no.	P1	P2	P3
 <p>Credenza with Steel Drawer</p>	30"	24"	26 5/8"	DS4LC2CSV30L	\$3,754.	\$4,057.	\$4,206.
	36"	24"	26 5/8"	DS4LC2CSV36L	3,754.	4,057.	4,206.
	42"	24"	26 5/8"	DS4LC2CSV42L	3,754.	4,057.	4,206.
	48"	24"	26 5/8"	DS4LC2CSV48L	3,824.	4,135.	4,290.
	54"	24"	26 5/8"	DS4LC2CSV54L	3,897.	4,214.	4,375.
	60"	24"	26 5/8"	DS4LC2CSV60L	3,974.	4,294.	4,454.
	66"	24"	26 5/8"	DS4LC2CSV66L	4,044.	4,375.	4,543.
	72"	24"	26 5/8"	DS4LC2CSV72L	4,117.	4,451.	4,624.
 <p>Credenza with Laminate Drawer</p>	30"	24"	26 5/8"	DS4LC2CLV30L	4,163.	4,465.	4,617.
	36"	24"	26 5/8"	DS4LC2CLV36L	4,163.	4,465.	4,617.
	42"	24"	26 5/8"	DS4LC2CLV42L	4,163.	4,465.	4,617.
	48"	24"	26 5/8"	DS4LC2CLV48L	4,233.	4,545.	4,698.
	54"	24"	26 5/8"	DS4LC2CLV54L	4,306.	4,624.	4,784.
	60"	24"	26 5/8"	DS4LC2CLV60L	4,382.	4,703.	4,863.
	66"	24"	26 5/8"	DS4LC2CLV66L	4,451.	4,784.	4,952.
	72"	24"	26 5/8"	DS4LC2CLV72L	4,526.	4,860.	5,033.
 <p>Credenza with Veneer Drawer</p>	30"	24"	26 5/8"	DS4LC2CVV30L	4,250.	4,552.	4,703.
	36"	24"	26 5/8"	DS4LC2CVV36L	4,250.	4,552.	4,703.
	42"	24"	26 5/8"	DS4LC2CVV42L	4,250.	4,552.	4,703.
	48"	24"	26 5/8"	DS4LC2CVV48L	4,322.	4,633.	4,786.
	54"	24"	26 5/8"	DS4LC2CVV54L	4,394.	4,711.	4,873.
	60"	24"	26 5/8"	DS4LC2CVV60L	4,469.	4,792.	4,952.
	66"	24"	26 5/8"	DS4LC2CVV66L	4,541.	4,873.	5,041.
	72"	24"	26 5/8"	DS4LC2CVV72L	4,614.	4,949.	5,119.


Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
<p>Credenza with a Drawer:</p> <ol style="list-style-type: none"> 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish 5. Door edge finish <p>(laminates and veneer only) (laminates only)</p>	<p>Credenza with a Drawer:</p> <p><i>Example:</i> DS4LC2CSV42L /117/Y319</p> <hr/> <p>DS4LC2C Pattern Number SV42L</p> <hr/> <p>117 Dark grey paint Y319 Cherry Techwood top</p>	<p>Credenza with a Drawer:</p> <p>Note: Credenzas are only available in Knoll core finishes.</p>	<p>Credenza with a Drawer:</p> <p>Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$40 from the list price.</p> <p>Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.</p>

*Double Depth with Veneer Top
With a Sliding Door and with a Drawer*

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Steel Sliding Door and Drawer	30"	24"	26 ⁵ / ₈ "	DS4LC2DSV30L	\$3,918.	\$4,233.	\$4,389.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DSV36L	3,918.	4,233.	4,389.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DSV42L	3,918.	4,233.	4,389.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DSV48L	3,995.	4,320.	4,477.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DSV54L	4,075.	4,401.	4,568.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DSV60L	4,149.	4,488.	4,657.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DSV66L	4,228.	4,572.	4,743.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DSV72L	4,306.	4,657.	4,836.

 Credenza with Laminate Sliding Door and Drawer	30"	24"	26 ⁵ / ₈ "	DS4LC2DLV30L	4,603.	4,984.	5,175.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DLV36L	4,603.	4,984.	5,175.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DLV42L	4,603.	4,984.	5,175.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DLV48L	4,681.	5,071.	5,267.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DLV54L	4,762.	5,158.	5,356.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DLV60L	4,840.	5,244.	5,448.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DLV66L	4,915.	5,330.	5,540.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DLV72L	4,998.	5,416.	5,629.

 Credenza with Veneer Sliding Door and Drawer	30"	24"	26 ⁵ / ₈ "	DS4LC2DVV30L	4,807.	5,204.	5,408.
	36"	24"	26 ⁵ / ₈ "	DS4LC2DVV36L	4,807.	5,204.	5,408.
	42"	24"	26 ⁵ / ₈ "	DS4LC2DVV42L	4,807.	5,204.	5,408.
	48"	24"	26 ⁵ / ₈ "	DS4LC2DVV48L	4,898.	5,313.	5,517.
	54"	24"	26 ⁵ / ₈ "	DS4LC2DVV54L	4,995.	5,412.	5,627.
	60"	24"	26 ⁵ / ₈ "	DS4LC2DVV60L	5,089.	5,517.	5,735.
	66"	24"	26 ⁵ / ₈ "	DS4LC2DVV66L	5,180.	5,621.	5,844.
	72"	24"	26 ⁵ / ₈ "	DS4LC2DVV72L	5,277.	5,725.	5,947.

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Drawer/Door finish (laminates and veneer only) 5. Drawer/Door edge finish (laminates only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC2SV42L /117/Y319 DS4LC2D Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$80 from the list price. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

This page intentionally left blank

Flip-up Door Overdesk Units

Series 1 and Series 2 freestanding flip-up door overdesk units mount atop freestanding desks to provide overhead storage.

Pass-through communications or visual privacy can be obtained with a removeable privacy screen. When installed on freestanding desks, overdesks match up to 64" high panels to provide a consistent height within the facility.

Flip-up door overdesk units consist of an overhead cabinet with or without lock and enclosed back along with desk-mount stanchions. Tackable privacy screens are optional and mount between the stanchions. Overdesks 30" to 48" wide have single overhead doors while units 60" and 72" wide have double doors.

Available Sizes

- Height: 37 1/2"
- Depth: 13 1/2"
- Widths: 36", 42", 48", 54", 60", 66" and 72"

Flip-up Door Overdesk Attachment

Flip-up door overdesks can be mounted to both single and double pedestal desks. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper floorstanding worksurface support is used.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Construction

- Outer cabinet: 20-gauge steel
- Cabinet top and lower shelf: 18-gauge for 36", 42" and 48" widths and 16-gauge for 60" and 72" widths
- Overhead doors: 20-gauge painted steel
- Door end trim: Color injected, molded plastic
- Overhead door suspension: Steel ball-bearing
- Outer stanchions: 14-gauge steel
- Inner stanchions: 20-gauge steel

Wire Management

Vertical wire management channels for task light wires are located inside stanchions and are concealed by the inner stanchion.

Locks

Locks are standard on overdesks and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores (K001-K250). All locks are factory-installed and are black finish. Overdesks can also be specified without locks if required.

Optional lock retrofit kits are available for field installation in flip-up door overdesks without locks at a later date if required.

Tackable Privacy Screen

Flip-up door overdesk privacy screen provides visual privacy and a tackable surface. Privacy screens mount between flip-up door overdesk stanchions and are available in all overdesk widths.

Privacy screen construction is similar to the fabric insert used on Dividends panel frames. Two fabric wrapped inserts sandwich a honeycomb core providing both tackable and acoustic features.

Note: Tackable privacy screens are for use with Series 1 and Series 2 flip-up door overdesks only. They are not compatible with sliding door overdesks.

"Touchdown" Overhead Cabinets


Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up door overdesk.

Task Lights


Series 1 and 2 flip-up door overdesks will accept task lights. Task lights must be ordered separately.

Flip-Up Door Overdesk Applications




Overdesk units can span a single worksurface or two worksurfaces in "L" configuration.

Flip-Up Door Overdesk Unit Components





Flip-Up Door Overdesk Size Configurations



Flip-up Door Overdesk and Tackboards

Dividends and Series 2

description	w	d	h	pattern no.	black	P1	P2	P3	V1-P1	V1-P2	V1-P3
 Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions)	36"	13 1/2"	15"	DD2OD 36L	n/a	\$867.	\$958.	\$1,003.	n/a	n/a	n/a
	42"	13 1/2"	15"	DD2OD 42L	n/a	913.	1,006.	1,056.	n/a	n/a	n/a
	48"	13 1/2"	15"	DD2OD 48L	n/a	941.	1,036.	1,087.	n/a	n/a	n/a
	54"	13 1/2"	15"	DD2OD 54L	n/a	1,148.	1,261.	1,327.	n/a	n/a	n/a
	60"	13 1/2"	15"	DD2OD 60L	n/a	1,148.	1,261.	1,327.	n/a	n/a	n/a
	66"	13 1/2"	15"	DD2OD 66L	n/a	1,177.	1,296.	1,364.	n/a	n/a	n/a
	72"	13 1/2"	15"	DD2OD 72L	n/a	1,177.	1,296.	1,364.	n/a	n/a	n/a

 Series 2 Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions)	36"	13 1/2"	15"	DS2OD 36L	n/a	1,228.	1,414.	1,475.	1,499.	1,687.	1,747.
	42"	13 1/2"	15"	DS2OD 42L	n/a	1,254.	1,443.	1,503.	1,540.	1,726.	1,791.
	48"	13 1/2"	15"	DS2OD 48L	n/a	1,270.	1,459.	1,522.	1,596.	1,789.	1,847.
	54"	13 1/2"	15"	DS2OD 54L	n/a	1,545.	1,778.	1,858.	2,050.	2,284.	2,359.
	60"	13 1/2"	15"	DS2OD 60L	n/a	1,545.	1,778.	1,858.	2,050.	2,284.	2,359.
	66"	13 1/2"	15"	DS2OD 66L	n/a	1,596.	1,838.	1,916.	2,121.	2,361.	2,440.
	72"	13 1/2"	15"	DS2OD 72L	n/a	1,596.	1,838.	1,916.	2,121.	2,361.	2,440.

Vertical Dividers (for flip-up overheads and open shelves)				DS1 VD	108.	112.	117.	123.			
--	--	--	--	---------------	------	------	------	------	--	--	--

Package of 4



Ordering Information

Overdesk Cabinet

1. Pattern Number
2. Paint Finish
3. Door End Cap Finish

Order Code

Overdesk Cabinet

Example: **DD2OD 48L, 613, 113**

DD2OD	Pattern Number
48L	
613	Silver paint finish
113	Dark grey door end cap finish

Included with:

Overdesk Cabinet

Stanchion mount overdesk cabinets include an enclosed back.

Options

Overdesk Cabinet

To specify overhead cabinet without locks, replace the "L" suffix from the pattern number with "N". For 30" to 48" wide overdesk units, **Deduct \$20** For 54", 60", 66" and 72" wide overdesk units, **Deduct \$40**


To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number
Example: **DS3PML48EL**
(Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater).

Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Flip-up Door Overdesk and Tackboards

Dividends and Series 2 Tackboard

Dividends Horizon

description	w	h	pattern no.	grade							
				10	15	20	25	30	35	40	45
Flip-Up Door Overdesk	36"	20"	DD3 PS36	\$308.	\$317.	\$335.	\$340.	\$347.	\$353.	\$360.	\$371.
Tackable Privacy Screen	42"	20"	DD3 PS42	323.	335.	349.	354.	368.	373.	379.	389.
(for Dividends and Series 2 Overdesks)	48"	20"	DD3 PS48	337.	345.	360.	370.	379.	387.	392.	402.
	54"	20"	DD3 PS54	359.	371.	389.	395.	406.	412.	422.	429.
	60"	20"	DD3 PS60	359.	371.	389.	395.	406.	412.	422.	429.
	66"	20"	DD3 PS66	389.	398.	420.	425.	437.	445.	456.	465.
	72"	20"	DD3 PS72	389.	398.	420.	425.	437.	445.	456.	465.

Ordering Information

Overdesk Tackable Privacy Screen

1. Pattern Number
2. Fabric

Order Code

Overdesk Tackable Privacy Screen

Example: **DD3 PS48, W351-3**

DD3 PS48 Pattern Number

W351-3 Foundation Corn Silk

Included with:

Overdesk Tackable Privacy Screen

Options

Note: Flip-up Door overdesk tackable privacy screen is for use with Dividends and Series 2 Flip-up door overheads.

This page intentionally left blank

Sliding Door Overdesks

The rectilinear door profile of the sliding door overdesk was designed to complement the flat profile trim details of the Dividends Horizon system. Sliding door overdesks can be used in paneled workstation configurations or freestanding office applications.

Sliding door overdesks mount atop worksurfaces to provide overhead storage. When installed on a worksurface, sliding door overdesks match up to 57" and 64" high panels to provide a consistent height within the facility. 14" or 21" high sliding door overdesks consist of a top, shelf, mid cabinet septum, end panels/stanchions, and a door with a handle.


14" high cabinets and 21" high cabinets with full doors are standard with fully enclosed backs behind the storage area. No door units and 21" high cabinets with partial doors have a partial or full back option available. Partial backs cover the upper storage section of the cabinet. Full backs enclose both the upper and lower storage section of the cabinet.

21" high cabinets are able to be specified with a full or partial door. A partial door covers the upper section of the cabinet. A full door covers both the upper and lower section of the cabinet.

Available Sizes

- Height: 14" and 21"
- Depth: 13-1/2"
- Widths: 30", 36", 42", 48", 60", 66", and 72"

Sliding Door Overdesks



14" H

21" H

Construction

- **Horizontal top and shelf:** 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted steel
- **Sliding door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on top and edge.
- **End panels/stanchions:** 16-gauge painted steel
- **Sliding door mechanism:** integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Fixed Shelf:** 16-gauge painted steel
- **Door handle:** painted aluminum (same color as case)
- **Back panel:** 20-gauge painted steel

Interior Dimensions

The interior dimensions of sliding door overdesks are:

- Depth: 12 1/4"
- Usable interior height: 12-1/2" high for 14"H cabinets and upper portion of 21"H cabinets; 6-1/8"H for lower portion of 21"H cabinets.
- Width: 1" shorter than exterior width

Overdesk Attachment

Overdesks can be mounted to both single and double pedestal desks as well as panel hung worksurfaces. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper worksurface support is used.

Dividends Horizon Series 3 Overdesk units are sized to the nominal dimension, and are designed for use on the width dimension of Dividends Horizon rectangular worksurfaces.

Series 3 overheads are not compatible with use on extended corner worksurfaces, or a combination of other worksurfaces that are less than the nominal dimension.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Task Lights

Sliding door overdesks will accept task lights. Task lights must be ordered separately.


Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are a black finish. Overdesks can also be specified without locks if required.


Note: Sliding door overdesks are only available in Knoll Core finishes.

Interior Dimensions for 14"H Overhead

Front View, Interior Height




Top View, Interior Height




Interior Dimensions for 21"H Overhead

Front View, Interior Height



Top View, Interior Height




Sliding Door Overdesks


57" High Cabinet with 14" High Storage, 14" High Door

Dividends Horizon


description	w	pattern no.	P1	P2	P3
57" h Overdesk without Door with 14" Tall Cabinet	30"	DS3ODNS1573014	\$1,031.	\$1,136.	\$1,183.
	36"	DS3ODNS1573614	1,052.	1,158.	1,209.
	42"	DS3ODNS1574214	1,071.	1,177.	1,231.
	48"	DS3ODNS1574814	1,111.	1,218.	1,274.
	60"	DS3ODNS1576014	1,204.	1,325.	1,383.
	66"	DS3ODNS1576614	1,231.	1,357.	1,418.
	72"	DS3ODNS1577214	1,252.	1,376.	1,438.




57" h Overdesk with Steel Sliding Door and 14" Tall Cabinet	30"	DS3ODSS1573014L	1,115.	1,224.	1,277.
	36"	DS3ODSS1573614L	1,140.	1,252.	1,306.
	42"	DS3ODSS1574214L	1,166.	1,278.	1,335.
	48"	DS3ODSS1574814L	1,203.	1,319.	1,378.
	60"	DS3ODSS1576014L	1,314.	1,447.	1,509.
	66"	DS3ODSS1576614L	1,347.	1,481.	1,547.
	72"	DS3ODSS1577214L	1,368.	1,500.	1,566.



57" h Overdesk with Laminate Sliding Door and 14" Tall Cabinet	30"	DS3ODSL1573014L	1,471.	1,617.	1,689.
	36"	DS3ODSL1573614L	1,510.	1,661.	1,733.
	42"	DS3ODSL1574214L	1,548.	1,702.	1,778.
	48"	DS3ODSL1574814L	1,590.	1,745.	1,823.
	60"	DS3ODSL1576014L	1,628.	1,789.	1,868.
	66"	DS3ODSL1576614L	1,667.	1,832.	1,915.
	72"	DS3ODSL1577214L	1,705.	1,874.	1,958.



57" h Overdesk with Veneer Sliding Door and 14" Tall Cabinet	30"	DS3ODSV1573014L	1,550.	1,704.	1,781.
	36"	DS3ODSV1573614L	1,597.	1,753.	1,834.
	42"	DS3ODSV1574214L	1,643.	1,803.	1,886.
	48"	DS3ODSV1574814L	1,688.	1,853.	1,938.
	60"	DS3ODSV1576014L	1,733.	1,905.	1,989.
	66"	DS3ODSV1576614L	1,781.	1,955.	2,043.
	72"	DS3ODSV1577214L	1,825.	2,004.	2,095.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.


No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks 57" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
 57" h without Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODNS()573021	\$1,112.	\$1,223.	\$1,277.
	36"	DS3ODNS()573621	1,138.	1,252.	1,308.
	42"	DS3ODNS()574221	1,165.	1,279.	1,336.
	48"	DS3ODNS()574821	1,209.	1,331.	1,391.
	60"	DS3ODNS()576021	1,323.	1,456.	1,523.
	66"	DS3ODNS()576621	1,358.	1,495.	1,561.
	72"	DS3ODNS()577221	1,380.	1,516.	1,589.

 57" h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS2573021FL	1,269.	1,394.	1,456.
	36"	DS3ODSS2573621FL	1,293.	1,421.	1,483.
	42"	DS3ODSS2574221FL	1,331.	1,460.	1,527.
	48"	DS3ODSS2574821FL	1,405.	1,540.	1,611.
	60"	DS3ODSS2576021FL	1,541.	1,694.	1,768.
	66"	DS3ODSS2576621FL	1,592.	1,747.	1,829.
	72"	DS3ODSS2577221FL	1,625.	1,784.	1,864.

 57" h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL2573021FL	1,664.	1,829.	1,910.
	36"	DS3ODSL2573621FL	1,720.	1,890.	1,975.
	42"	DS3ODSL2574221FL	1,775.	1,952.	2,039.
	48"	DS3ODSL2574821FL	1,834.	2,013.	2,102.
	60"	DS3ODSL2576021FL	1,889.	2,077.	2,171.
	66"	DS3ODSL2576621FL	1,945.	2,139.	2,232.
	72"	DS3ODSL2577221FL	2,001.	2,199.	2,298.

 57" h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV2573021FL	1,749.	1,921.	2,006.
	36"	DS3ODSV2573621FL	1,815.	1,997.	2,088.
	42"	DS3ODSV2574221FL	1,887.	2,074.	2,166.
	48"	DS3ODSV2574821FL	1,954.	2,146.	2,244.
	60"	DS3ODSV2576021FL	2,024.	2,223.	2,324.
	66"	DS3ODSV2576621FL	2,092.	2,298.	2,401.
	72"	DS3ODSV2577221FL	2,160.	2,374.	2,481.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021FL, 613**

DS3ODSS Pattern Number
2573021FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1) = Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks 57" High Cabinet with 21" High Storage (Partial Height Door)

Dividends Horizon


description	w	pattern no.	P1	P2	P3
57" h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS()573021PL	\$1,269.	\$1,394.	\$1,456.
	36"	DS3ODSS()573621PL	1,293.	1,421.	1,483.
	42"	DS3ODSS()574221PL	1,331.	1,460.	1,527.
	48"	DS3ODSS()574821PL	1,405.	1,540.	1,611.
	60"	DS3ODSS()576021PL	1,541.	1,694.	1,768.
	66"	DS3ODSS()576621PL	1,592.	1,747.	1,829.
	72"	DS3ODSS()577221PL	1,625.	1,784.	1,864.



57" h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL()573021PL	1,654.	1,815.	1,897.
	36"	DS3ODSL()573621PL	1,710.	1,880.	1,961.
	42"	DS3ODSL()574221PL	1,765.	1,939.	2,026.
	48"	DS3ODSL()574821PL	1,820.	2,000.	2,091.
	60"	DS3ODSL()576021PL	1,879.	2,060.	2,154.
	66"	DS3ODSL()576621PL	1,933.	2,125.	2,220.
	72"	DS3ODSL()577221PL	1,988.	2,184.	2,284.



57" h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV()573021PL	1,734.	1,906.	1,991.
	36"	DS3ODSV()573621PL	1,798.	1,975.	2,061.
	42"	DS3ODSV()574221PL	1,859.	2,044.	2,137.
	48"	DS3ODSV()574821PL	1,923.	2,113.	2,208.
	60"	DS3ODSV()576021PL	1,985.	2,181.	2,282.
	66"	DS3ODSV()576621PL	2,050.	2,251.	2,351.
	72"	DS3ODSV()577221PL	2,110.	2,322.	2,426.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021PL, 613**

DS3ODSS Pattern Number
2573021PL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option

(1) = Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks 64" High Cabinet with 14" High Storage

Dividends Horizon


description	w	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODNS1643014	\$1,068.	\$1,173.	\$1,225.
	36"	DS3ODNS1643614	1,077.	1,182.	1,235.
	42"	DS3ODNS1644214	1,112.	1,218.	1,272.
	48"	DS3ODNS1644814	1,208.	1,326.	1,383.
	60"	DS3ODNS1646014	1,245.	1,367.	1,425.
	66"	DS3ODNS1646614	1,272.	1,397.	1,459.
	72"	DS3ODNS1647214	1,289.	1,416.	1,476.



64"h Steel Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSS1643014L	1,125.	1,234.	1,289.
	36"	DS3ODSS1643614L	1,151.	1,262.	1,316.
	42"	DS3ODSS1644214L	1,175.	1,289.	1,345.
	48"	DS3ODSS1644814L	1,213.	1,332.	1,391.
	60"	DS3ODSS1646014L	1,327.	1,457.	1,523.
	66"	DS3ODSS1646614L	1,364.	1,495.	1,561.
	72"	DS3ODSS1647214L	1,376.	1,510.	1,577.



64"h Laminate Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSL1643014L	1,483.	1,629.	1,702.
	36"	DS3ODSL1643614L	1,524.	1,673.	1,747.
	42"	DS3ODSL1644214L	1,563.	1,717.	1,794.
	48"	DS3ODSL1644814L	1,602.	1,761.	1,840.
	60"	DS3ODSL1646014L	1,643.	1,803.	1,886.
	66"	DS3ODSL1646614L	1,682.	1,847.	1,931.
	72"	DS3ODSL1647214L	1,721.	1,891.	1,976.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FL, 613**

DS3ODSS Pattern Number
2643014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks 64" High Cabinet with 14" High Storage

Dividends Horizon

description	w	pattern no.	P1	P2	P3
64" h Veneer Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSV1643014L	\$1,563.	\$1,718.	\$1,795.
	36"	DS3ODSV1643614L	1,611.	1,768.	1,847.
	42"	DS3ODSV1644214L	1,658.	1,820.	1,901.
	48"	DS3ODSV1644814L	1,704.	1,871.	1,955.
	60"	DS3ODSV1646014L	1,751.	1,922.	2,009.
	66"	DS3ODSV1646614L	1,798.	1,974.	2,061.
	72"	DS3ODSV1647214L	1,844.	2,024.	2,117.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FL, 613**

DS3ODSS Pattern Number
2643014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Paint Configuration Option:

Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks 64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon


description	w	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODNS()643021	\$1,136.	\$1,250.	\$1,304.
	36"	DS3ODNS()643621	1,154.	1,269.	1,327.
	42"	DS3ODNS()644221	1,182.	1,303.	1,365.
	48"	DS3ODNS()644821	1,259.	1,383.	1,448.
	60"	DS3ODNS()646021	1,381.	1,519.	1,590.
	66"	DS3ODNS()646621	1,425.	1,567.	1,640.
	72"	DS3ODNS()647221	1,458.	1,604.	1,677.



64"h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS2643021FL	1,277.	1,404.	1,464.
	36"	DS3ODSS2643621FL	1,303.	1,428.	1,495.
	42"	DS3ODSS2644221FL	1,337.	1,468.	1,536.
	48"	DS3ODSS2644821FL	1,412.	1,548.	1,620.
	60"	DS3ODSS2646021FL	1,548.	1,702.	1,778.
	66"	DS3ODSS2646621FL	1,599.	1,758.	1,837.
	72"	DS3ODSS2647221FL	1,634.	1,794.	1,874.



64"h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL2643021FL	1,679.	1,845.	1,928.
	36"	DS3ODSL2643621FL	1,734.	1,906.	1,991.
	42"	DS3ODSL2644221FL	1,792.	1,968.	2,056.
	48"	DS3ODSL2644821FL	1,847.	2,031.	2,121.
	60"	DS3ODSL2646021FL	1,904.	2,093.	2,188.
	66"	DS3ODSL2646621FL	1,960.	2,154.	2,251.
	72"	DS3ODSL2647221FL	2,017.	2,217.	2,317.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021FL, 613**

DS3ODSS Pattern Number
2643021FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1) = Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks

64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV2643021FL	\$1,764.	\$1,938.	\$2,025.
	36"	DS3ODSV2643621FL	1,834.	2,013.	2,102.
	42"	DS3ODSV2644221FL	1,901.	2,090.	2,182.
	48"	DS3ODSV2644821FL	1,969.	2,166.	2,259.
	60"	DS3ODSV2646021FL	2,039.	2,239.	2,341.
	66"	DS3ODSV2646621FL	2,106.	2,316.	2,419.
	72"	DS3ODSV2647221FL	2,176.	2,391.	2,496.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021FL,**
613

DS3ODSS Pattern Number

2643021FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options


No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks 64" High Cabinet with 21" High Storage (Partial Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
 64" h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS()643021PL	\$1,277.	\$1,404.	\$1,464.
	36"	DS3ODSS()643621PL	1,303.	1,428.	1,495.
	42"	DS3ODSS()644221PL	1,337.	1,468.	1,536.
	48"	DS3ODSS()644821PL	1,412.	1,548.	1,620.
	60"	DS3ODSS()646021PL	1,548.	1,702.	1,778.
	66"	DS3ODSS()646621PL	1,599.	1,758.	1,837.
	72"	DS3ODSS()647221PL	1,634.	1,794.	1,874.

 64" h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL()643021PL	1,669.	1,835.	1,917.
	36"	DS3ODSL()643621PL	1,724.	1,895.	1,979.
	42"	DS3ODSL()644221PL	1,782.	1,957.	2,044.
	48"	DS3ODSL()644821PL	1,837.	2,017.	2,107.
	60"	DS3ODSL()646021PL	1,892.	2,081.	2,174.
	66"	DS3ODSL()646621PL	1,947.	2,141.	2,235.
	72"	DS3ODSL()647221PL	2,003.	2,202.	2,301.

 64" h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV()643021PL	1,751.	1,923.	2,009.
	36"	DS3ODSV()643621PL	1,811.	1,994.	2,083.
	42"	DS3ODSV()644221PL	1,877.	2,059.	2,152.
	48"	DS3ODSV()644821PL	1,939.	2,131.	2,225.
	60"	DS3ODSV()646021PL	2,001.	2,199.	2,296.
	66"	DS3ODSV()646621PL	2,062.	2,267.	2,370.
	72"	DS3ODSV()647221PL	2,127.	2,338.	2,443.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021PL, 613**

DS3ODSS Pattern Number

2643021PL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option

(1) = Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


57" High Cabinet with 14" High Storage, 14" High Door

Dividends Horizon


description	w	pattern no.	P1	P2	P3
57" h Overdesk without Door with 14" Tall Cabinet with tackboard	30"	DS3ODNS1573014T	\$1,362.	\$1,465.	\$1,513.
	36"	DS3ODNS1573614T	1,388.	1,495.	1,545.
	42"	DS3ODNS1574214T	1,427.	1,535.	1,589.
	48"	DS3ODNS1574814T	1,477.	1,585.	1,641.
	60"	DS3ODNS1576014T	1,597.	1,718.	1,776.
	66"	DS3ODNS1576614T	1,625.	1,751.	1,811.
	72"	DS3ODNS1577214T	1,676.	1,801.	1,863.



57" h Overdesk with Steel Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSS1573014LT	1,445.	1,553.	1,605.
	36"	DS3ODSS1573614LT	1,477.	1,589.	1,643.
	42"	DS3ODSS1574214LT	1,524.	1,635.	1,691.
	48"	DS3ODSS1574814LT	1,571.	1,686.	1,747.
	60"	DS3ODSS1576014LT	1,709.	1,840.	1,903.
	66"	DS3ODSS1576614LT	1,744.	1,875.	1,941.
	72"	DS3ODSS1577214LT	1,792.	1,925.	1,990.



57" h Overdesk with Laminate Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSL1573014LT	1,801.	1,946.	2,019.
	36"	DS3ODSL1573614LT	1,847.	1,997.	2,072.
	42"	DS3ODSL1574214LT	1,905.	2,059.	2,136.
	48"	DS3ODSL1574814LT	1,957.	2,110.	2,189.
	60"	DS3ODSL1576014LT	2,022.	2,182.	2,260.
	66"	DS3ODSL1576614LT	2,059.	2,225.	2,307.
	72"	DS3ODSL1577214LT	2,130.	2,298.	2,384.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

57" High Cabinet with 14" High Storage, 14" High Door

Dividends Horizon

description	w	pattern no.	P1	P2	P3
57" h Overdesk with Veneer Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSV1573014LT	\$1,879.	\$2,033.	\$2,108.
	36"	DS3ODSV1573614LT	1,935.	2,091.	2,172.
	42"	DS3ODSV1574214LT	2,001.	2,160.	2,244.
	48"	DS3ODSV1574814LT	2,056.	2,222.	2,305.
	60"	DS3ODSV1576014LT	2,129.	2,300.	2,384.
	66"	DS3ODSV1576614LT	2,174.	2,348.	2,437.
	72"	DS3ODSV1577214LT	2,249.	2,429.	2,519.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 1573014FL, 613**

DS3ODSS Pattern Number
1573014FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


57" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon


description	w	pattern no.	P1	P2	P3
57" h without Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODNS()573021T	\$1,340.	\$1,452.	\$1,506.
	36"	DS3ODNS()573621T	1,375.	1,489.	1,544.
	42"	DS3ODNS()574221T	1,422.	1,536.	1,593.
	48"	DS3ODNS()574821T	1,476.	1,597.	1,661.
	60"	DS3ODNS()576021T	1,617.	1,750.	1,815.
	66"	DS3ODNS()576621T	1,652.	1,789.	1,854.
	72"	DS3ODNS()577221T	1,705.	1,841.	1,915.



57" h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS2573021FLT	1,498.	1,624.	1,684.
	36"	DS3ODSS2573621FLT	1,532.	1,660.	1,721.
	42"	DS3ODSS2574221FLT	1,587.	1,718.	1,784.
	48"	DS3ODSS2574821FLT	1,672.	1,807.	1,877.
	60"	DS3ODSS2576021FLT	1,836.	1,987.	2,062.
	66"	DS3ODSS2576621FLT	1,886.	2,040.	2,121.
	72"	DS3ODSS2577221FLT	1,951.	2,107.	2,188.



57" h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL2573021FLT	1,892.	2,057.	2,139.
	36"	DS3ODSL2573621FLT	1,957.	2,129.	2,212.
	42"	DS3ODSL2574221FLT	2,033.	2,209.	2,296.
	48"	DS3ODSL2574821FLT	2,100.	2,282.	2,370.
	60"	DS3ODSL2576021FLT	2,183.	2,370.	2,462.
	66"	DS3ODSL2576621FLT	2,239.	2,433.	2,527.
	72"	DS3ODSL2577221FLT	2,326.	2,525.	2,623.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabrics

Order Code

Sliding Door Overdesk

Example: DS3ODSS 2573021FLT, 613

DS3ODSS Pattern Number
2573021FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1) = Back covering overhead only
(2) = Back covering overhead and shelf section

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

57" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
57" h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV2573021FLT	\$1,978.	\$2,149.	\$2,235.
	36"	DS3ODSV2573621FLT	2,054.	2,233.	2,325.
	42"	DS3ODSV2574221FLT	2,144.	2,332.	2,423.
	48"	DS3ODSV2574821FLT	2,222.	2,414.	2,511.
	60"	DS3ODSV2576021FLT	2,317.	2,516.	2,617.
	66"	DS3ODSV2576621FLT	2,386.	2,592.	2,695.
	72"	DS3ODSV2577221FLT	2,485.	2,700.	2,805.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabrics

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2573021FLT, 613**

DS3ODSS Pattern Number
2573021FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1) = Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


57" High Cabinet with 21" High Storage (Partial Height Door)

Dividends Horizon


description	w	pattern no.	P1	P2	P3
57" h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	36"	DS3ODSS()573021PLT	\$1,498.	\$1,624.	\$1,684.
	36"	DS3ODSS()573621PLT	1,532.	1,660.	1,721.
	42"	DS3ODSS()574221PLT	1,587.	1,718.	1,784.
	48"	DS3ODSS()574821PLT	1,672.	1,807.	1,877.
	60"	DS3ODSS()576021PLT	1,836.	1,987.	2,062.
	66"	DS3ODSS()576621PLT	1,886.	2,040.	2,121.
	72"	DS3ODSS()577221PLT	1,951.	2,107.	2,188.



57" h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL()573021PLT	1,884.	2,045.	2,128.
	36"	DS3ODSL()573621PLT	1,947.	2,118.	2,199.
	42"	DS3ODSL()574221PLT	2,023.	2,196.	2,284.
	48"	DS3ODSL()574821PLT	2,088.	2,266.	2,358.
	60"	DS3ODSL()576021PLT	2,174.	2,355.	2,449.
	66"	DS3ODSL()576621PLT	2,227.	2,417.	2,513.
	72"	DS3ODSL()577221PLT	2,312.	2,510.	2,608.



57" h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV()573021PLT	1,966.	2,137.	2,222.
	36"	DS3ODSV()573621PLT	2,035.	2,212.	2,300.
	42"	DS3ODSV()574221PLT	2,117.	2,302.	2,394.
	48"	DS3ODSV()574821PLT	2,190.	2,381.	2,476.
	60"	DS3ODSV()576021PLT	2,281.	2,476.	2,574.
	66"	DS3ODSV()576621PLT	2,343.	2,543.	2,646.
	72"	DS3ODSV()577221PLT	2,436.	2,646.	2,751.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: DS3ODSS 2573021PLF, 613

DS3ODSS Pattern Number
2573021PLF

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Back option for No Door units
(1) = Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks with Tackboard

64" High Cabinet with 14" High Storage

Dividends Horizon

description	w	pattern no.	P1	P2	P3
 64" h without Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODNS1643014T	\$1,429.	\$1,536.	\$1,587.
	36"	DS3ODNS1643614T	1,448.	1,553.	1,605.
	42"	DS3ODNS1644214T	1,503.	1,612.	1,666.
	48"	DS3ODNS1644814T	1,613.	1,728.	1,788.
	60"	DS3ODNS1646014T	1,677.	1,799.	1,858.
	66"	DS3ODNS1646614T	1,705.	1,831.	1,891.
	72"	DS3ODNS1647214T	1,756.	1,883.	1,943.

 64" h Steel Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSS1643014LT	1,489.	1,596.	1,652.
	36"	DS3ODSS1643614LT	1,522.	1,634.	1,687.
	42"	DS3ODSS1644214LT	1,569.	1,681.	1,739.
	48"	DS3ODSS1644814LT	1,617.	1,734.	1,796.
	60"	DS3ODSS1646014LT	1,758.	1,889.	1,955.
	66"	DS3ODSS1646614LT	1,795.	1,927.	1,995.
	72"	DS3ODSS1647214LT	1,843.	1,978.	2,043.

 64" h Laminate Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSL1643014LT	1,845.	1,991.	2,064.
	36"	DS3ODSL1643614LT	1,894.	2,043.	2,117.
	42"	DS3ODSL1644214LT	1,956.	2,108.	2,186.
	48"	DS3ODSL1644814LT	2,006.	2,166.	2,245.
	60"	DS3ODSL1646014LT	2,077.	2,235.	2,318.
	66"	DS3ODSL1646614LT	2,115.	2,282.	2,365.
	72"	DS3ODSL1647214LT	2,188.	2,359.	2,443.

Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FLT, 613**

DS3ODSS Pattern Number
2643014FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

64" High Cabinet with 14" High Storage

Dividends Horizon

description	w	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSV1643014LT	\$1,926.	\$2,081.	\$2,157.
	36"	DS3ODSV1643614LT	1,980.	2,140.	2,220.
	42"	DS3ODSV1644214LT	2,051.	2,212.	2,295.
	48"	DS3ODSV1644814LT	2,107.	2,274.	2,359.
	60"	DS3ODSV1646014LT	2,183.	2,355.	2,442.
	66"	DS3ODSV1646614LT	2,230.	2,406.	2,495.
	72"	DS3ODSV1647214LT	2,311.	2,491.	2,585.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643014FLT, 613**

DS3ODSS Pattern Number
2643014FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.


Sliding Door Overdesks with Tackboard

64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
 64" h without Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODNS()643021T	\$1,465.	\$1,579.	\$1,634.
	36"	DS3ODNS()643621T	1,492.	1,605.	1,664.
	42"	DS3ODNS()644221T	1,539.	1,661.	1,721.
	48"	DS3ODNS()644821T	1,627.	1,751.	1,814.
	60"	DS3ODNS()646021T	1,774.	1,914.	1,983.
	66"	DS3ODNS()646621T	1,820.	1,960.	2,034.
	72"	DS3ODNS()647221T	1,883.	2,030.	2,101.

 64" h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS2643021FLT	1,605.	1,731.	1,793.
	36"	DS3ODSS2643621FLT	1,640.	1,766.	1,833.
	42"	DS3ODSS2644221FLT	1,695.	1,827.	1,892.
	48"	DS3ODSS2644821FLT	1,778.	1,917.	1,987.
	60"	DS3ODSS2646021FLT	1,942.	2,096.	2,173.
	66"	DS3ODSS2646621FLT	1,995.	2,151.	2,230.
	72"	DS3ODSS2647221FLT	2,058.	2,220.	2,298.

 64" h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL2643021FLT	2,009.	2,176.	2,258.
	36"	DS3ODSL2643621FLT	2,073.	2,245.	2,330.
	42"	DS3ODSL2644221FLT	2,148.	2,325.	2,413.
	48"	DS3ODSL2644821FLT	2,216.	2,398.	2,489.
	60"	DS3ODSL2646021FLT	2,298.	2,486.	2,582.
	66"	DS3ODSL2646621FLT	2,355.	2,548.	2,644.
	72"	DS3ODSL2647221FLT	2,442.	2,642.	2,743.


Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk 1. Pattern number 2. Case finish 3. Door finish 4. Tackboard fabric	Sliding Door Overdesk <hr/> <i>Example:</i> DS3ODSS 2643021FLT, 613 <hr/> DS3ODSS Pattern Number 2643021FLT <hr/> 613 Silver Paint Finish	Sliding Door Overdesk <hr/> Note: Overheads are only available in Knoll core finishes. <hr/> Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20. <hr/> Back option for No Door units (1) = Back covering overhead only (2) = Back covering overhead and shelf section <hr/> Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	w	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV2643021FLT	\$2,094.	\$2,266.	\$2,355.
	36"	DS3ODSV2643621FLT	2,172.	2,350.	2,441.
	42"	DS3ODSV2644221FLT	2,259.	2,447.	2,539.
	48"	DS3ODSV2644821FLT	2,337.	2,533.	2,627.
	60"	DS3ODSV2646021FLT	2,433.	2,632.	2,734.
	66"	DS3ODSV2646621FLT	2,500.	2,710.	2,814.
	72"	DS3ODSV2647221FLT	2,600.	2,816.	2,920.



Ordering Information

Sliding Door Overdesk

1. Pattern number
2. Case finish
3. Door finish
4. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS 2643021FLT, 613**

DS3ODSS Pattern Number
2643021FLT

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1)= Back covering overhead only
(2) = Back covering overhead and shelf section


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


64" High Cabinet with 21" High Storage (Partial Height Door)

Dividends Horizon


description	w	pattern no.	P1	P2	P3
64" h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS()643021PLT	\$1,605.	\$1,731.	\$1,793.
	36"	DS3ODSS()643621PLT	1,640.	1,766.	1,833.
	42"	DS3ODSS()644221PLT	1,695.	1,827.	1,892.
	48"	DS3ODSS()644821PLT	1,778.	1,917.	1,987.
	60"	DS3ODSS()646021PLT	1,942.	2,096.	2,173.
	66"	DS3ODSS()646621PLT	1,995.	2,151.	2,230.
	72"	DS3ODSS()647221PLT	2,058.	2,220.	2,298.



64" h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL()643021PLT	1,998.	2,165.	2,246.
	36"	DS3ODSL()643621PLT	2,061.	2,232.	2,316.
	42"	DS3ODSL()644221PLT	2,138.	2,313.	2,401.
	48"	DS3ODSL()644821PLT	2,204.	2,385.	2,476.
	60"	DS3ODSL()646021PLT	2,287.	2,475.	2,566.
	66"	DS3ODSL()646621PLT	2,341.	2,535.	2,630.
	72"	DS3ODSL()647221PLT	2,428.	2,627.	2,725.



64" h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV()643021PLT	2,081.	2,253.	2,339.
	36"	DS3ODSV()643621PLT	2,148.	2,331.	2,419.
	42"	DS3ODSV()644221PLT	2,233.	2,416.	2,511.
	48"	DS3ODSV()644821PLT	2,306.	2,498.	2,592.
	60"	DS3ODSV()646021PLT	2,395.	2,594.	2,690.
	66"	DS3ODSV()646621PLT	2,456.	2,663.	2,763.
	72"	DS3ODSV()647221PLT	2,552.	2,761.	2,868.



Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk 1. Pattern number 2. Case finish 3. Door finish 4. Tackboard fabric	Sliding Door Overdesk <i>Example:</i> DS3ODSS 2643021PLT, 613 <hr/> DS3ODSS Pattern Number 2643021PLT <hr/> 613 Silver Paint Finish	Sliding Door Overdesk Note: Overheads are only available in Knoll core finishes. Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20. Back option for No Door units (1) = Back covering overhead only (2) = Back covering overhead and shelf section Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

This page intentionally left blank

Available Worksurface Styles

- Rectangular
- Rectilinear corner
- Split top corner
- Curvilinear corner
- Trapezoid
- Smooth wave
- Curvilinear wave end
- Half-round
- Quarter-round
- Blended "D" shape
- "D" shape peninsula
- "P" and "9" shape peninsula
- Counter Worksurfaces
- Transition

Universal Applications

The undersides of worksurfaces are pre-drilled to accept various panel-hung and freestanding supports. Cascade edge worksurfaces do not have pre-drilled holes.

All supports must be ordered separately.

In panel-hung applications, worksurfaces are supported by:

- Cantilevers
- Pedestals
- Panel-to-worksurface brackets
- Flat brackets
- Panel-mounted C-leg support
- Open support legs

In peninsula applications, worksurfaces are supported by panels on one end and the other end is supported by:

- Support column
- A leg
- T support base

For freestanding applications, worksurface support is provided by:

- Pedestals
- End units
- Flat brackets

Construction

Laminate

- Surface material: .028 laminate on top surface with a paper backer on under side
- Edge material: 2mm ABS on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

Techwood

- Surface material: 0.6mm veneer
- Edge material: 2mm veneer on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

For available sizes, refer to the individual worksurface categories within this section.

Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed centered along the rear edge of rectangular, rectilinear corner,

curvilinear wave end, and curvilinear corner worksurfaces. Grommets can also be retrofitted to worksurfaces by ordering an edge grommet kit (pattern number D1WSG). The edge grommet kit allows grommets to be field-installed in any location along the rear edge of worksurfaces.

Note: Edge grommets on 'D', '9', and 'P' peninsula worksurfaces are located on the panel hung side.

Cable Management


A 1/2" reveal is provided between the worksurface and panel for cable management. When edge grommets are specified, the grommet works in conjunction with the 1/2" reveal to allow plugs to be inserted through the grommet and cables to be positioned anywhere along the rear edge of the worksurface.

Loading Capacities


Maximum weight allowed for worksurfaces:

- 24"-42" wide: 200 lbs.
- 48" wide: 216 lbs.
- 54" wide: 243 lbs.
- 60" wide: 270 lbs.
- 66" wide: 297 lbs.
- 72" wide: 324 lbs.
- 78" wide: 351 lbs.
- 84" wide: 378 lbs.
- 90" wide: 405 lbs.
- 96" wide: 432 lbs.


Note: Installations which violate these requirements will not be covered by the Knoll, Inc. warranty.






Worksurfaces and Supports, Panel Application



Worksurfaces and Supports, Freestanding Application



2mm ABS Edge Detail



Worksurface Cable Management

Laminate Worksurface Grain Direction

The standard grain direction for wood grain or brushed laminates for each worksurface shape is shown below.


When wood grain or brushed laminates are specified on Dividends Horizon corner worksurfaces, a left, right or diagonal grain direction option must be specified as shown below. Insert the desired grain direction option (L, R or D) after the laminate finish code. The diagonal option is an upcharge. This option applies only to corner worksurfaces with the same dimension on each rear side.

Techwood Worksurface Grain Direction


The standard grain direction for Techwood worksurfaces for each worksurface shape is shown below.

Techwood corner worksurfaces with the same dimension on each rear side have a diagonal grain direction.

Laminate Worksurface Grain Direction



Techwood Worksurface Grain Direction



Panel-Hung Worksurface Support

All worksurfaces require support every 48" in width. In panel-hung applications, mid-span support must be provided by cantilevers, panel-mounted C-legs or open support legs.

When worksurfaces are mounted perpendicular to panels, the worksurface depth must equal the width of the panel when using panel-to-worksurface brackets.

Cantilevers are available in three depths to match worksurface depths.

- 18" deep worksurfaces are supported by 18" deep cantilevers.
- 24" deep worksurfaces are supported by 24" deep cantilevers.
- 30" deep worksurfaces are not recommended to be supported by cantilevers. 30" deep cantilevers are used for mid-span support.
- 36" deep worksurfaces cannot be supported by cantilevers.

Panel-mounted C-leg supports are available to support 24" and 30" worksurface depths in heavier worksurface load applications.


Open support legs are available to support 18", 24" and 30" worksurfaces depths.

Freestanding Worksurface Support


For freestanding desk applications, specify freestanding pedestals, end units and/or intermediate support every 48" in width.

- 18" deep worksurfaces can be supported by 18" deep pedestals and end units only
- 24" deep worksurfaces can be supported by either 18" or 24" deep pedestals or end units
- 30" deep worksurfaces can be supported by either 24" or 30" deep pedestals or end units
- 36" deep worksurfaces can only be supported by 30" deep pedestals or end units and provide a 6" front overhang for desk applications.

Maximum Width Between Panel-Hung Worksurface Supports



Maximum Width Between Freestanding Worksurface Supports












Worksurface Reinforcement

Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.



Notes:

- Whenever using pedestals they should be connected to panels with panel-to-worksurface brackets
- Panel runs must be floor-supported every 8 feet (i.e., pedestal with panel-to-worksurface brackets or panel-mounted C-leg)
- When a panel mounted C-leg is used, unsupported worksurface span is not to exceed 48".



Legend

-  Pedestal or End Unit
-  Panel Mounted C-leg Support
-  Cantilever or C-leg
-  Flat Bracket
-  Flat Bracket with Cantilever or Shared C-leg
-  Panel-to-worksurface Bracket
-  Pedestal or C-leg
-  End Unit
-  Intermediate

Worksurface Reinforcement Panel Hung Application



Worksurface Reinforcement Freestanding Desk Application



Rectangular Worksurfaces

18" and 24" Deep Specifications

Rectangular Worksurfaces

Dividends Horizon rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes

- Depths: 18" and 24"
- Widths: 24" to 96"


Panel-Hung Applications

When a worksurface spans multiple panels a cantilever or freestanding support is required every 48" of width.


Freestanding Applications

Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.


The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.




24"D Rectangular Worksurface





18"D Rectangular Worksurface



Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support





Freestanding Desk Applications

Rectangular Worksurfaces

18" and 24" Deep

Dividends Horizon

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
18" Deep Rectangular No Grommets 	24"	23 13/16"	17 1/2"	1 1/4"	D1R 2418N	\$180.	\$198.	\$215.	\$442.
	30"	29 13/16"	17 1/2"	1 1/4"	D1R 3018N	190.	209.	227.	465.
	36"	35 13/16"	17 1/2"	1 1/4"	D1R 3618N	212.	234.	256.	487.
	42"	41 13/16"	17 1/2"	1 1/4"	D1R 4218N	246.	269.	293.	510.
	48"	47 13/16"	17 1/2"	1 1/4"	D1R 4818N	273.	300.	329.	532.
	54"	53 13/16"	17 1/2"	1 1/4"	D1R 5418N	291.	319.	349.	550.
	60"	59 13/16"	17 1/2"	1 1/4"	D1R 6018N	316.	347.	379.	572.
	66"	65 13/16"	17 1/2"	1 1/4"	D1R 6618N	341.	375.	409.	594.
	72"	71 13/16"	17 1/2"	1 1/4"	D1R 7218N	358.	394.	430.	615.
	78"	77 13/16"	17 1/2"	1 1/4"	D1R 7818N	386.	423.	463.	640.
	84"	83 13/16"	17 1/2"	1 1/4"	D1R 8418N	406.	446.	486.	665.
	90"	89 13/16"	17 1/2"	1 1/4"	D1R 9018N	453.	499.	540.	691.
96"	95 13/16"	17 1/2"	1 1/4"	D1R 9618N	501.	548.	599.	716.	
24" Deep Rectangular No Grommets 	24"	23 13/16"	23 1/2"	1 1/4"	D1R 2424N	191.	211.	231.	456.
	30"	29 13/16"	23 1/2"	1 1/4"	D1R 3024N	220.	241.	261.	482.
	36"	35 13/16"	23 1/2"	1 1/4"	D1R 3624N	244.	266.	291.	507.
	42"	41 13/16"	23 1/2"	1 1/4"	D1R 4224N	279.	305.	338.	534.
	48"	47 13/16"	23 1/2"	1 1/4"	D1R 4824N	310.	344.	376.	560.
	54"	53 13/16"	23 1/2"	1 1/4"	D1R 5424N	339.	372.	405.	590.
	60"	59 13/16"	23 1/2"	1 1/4"	D1R 6024N	367.	401.	436.	619.
	66"	65 13/16"	23 1/2"	1 1/4"	D1R 6624N	393.	432.	472.	645.
	72"	71 13/16"	23 1/2"	1 1/4"	D1R 7224N	411.	454.	495.	674.
	78"	77 13/16"	23 1/2"	1 1/4"	D1R 7824N	442.	485.	528.	706.
	84"	83 13/16"	23 1/2"	1 1/4"	D1R 8424N	467.	516.	561.	736.
	90"	89 13/16"	23 1/2"	1 1/4"	D1R 9024N	527.	577.	632.	767.
96"	95 13/16"	23 1/2"	1 1/4"	D1R 9624N	573.	633.	692.	797.	

w* = nominal width

Dimensions listed under w d t are actual to the nearest 1/16"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 4818N, 114, 114**

D1R Pattern Number
4818N

114 Folkstone Grey
Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$18.

Rectangular Worksurfaces

19" Deep Specifications

Rectangular Worksurfaces

The 19" deep rectangular worksurface aligns with the depth of a doublewide pedestal.

Dividends Horizon worksurfaces provide a 1/2" reveal between the worksurface and panel for cable management.

Dividends Horizon 19" deep rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes

- Depths: 19"
- Widths: 24" to 96"


Panel-Hung Applications

When a worksurface spans multiple panels, a cantilever or freestanding support is required every 48" of width.


Freestanding Applications

Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.


The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.




19"D Rectangular Worksurface



Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support




19" Deep Worksurface Application

Doublewide Pedestal

Rectangular Worksurfaces

19" Deep

Dividends Horizon

description	w*	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
19" Deep Rectangular - No Grommets (for use with doublewide pedestals) 	24"	23 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R2419N	\$182.	\$200.	\$219.	\$444.
	30"	29 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R3019N	196.	214.	233.	467.
	36"	35 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R3619N	219.	240.	260.	492.
	42"	41 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R4219N	251.	276.	300.	514.
	48"	47 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R4819N	279.	306.	337.	538.
	54"	53 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R5419N	299.	329.	358.	559.
	60"	59 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R6019N	325.	356.	390.	580.
	66"	65 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R6619N	348.	385.	420.	601.
	72"	71 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R7219N	370.	405.	443.	625.
	78"	77 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R7819N	393.	432.	473.	652.
	84"	83 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R8419N	418.	459.	501.	676.
	90"	89 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R9019N	465.	510.	558.	703.
	96"	95 ^{13/16"}	18 ^{3/4"}	1 ^{1/4"}	D1R9619N	512.	563.	616.	729.

w* = nominal width

Dimensions listed under w d t are actual to the nearest 1/16"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 4819N, 114, 114**

D1R Pattern Number
4819N

114 Folkstone Grey
Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$18.

Rectangular Worksurfaces

Dividends Horizon rectangular worksurfaces are universal and can be used in:

- Panel-hung applications
- Freestanding applications

See page 166 for the following:

- Worksurface construction
- Optional edge grommets
- Loading capacities

Available Sizes

- Depths: 30" and 36"
- Widths: 24" to 96" (30"D), 60" to 72" (36"D)

Panel-Hung Applications

When a worksurface spans multiple panels a cantilever or freestanding floor support is required every 48". 36" deep worksurfaces cannot be supported by cantilevers. Worksurfaces over 48" W require mid-span support


Freestanding Applications

Refer to the freestanding desk section for "preconfigured" applications. Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.


The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.

Overhang Desks


Overhang desks can be ordered by component by specifying desk supports and worksurfaces separately. To specify, select either a 30" or 36" deep worksurface in 60", 66" or 72" widths. Back panels should be specified to match the worksurface width while supports (pedestals or end units) should be one size smaller than the worksurface depth to provide a 6" front overhang. Example: 36" deep worksurface with 30" deep pedestals or end units.





30"D Rectangular Worksurface



36"D Rectangular Worksurface



Worksurfaces over 48"W require mid-span support





Freestanding Desk Applications

Rectangular Worksurfaces

30" and 36" Deep

Dividends Horizon

description	w	w	d	t	pattern no.	lamine w/ ABS edge	lamine w/ woodgrain edge	lamine w/ metal edge	techwood w/ techwood edge
30" Deep Rectangular No Grommets 	24"	23 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 2430N	\$245.	\$267.	\$292.	\$472.
	30"	29 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 3030N	273.	300.	329.	509.
	36"	35 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 3630N	302.	334.	366.	544.
	42"	41 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 4230N	329.	360.	392.	580.
	48"	47 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 4830N	367.	401.	436.	617.
	54"	53 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 5430N	415.	455.	497.	643.
	60"	59 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 6030N	456.	502.	545.	671.
	66"	65 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 6630N	506.	558.	610.	697.
	72"	71 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 7230N	527.	577.	632.	722.
	78"	77 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 7830N	562.	622.	676.	757.
	84"	83 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 8430N	597.	657.	718.	788.
	90"	89 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 9030N	642.	706.	770.	822.
96"	95 ^{13/16} "	29 ^{1/2} "	1 ^{1/4} "	D1R 9630N	689.	758.	826.	855.	
36" Deep Rectangular No Grommets 	60"	59 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 6036N	583.	641.	699.	796.
	66"	65 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 6636N	644.	711.	772.	823.
	72"	71 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 7236N	711.	783.	853.	854.
	78"	77 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 7836N	757.	805.	860.	863.
	84"	83 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 8436N	802.	825.	866.	872.
	90"	89 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 9036N	863.	888.	923.	938.
	96"	95 ^{13/16} "	35 ^{1/2} "	1 ^{1/4} "	D1R 9636N	924.	951.	977.	1,004.

w* = nominal width

Dimensions listed under w h t are actual to the nearest 1/16"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 6030N, 114, 114**

D1R Pattern Number
6030N

114 Folkstone Grey
Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$18.

Curvilinear Wave End Worksurfaces

Dividends Horizon curvilinear wave end worksurfaces are primarily used in panel-hung applications.

Available Sizes

Curvilinear wave end worksurfaces are handed with one side deeper than the other.

- Depths: 24"/30", 18"/30", 24"/36"
- Widths: 36" to 72"

Curvilinear Wave End Applications

36" to 48" wide wave ends are generally used as worksurface returns attached to curvilinear corners.

72" wide wave ends are used as primary worksurfaces with returns attached at the deep end.

Note: Only 18" and 24" deep returns can be attached to 72" wide wave end worksurfaces.

Curvilinear Wave End Support

In applications where worksurface ends are mounted perpendicular to panels, panel-to-worksurface brackets or a cantilever and a panel-to-worksurface bracket can be used as shown below.

72" wide curvilinear wave ends always require mid-span cantilever support including applications involving pedestal support at one end.

Pedestal Support Applications

Pedestals can be used as supports in the following locations:

- The deep end of all curvilinear wave ends
- The shallow end of all 48" and 72" wide curvilinear wave end worksurfaces

Recommended Pedestal Depths


- 18" deep wave ends require 18" deep pedestals
- 24" deep wave ends can use either a 18" or 24" deep pedestal
- 30" deep wave ends can use either a 24" or 30" deep pedestal
- 36" deep wave ends require a 30" deep pedestal

Note: When the pedestal depth is less than the worksurface depth, a panel-to-worksurface bracket must be used in the rear corner of the worksurface to the panel.

Freestanding Applications

Curvilinear wave end worksurfaces can be used to create unique freestanding workstations supported by pedestals and end units. The most common application is a 72" wide wave end worksurface with a single pedestal and end unit attached to a freestanding return.



Curvilinear Wave End Worksurface



Curvilinear Wave End Worksurface Sizes



72"W	30"/18"D	18"/30"D
72"W	30"/24"D	24"/30"D
72"W	36"/24"D	24"/36"D

Curvilinear Wave End Applications



** Requires a return panel, panel-mounted C-leg support, open support leg, or a pedestal with a panel-to-worksurface bracket for support.

Pedestal Support Applications





Pedestal on shallow end of curvilinear wave ends

Curvilinear Wave End Worksurfaces

Mixed Depths

Dividends Horizon

description	w*							t	pattern no.	laminate w/	laminate w/	techwood w/
		1	2	3	A	B	edge			woodgrain	laminate w/	techwood
									ABS	edge	metal edge	edge
Curvilinear Wave End Left No Grommets 	36"	35 13/16"	23 1/2"	29 1/2"	14 15/16"	2 15/16"	1 1/4"	D1W 363024N	\$514.	\$563.	\$619.	\$985.
	42"	41 13/16"	23 1/2"	29 1/2"	14 15/16"	8 15/16"	1 1/4"	D1W 423024N	539.	595.	645.	1,015.
	48"	47 13/16"	23 1/2"	29 1/2"	14 15/16"	14 15/16"	1 1/4"	D1W 483024N	574.	634.	693.	1,042.
	72"	71 13/16"	17 1/2"	29 1/2"	23 7/16"	14 15/16"	1 1/4"	D1W 723018N	714.	784.	855.	1,071.
	72"	71 13/16"	23 1/2"	29 1/2"	23 7/16"	30 7/16"	1 1/4"	D1W 723024N	734.	806.	883.	1,102.
	72"	71 13/16"	23 1/2"	35 1/2"	23 7/16"	14 15/16"	1 1/4"	D1W 723624N	759.	831.	910.	1,130.
Curvilinear Wave End Right No Grommets 	36"	35 13/16"	29 1/2"	23 1/2"	2 15/16"	14 15/16"	1 1/4"	D1W 362430N	514.	563.	619.	985.
	42"	41 13/16"	29 1/2"	23 1/2"	8 15/16"	14 15/16"	1 1/4"	D1W 422430N	539.	595.	645.	1,015.
	48"	47 13/16"	29 1/2"	23 1/2"	14 15/16"	14 15/16"	1 1/4"	D1W 482430N	574.	634.	693.	1,042.
	72"	71 13/16"	29 1/2"	17 1/2"	14 15/16"	23 7/16"	1 1/4"	D1W 721830N	714.	784.	855.	1,071.
	72"	71 13/16"	29 1/2"	23 1/2"	30 7/16"	23 7/16"	1 1/4"	D1W 722430N	734.	806.	883.	1,102.
	72"	71 13/16"	35 1/2"	23 1/2"	14 15/16"	23 7/16"	1 1/4"	D1W 722436N	759.	831.	910.	1,130.

w* = nominal width

A and B = straight edge length

Dimensions listed under 1, 2 and 3 are actual to nearest 1/16"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 6030N, 114, 114**

D1R Pattern Number
6030N

114 Folkstone
Grey Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces


Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$18.

description	w*	w	depth left	depth right	t	pattern no.	laminate w/	laminate w/	laminate w/	techwood w/
							ABS edge	woodgrain edge	metal edge	techwood edge
Smooth Wave 	48"	47 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S481824N	\$574.	\$634.	\$693.	\$1,003.
	48"	47 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S481830N	574.	634.	693.	1,006.
	48"	47 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S482418N	574.	634.	693.	1,013.
	48"	47 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S482430N	574.	634.	693.	1,016.
	48"	47 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S483018N	574.	634.	693.	1,020.
	48"	47 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S483024N	574.	634.	693.	1,023.
	60"	59 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S601824N	668.	734.	800.	1,028.
	60"	59 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S601830N	668.	734.	800.	1,032.
	60"	59 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S602418N	668.	734.	800.	1,037.
	60"	59 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S602430N	668.	734.	800.	1,042.
	60"	59 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S603018N	668.	734.	800.	1,048.
	60"	59 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S603024N	668.	734.	800.	1,052.
	66"	65 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S661824N	714.	785.	858.	1,056.
	66"	65 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S661830N	714.	785.	858.	1,059.
	66"	65 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S662418N	714.	785.	858.	1,064.
	66"	65 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S662430N	714.	785.	858.	1,069.
	66"	65 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S663018N	714.	785.	858.	1,073.
	66"	65 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S663024N	714.	785.	858.	1,076.
	72"	71 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S721824N	759.	831.	910.	1,081.
	72"	71 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S721830N	759.	831.	910.	1,085.
	72"	71 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S722418N	759.	831.	910.	1,091.
	72"	71 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S722430N	759.	831.	910.	1,099.
	72"	71 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S723018N	759.	831.	910.	1,103.
	72"	71 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S723024N	759.	831.	910.	1,106.
	78"	77 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S781824N	802.	884.	963.	1,111.
	78"	77 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S781830N	802.	884.	963.	1,113.
	78"	77 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S782418N	802.	884.	963.	1,114.
	78"	77 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S782430N	802.	884.	963.	1,119.
	78"	77 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S783018N	802.	884.	963.	1,124.
	78"	77 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S783024N	802.	884.	963.	1,129.
	84"	83 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S841824N	851.	933.	1,019.	1,132.
	84"	83 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S841830N	851.	933.	1,019.	1,137.
84"	83 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S842418N	851.	933.	1,019.	1,141.	
84"	83 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S842430N	851.	933.	1,019.	1,145.	
84"	83 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S843018N	851.	933.	1,019.	1,149.	
84"	83 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S843024N	851.	933.	1,019.	1,155.	

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 6030N, 114, 114**

D1W	Dividends Worksurface
S	Smooth Wave Shape
72	Overall width in inches
30	Nominal depth at user's left side
24	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets, replace the "N" suffix from the pattern number with a "G".

Add \$28

This page intentionally left blank

Faceted Worksurfaces

20, 24 and 30 Deep Specifications

Faceted Worksurfaces

Dividends Horizon Faceted Worksurfaces make the most of compact workspaces with their Outward Facing Design and layered approach that defines active, secondary and collaborative work zones.

Planning with Faceted Worksurfaces

Dividends Horizon Faceted Worksurfaces require three unique components to complete the installation:

1. Layered Cantilever Assembly: DBVDC(L) (R) supports both Primary Faceted and the Secondary Faceted Worksurface.

Note: the Faceted Worksurfaces and the Layered Cantilever Assemblies are handed. Specify the same hand Layered Cantilever Assembly as the Primary Faceted Worksurface.

2. 2.5" Column Support: DBSCR, supports both the Primary Faceted and Bench Faceted Worksurfaces at their widest end. The 2.5" Column Support adjusts from the top, beneath the worksurface, creating a more refined aesthetic.

3. Satellite Support Assembly: DSSA(C) (R), is available in two shapes, Circular or Soft Rectangle and clamps to the edge of either the Primary or Bench Faceted Worksurface at their widest end.

The Satellite Support Assembly comes in two parts: the Satellite Mechanism and the Satellite Top. The Satellite Mechanism is available in all core paint finishes. The Satellite Top is powder coated MDF and available in three colors: Brilliant Blue (135), Honey Yellow (136) and Ruby Red (137).


The Satellite Mechanism is approximately 2.5" wide and raises the Satellite Top 3" above the worksurface. The Circular Satellite Top is approximately 16" in diameter and the Soft Rectangle Satellite Top is approximately 16" x 18".

Available Sizes


- Faceted Primary
Depths: 24"/18" and 30"/19"
Widths: 60" to 96"
- Faceted Secondary
Depths 20"/12"
Widths 60" to 96"
- Faceted Bench
Depths 24"/18" and 30"/19"
Widths: 60" to 96"

Panel-Hung Applications


When a worksurface spans multiple panels a cantilever or freestanding support is required every 48" of width.



Faceted Primary Worksurface



Faceted Secondary Worksurface



Faceted Bench Worksurface

Faceted Sizes Available

Faceted Primary


24"D		30"D	
60"		60"	
66"		66"	
72"		72"	
84"		84"	
90"		90"	
96"		96"	

Faceted Secondary


20"D	
60"	
66"	
72"	
84"	
90"	
96"	

Faceted Bench

24"D		30"D	
60"		60"	
66"		66"	
72"		72"	
84"		84"	
90"		90"	
96"		96"	



Primary Faceted Worksurface with Secondary Faceted Worksurface, Satellite Assembly and 2.5" Column Support



Faceted Bench Worksurface with Satellite Assembly, 2.5" Column Support and Anchor Credenza

*Faceted Primary and Secondary Worksurfaces***Faceted Primary and Secondary Worksurfaces**

Dividends Horizon Faceted Primary and Secondary worksurfaces are layered perpendicularly and used in panel hung applications

Available Sizes (Primary)

Faceted Primary worksurfaces have an Outward Facing Design and are handed with one side deeper than the other.

- Depths: 24"/18" and 30"/19"
- Widths: 60" to 96"

Available Sizes (Secondary)

Faceted Secondary worksurfaces are handed with one end deeper than another.

- Depths: 20"/12"
- Widths: 60" to 96"

Note: end with the greatest depth determines handedness

Faceted Worksurface Applications

Primary Faceted worksurfaces are designed to be used with the Secondary Faceted worksurfaces as a return. The Secondary surface mounts beneath with Primary surface using the Layered Cantilever Assembly DBVDC(L) left DBVDC(R) right.

Faceted Bench Worksurface Applications

Faceted Bench worksurfaces are designed to be used with a credenza as a return. The shallow end of the Faceted Bench Worksurface is supported by a Crendeza Spacer, BW1CSB.

Primary Faceted Worksurface Support

Primary Faceted worksurfaces are supported by a panel-to-worksurface bracket at the deepest end and the Layered Cantilever Assembly at the shallow end. The Column Support (DBSCR) is also used to support the worksurface.

72" wide worksurfaces always require either a mid-span cantilever support or worksurface reinforcement strap (DB1WR72).

Storage Support Applications

Faceted Primary and Secondary Worksurfaces can be supported (on the shallow end) by Anchor Storage Lockers using L-bracket WLLB.

Recommended Pedestal Depths





Dividends Horizon Faceted Worksurfaces are primarily used with mobile pedestals which can double as guest seating.

Faceted Secondary surfaces are designed for use with 18" deep mobile pedestals.

Faceted Worksurfaces

Faceted Primary Worksurfaces

Dividends Horizon

description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
24" Deep Primary Desk, Left Hand 	60"	59 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP6024LN	\$665.
	66"	65 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP6624LN	708.
	72"	71 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP7224LN	751.
	78"	77 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP7824LN	794.
	84"	83 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP8424LN	836.
	90"	89 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP9024LN	879.
	96"	95 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDP9624LN	922.
24" Deep Primary Desk, Right Hand 	60"	59 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP6024RN	665.
	66"	65 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP6624RN	708.
	72"	71 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP7224RN	751.
	78"	77 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP7824RN	794.
	84"	83 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP8424RN	836.
	90"	89 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP9024RN	879.
	96"	95 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDP9624RN	922.
30" Deep Primary Desk, Left Hand 	60"	59 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP6030LN	675.
	66"	65 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP6630LN	718.
	72"	71 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP7230LN	761.
	78"	77 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP7830LN	804.
	84"	83 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP8430LN	847.
	90"	89 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP9030LN	889.
	96"	95 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDP9630LN	932.
30" Deep Primary Desk, Right Hand 	60"	59 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP6030RN	675.
	66"	65 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP6630RN	718.
	72"	71 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP7230RN	761.
	78"	77 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP7830RN	804.
	84"	83 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP8430RN	847.
	90"	89 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP9030RN	889.
	96"	95 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDP9630RN	932.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

<i>Example:</i>	DVDP7230LN114114
DVD	Dividends Worksurface
P	Primary, Faceted
72	Overall width in inches
30	Overall Depth in inches
L	Left or Right handed
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included With



Worksurfaces

Note: Faceted worksurfaces available in standard laminates only.

Options

Faceted Worksurfaces

Faceted Secondary Worksurfaces

description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
20" Deep Secondary Desk, Left Hand 	60"	59 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS6020LN	\$537.
	66"	65 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS6620LN	579.
	72"	71 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS7220LN	622.
	78"	77 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS7820LN	665.
	84"	83 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS8420LN	708.
	90"	89 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS9020LN	751.
	96"	95 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS9620LN	794.
20" Deep Secondary Desk, Right Hand 	60"	59 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS6020RN	537.
	66"	65 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS6620RN	579.
	72"	71 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS7220RN	622.
	78"	77 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS7820RN	665.
	84"	83 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS8420RN	708.
	90"	89 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS9020RN	751.
	96"	95 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS9620RN	794.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **DVDS6020LN, 114, 114**

DVD	Dividends Worksurface
S	Secondary, Faceted
60	Overall width in inches
20	Overall depth in inches
L	Left or Right handed
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included With

Worksurfaces

Note: Faceted worksurfaces available in standard laminates only.

Options

Faceted Bench Worksurfaces

Dividends Horizon Faceted Bench worksurfaces are used primarily as a primary worksurface in Bench applications or as a primary worksurface in panel hung applications with a return.

Available Sizes

Faceted Bench worksurfaces have an Outward Facing Design and are handed with one side deeper than the other.

- Depths: 24"/18" and 30"/19"
- Widths: 60" to 96"

Note: end with the greatest depth determines handedness

Faceted Bench Worksurface Applications

Faceted Bench worksurfaces are designed to be used with either a storage element as a return or a rectilinear surface mounted beneath with Primary surface using the Layered Cantilever Assembly DBVDC(L or R)

Faceted Bench Worksurface Support

Primary Faceted worksurfaces are supported by a panel-toworksurface bracket at the deepest end and either an 18" Cantilever or the Layered Cantilever Assembly at the shallow end. The Column Support (DBSCR) is also used to support the worksurface. See image below.

72" wide worksurfaces always require either a mid-span cantilever support or a worksurface reinforcement strap (DB1WR72).

Storage Support Applications





Faceted Bench Worksurfaces can be supported on the shallow end with a Credenza Spacer (BW1CSB) and Crendeza or by Anchor Storage Lockers using L-bracket WLLB.

Recommended Pedestal Depths

Dividends Horizon Faceted Bench Worksurfaces are primarily used with mobile pedestals which can double as guest seating.

Faceted Worksurfaces

Faceted Bench Worksurfaces

description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
24" Deep Faceted Bench, Left Hand 	60"	59 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB6024LN	\$665.
	66"	65 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB6624LN	708.
	72"	71 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB7224LN	751.
	78"	77 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB7824LN	794.
	84"	83 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB8424LN	836.
	90"	89 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB9024LN	879.
	96"	95 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB9624LN	922.
24" Deep Faceted Bench, Right Hand 	60"	59 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB6024RN	665.
	66"	65 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB6624RN	708.
	72"	71 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB7224RN	751.
	78"	77 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB7824RN	794.
	84"	83 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB8424RN	836.
	90"	89 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB9024RN	879.
	96"	95 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB9624RN	922.
30" Deep Faceted Bench, Left Hand 	60"	59 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB6030LN	675.
	66"	65 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB6630LN	718.
	72"	71 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB7230LN	761.
	78"	77 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB7830LN	804.
	84"	83 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB8430LN	847.
	90"	89 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB9030LN	889.
	96"	95 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB9630LN	932.
30" Deep Faceted Bench, Right Hand 	60"	59 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB6030RN	675.
	66"	65 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB6630RN	718.
	72"	71 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB7230RN	761.
	78"	77 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB7830RN	804.
	84"	83 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB8430RN	847.
	90"	89 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB9030RN	889.
	96"	95 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB9630RN	932.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: DVDB6024LN,114,114


DVD	Dividends Worksurface
B	Faceted, Bench
60	Overall width in inches
24	Overall depth in inches
L	Left or right handed
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included With

Worksurfaces

Note: Faceted worksurfaces available in standard laminates only.

Options

description	w*	w	depth left	depth right	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Trapezoidal 	48"	47 ^{13/16} "	23 ^{1/2} "	29 ^{1/2} "	1 ^{1/4} "	D1W T482430N	\$574.	\$634.	\$693.	\$718.
	48"	47 ^{13/16} "	29 ^{1/2} "	23 ^{1/2} "	1 ^{1/4} "	D1W T483024N	574.	634.	693.	718.
	60"	59 ^{13/16} "	23 ^{1/2} "	29 ^{1/2} "	1 ^{1/4} "	D1W T602430N	668.	734.	800.	759.
	60"	59 ^{13/16} "	29 ^{1/2} "	23 ^{1/2} "	1 ^{1/4} "	D1W T603024N	668.	734.	800.	759.
	66"	65 ^{13/16} "	23 ^{1/2} "	29 ^{1/2} "	1 ^{1/4} "	D1W T662430N	714.	785.	858.	798.
	66"	65 ^{13/16} "	29 ^{1/2} "	23 ^{1/2} "	1 ^{1/4} "	D1W T663024N	714.	785.	858.	798.
	72"	71 ^{13/16} "	23 ^{1/2} "	29 ^{1/2} "	1 ^{1/4} "	D1W T722430N	759.	831.	910.	838.
	72"	71 ^{13/16} "	29 ^{1/2} "	23 ^{1/2} "	1 ^{1/4} "	D1W T723024N	759.	831.	910.	838.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1W T482430N**

D1W	Dividends Worksurface
T	Trapezoidal Shape
48	Overall Width, inches
24	Nominal depth at user's left side
30	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurface

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets replace the "N" suffix from the pattern number with a "G".

Add \$28

This page intentionally left blank

Corner Worksurfaces

Rectilinear and Split Top Corner Specifications

Rectilinear Corner Worksurfaces

Dividends Horizon rectilinear corner worksurfaces are used in panel-hung and freestanding applications.

Split Top Corner Worksurfaces

Split top corner worksurfaces allow for height and angle adjustment on the front work surface.

The depth of the front keyboard work surface is 10 ⁵/₈". The front surface adjusts from a - 5 ³/₄" below the work surface to a + 7" above. The mechanism has a tilt feature of ±10 degrees.

Included with the split top work surface is the back corner work surface, the front corner work surface, the split top mechanism, one rear corner panel-to-work surface bracket and two flat brackets for attachment to return work surfaces. Cantilevers must be ordered separately and are specified to the size return

work surface depth (i.e 24" cantilevers for 24" deep return work surfaces). Panel-mounted C-leg or Open Leg work surface supports may be used in place of cantilevers.

Available Sizes

- Widths: 36", 42" and 48"
- Returns: 18", 24" and 30"
- Thickness: 1 ¹/₄"

Corner Worksurface Support

Corner worksurfaces must be supported by cantilevers at each end and a panel-to-work surface bracket at the rear corner. Panel-mounted C-leg or Open Leg work surface supports may be used instead of cantilevers for corner work surface support. Cantilevers and panel-mounted C-leg or Open Leg supports are ordered separately. Panel-to-work surface bracket is included.


Corner Worksurface Applications

Corner worksurfaces attach to adjacent work surfaces with cantilevers and flat brackets. Suggested applications are illustrated below.


Note: All dimensions are nominal except for front edge dimension.

Note: Series 3 overdesk units are not compatible with corner work surfaces.


Rectilinear Corner Worksurface




Rectilinear Split-Top Corner Worksurface




Rectilinear and Split Top Corner Worksurface Sizes Available



Corner Worksurface Support



Corner Worksurface Applications







** Requires a return panel, panel-mounted C-leg or Open Leg support or a pedestal with a panel-to-work surface bracket for support.

Corner Worksurfaces

Rectilinear and Split Top Corner

Mixed Depths

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Rectilinear Corner Worksurface No Grommets 	36"	36"	18"	18"	1 1/4"	D1C 3618N	\$440.	\$483.	\$527.	\$891.
	36"	36"	24"	24"	1 1/4"	D1C 3624N	447.	495.	538.	976.
	42"	42"	24"	24"	1 1/4"	D1C 4224N	504.	555.	603.	1,058.
	48"	48"	24"	24"	1 1/4"	D1C 4824N	575.	635.	694.	1,142.
	48"	48"	30"	30"	1 1/4"	D1C 4830N	595.	654.	714.	1,226.
Rectilinear Corner Worksurface. 24" Deep Return Left 30" Deep Return Right No Grommets 	42"	42"	24"	30"	1 1/4"	D1C 422430N	528.	580.	634.	1,149.
	48"	48"	24"	30"	1 1/4"	D1C 482430N	599.	660.	721.	1,226.
Rectilinear Corner Worksurface. 30" Deep Return Left 24" Deep Return Right No Grommets 	42"	42"	30"	24"	1 1/4"	D1C 423024N	528.	580.	634.	1,149.
	48"	48"	30"	24"	1 1/4"	D1C 483024N	599.	660.	721.	1,226.
Split Top Corner Worksurface No Grommets 	42"	42"	24"	24"	1 1/4"	D1CS 4224N	1,792.	1,970.	2,150.	3,046.
	48"	48"	24"	24"	1 1/4"	D1CS 4824N	1,845.	2,027.	2,213.	3,147.
	48"	48"	30"	30"	1 1/4"	D1CS 4830N	1,857.	2,043.	2,231.	3,250.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2" less than shown above.

Ordering Information	Order Code	Included with:	Options
Worksurfaces 1. Pattern Number 2. Top Finish Type 3. Edge Finish Split Top Corner Worksurfaces 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Worksurfaces <i>Example:</i> D1C 423024N, 117, 115 D1C Pattern Number 423024N 117 Soft Grey Laminate 115 Medium Grey Edge Band Split Top Corner Worksurfaces <i>Example:</i> D1CS 4224N, 117, 117 D1CS Pattern Number 4224N 117 Soft Grey Laminate 117 Soft Grey Edge Band	Worksurfaces <ul style="list-style-type: none"> • Worksurface • Panel-to-Worksurface Bracket Split Top Corner Worksurfaces <ul style="list-style-type: none"> • Front Worksurface • Back Worksurface • Split Top Mechanism • Flat Brackets • Panel-to-Worksurface Bracket <p>Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.</p> <p>Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.</p> <p>Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.</p>	Worksurfaces <ul style="list-style-type: none"> • 2 Center-Located Edge Grommets • Woodgrain PVC edge • Metal edge • Techwood edge <p>To specify edge grommets, replace the "N" suffix from the pattern number with a "G". Add \$29</p> Split Top Corner Worksurfaces <ul style="list-style-type: none"> • 2 Center-Located Edge Grommets • Woodgrain PVC edge • Metal edge • Techwood edge <p>Note: Overdesk units are not compatible with corner worksurfaces.</p>

Corner Worksurfaces

Curvilinear Corner "L" Shape - 24" Depths Specifications

Curvilinear Corner L Shape Worksurfaces

Dividends Horizon curvilinear corner "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support

Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support.

Cantilevers, panel-mounted c-leg and open support legs are ordered separately. A panel-to-worksurface bracket is included.


Note: Worksurfaces greater than 48" wide require an additional mid-span cantilever support along the 60" or 72" side.

Note: A pedestal, panel-mounted C-leg or Open Leg Support can be substituted for a cantilever in the following locations:




- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces

Note: Series 3 overdesk units are not compatible with corner worksurfaces.


Curvilinear Corner Worksurface





Curvilinear Corner Worksurface Support Options



Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Support Leg with panel-to-worksurface bracket for support

Corner Worksurfaces

Curvilinear Corner "L" Shape - 24" Depths

24" Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminates w/	laminates w/	laminates w/	techwood w/
							ABS edge	woodgrain edge	metal edge	techwood edge
Curvilinear Corner "L" Shape Worksurface 24" Deep Returns Left and Right	36"	36"	24"	24"	1 1/4"	D1L 3636SSN	\$477.	\$524.	\$571.	\$1,100.
	42"	42"	24"	24"	1 1/4"	D1L 4242SSN	573.	633.	692.	1,167.
	42"	60"	24"	24"	1 1/4"	D1L 4260SSN	791.	870.	949.	1,302.
	42"	66"	24"	24"	1 1/4"	D1L 4266SSN	812.	900.	977.	1,336.
	42"	72"	24"	24"	1 1/4"	D1L 4272SSN	843.	927.	1,014.	1,404.
	42"	78"	24"	24"	1 1/4"	D1L 4278SSN	853.	938.	1,022.	1,468.
	48"	48"	24"	24"	1 1/4"	D1L 4848SSN	645.	714.	774.	1,232.
	48"	60"	24"	24"	1 1/4"	D1L 4860SSN	800.	880.	958.	1,370.
	48"	66"	24"	24"	1 1/4"	D1L 4866SSN	828.	912.	993.	1,437.
	48"	72"	24"	24"	1 1/4"	D1L 4872SSN	861.	945.	1,027.	1,501.
	48"	78"	24"	24"	1 1/4"	D1L 4878SSN	949.	1,042.	1,137.	1,535.
	48"	84"	24"	24"	1 1/4"	D1L 4884SSN	1,064.	1,171.	1,278.	1,567.
	60"	42"	24"	24"	1 1/4"	D1L 6042SSN	791.	870.	949.	1,302.
	60"	48"	24"	24"	1 1/4"	D1L 6048SSN	800.	880.	958.	1,370.
	66"	42"	24"	24"	1 1/4"	D1L 6642SSN	812.	900.	977.	1,336.
	66"	48"	24"	24"	1 1/4"	D1L 6648SSN	828.	912.	993.	1,437.
	72"	42"	24"	24"	1 1/4"	D1L 7242SSN	843.	927.	1,014.	1,404.
	72"	48"	24"	24"	1 1/4"	D1L 7248SSN	861.	945.	1,027.	1,501.
	78"	42"	24"	24"	1 1/4"	D1L 7842SSN	853.	938.	1,022.	1,468.
	78"	48"	24"	24"	1 1/4"	D1L 7848SSN	949.	1,042.	1,137.	1,535.
	84"	48"	24"	24"	1 1/4"	D1L 8448SSN	1,064.	1,171.	1,278.	1,567.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2" less than shown above.

Ordering Information	Order Code	Included with:	Options
1. Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
2. Pattern Number	<i>Example:</i> D1L 4860SSN, 117, 117	<ul style="list-style-type: none"> Worksurface Panel-to-Worksurface Bracket 	<ul style="list-style-type: none"> 2 center-located edge grommets Woodgrain ABS edge Metal edge Techwood
3. Top Finish Type	D1L Pattern Number	<p>Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.</p> <p>Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.</p> <p>Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.</p>	<p>To specify edge grommets, replace the "N" suffix from the pattern number with "G" Add \$29</p> <p>Note: Overdesk units are not compatible with corner worksurfaces.</p>
4. Edge Finish	4860SSN		
	117 Soft Grey laminate		
	117 Soft Grey Edge Band		

Corner Worksurfaces

Curvilinear Corner "L" shape-Mixed Depths Specifications

Curvilinear Corner "L" Shape Worksurfaces

Dividends Horizon curvilinear corner, "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support

Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support.

Cantilevers and panel-mounted C-leg or open leg supports are ordered separately. A panel-to-worksurface bracket is included.

Note: 60" and 72" wide curvilinear corners require an additional mid-span cantilever support along the 60" or 72" side.


Note: A pedestal or panel-mounted C-leg can be substituted for a cantilever in the following locations:

- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces


Curvilinear Corner Worksurface Applications

Curvilinear "L" shape corner worksurfaces are primarily used with wave end and rectangular worksurface returns.




Curvilinear Corner Worksurface





Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Support Options



Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Leg Support with panel-to-worksurface bracket for support

Corner Worksurfaces

Curvilinear Corner "L" shape-Mixed Depths

Mixed Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminates w/ ABS edge	laminates w/ woodgrain edge	laminates w/ metal edge	techwood w/ techwood edge
Curvilinear Corner "L" Shape Worksurface. 30" Deep Returns Left and Right	48"	48"	30"	30"	1 1/4"	D1L 4848DDN	\$697.	\$767.	\$833.	\$1,247.
Curvilinear Corner "L" Shape Worksurface 24" Deep Return Left 30" Deep Return Right 	48"	48"	24"	30"	1 1/4"	D1L 4848SDN	689.	758.	826.	1,247.
	48"	60"	24"	30"	1 1/4"	D1L 4860SDN	786.	866.	941.	1,280.
	48"	66"	24"	30"	1 1/4"	D1L 4866SDN	825.	908.	989.	1,311.
	48"	72"	24"	30"	1 1/4"	D1L 4872SDN	866.	951.	1,035.	1,344.
	60"	48"	24"	30"	1 1/4"	D1L 6048SDN	770.	847.	925.	1,380.
	66"	48"	24"	30"	1 1/4"	D1L 6648SDN	809.	889.	975.	1,414.
	72"	48"	24"	30"	1 1/4"	D1L 7248SDN	851.	936.	1,020.	1,447.
Curvilinear Corner "L" Shape Worksurface 30" Deep Return Left 24" Deep Return Right 	48"	48"	30"	24"	1 1/4"	D1L 4848DSN	689.	758.	826.	1,247.
	48"	60"	30"	24"	1 1/4"	D1L 4860DSN	770.	847.	925.	1,280.
	48"	66"	30"	24"	1 1/4"	D1L 4866DSN	809.	889.	975.	1,311.
	48"	72"	30"	24"	1 1/4"	D1L 4872DSN	851.	936.	1,020.	1,344.
	60"	48"	30"	24"	1 1/4"	D1L 6048DSN	786.	866.	941.	1,380.
	66"	48"	30"	24"	1 1/4"	D1L 6648DSN	825.	908.	989.	1,414.
	72"	48"	30"	24"	1 1/4"	D1L 7248DSN	866.	951.	1,035.	1,447.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2" less than shown above.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Band Finish

Order Code

Worksurfaces

Example: **D1L 4860SDN, 117, 117**

D1L	Pattern Number
4860SDN	
117	Soft Grey Laminate
117	Soft Grey edge band

Included with:

Worksurfaces

- Worksurface
- Panel-to-worksurface bracket

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 2 center-located edge grommets
- Woodgrain ABS edge
- Metal edge
- Techwood

To specify edge grommets, replace the "N" suffix from the pattern number with "G"

Add \$29

Note: An overdesk unit will not align with the width of a corner worksurface due to the 1/2" wire drop gap. The overdesk will be 1/2" too wide.

Peninsula Worksurfaces

"D", "P", "9" and Blended "D" Specifications

"D", Blended "D", Conferencing, "P" and "9" Shape Peninsula Worksurfaces

Dividends Horizon peninsula worksurfaces mount perpendicular to panels of the same width to provide conferencing area within a workstation.

"D", "P" and "9" tops are supported by panel-to-worksurface brackets on the flat end and a support column, T leg or A leg support at the free end. Adjacent worksurfaces can attach to peninsula tops with flat brackets.

All brackets and supports are ordered separately. "D", "P" and "9" shape peninsula worksurfaces may be used in freestanding applications.

"D" Shaped Peninsula

Available Sizes

- Depths: 24", 30" and 36"
- Widths: 48", 60", 66" and 72"
- Thickness: 1 1/4"

"P" and "9" Shaped Peninsula

Available Sizes

- Depth: 30" panel depth
- Widths: 66", 72" and 78"
- Conferencing diameter: 36" and 42"
- Thickness: 1 1/4"

Blended "D" Peninsula


Available Sizes

- Depths: 48"
- Widths: 72" and 66"
- Thickness: 1 1/4"


Conferencing Worksurfaces

- Depth: 48"
- Width: 60"
- Thickness: 1 1/4"


"D" and "P" Shape Peninsula Worksurfaces







Blended "D" Shape Peninsula Worksurface



Conferencing Worksurface Dimensions



Peninsula Worksurfaces
 “D”, “P”, “9” and Blended “D”
 Mixed Depths

description	type	w *	w	d	dia.	t	pattern no.	laminata w/	laminata w/	laminata w/	techwood w/	
								ABS edge	woodgrain edge	metal edge	techwood edge	
“D” Peninsula Worksurface Laminate No Grommets 		48"	47 ^{13/16} "	23 ^{13/16} "		1 ^{1/4} "	D1D 4824N	\$472.	\$520.	\$567.	\$1,172.	
		48"	47 ^{13/16} "	29 ^{13/16} "		1 ^{1/4} "	D1D 4830N	520.	571.	626.	1,211.	
		60"	59 ^{13/16} "	29 ^{13/16} "		1 ^{1/4} "	D1D 6030N	665.	732.	798.	1,250.	
		66"	65 ^{13/16} "	29 ^{13/16} "		1 ^{1/4} "	D1D 6630N	726.	797.	870.	1,289.	
		72"	71 ^{13/16} "	29 ^{13/16} "		1 ^{1/4} "	D1D 7230N	763.	838.	916.	1,327.	
		72"	71 ^{13/16} "	35 ^{13/16} "		1 ^{1/4} "	D1D 7236N	833.	918.	1,003.	1,367.	
Blended “D” Peninsula Worksurface (Left hand shown) 	LH w/ 24" return depth	66"	65 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD6648SL	771.	851.	926.	2,735.	
		72"	71 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD7248SL	788.	869.	947.	2,759.	
	LH w/ 30" return depth	66"	65 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD6648DL	812.	900.	977.	2,735.	
		72"	71 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD7248DL	842.	926.	1,013.	2,759.	
	RH w/ 24" return depth	66"	65 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD6648SR	771.	851.	926.	2,735.	
		72"	71 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD7248SR	788.	869.	947.	2,759.	
	RH w/ 30" return depth	66"	65 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD6648DR	812.	900.	977.	2,735.	
		72"	71 ^{13/16} "	47 ^{13/16} "		1 ^{1/4} "	D1BD7248DR	842.	926.	1,013.	2,759.	
	Conferencing worksurface (left hand shown) 		60"	59 ^{13/16} "	48"	24"	1 ^{1/4} "	DB1BD48SL	1,063.	1,170.	1,277.	2,707.
			60"	59 ^{13/16} "	48"	24"	1 ^{1/4} "	DB1BD48SR	1,063.	1,170.	1,277.	2,707.
	Peninsula Worksurface-Laminate No Grommets (9-shaped shown) 	P-shaped	66"	65 ^{13/16} "	29 ^{13/16} "	36"	1 ^{1/4} "	D1P 6630N	759.	831.	910.	1,751.
			72"	71 ^{13/16} "	29 ^{13/16} "	42"	1 ^{1/4} "	D1P 7230N	772.	852.	927.	1,800.
78"			77 ^{13/16} "	29 ^{13/16} "	42"	1 ^{1/4} "	D1P 7830N	868.	953.	1,037.	1,851.	
9-shaped		66"	65 ^{13/16} "	29 ^{13/16} "	36"	1 ^{1/4} "	D19 6630N	759.	831.	910.	1,751.	
		72"	71 ^{13/16} "	29 ^{13/16} "	42"	1 ^{1/4} "	D19 7230N	772.	852.	927.	1,800.	
		78"	77 ^{13/16} "	29 ^{13/16} "	42"	1 ^{1/4} "	D19 7830N	868.	953.	1,037.	1,851.	

w* = nominal width
 Dimensions listed under w d t are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
“D” Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	“D” Worksurface <hr/> <i>Example:</i> D1H 6030, 114, 114 D1H 6030 Pattern Number 114 Folkstone Grey Laminate <hr/> 114 Folkstone Grey Edge Band	Worksurface Note: Support column and panel-to-worksurface brackets must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces <ul style="list-style-type: none"> • Woodgrain ABS edge • Metal edge • Techwood edge To specify an edge grommet, replace “N” suffix from pattern number with “G”. Add \$19.

Curvilinear Half-Round Worksurfaces

Curvilinear half-round worksurfaces are sized to match up to the width of two back-to-back 24" deep or two back-to-back 30" deep freestanding desks.

Panel-supported half-round worksurfaces are notched along the flat end to accommodate the panel end trim.

Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the half-round worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes

- Depths: 18" and 24"
- Widths: 48" and 63"
- Thickness: 1 1/4"

Note: All Dividends Horizon worksurfaces include a 1/2" wire drop at the rear edge. When used back to back with Half-Round worksurface, these two 1/2" wire drops will meet to form a 1" space between worksurfaces.

Transition Worksurfaces

Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the transition worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes

- Depths: 24", 36", 48"
- Widths: 48"
- Thickness: 1 1/4"

Corner Round Worksurfaces

Corner-round worksurfaces are designed to "finish" a run of panel-mounted worksurfaces. Corner-round may be specified in two ways.

In a 90° "L" configuration, a notched corner-round worksurface is used to wrap around the panels. Two cantilevers and flat brackets (must be ordered separately) support the corner-round worksurface.

In an end run configuration, the corner-round worksurface is handed and must be specified as a left-hand or a right-hand top. One cantilever with a flat bracket and one panel-to-worksurface bracket (must be ordered separately) support the corner-round top.


Available Sizes

- Depth: 24"
- Width: 24"
- Thickness: 1 1/4"


Optional Edge Grommets

Grommets are not available for worksurfaces on this page.


Curvilinear Half-Round Worksurfaces (without panels)



Curvilinear Half-Round Worksurfaces (with panels)




Corner-Round Worksurface




Notched Corner Worksurfae



Corner-Round Applications



Corner-Round - Notched "L" Configuration






Corner-Round - End Run Configuration (right-hand shown) Quarter-round Surface

Curvilinear Half- and Corner-Round Worksurfaces

Mixed Depths

Dividends Horizon

description	type	w	return depth	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
 Curvilinear Half-Round Worksurface	w/o panels	48"	18"	1 1/4"	D1H4818	\$411.	\$454.	\$495.	\$1,128.
	w/o panels	60"	24"	1 1/4"	D1H6024	566.	624.	679.	1,226.
	w/panels	51"	18"	1 1/4"	D1H5118P	419.	462.	502.	1,175.
	w/panels	63"	24"	1 1/4"	D1H6324P	572.	632.	691.	1,277.
 Transition Worksurface	w panels	51"	24"	1 1/4"	D2H5124P	504.	555.	603.	1,309.
	w panels	51"	36"	1 1/4"	D2H5136P	514.	563.	619.	1,356.
	w panels	51"	48"	1 1/4"	D2H5148P	524.	574.	630.	1,396.
	w/o panels	48"	24"	1 1/4"	D2H4824	499.	545.	596.	1,183.
	w/o panels	48"	36"	1 1/4"	D2H4836	505.	556.	609.	1,226.
	w/o panels	48"	48"	1 1/4"	D2H4848	517.	567.	622.	1,268.
 Corner Round Worksurface	left	23 13/16"	23 1/2"	1 1/4"	D1CRL24	323.	352.	383.	1,404.
	notched	23 1/2"	23 1/2"	1 1/4"	D1CRN24	323.	352.	383.	1,404.
	right	23 13/16"	23 1/2"	1 1/4"	D1CRR24	323.	352.	383.	1,404.

Ordering Information	Order Code	Included with:	Options
Half-Round Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Half-Round Worksurface <hr/> <i>Example:</i> D1H 5118P, 118, 118 D1H Pattern Number 5118P <hr/> 118 Bright White Laminate 118 Bright White Edge Band Transition Worksurface <hr/> <i>Example:</i> D2H 5136P, 117, 117 D2H Pattern Number 5136P <hr/> 117 Soft Grey Laminate 117 Soft Grey Edge Band	Half-Round Worksurface <ul style="list-style-type: none"> • Worksurface • 2 flat brackets Note: Support column must be ordered separately. Transition Worksurface <ul style="list-style-type: none"> • Worksurface • 2 flat brackets Note: Support column must be ordered separately. Corner Round Worksurface <ul style="list-style-type: none"> • Worksurface Note: 2 cantilevers must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Half-Round Worksurface <ul style="list-style-type: none"> • Woodgrain ABS edge • Metal edge • Techwood edge Transition Worksurface <ul style="list-style-type: none"> • Woodgrain ABS edge • Metal edge • Techwood edge Corner-Round Worksurface <ul style="list-style-type: none"> • Woodgrain ABS edge • Metal edge • Techwood edge Curvilinear Half-Round and Transition Worksurface Option Add an 'F' suffix to the pattern number when using with flat profile panel trim.

Transaction Counter Worksurfaces

15" Deep Specifications

15"D Counter Worksurfaces

Dividends Horizon 15"D counter worksurfaces attach to the tops of 42" high panels to provide a transaction area within workstations. Three types are available:

- Straight
- Square corner
- Quarter-round corner

Available Sizes

- Depth: 15"
- Widths: 24" to 96"
- Thickness: 1 1/4"

Straight Counter Worksurface Support

Straight counter worksurfaces can span single or multiple panels. Counter worksurfaces are supported by four counter worksurface brackets which are included with the straight counter worksurfaces. Counter worksurface brackets are required at panel or post junctions for proper support.

Note: High-low panel end trim must be field cut when using countertops in a high-low straight panel run application.

Note: Counter worksurfaces may NOT be used with on any screens or 36H panels.

Square and Quarter-Round Corner Counter Worksurfaces

Square corners allow rectilinear "L", "T" and "X" configurations while quarter-round corners allow radiused "L" configurations. When using corner counter worksurfaces, all adjoining straight counter worksurfaces must be 6" less than panel(s) width dimension. Square and quarter-round counter worksurfaces are supported by flat brackets which are included with corner worksurfaces. Additional support is provided by counter worksurface brackets from the adjoining straight counter worksurfaces.

Square-corner counter worksurfaces include three flat brackets while quarter-round counters include two flat brackets. Flat brackets are dark grey finish.

Counter Worksurface Corner Applications


Suggested applications and configurations are illustrated below.

Note: When connecting a 15" deep counter worksurface with either corner counter worksurface, specify 6" shorter than the required width to accommodate the width of the corner counter worksurface.

Counter Worksurface Supports

Straight counter worksurfaces 24" to 48" wide include four counter worksurface brackets while straight counters 54" to 96" wide include six counter worksurface brackets.

15"D Counter Worksurface



15"D Square-Shape Counter Worksurface




15"D Quarter Round Counter Worksurface



15"D Counter Worksurface Sizes Available

15D	
24	
30	
36	
42	
48	
54	
60	
66	
72	
78	
84	
90	
96	
15	
15	

15"D Counter Worksurface Applications






Transaction Counter Worksurfaces

Rectangular, Square Corner and Quarter-round Corner

15" Deep

Dividends Horizon

description	w *	w	d	t	pattern no.	laminata w/ ABS edge	laminata w/ woodgrain edge	laminata w/ metal edge	techwood w/ techwood edge
15" Deep Quarter-Round Shape Corner Counter Worksurface 	15"	14 ^{13/16"}	15"	1 ^{1/4"}	D1R 1515C	\$217.	\$241.	\$262.	\$879.
15" Deep Square-Shape Corner Counter Worksurface 	15"	14 ^{13/16"}	15"	1 ^{1/4"}	D1R 1515S	199.	221.	241.	550.
15" Deep Rectangular Counter Worksurface 	24"	23 ^{13/16"}	15"	1 ^{1/4"}	D1R 2415	293.	320.	350.	665.
	30"	29 ^{13/16"}	15"	1 ^{1/4"}	D1R 3015	316.	348.	377.	696.
	36"	35 ^{13/16"}	15"	1 ^{1/4"}	D1R 3615	323.	356.	388.	728.
	42"	41 ^{13/16"}	15"	1 ^{1/4"}	D1R 4215	324.	357.	391.	755.
	48"	47 ^{13/16"}	15"	1 ^{1/4"}	D1R 4815	324.	357.	391.	787.
	54"	54 ^{13/16"}	15"	1 ^{1/4"}	D1R 5415	338.	369.	408.	814.
	60"	59 ^{13/16"}	15"	1 ^{1/4"}	D1R 6015	357.	396.	432.	846.
	66"	65 ^{13/16"}	15"	1 ^{1/4"}	D1R 6615	369.	409.	447.	875.
	72"	71 ^{13/16"}	15"	1 ^{1/4"}	D1R 7215	406.	447.	488.	905.
	78"	77 ^{13/16"}	15"	1 ^{1/4"}	D1R 7815	432.	472.	516.	934.
	84"	83 ^{13/16"}	15"	1 ^{1/4"}	D1R 8415	452.	498.	544.	965.
	90"	89 ^{13/16"}	15"	1 ^{1/4"}	D1R 9015	475.	522.	568.	997.
	96"	95 ^{13/16"}	15"	1 ^{1/4"}	D1R 9615	498.	549.	596.	1,024.




w* = nominal width

Dimensions listed under w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
15"D Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish 4. Counter Worksurface Bracket Finish Square-Shape Corner Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish Quarter-Round Shape Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	15"D Counter Worksurface <i>Example:</i> D1R 3615, 117, 117, 117 D1R 3615 Pattern Number 117 Soft Grey Laminate 117 Soft Grey Edge Band 117 Soft Grey Bracket Finish Square-Shape Counter Worksurface <i>Example:</i> D1R 1515S, 117, 117 D1R Pattern Number 1515S 117 Soft Grey Laminate 117 Soft Grey Edge Band Quarter-Round Shape Counter Worksurface <i>Example:</i> D1R 1515C, 117, 117 D1R Pattern Number 1515C 117 Soft Grey Laminate 117 Soft Grey Edge Band	15"D Counter Worksurface <ul style="list-style-type: none"> Four counter worksurface brackets Attachment hardware Square-Shape Counter Worksurface <ul style="list-style-type: none"> Three counter worksurface flat brackets Attachment hardware Quarter-Round Shape Counter Worksurface <ul style="list-style-type: none"> Two counter worksurface flat brackets Attachment hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	15"D Counter Worksurface <ul style="list-style-type: none"> Woodgrain ABS edge Metal edge Techwood edge Square-Shape Counter Worksurface <ul style="list-style-type: none"> Woodgrain ABS edge Metal edge Techwood edge Quarter-Round Shape Counter Worksurface <ul style="list-style-type: none"> Woodgrain ABS edge Metal edge Techwood edge

Rectangular with Cascade Edge 24" and 30" Deep

Dividends Horizon

description	w	d	t	pattern no.	Solid	Woodgrain
24" D Rectangular 	24"	24"	1 1/4"	DCE1R2424N	\$234.	\$268.
	30"	24"	1 1/4"	DCE1R3024N	268.	308.
	36"	24"	1 1/4"	DCE1R3624N	295.	340.
	42"	24"	1 1/4"	DCE1R4224N	340.	392.
	48"	24"	1 1/4"	DCE1R4824N	382.	440.
	54"	24"	1 1/4"	DCE1R5424N	411.	472.
	60"	24"	1 1/4"	DCE1R6024N	446.	513.
	66"	24"	1 1/4"	DCE1R6624N	482.	552.
	72"	24"	1 1/4"	DCE1R7224N	503.	579.
	78"	24"	1 1/4"	DCE1R7824N	541.	621.
	84"	24"	1 1/4"	DCE1R8424N	572.	657.
	90"	24"	1 1/4"	DCE1R9024N	645.	740.
96"	24"	1 1/4"	DCE1R9624N	704.	809.	
30" D Rectangular 	24"	30"	1 1/4"	DCE1R2430N	296.	342.
	30"	30"	1 1/4"	DCE1R3030N	333.	382.
	36"	30"	1 1/4"	DCE1R3630N	371.	426.
	42"	30"	1 1/4"	DCE1R4230N	403.	461.
	48"	30"	1 1/4"	DCE1R4830N	446.	513.
	54"	30"	1 1/4"	DCE1R5430N	504.	580.
	60"	30"	1 1/4"	DCE1R6030N	555.	637.
	66"	30"	1 1/4"	DCE1R6630N	619.	711.
	72"	30"	1 1/4"	DCE1R7230N	645.	740.
	78"	30"	1 1/4"	DCE1R7830N	687.	790.
	84"	30"	1 1/4"	DCE1R8430N	731.	841.
	90"	30"	1 1/4"	DCE1R9030N	786.	904.
96"	30"	1 1/4"	DCE1R9630N	841.	966.	
Sample 	12"	12"	1 1/4"	DCE1R1212G	144.	167.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example: DCE1R4824N, 118	
DCE1	Dividends Cascade Edge Worksurface
R	Rectangular
48	Width
24	Depth
N	No Grommet
118	Bright White finish

Included with:

Specify worksurface supports separately.

Available Colors:

Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice

Woodgrain:

124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut



Options

Worksurfaces

- Center-Located Edge Grommet
To specify, replace the "N" suffix from the pattern number with "G".

Add \$22.

Shaded area on worksurface drawings represents cascade edge detail.

description	A	B	C	pattern no.	Solid	Woodgrain
Blended “D”  right hand shown	66”	48”	24”	DCE1BD6648S(L/R)	\$943.	\$1,084.
	66”	48”	30”	DCE1BD6648D(L/R)	991.	1,141.
	72”	48”	24”	DCE1BD7248S(L/R)	964.	1,110.
	72”	48”	30”	DCE1BD7248D(L/R)	1,027.	1,182.
	78”	48”	24”	DCE1BD7848S(L/R)	1,114.	1,280.
	78”	48”	30”	DCE1BD7848D(L/R)	1,151.	1,322.
	84”	48”	24”	DCE1BD8448S(L/R)	1,144.	1,315.
	84”	48”	30”	DCE1BD8448D(L/R)	1,217.	1,397.
Blended “L” 	36”	24”	24”	DCE1L3636SSN	582.	671.
	42”	24”	24”	DCE1L4242SSN	704.	809.
	42”	24”	30”	DCE1L4242SDN	836.	959.
	42”	30”	24”	DCE1L4242DSN	836.	959.
	48”	24”	24”	DCE1L4848SSN	790.	909.
	48”	24”	30”	DCE1L4848SDN	947.	1,089.
	48”	30”	24”	DCE1L4848DSN	947.	1,089.
	48”	30”	30”	DCE1L4848DDN	849.	977.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

<i>Example:</i>	DCE1BD7248SL, 118
DCE1	Dividends Cascade Edge worksurface
BD	Blended “D”
72	Width
48	Depth
S	24”d return
L	Extended Left
118	Bright White

Included with:

Available Colors:

Solid:

114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice

Woodgrain:

124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options


Worksurfaces

- Center-Located Edge Grommet (Blended “L” only)To specify, replace the “**N**” suffix from the pattern number with “**G**”.
Add \$44.

Note: Support column and panel-to-worksurface brackets must be ordered separately.

Shaded area on worksurface drawings represents cascade edge detail.

Note: When wood grain or brushed laminates are specified on Cascade corner worksurfaces with two “A” sides of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.

description	Width B	Width C	Width A	Width D	t	pattern no.	Solid	Woodgrain
Blended “L” 	42"	60"	24"	24"	1 1/4"	DCE1L4260SSN	\$966.	\$1,111.
	42"	66"	24"	24"	1 1/4"	DCE1L4266SSN	991.	1,141.
	42"	72"	24"	24"	1 1/4"	DCE1L4272SSN	1,028.	1,184.
	42"	78"	24"	24"	1 1/4"	DCE1L4278SSN	1,041.	1,195.
	48"	60"	24"	24"	1 1/4"	DCE1L4860SSN	979.	1,124.
	48"	60"	24"	30"	1 1/4"	DCE1L4860SDN	959.	1,105.
	48"	60"	30"	24"	1 1/4"	DCE1L4860DSN	959.	1,105.
	48"	66"	24"	24"	1 1/4"	DCE1L4866SSN	1,014.	1,165.
	48"	66"	24"	30"	1 1/4"	DCE1L4866SDN	1,010.	1,162.
	48"	66"	30"	24"	1 1/4"	DCE1L4866DSN	1,010.	1,162.
	48"	72"	24"	24"	1 1/4"	DCE1L4872SSN	1,051.	1,208.
	48"	72"	24"	30"	1 1/4"	DCE1L4872SDN	1,057.	1,217.
	48"	72"	30"	24"	1 1/4"	DCE1L4872DSN	1,057.	1,217.
	48"	78"	24"	24"	1 1/4"	DCE1L4878SSN	1,158.	1,333.
	48"	84"	24"	24"	1 1/4"	DCE1L4884SSN	1,302.	1,499.
	60"	42"	24"	24"	1 1/4"	DCE1L6042SSN	966.	1,111.
	60"	48"	24"	24"	1 1/4"	DCE1L6048SSN	979.	1,124.
	60"	48"	24"	30"	1 1/4"	DCE1L6048SDN	959.	1,105.
	60"	48"	30"	24"	1 1/4"	DCE1L6048DSN	959.	1,105.
	66"	42"	24"	24"	1 1/4"	DCE1L6642SSN	991.	1,141.
	66"	48"	24"	24"	1 1/4"	DCE1L6648SSN	1,014.	1,165.
	66"	48"	24"	30"	1 1/4"	DCE1L6648SDN	1,010.	1,162.
	66"	48"	30"	24"	1 1/4"	DCE1L6648DSN	1,010.	1,162.
	72"	42"	24"	24"	1 1/4"	DCE1L7242SSN	1,028.	1,184.
	72"	48"	24"	24"	1 1/4"	DCE1L7248SSN	1,051.	1,208.
	72"	48"	24"	30"	1 1/4"	DCE1L7248SDN	1,057.	1,217.
	72"	48"	30"	24"	1 1/4"	DCE1L7248DSN	1,057.	1,217.
	78"	42"	24"	24"	1 1/4"	DCE1L7842SSN	1,041.	1,195.
78"	48"	24"	24"	1 1/4"	DCE1L7848SSN	1,158.	1,333.	
84"	48"	24"	24"	1 1/4"	DCE1L8448SSN	1,302.	1,499.	

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code





Worksurfaces	
Example:	DCE1L4872SDG,114
DCE1	Dividends Cascade Edge worksurface
L	Blended “L”
48	Width
72	Depth
S	24”d, left side
D	30”d, right side
G	Grommet
114	Folkstone Grey

Included with:

Available Colors:	
Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice
Woodgrain:	
124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options

- Worksurfaces**
- Center-Located Edge Grommet
To specify, replace the “N” suffix from the pattern number with “G”.
Add \$44.
- Note:** Specify the panel-to-worksurface brackets separately.
- Shaded area on worksurface drawings represents cascade edge detail.

description	w	d	t	pattern no.	Solid	Woodgrain
 Half Round	48"	18"	1 1/4"	DCE1H4818	\$503.	\$579.
	48"	18"	1 1/4"	DCE1H4818P	503.	579.
	60"	24"	1 1/4"	DCE1H6024	692.	798.
	60"	24"	1 1/4"	DCE1H6024P	692.	798.
 LH Corner Round	24"	24"	1 1/4"	DCE1CR24L	268.	308.
 RH Corner Round	24"	24"	1 1/4"	DCE1CR24R	268.	308.
 Notched Corner Round	24"	24"	1 1/4"	DCE1CR24N	268.	308.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example:	DCE1H4818P,117
DCE1	Dividends Cascade Edge worksurface
H	Half Round
48	Width
18	Depth
P	Notched for panel
117	Soft Grey

Included with:



Available Colors:	
Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice
Woodgrain:	
124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options

P= Notched for panel

Note: Specify all support brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

description	1	2	3	A	B	t	pattern no.	Solid	Woodgrain
Wave End, RH 	36"	30"	24"	3"	15"	1 1/4"	DCE1W362430N	\$626.	\$720.
	42"	30"	24"	9"	15"	1 1/4"	DCE1W422430N	658.	757.
	48"	30"	24"	15"	15"	1 1/4"	DCE1W482430N	705.	811.
	72"	30"	24"	30 1/2"	23 1/2"	1 1/4"	DCE1W722430N	897.	1,030.
<i>shown with grommet</i>									
Wave End, LH 	36"	24"	30"	15"	3"	1 1/4"	DCE1W363024N	626.	720.
	42"	24"	30"	15"	9"	1 1/4"	DCE1W423024N	658.	757.
	48"	24"	30"	15"	15"	1 1/4"	DCE1W483024N	705.	811.
	72"	24"	30"	23 1/2"	30 1/2"	1 1/4"	DCE1W723024N	897.	1,030.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example:	DCE1W483024N,118
DCE1	Dividends Cascade
	Edge worksurface
W	Wave End
48	Width
30	30"d, left side
24	24"d, right side
N	No grommet
118	Bright White

Included with:

Available Colors:	
Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice
Woodgrain:	
124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options

- Worksurfaces**
- Center-Located Edge Grommet
To specify, replace the "N" suffix from the pattern number with "G".
Add \$21.
- Note:** Specify all support brackets separately.
- Shaded area on worksurface drawings represents cascade edge detail.

This page intentionally left blank

Worksurface Supports

Worksurfaces are shipped without supports which must be ordered separately.

A variety of worksurface supports are available. They include:

- Cantilevers
- Flat brackets
- Panel-to-worksurface brackets

In addition, freestanding pedestals and end units can also be used for worksurface support.

Cantilevers and panel-to-worksurface brackets are used strictly in panel-mount applications while flat brackets, pedestals and end units can be used in both panel-mounted and freestanding applications.

Cantilevers

Cantilevers provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary cantilever applications include:

- Corner worksurfaces
- Worksurface mid-span support
- 18" and 24" deep rectangular worksurface support in moderate load situations

Note: For heavy load applications, panel-to-worksurface brackets, freestanding pedestal, panel-mount C-leg, or open support leg is recommended. In applications involving 30" deep worksurfaces, cantilevers are only recommended for mid-span support.

Cantilevers are left- and right-handed and are available in three depths (18", 24" and 30") to support 18", 24" and 30" deep worksurfaces.

Note: 36" deep worksurfaces cannot be supported by cantilevers.

- **Attachment:** Cantilevers lock into the panel's slotted standard and adjust vertically in 1 1/2" increments. Cantilevers are left- or right-handed
- **Construction:** 14-gauge, black painted steel

Flat Brackets

Flat brackets are used to join a primary worksurface with an adjacent return or bridge unit worksurface at the same height.

Flat brackets are available in three depths to support 18", 24" and 30" deep worksurface returns.

- **Attachment:** Flat brackets attach to pre-drilled positions on the undersides of worksurfaces with provided screws
- **Construction:** 14-gauge painted steel

Shared Cantilevers

Adjacent worksurfaces can share a single cantilever if the appropriate flat bracket is used in conjunction with the appropriate cantilever (i.e. 18" cantilever with 18" flat bracket).

Panel-to-Worksurface Brackets, Worksurface Support

Panel-to-worksurface brackets are used to:

- Mount worksurfaces perpendicular to panels
- Anchor the rear corner of corner worksurfaces to panels
- Secure a panel to a pedestal

Panel-to-worksurface brackets provide the most secure panel-hung support for heavily loaded worksurfaces.

Panel worksurface brackets are handed left or right.

Note: The panel width must match the worksurface depth for panel-to-worksurface brackets to connect worksurfaces perpendicular to panels.

- **Attachment:** Panel-to-worksurface brackets lock into the panel's slotted standard and adjust vertically in 1 1/2" increments
- **Construction:** 14-gauge painted steel

Panel-to-Worksurface Brackets, Stabilizing Support

Panel-to-worksurface brackets are also used in conjunction with pedestals to stabilize panel runs.

In applications where the worksurface is "wrapped" with a return panel and a pedestal is installed below the worksurface at the "wrapped" end, a panel-to-worksurface bracket is used at the front corner of the worksurface. In pedestal applications, the panel-to-worksurface bracket connects the pedestal at the rear corner of the pedestal to the panel (as shown in the illustration below) or front corner of the pedestal to the panel when a return wing panel is used.


Panel-to-Worksurface Brackets, Off-Module Support

For applications where the width of the panel exceeds the depth of the worksurface, specify off-module panel-to-worksurface brackets which allow off module worksurface support.


Worksurface Reinforcement

Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.


Panel Mounted Worksurface Bracket Application




Flat Bracket Application




Shared Cantilever Application




Stabilizing Support



Off-Module Support










Worksurface Reinforcement Panel Hung Application



Panel Mounted Worksurface Brackets

Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets

Dividends Horizon

description	type	w	d	h	pattern no.	black	P1	P2	P3	list
Cantilever Bracket Left or Right (Left Shown) (package of 10) 	For 18"D WS	1 ⁵ / ₁₆ "	12 ³ / ₁₆ "	11 ¹³ / ₁₆ "	DB1C 18 (L or R) 10	\$434.	\$456.	\$476.	\$499.	
	For 24"D WS	1 ⁵ / ₁₆ "	20 ⁵ / ₈ "	10 ¹ / ₂ "	DB1C 24 (L or R) 10	541.	567.	594.	623.	
	For 30"D WS	1 ⁵ / ₁₆ "	26 ¹⁵ / ₁₆ "	10 ¹ / ₂ "	DB1C 30 (L or R) 10	772.	811.	848.	888.	
Cantilever Brackets, Left or Right (Left Shown) (single pack) 	For 18"D WS	1 ⁵ / ₁₆ "	12 ³ / ₁₆ "	11 ¹³ / ₁₆ "	DB1C18 (L or R)	53.	55.	58.	59.	
	For 24"D WS	1 ⁵ / ₁₆ "	20 ⁵ / ₈ "	10 ¹ / ₂ "	DB1C24 (L or R)	68.	73.	78.	80.	
	For 30"D WS	1 ⁵ / ₁₆ "	26 ¹⁵ / ₁₆ "	10 ¹ / ₂ "	DB1C30 (L or R)	95.	100.	106.	111.	
Cantilever Brackets for 120° Planning (Left Shown)(single pack) 		20 ⁵ / ₈ "		1 ⁵ / ₁₆ "	DB120C (L or R)	68.	73.	78.	80.	
Flat Bracket (single pack) 	For 18"D WS	3 ³ / ₄ "	8 ⁵ / ₁₆ "		DB1F18SP	27.	n/a	n/a	n/a	27.
	For 24"D WS	3 ³ / ₄ "	14 ⁵ / ₈ "		DB1F24SP	31.	n/a	n/a	n/a	31.
	For 30"D WS	3 ³ / ₄ "	20 ¹⁵ / ₁₆ "		DB1F30SP	35.	n/a	n/a	n/a	35.
Flat Bracket (package of 10) 	For 18"D WS	3 ³ / ₄ "	8 ⁵ / ₁₆ "		DB1F18TP	147.	n/a	n/a	n/a	147.
	For 24"D WS	3 ³ / ₄ "	14 ⁵ / ₈ "		DB1F24TP	244.	n/a	n/a	n/a	244.
	For 30"D WS	3 ³ / ₄ "	20 ¹⁵ / ₁₆ "		DB1F30TP	281.	n/a	n/a	n/a	281.
Worksurface Reinforcement 		54"	4"		DB1WR54	71.	n/a	n/a	n/a	71.
		60"	4"		DB1WR60	72.	n/a	n/a	n/a	72.
		66"	4"		DB1WR66	75.	n/a	n/a	n/a	75.
		72"	4"		DB1WR72	78.	n/a	n/a	n/a	78.
Panel-to-Worksurface Brackets 	Left (Shown)	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSL	9.	9.	10.	11.	
	Right	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSR	9.	9.	10.	11.	
	Pair	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSP	19.	19.	23.	27.	

Worksurface Supports

Ordering Information

Panel-to-Worksurface Bracket, Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket, Off Module

Example: **DB1P WS36, 113**

DB1P	Pattern Number
WS36	
113	Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket, Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket, Off Module

Panel Mounted Worksurface Brackets

Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets

Dividends Horizon


description	type	w	d	h	pattern no.	black	P1	P2	P3	list
Panel-to-Worksurface Brackets (package of 10)	Left (Shown)	3"	3"	4 ^{11/16} "	DB1PWSL10	\$81.	\$81.	\$91.	\$103.	
	Right	3"	3"	4 ^{11/16} "	DB1PWSR10	81.	81.	91.	103.	




Panel-to-Worksurface Brackets for use with Worksurface Height Panels ONLY	Left	3"	3"	4 ^{11/16} "	DB1PWSLWH	27.	29.	31.	33.	
	Right	3"	3"	4 ^{11/16} "	DB1PWSRWH	27.	29.	31.	33.	
	Pair	3"	3"	4 ^{11/16} "	DB1PWSPWH	50.	54.	59.	65.	



Panel-to-Worksurface Brackets (Off Module)	For 24" Wide Panel				DB1PWS24	n/a	75.	81.	83.	
	For 30" Wide Panel				DB1PWS30	n/a	79.	85.	89.	
	For 36" Wide Panel				DB1PWS36	n/a	82.	89.	93.	
	For 42" Wide Panel				DB1PWS42	n/a	87.	98.	105.	
	For 48" Wide Panel				DB1PWS48	n/a	93.	105.	109.	



Layered Cantilever Assembly Left or Right					DBVDC (L or R)	96.	101.	108.	112.	n/a
---	--	--	--	--	-----------------------	-----	------	------	------	-----



Right hand shown

Ordering Information	Order Code	Included with:	Options
Panel-to-Worksurface Bracket, Off Module 1. Pattern Number 2. Trim Finish	Panel-to-Worksurface Bracket, Off Module <i>Example:</i> DB1P WS36, 113 <hr/> DB1P Pattern Number WS36 <hr/> 113 Dark Grey Finish	Panel-to-Worksurface Bracket, Off Module <ul style="list-style-type: none"> • Trim finish mounting rail • Worksurface brackets 	Panel-to-Worksurface Bracket, Off Module

This page intentionally left blank

Screen-to-Worksurface Brackets, Worksurface Support

Screen-to-worksurface brackets are used to:

- Mount worksurfaces perpendicular to screens
- Anchor the rear corner of corner worksurfaces to screens


Screen-to-worksurface brackets provide the most secure screen-hung support for heavily loaded worksurfaces.

Screen worksurface brackets are handed left or right.


Note: The screen width must match the worksurface depth for screen-to-worksurface brackets to connect worksurfaces perpendicular to screens.

- **Attachment:** Screen-to-worksurface brackets lock into the screen's slotted standard and adjust vertically in 1 1/2" increments
- **Construction:** 14-gauge painted steel

Screen-to-Worksurface Support Application



Screen-to-Worksurface Brackets



Screen-to-Worksurface Brackets

Screen mid-span worksurface support

description	type	w	d	h	pattern no.	P1	P2	P3
Screen-to-Worksurface Brackets (Individual)	Left				DB1SWSL	\$7.	\$9.	\$12.
	Right				DB1WSR	7.	9.	12.



Left hand shown

Screen-to-Worksurface Brackets (Pair)	Left/Right				DB1SWSP	33.	35.	37.
--	------------	--	--	--	----------------	-----	-----	-----

Screen Mid-Span Worksurface Support	left hand				DBSMLH	29.	30.	31.
	right hand				DBSMRH	29.	30.	31.



Left hand shown

Ordering Information

Panel-to-Worksurface Bracket, Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket, Off Module

Example: **DB1P WS36, 113**

DB1P Pattern Number

WS36

113 Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket, Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket, Off Module

Panel-Mounted C-Legs, Open Support Legs, and Worksurface End Panels

Panel-mounted C-legs, open support legs, and worksurface end panels provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary panel-mounted support applications include:

- Rectangular worksurface end support for 24" and 30" depth worksurfaces
- Mid span worksurface support for 24" and 30" depth worksurfaces
- Corner and split top corner worksurface support
- Support for heavier worksurface load applications
- Shared support between two adjacent worksurfaces

Note: 18" deep and 36" worksurface may not be used with panel-mounted C-leg worksurface support.

Construction

C-leg support:

- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: $\frac{3}{16}$ " steel plate

Open Support Leg:

- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: $\frac{3}{16}$ " steel plate

Worksurface End Panel:


- Panel: 20 gauge steel
- Mounting brackets: 14 gauge steel

Note: Open support legs and worksurface end panels are only available in Knoll Core finishes


Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used on the end of a panel run.

Note: Worksurface end panels are for use with panels only and are non-handed.


Panel-Mounted C-Leg Support




Panel-Mounted C-Leg Support (radiused foot)



Open Support Leg



Worksurface End Panel



Panel Mounted Worksurface Supports

Open Support Leg, C-Leg and Worksurface End Panel

Dividends Horizon

description	type	w	d	h	pattern no.	P1	P2	P3
Panel Mounted C-Leg Worksurface Support (Left-hand shown)	Left-hand C-Leg			26 ⁷ / ₈ "	DB1CL24L	\$375.	\$412.	\$429.
	Right-hand C-Leg			26 ⁷ / ₈ "	DB1CL 24R	375.	412.	429.
	Shared C-Leg			26 ⁷ / ₈ "	DB1CL24S	396.	436.	458.
Panel Mounted C-Leg Worksurface Support Radiused Foot (Right-hand shown)	LH Shared Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24LS	470.	520.	541.
	LH Single Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24L	446.	490.	512.
	RH Shared Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24RS	470.	520.	541.
	RH Single Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24R	446.	490.	512.
Open Support Leg Panel Attachment		3"	15"	26 ⁷ / ₈ "	DB1LSP15()	358.	380.	395.
		3"	18"	26 ⁷ / ₈ "	DB1LSP18()	358.	380.	395.
		3"	24"	26 ⁷ / ₈ "	DB1LSP24()	353.	373.	391.
		3"	30"	26 ⁷ / ₈ "	DB1LSP30()	371.	388.	409.
		3"	36"	26 ⁷ / ₈ "	DB1LSP36()	392.	412.	429.
Open Support Leg Screen Attachment		3"	15"	26 ⁷ / ₈ "	DB1LSS15()	358.	380.	395.
		3"	18"	26 ⁷ / ₈ "	DB1LSS18()	358.	380.	395.
		3"	24"	26 ⁷ / ₈ "	DB1LSS24()	353.	373.	391.
		3"	30"	26 ⁷ / ₈ "	DB1LSS30()	371.	388.	409.
		3"	36"	26 ⁷ / ₈ "	DB1LSS36()	392.	412.	429.
Worksurface End Panel Panel Attachment		1 ¹ / ₄ "	15"	26 ⁷ / ₈ "	DB1PSP15	327.	357.	377.
		1 ¹ / ₄ "	18"	26 ⁷ / ₈ "	DB1PSP18	340.	375.	391.
		1 ¹ / ₄ "	19"	26 ⁷ / ₈ "	DB1PSP19	356.	385.	403.
		1 ¹ / ₄ "	24"	26 ⁷ / ₈ "	DB1PSP24	373.	411.	428.
		1 ¹ / ₄ "	30"	26 ⁷ / ₈ "	DB1PSP30	400.	442.	462.
		1 ¹ / ₄ "	36"	26 ⁷ / ₈ "	DB1PSP36	427.	470.	491.

Ordering Information

Panel-Mounted C-Leg Worksurface Support

1. Pattern Number
2. Paint Finish

Worksurface End Panel

1. Pattern Number
2. Paint Finish

Open Support Leg

1. Pattern Number
2. Paint Finish

Order Code

Panel Mounted C-Leg Worksurface Support

Example: **DB1 CL24R, 117**

DB1 Pattern Number

CL24R

117 Soft Grey finish

Worksurface End Panel

Example: **DB1 PSP 24**

DB1 PSP Pattern Number

24

117 Soft Grey finish

Included with:

Panel-Mounted C-Leg Worksurface Support

- C-leg foot
- C-leg column
- Panel attachment bracket
- C-leg flat bracket
- Leveling glides

Worksurface End Panel

- Panel attachment bracket
- Leveling glides

Note: Open Support Legs are only available in Knoll core finishes.

Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used at the end of a panel run.

Options

Open Support Leg Option

- (R) = Right-hand leg
(L) = Left-hand leg
(S) = Shared leg

Note: Worksurface end panels are for use with panels only.

Round Support Column

4" diameter round column may be used to support the rounded end of panel-mounted curvilinear half-round, "D", "P", "9", and blended "D" peninsula tops. Column is available in all Knoll core paint finishes

Construction

- Material: 4" diameter steel tube
- Mounting bracket: heavy gauge steel plate, 6 x 6

T-Support Column

The T-support column may be used to support the rounded end of a panel-mounted curvilinear half-round, "D", "P", "9", and blended "D" peninsula tops. The T-support column is recommended for use with "D" peninsula worksurfaces used in freestanding applications. The T-support column is available in all Dividends paint finishes.

Construction

T-support column specifications:

- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: heavy gauge steel plate

T-End Unit

The T-end unit is used on the end of a freestanding "D" peninsula worksurface top. The T-end is available in a depth of 24" and 30" for use with "D", "P" and "9" top depths of 24" and 30".

Construction

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel

A Leg


An A leg may be used to support panel mounted curvilinear half-round, "D", "P", "9" and blended "D" peninsula tops. A legs are available in any Knoll Core paint finish.

Construction


- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: 14 gauge steel

Note: A legs are only available in Knoll Core finishes


Round Column with Panel "D" Worksurface




T-Support Base with Panel "D" Worksurface



T-End Unit with Freestanding "D" Worksurface








A-Leg with Panel "D" Worksurface



Peninsula Worksurface Supports

Round Support Column, T-Support Base and A Leg

Dividends Horizon

description	w	d	h	pattern no.	P1	P2	P3
 T-End Unit	21 ¹³ / ₁₆ "	12"	26 ⁷ / ₈ "	DD1TEU24	\$353.	\$390.	\$409.
	27 ¹³ / ₁₆ "	12"	26 ⁷ / ₈ "	DD1TEU30	388.	425.	445.
 T-Support Base	23 ¹ / ₂ "	12"	26 ⁷ / ₈ "	DB1TB	334.	368.	383.
 Round Support Column	4"	4"	26 ⁷ / ₈ "	DB1S CR	288.	301.	323.
 A Leg	3"	15"	26 ⁷ / ₈ "	DB1LS15A	379.	417.	432.
	3"	18"	26 ⁷ / ₈ "	DB1LS18A	391.	429.	447.
	3"	24"	26 ⁷ / ₈ "	DB1LS24A	403.	444.	462.
	3"	30"	26 ⁷ / ₈ "	DB1LS30A	418.	458.	475.
	3"	36"	26 ⁷ / ₈ "	DB1LS36A	427.	470.	489.
 2.5" Round Support Column				DBSCR	288.	301.	323.

Dimensions listed under w d t are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
T-End Unit 1. Pattern Number 2. Paint Finish	T-End Unit <i>Example:</i> DD1TEU24, 115 DD1TEU24 Pattern Number 115 Medium Grey Paint Finish	T-End Unit • Worksurface T-Support Base Note: The A leg is for use in peninsula worksurface applications only. It is not to be used in freestanding applications. Note: A Legs are only available in Knoll core finishes.	T-End Unit T-Support Base A Leg Round Support Column
T-Support Base 1. Pattern Number 2. Paint Finish	T-Support Base <i>Example:</i> DB1TB, 115 DB1TB Pattern Number 115 Medium Grey Paint Finish		
A Leg 1. Pattern Number 2. Paint Finish			
Round Support Column 1. Pattern Number 2. Paint Finish	Round Support Column <i>Example:</i> DB1SCR, 118 DB1SCR Pattern Number 118 Bright White Paint Finish		

Y Leg Tables

Freestanding and Credenza Supported Specifications

Dividends Horizon Tables

The design details of Dividends Horizon tables are consistent with the scale and visual language of the Dividends Horizon system. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon Y Leg tables are available in two versions:

- Freestanding Y Leg
- Credenza Supported Y Leg

Freestanding Y Leg Tables

Freestanding Y Leg tables include a worksurface and base assembly. All freestanding table sizes are available with two Y legs and a horizontal stretcher connecting the two columns.

In addition, 24 and 30 inch deep tables are available without a stretcher. Tables without stretcher include an integral worksurface support plate. 36 and 42 inch deep tables are available only with a stretcher.

Available Sizes

- Width: 60-96 inches
- Depth: 24-42 inches
- Height: 28-1/2 inches

Credenza Supported Y Leg Tables

The unique Dividends Horizon Credenza Supported Y Leg tables are designed to be used in concert with Dividends Horizon low credenzas, specified separately.

Credenza Supported Tables include one Y Leg, credenza support spacer, and a worksurface with integral stiffening plate.

Note: Credenza supported tables may be used with laminate or veneer top credenzas only, and are not compatible with steel top credenzas.

Available Sizes

- Width: 60-96 inches
- Depth: 24-36 inches
- Height: 28-1/2 inches

Optional Edge Grommet

Edge grommets are optional and can be factory installed centered along the rear edge of rectangular or racetrack freestanding or credenza supported Y Leg tables.


Construction

- Worksurface:
 - Material: 0.028 inch thick laminate or 0.6mm thick veneer on 1-1/8" particle board core
 - Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16 inch thick Techwood edge
- Bases:
 - Stretcher: extruded aluminum
 - Stiffening plate: 4 inch deep 12 gauge steel plate (length varies)
 - Foot: die cast aluminum
 - Column: extruded aluminum with 3/16 inch thick structural plate
 - Credenza support spacer: 2-15/16 inches high x 9-5/8 inches wide x 1-9/16 inches deep steel box with a flat bracket on top


Note: Dividends Horizon tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: The stiffening plate on tables without a stretcher prevents the field installation of a grommet or plexus box. (see illustration below)


24" Deep Freestanding Racetrack Y Leg Table with Stretcher



24" Deep Credenza Supported Racetrack Y Leg Table



24" Deep Freestanding Racetrack Y Leg Table without Stretcher




Y Leg Tables

Freestanding Rectangular Table Top


24" and 30" Deep

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
24" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6024NS	\$1,774.	\$1,954.	\$2,032.	\$2,034.	\$2,236.	\$2,329.
	66"	65 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6624NS	1,795.	1,976.	2,053.	2,064.	2,275.	2,366.
	72"	71 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7224NS	1,813.	1,997.	2,078.	2,100.	2,310.	2,403.
	78"	77 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7824NS	1,836.	2,017.	2,098.	2,136.	2,349.	2,443.
	84"	83 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8424NS	1,869.	2,054.	2,138.	2,171.	2,387.	2,482.
	90"	89 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9024NS	1,900.	2,093.	2,176.	2,202.	2,425.	2,519.
	96"	95 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9624NS	1,935.	2,130.	2,213.	2,235.	2,459.	2,560.



(with stretcher shown)

30" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6030NS	1,820.	2,003.	2,085.	2,080.	2,286.	2,377.
	66"	65 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6630NS	1,846.	2,032.	2,113.	2,118.	2,330.	2,423.
	72"	71 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7230NS	1,871.	2,057.	2,141.	2,156.	2,373.	2,469.
	78"	77 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7830NS	1,896.	2,088.	2,172.	2,197.	2,416.	2,513.
	84"	83 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8430NS	1,933.	2,128.	2,211.	2,235.	2,459.	2,560.
	90"	89 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9030NS	1,968.	2,166.	2,252.	2,276.	2,501.	2,603.
	96"	95 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9630NS	2,004.	2,205.	2,292.	2,316.	2,546.	2,649.



(with stretcher shown)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Y Leg Table: 1. Pattern number 2. Base/Stretcher Paint Finish 3. Top Finish 4. Edge Finish	Freestanding Y Leg Table: <i>Example:</i> DT1ARY6024NS, 114, 114 DT1 Dividends Horizon Table A 2 Leg table assembly R Rectangular shape Y Y Leg Base 60 Overall width in inches 24 Overall depth in inches N No grommet S Stretcher 114 Base/ stretcher paint finish 114 Laminate top finish 114 Edgeband finish	Freestanding Y Leg Table: <ul style="list-style-type: none"> (2) Y Legs Hardware kit Table top Stretcher or stiffening plate Note: Y Leg tables are finished with textured paint, including 613 Silver. Note: Y Leg Tables are only available in Knoll core finishes.	Grommet Option: <ul style="list-style-type: none"> To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18. Stretcher Option: <ul style="list-style-type: none"> A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from the pattern number with an "N". Stretchers are required on 36" and 42" depths.


Y Leg Tables

Freestanding Rectangular Table Top


36" and 42" Deep

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
36" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6036N	\$1,882.	\$2,066.	\$2,150.	\$2,172.	\$2,388.	\$2,482.
	66"	65 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6636N	1,915.	2,104.	2,189.	2,212.	2,435.	2,531.
	72"	71 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7236N	1,946.	2,141.	2,228.	2,255.	2,481.	2,580.
	78"	77 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7836N	1,979.	2,178.	2,264.	2,297.	2,528.	2,629.
	84"	83 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8436N	2,011.	2,213.	2,302.	2,341.	2,574.	2,676.
	90"	89 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9036N	2,044.	2,249.	2,340.	2,384.	2,623.	2,725.
	96"	95 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9636N	2,080.	2,286.	2,377.	2,427.	2,669.	2,773.



42" Deep Rectangular with (2) Y-Legs, No Grommet	84"	83 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8442N	2,062.	2,272.	2,364.	2,619.	2,880.	2,998.
	90"	89 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9042N	2,107.	2,319.	2,412.	2,656.	2,921.	3,038.
	96"	95 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9642N	2,140.	2,355.	2,448.	2,691.	2,960.	3,078.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Y Leg Table: 1. Pattern number 2. Base/Stretcher Paint Finish 3. Top Finish 4. Edge Finish	Freestanding Y Leg Table: <i>Example:</i> DT1ARY6024NS, 114, 114 DT1 Dividends Horizon Table A 2 Leg table assembly R Rectangular shape Y Y Leg Base 60 Overall width in inches 24 Overall depth in inches N No grommet S Stretcher 114 Base/ stretcher paint finish 114 Laminate top finish 114 Edgeband finish	Freestanding Y Leg Table: <ul style="list-style-type: none"> • (2) Y Legs • Hardware kit • Table top • Stretcher or stiffening plate Note: Y Leg tables are finished with textured paint, including 613 Silver. Note: Y Leg Tables are only available in Knoll core finishes.	Grommet Option: <ul style="list-style-type: none"> • To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18. Stretcher Option: <ul style="list-style-type: none"> • A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from the pattern number with an "N". Stretchers are required on 36" and 42" depths.

Y Leg Tables

Freestanding Racetrack Table Top

24" and 30" Deep

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
24" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6024NS	\$1,773.	\$1,953.	\$2,031.	\$3,167.	\$3,483.	\$3,625.
	66"	65 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6624NS	1,831.	2,011.	2,093.	3,197.	3,515.	3,657.
	72"	71 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7224NS	1,884.	2,073.	2,154.	3,224.	3,550.	3,690.
	78"	77 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7824NS	1,938.	2,133.	2,217.	3,255.	3,583.	3,723.
	84"	83 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8424NS	1,972.	2,170.	2,255.	3,283.	3,612.	3,757.
	90"	89 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9024NS	2,004.	2,205.	2,292.	3,313.	3,644.	3,791.
	96"	95 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9624NS	2,039.	2,242.	2,333.	3,343.	3,676.	3,824.



(with stretcher shown)

30" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6030NS	1,844.	2,027.	2,109.	3,214.	3,537.	3,678.
	66"	65 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6630NS	1,895.	2,087.	2,170.	3,246.	3,570.	3,714.
	72"	71 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7230NS	1,947.	2,141.	2,228.	3,276.	3,604.	3,750.
	78"	77 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7830NS	1,999.	2,198.	2,286.	3,309.	3,640.	3,787.
	84"	83 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8430NS	2,037.	2,240.	2,330.	3,342.	3,675.	3,822.
	90"	89 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9030NS	2,074.	2,281.	2,372.	3,373.	3,710.	3,858.
	96"	95 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9630NS	2,110.	2,323.	2,414.	3,403.	3,744.	3,895.



(with stretcher shown)

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Freestanding Y Leg Table:	Freestanding Y Leg Table:	Freestanding Y Leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1ATY6024NS, 114, 114	<ul style="list-style-type: none"> (2) Y Legs Hardware kit Table top Stretcher or stiffening plate 	<ul style="list-style-type: none"> To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Note: Y Leg tables are finished with textured paint, including 613 Silver.	Stretcher Option:
3. Top Finish	A 2 Leg table assembly	Note: Y Leg Tables are only available in Knoll core finishes.	<ul style="list-style-type: none"> A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from pattern number with an "N". Stretchers are required on 36" and 42" depths.
4. Edge Finish	T Racetrack shape		
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches		
	N No grommet		
	S Stretcher		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		


Y Leg Tables

Freestanding Racetrack Table Top


36" and 42" Deep

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
36" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6036N	\$1,906.	\$2,098.	\$2,182.	\$3,261.	\$3,588.	\$3,732.
	66"	65 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6636N	1,967.	2,163.	2,249.	3,297.	3,625.	3,770.
	72"	71 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7236N	2,025.	2,229.	2,318.	3,329.	3,662.	3,811.
	78"	77 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7836N	2,087.	2,292.	2,386.	3,363.	3,700.	3,849.
	84"	83 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8436N	2,118.	2,331.	2,423.	3,398.	3,737.	3,889.
	90"	89 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9036N	2,151.	2,367.	2,460.	3,431.	3,777.	3,928.
	96"	95 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9636N	2,184.	2,402.	2,498.	3,466.	3,814.	3,966.



42" Deep Racetrack with (2) Y-Legs, No Grommet	84"	83 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8442N	2,170.	2,386.	2,480.	3,458.	3,805.	3,955.
	90"	89 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9042N	2,210.	2,433.	2,529.	3,495.	3,844.	3,995.
	96"	95 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9642N	2,249.	2,476.	2,573.	3,528.	3,883.	4,039.



w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"


Ordering Information	Order Code	Included With	Options
Freestanding Y Leg Table: 1. Pattern number 2. Base/Stretcher Paint Finish 3. Top Finish 4. Edge Finish	Freestanding Y Leg Table: <i>Example:</i> DT1ATY6024NS, 114, 114 DT1 Dividends Horizon Table A 2 Leg table assembly T Racetrack shape Y Y Leg Base 60 Overall width in inches 24 Overall depth in inches N No grommet S Stretcher 114 Base/ stretcher paint finish 114 Laminate top finish 114 Edgeband finish	Freestanding Y Leg Table: <ul style="list-style-type: none"> (2) Y Legs Hardware kit Table top Stretcher or stiffening plate Note: Y Leg tables are finished with textured paint, including 613 Silver. Note: Y Leg Tables are only available in Knoll core finishes.	Grommet Option: <ul style="list-style-type: none"> To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18. Stretcher Option: <ul style="list-style-type: none"> A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from pattern number with an "N". Stretchers are required on 36" and 42" depths.

Y Leg Tables

Credenza Supported Rectangular Table Top


24", 30" and 36" deep

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
24" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6024N	\$1,483.	\$1,633.	\$1,698.	\$1,739.	\$1,914.	\$1,988.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6624N	1,502.	1,653.	1,720.	1,771.	1,949.	2,026.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7224N	1,522.	1,674.	1,743.	1,805.	1,985.	2,063.
	78"	77 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7824N	1,540.	1,696.	1,763.	1,841.	2,024.	2,104.
	84"	83 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8424N	1,574.	1,732.	1,802.	1,875.	2,059.	2,143.
	90"	89 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9024N	1,611.	1,768.	1,841.	1,906.	2,098.	2,181.
	96"	95 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9624N	1,643.	1,806.	1,880.	1,941.	2,136.	2,221.




(credenza not included)

30" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6030N	1,527.	1,678.	1,746.	1,785.	1,961.	2,040.
	66"	65 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6630N	1,551.	1,706.	1,773.	1,823.	2,005.	2,087.
	72"	71 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7230N	1,576.	1,733.	1,803.	1,863.	2,049.	2,131.
	78"	77 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7830N	1,602.	1,762.	1,835.	1,900.	2,093.	2,176.
	84"	83 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8430N	1,639.	1,802.	1,875.	1,941.	2,136.	2,221.
	90"	89 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9030N	1,674.	1,843.	1,918.	1,980.	2,179.	2,264.
	96"	95 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9630N	1,711.	1,884.	1,958.	2,018.	2,222.	2,309.



(credenza not included)

36" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6036N	1,619.	1,782.	1,850.	1,905.	2,097.	2,181.
	66"	65 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6636N	1,648.	1,812.	1,887.	1,946.	2,141.	2,226.
	72"	71 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7236N	1,679.	1,847.	1,921.	1,984.	2,183.	2,272.
	78"	77 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7836N	1,710.	1,882.	1,956.	2,025.	2,228.	2,317.
	84"	83 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8436N	1,752.	1,928.	2,004.	2,062.	2,270.	2,361.
	90"	89 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9036N	1,795.	1,975.	2,053.	2,104.	2,315.	2,406.
	96"	95 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9636N	1,839.	2,022.	2,101.	2,143.	2,357.	2,451.



(credenza not included)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest¹/₁₆"


Ordering Information	Order Code	Included with	Options
Credenza Supported Y Leg Table:	Credenza Supported Y Leg Table:	Credenza Supported Y leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1CRY6024N, 114, 114	<ul style="list-style-type: none"> (1) Y Leg (1) Credenza support spacer Hardware kit Table top Stiffening plate 	<ul style="list-style-type: none"> To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Credenza must be specified separately	Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.
3. Top Finish	C Credenza support assembly	Note: Y Leg tables are finished with textured paint, including 613 Silver.	
4. Edge Finish	R Rectangular shape	Note: Y Leg Tables are only available in Knoll core finishes.	
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Y Leg Tables

Credenza Supported Racetrack Table Top


24", 30" and 36" deep

description	w*	w	d	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY6024N	\$1,481.	\$1,629.	\$1,696.	\$2,900.	\$3,188.	\$3,275.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY6624N	1,536.	1,689.	1,757.	2,915.	3,208.	3,303.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY7224N	1,591.	1,750.	1,818.	2,930.	3,224.	3,326.
	78"	77 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY7824N	1,645.	1,808.	1,883.	2,949.	3,244.	3,352.
	84"	83 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY8424N	1,664.	1,831.	1,901.	2,962.	3,261.	3,377.
	90"	89 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY9024N	1,681.	1,849.	1,923.	2,980.	3,277.	3,401.
	96"	95 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY9624N	1,699.	1,870.	1,943.	2,997.	3,298.	3,427.




(credenza not included)

30" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY6030N	1,551.	1,706.	1,773.	2,917.	3,209.	3,316.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY6630N	1,603.	1,763.	1,836.	2,951.	3,245.	3,356.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY7230N	1,655.	1,818.	1,892.	2,981.	3,280.	3,398.
	78"	77 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY7830N	1,706.	1,878.	1,953.	3,013.	3,316.	3,437.
	84"	83 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY8430N	1,744.	1,918.	1,996.	3,048.	3,352.	3,477.
	90"	89 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY9030N	1,782.	1,958.	2,037.	3,078.	3,389.	3,518.
	96"	95 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY9630N	1,815.	1,999.	2,081.	3,112.	3,423.	3,560.



(credenza not included)

36" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY6036N	1,642.	1,805.	1,879.	2,934.	3,227.	3,356.
	66"	65 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY6636N	1,699.	1,870.	1,943.	2,984.	3,281.	3,413.
	72"	71 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY7236N	1,757.	1,933.	2,010.	3,032.	3,336.	3,468.
	78"	77 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY7836N	1,813.	1,997.	2,078.	3,082.	3,390.	3,522.
	84"	83 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY8436N	1,856.	2,042.	2,126.	3,129.	3,443.	3,583.
	90"	89 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY9036N	1,898.	2,089.	2,173.	3,178.	3,497.	3,637.
	96"	95 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY9636N	1,940.	2,135.	2,220.	3,226.	3,551.	3,693.



(credenza not included)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with	Options
Credenza Supported Y Leg Table: 1. Pattern number 2. Base/Stretcher Paint Finish 3. Top Finish 4. Edge Finish	Credenza Supported Y Leg Table: <i>Example:</i> DT1CTY6024N, 114, 114 <hr/> DT1 Dividends Horizon Table <hr/> C Credenza support assembly <hr/> T Racetrack shape <hr/> Y Y Leg Base <hr/> 60 Overall width in inches <hr/> 24 Overall depth in inches <hr/> N No grommet <hr/> 114 Base/ stretcher paint finish <hr/> 114 Laminate top finish <hr/> 114 Edgeband finish	Credenza Supported Y Leg Table: <ul style="list-style-type: none"> (1) Y Leg (1) Credenza support spacer Hardware kit Table top Stiffening plate Credenza must be specified separately Note: Y Leg tables are finished with textured paint, including 613 Silver. Note: Y Leg Tables are only available in Knoll core finishes.	Grommet Option: <ul style="list-style-type: none"> To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18. Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.

This page intentionally left blank

X Base Tables

Dividends Horizon X base tables are designed to be used along with the Dividends Horizon system to create a consistent aesthetic throughout the entire office. With various height and width options, X base tables can be used in a multitude of applications, including collaboration areas in the open plan, break rooms, and lounge areas.

Available with a round, square or rounded square top shape with either a laminate or veneer finish, a Dividends Horizon X base table is appropriate for use in a vast array of applications from the private office to the open plan and even to lounge areas. The five height options allow for the same table base to be used in various applications while maintaining visual consistency throughout the space.

X base tables include a top, support column, and X base.

Available Sizes

- Width: 30 - 48 inches
- Depth: 30 - 48 inches
- Heights: 17, 21, 28-1/2, 36, and 42 inches

Construction

• Worksurface:

- Material: 0.028" thick laminate or 0.6mm thick veneer on 1-1/8" particle board core
- Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge.

• Base:

- Foot: die cast aluminum
- Column: extruded aluminum with 3/16" thick structural plate

Table Supports

X bases may be specified separately for use with an alternative table top. The appropriate X base size must be selected according to the width of the table top being used. X bases are available in five heights and may be used with table tops that are 30 to 48 inches wide.

Available Sizes

Heights: 17, 21, 28-1/2, 36, and 42 inches

Construction

• Base:

- Foot: die cast aluminum
- Column: extruded aluminum with 3/16" thick structural plate

Note: Dividends Horizon tables are only available in Knoll Core paint and laminate finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Square X Base Table



Round X Base Table




Rounded Square X Base Table





X Base Tables


Square Table Tops


17", 21", 28", 36" and 42" High

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
 17" High Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX303017	\$1,079.	\$1,190.	\$1,238.	\$1,594.	\$1,762.	\$1,834.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX363617	1,126.	1,243.	1,293.	1,684.	1,854.	1,930.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX424217	1,251.	1,377.	1,431.	1,784.	1,962.	2,042.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX484817	1,311.	1,447.	1,503.	1,853.	2,041.	2,126.

 21" High Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX303021	1,079.	1,190.	1,238.	1,594.	1,762.	1,834.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX363621	1,126.	1,243.	1,293.	1,684.	1,854.	1,930.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX424221	1,251.	1,377.	1,431.	1,784.	1,962.	2,042.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX484821	1,311.	1,447.	1,503.	1,853.	2,041.	2,126.

 28" High Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX3030	1,106.	1,216.	1,263.	1,619.	1,787.	1,856.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX3636	1,152.	1,266.	1,316.	1,709.	1,880.	1,955.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX4242	1,273.	1,404.	1,458.	1,806.	1,987.	2,064.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX4848	1,335.	1,469.	1,529.	1,879.	2,063.	2,148.

 36" High Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX303036	1,166.	1,276.	1,326.	1,679.	1,847.	1,918.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX363636	1,213.	1,328.	1,378.	1,768.	1,940.	2,015.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX424236	1,334.	1,462.	1,519.	1,869.	2,049.	2,129.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX484836	1,397.	1,531.	1,590.	1,939.	2,128.	2,209.

 42" High Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX303042	1,189.	1,301.	1,348.	1,704.	1,872.	1,941.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX363642	1,235.	1,353.	1,405.	1,794.	1,964.	2,040.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX424242	1,362.	1,488.	1,542.	1,892.	2,074.	2,151.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX484842	1,421.	1,554.	1,615.	1,962.	2,150.	2,233.

w* = nominal width
 Dimensions listed under w d t h are actual to the nearest 1/16"






Ordering Information	Order Code	Included with:	Options
X Base Table: 1. Pattern number 2. Base Paint Finish 3. Top Finish 4. Edge Finish	X Base Table: <i>Example:</i> DT1ASX3030, 114, 114, 114 <hr/> DT1 Dividends Horizon Table <hr/> A Table assembly <hr/> S Square shape <hr/> X X Base <hr/> 30 Overall width in inches <hr/> 30 Overall depth in inches <hr/> 114 Base finish <hr/> 114 Laminate top finish <hr/> 114 Edgeband finish	X Base Table: <ul style="list-style-type: none"> • (1) X Base • Hardware kit • Table top Note: X Base Tables are finished with textured paint, including 613 Silver. Note: X Base Tables are only available in Knoll core finishes.	

X Base Tables

Round Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
 17" High Round X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX3017	\$1,090.	\$1,204.	\$1,253.	\$2,436.	\$2,680.	\$2,789.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX3617	1,136.	1,252.	1,302.	2,532.	2,788.	2,901.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX4217	1,256.	1,383.	1,441.	2,652.	2,921.	3,039.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX4817	1,316.	1,452.	1,509.	2,725.	3,001.	3,122.
 21" High Round X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX3021	1,090.	1,204.	1,253.	2,436.	2,680.	2,789.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX3621	1,136.	1,252.	1,302.	2,532.	2,788.	2,901.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX4221	1,256.	1,383.	1,441.	2,652.	2,921.	3,039.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX4821	1,316.	1,452.	1,509.	2,725.	3,001.	3,122.
 28" High Round X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX30	1,116.	1,227.	1,276.	2,459.	2,705.	2,814.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX36	1,160.	1,274.	1,327.	2,556.	2,813.	2,923.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX42	1,279.	1,410.	1,464.	2,678.	2,946.	3,065.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX48	1,342.	1,475.	1,535.	2,750.	3,025.	3,146.
 36" High Round X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX3036	1,176.	1,288.	1,336.	2,520.	2,763.	2,874.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX3636	1,220.	1,335.	1,386.	2,617.	2,873.	2,985.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX4236	1,341.	1,468.	1,525.	2,738.	3,007.	3,125.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX4836	1,405.	1,537.	1,596.	2,811.	3,087.	3,207.
 42" High Round X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX3042	1,201.	1,312.	1,364.	2,545.	2,789.	2,900.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX3642	1,246.	1,363.	1,413.	2,642.	2,898.	3,009.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX4242	1,367.	1,494.	1,548.	2,762.	3,030.	3,149.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX4842	1,426.	1,561.	1,620.	2,836.	3,111.	3,229.

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

Example: **DT1ACX3030, 114, 114, 114**

DT1	Dividends Horizon Table
A	Table assembly
C	Round shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.





Options

X Base Tables

Rounded Square Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
 17" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX303017	\$1,090.	\$1,204.	\$1,253.	\$2,436.	\$2,680.	\$2,789.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX363617	1,136.	1,252.	1,302.	2,532.	2,788.	2,901.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX424217	1,256.	1,383.	1,441.	2,652.	2,921.	3,039.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX484817	1,316.	1,452.	1,509.	2,725.	3,001.	3,122.
 21" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX303021	1,090.	1,204.	1,253.	2,436.	2,680.	2,789.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX363621	1,136.	1,252.	1,302.	2,532.	2,788.	2,901.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX424221	1,256.	1,383.	1,441.	2,652.	2,921.	3,039.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX484821	1,316.	1,452.	1,509.	2,725.	3,001.	3,122.
 28" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX3030	1,116.	1,227.	1,276.	2,459.	2,705.	2,814.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX3636	1,160.	1,274.	1,327.	2,556.	2,813.	2,923.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX4242	1,279.	1,410.	1,464.	2,678.	2,946.	3,065.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX4848	1,342.	1,475.	1,535.	2,750.	3,025.	3,146.
 36" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX303036	1,176.	1,288.	1,336.	2,520.	2,763.	2,874.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX363636	1,220.	1,335.	1,386.	2,617.	2,873.	2,985.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX424236	1,341.	1,468.	1,525.	2,738.	3,007.	3,125.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX484836	1,405.	1,537.	1,596.	2,811.	3,087.	3,207.

Tables

w* = nominal width
 Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
X Base Table: 1. Pattern number 2. Base Paint Finish 3. Top Finish 4. Edge Finish	X Base Table: <i>Example:</i> DT1ADX3030, 114, 114, 114 DT1 Dividends Horizon Table A Table assembly D Rounded Square shape X X Base 30 Overall width in inches 30 Overall depth in inches 114 Base finish 114 Laminate top finish 114 Edgeband finish	X Base Table: <ul style="list-style-type: none"> (1) X Base Hardware kit Table top Note: X Base Tables are finished with textured paint, including 613 Silver. Note: X Base Tables are only available in Knoll core finishes.	

X Base Tables

Rounded Square Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
42" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	42"	DT1ADX303042	\$1,201.	\$1,312.	\$1,364.	\$2,545.	\$2,789.	\$2,900.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	42"	DT1ADX363642	1,246.	1,363.	1,413.	2,642.	2,898.	3,009.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	42"	DT1ADX424242	1,367.	1,494.	1,548.	2,762.	3,030.	3,149.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	42"	DT1ADX484842	1,426.	1,561.	1,620.	2,836.	3,111.	3,229.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information

X Base Table:

1. Pattern number
2. Base Paint Finish
3. Top Finish
4. Edge Finish

Order Code

X Base Table:

<i>Example:</i>	DT1ADX3030, 114, 114, 114
DT1	Dividends Horizon Table
A	Table assembly
D	Rounded Square shape
X	X Base
30	Overall width in inches
30	Overall depth in inches
114	Base finish
114	Laminate top finish
114	Edgeband finish

Included with:

X Base Table:

- (1) X Base
- Hardware kit
- Table top

Note: X Base Tables are finished with textured paint, including 613 Silver.

Note: X Base Tables are only available in Knoll core finishes.

Options

Table Supports

X Bases

Credenza Support Spacer

description	w	h	d	pattern no.	P1	P2	P3
Small X-Base, for use with 30" or 36" wide round, square or rounded square table tops		17"		DT1BXS17	\$580.	\$641.	\$668.
		21"		DT1BXS21	580.	641.	668.
		28"		DT1BXS	603.	666.	693.
		36"		DT1BXS36	666.	725.	753.
		42"		DT1BXS42	689.	751.	777.



Large X Base, for use with 42" or 48" wide round, square or rounded square table tops		17"		DT1BXL17	640.	706.	735.
		21"		DT1BXL21	640.	706.	735.
		28"		DT1BXL	665.	730.	760.
		36"		DT1BXL36	724.	791.	820.
		42"		DT1BXL42	749.	816.	844.



Credenza Support Spacer For use with Dividends Horizon Credenza	9 ⁵ / ₈ "	2 ¹⁵ / ₁₆ "	1 ⁹ / ₁₆ "	DT1S	172.	191.	199.
--	---------------------------------	-----------------------------------	----------------------------------	-------------	------	------	------



Small T-Base, for use with 24" or 30" deep tops		28"		DT1BTS	603.	666.	693.
---	--	-----	--	---------------	------	------	------



Large T-Base, for use with 24" or 30" deep tops		28"		DT1BTL	665.	730.	760.
---	--	-----	--	---------------	------	------	------



Ordering Information

Table Supports:

1. Pattern number
2. Paint Finish

Order Code

X Base:

Example: **DT1BXS, 114**

DT1 Dividends Horizon Table

B Base

S X Shape

114 Paint finish

Credenza Support Spacer:

Example: **DT1S, 114**

DT1 Dividends Horizon Table

S Support Spacer

114 Paint finish

Included with:

X Base:

- X Base
- Hardware kit

T Base:

- T Base
- Hardware kit

Credenza Support spacer:

- Support spacer
- Hardware Kit

Note: X and T bases are painted with textured paint, including 613 Silver.


Note: Table supports are only available in Knoll core finishes.

Options

Casters are designed for use on X- and Y-bases only.

Tables with casters may not exceed 28"h, 84"w or 42"d.

Table Supports
X Bases
Credenza Support Spacer

description	w	h	d	pattern no.	P1	P2	P3
Caster Kit (set of 4) black only 		1"		DT1CK4	\$41.	\$0.	\$0.

Ordering Information

Table Supports:

1. Pattern number
2. Paint Finish

Order Code

X Base:

Example: **DT1BXS, 114**

DT1 Dividends Horizon Table

B Base

S X Shape

114 Paint finish

Credenza Support Spacer:

Example: **DT1S, 114**

DT1 Dividends Horizon Table

S Support Spacer

114 Paint finish

Included with:

X Base:

- X Base
- Hardware kit

T Base:

- T Base
- Hardware kit

Credenza Support spacer:

- Support spacer
- Hardware Kit

Note: X and T bases are painted with textured paint, including 613 Silver.

Note: Table supports are only available in Knoll core finishes.

Options


Casters are designed for use on X- and Y-bases only.

Tables with casters may not exceed 28"h, 84"w or 42"d.


Table Supports

C-Leg and T-Leg Bases


Fixed Height and Height Adjustable

description	type	w*	w	d	pattern no.	Fixed (F)	Pin-Set (P)	Handcrank (H)	Electric (E)	Advanced Electric (A)
	For use with 36"W, 24"D C-Leg Top	36"	34"	23"	DT1BC3423()	\$1,018.	\$1,357.	\$2,035.	\$3,535.	\$3,721.
	For use with 42"W, 24"D C-Leg Top	42"	40"	23"	DT1BC4023()	1,018.	1,357.	2,035.	3,535.	3,721.
	For use with 48"W, 24"D C-Leg Top	48"	46"	23"	DT1BC4623()	1,018.	1,357.	2,035.	3,535.	3,721.
	For use with 54"W, 24"D C-Leg Top	54"	52"	23"	DT1BC5223()	1,018.	1,357.	2,035.	3,535.	3,721.
	For use with 60"W, 24"D C-Leg Top	60"	58"	23"	DT1BC5823()	1,018.	1,357.	2,035.	3,535.	3,721.
	For use with 66"W, 24"D C-Leg Top	66"	64"	23"	DT1BC6423()	1,041.	1,380.	2,059.	3,558.	3,746.
	For use with 72"W, 24"D C-Leg Top	72"	70"	23"	DT1BC7023()	1,041.	1,380.	2,059.	3,558.	3,746.

Fixed Shown

	For use with 36"W, 30"D C-Leg Top	36"	34"	29"	DT1BC3429()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 42"W, 30"D C-Leg Top	42"	40"	29"	DT1BC4029()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 48"W, 30"D C-Leg Top	48"	46"	29"	DT1BC4629()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 54"W, 30"D C-Leg Top	54"	52"	29"	DT1BC5229()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 60"W, 30"D C-Leg Top	60"	58"	29"	DT1BC5829()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 66"W, 30"D C-Leg Top	66"	64"	29"	DT1BC6429()	1,091.	1,430.	2,107.	3,605.	3,794.
	For use with 72"W, 30"D C-Leg Top	72"	70"	29"	DT1BC7029()	1,091.	1,430.	2,107.	3,605.	3,794.

Fixed Shown

	For use with 48"W, 30" or 36"D T-Leg Top	48"	46"	29"	DT1BT4629()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 54"W, 30" or 36"D T-Leg Top	54"	52"	29"	DT1BT5229()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 60"W, 30" or 36"D T-Leg Top	60"	58"	29"	DT1BT5829()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 66"W, 30" or 36"D T-Leg Top	66"	64"	29"	DT1BT6429()	1,091.	1,430.	2,107.	3,605.	3,794.
	For use with 72"W, 30" or 36"D T-Leg Top	72"	70"	29"	DT1BT7029()	1,091.	1,430.	2,107.	3,605.	3,794.

Pin-Set Shown

Tables

Ordering Information

Table Supports

1. Pattern Number
2. Base Type
3. Shroud Option
4. Base Finish
5. Shroud/Feet Paint Finish (optional)

w* = nominal width

Order Code

Table Supports

Example: **DT1BC5829HS, 9005, 613**

DT1B	Universal Base
C	C-Leg
58	Width
29	Depth
H	Handcrank
S	Shroud
9005	Black Base Finish
613	Shroud/Feet Paint Finish

Included With

Table Supports
Mounting hardware
Shrouds (optional)

Options

Table Supports

Base Type Options:

- (F) = Fixed (27" High)
- (P) = Pin-Set (22" - 35" High)
- (H) = Handcrank (22" - 35" High)
- (E) = Electric (27" - 46 1/2" High)
- (A) = Advanced Electric (21" - 47 1/2" High)




Shroud Option:

Add an 'S' suffix to the pattern number to specify a painted shroud for the lower leg with matching foot and add \$100 to the list price. Add an 'N' suffix to specify a leg without a shroud.

Table Supports

C-Leg and T-Leg Bases

Fixed Height and Height Adjustable

description	type	w*	w	d	pattern no.	Fixed (F)	Pin-Set (P)	Handcrank (H)	Electric (E)	Advanced Electric (A)
C-Leg Corner Base	For use with Corner C-Leg Top	48"	46"	16"	DT1BK464616()	\$1,647.	\$2,157.	n/a	\$5,423.	\$5,709.
										
<i>Fixed Shown</i>										
T-Leg Corner Base	For use with 42" Corner T-Leg Top	32"	30"	29"	DT1BT3029()	1,066.	1,405.	2,084.	3,582.	3,769.
	For use with 48" Corner C-Leg/T-Leg Top	36"	34"	29"	DT1BT3429()	1,066.	1,405.	2,084.	3,582.	3,769.
										
<i>Fixed Shown</i>										
C-Leg 120° Base	For use with 120° Top	48"	46"	16"	DT1BY464616()	1,647.	2,157.	n/a	5,423.	5,709.
										

Ordering Information

Table Supports

1. Pattern Number
2. Base Type
3. Shroud Option
4. Base Finish
5. Shroud/Feet Paint Finish (optional)

w* = nominal width

Order Code

Table Supports

Example: **DT1BC5829HS, 9005, 613**

DT1B	Universal Base
C	C-Leg
58	Width
29	Depth
H	Handcrank
S	Shroud
9005	Black Base Finish
613	Shroud/Feet Paint Finish

Included With

Table Supports

Mounting hardware
Shrouds (optional)

Options

Table Supports

Base Type Options:

- (F) = Fixed (27" High)
- (P) = Pin-Set (22" - 35" High)
- (H) = Handcrank (22" - 35" High)
- (E) = Electric (27" - 46 1/2" High)
- (A) = Advanced Electric (21" - 47 1/2" High)



Shroud Option:

Add an 'S' suffix to the pattern number to specify a painted shroud for the lower leg with matching foot and add \$100 to the list price. Add an 'N' suffix to specify a leg without a shroud.

Table Supports

C-Leg and T-Leg Bases







Fixed Height and Height Adjustable

description	type	w	d	h	pattern no.	list
Electric Table Memory Switch with Digital Display 	For use with Electric C-Leg and T-Leg bases	5"	.75"	1"	SISDDPS	\$399.
Locking Casters, Set of 4 	For use with C-Leg and T-Leg bases	2"	2"	1.5"	SISLC4	53.
Chicago 9' Power Cord	For use in the City of Chicago	108"			SISPCH	89.

Ordering Information	Order Code	Included With	Options
Table Supports	Table Supports	Table Supports	Table Supports
1. Pattern Number	<i>Example:</i> SISDDPS SIS Universal Base DDPS Electric Table Memory Switch with Digital Display		

Rectangular, Corner & 120°, C-Leg and T-Leg Worksurface 24", 30" and 36" Deep Rectangular

Dividends Horizon

description	type	w*	w	d*	d	h	pattern no.	Laminate w/ w/ ABS edge	Laminate w/ woodgrain edge	Techwood w/ Techwood edge
 C-Leg Rectangular Tops, 24" Deep	For use with 24"D C-Leg base	36"	34"	24"	23"		DT1R3423N	\$239.	\$261.	\$497.
	For use with 24"D C-Leg base	42"	40"	24"	23"		DT1R4023N	274.	299.	524.
	For use with 24"D C-Leg base	48"	46"	24"	23"		DT1R4623N	304.	337.	549.
	For use with 24"D C-Leg base	54"	52"	24"	23"		DT1R5223N	332.	365.	578.
	For use with 24"D C-Leg base	60"	58"	24"	23"		DT1R5823N	360.	393.	607.
	For use with 24"D C-Leg base	66"	64"	24"	23"		DT1R6423N	385.	424.	632.
	For use with 24"D C-Leg base	72"	70"	24"	23"		DT1R7023N	403.	445.	661.
 C-Leg and T-Leg Rectangular Tops, 30" Deep	For use with 30"D C-Leg base	36"	34"	30"	29"		DT1R3429N	296.	327.	533.
	For use with 30"D C-Leg base	42"	40"	30"	29"		DT1R4029N	323.	353.	569.
	For use with 30"D C-Leg or T-Leg base	48"	46"	30"	29"		DT1R4629N	360.	393.	605.
	For use with 30"D C-Leg or T-Leg base	54"	52"	30"	29"		DT1R5229N	407.	446.	630.
	For use with 30"D C-Leg or T-Leg base	60"	58"	30"	29"		DT1R5829N	447.	492.	658.
	For use with 30"D C-Leg or T-Leg base	66"	64"	30"	29"		DT1R6429N	496.	547.	683.
	For use with 30"D C-Leg or T-Leg base	72"	70"	30"	29"		DT1R7029N	517.	566.	708.
 T-Leg Rectangular Tops, 36" Deep	For use with 30"D T-Leg base	48"	46"	36"	35"		DT1R4635N	470.	504.	718.
	For use with 30"D T-Leg base	54"	52"	36"	35"		DT1R5235N	519.	558.	743.
	For use with 30"D T-Leg base	60"	58"	36"	35"		DT1R5835N	572.	628.	780.
	For use with 30"D T-Leg base	66"	64"	36"	35"		DT1R6435N	631.	697.	807.
	For use with 30"D T-Leg base	72"	70"	36"	35"		DT1R7035N	697.	768.	837.
 C-Leg/T-Leg Corner Tops, 24" or 30" Deep	For use with C-Leg/T-Leg Corner base	48"	46"	24"	23"		DT1L4646SSN	632.	700.	1,208.
	For use with C-Leg/T-Leg Corner base	48"	46"	30"	29"		DT1L4646DDN	683.	752.	1,223.
 T-Leg Corner Top, 24" Deep	For use with T-Leg Corner base	42"	40"	24"	23"		DT1L4040SSN	562.	621.	1,144.
 C-Leg 120° Tops	For use with 120° base	48"	46"	24"	23"		DT1Y4623N	889.	975.	n/a

Ordering Information

Dividends Horizon Tops

1. Pattern Number
2. Top Finish
3. Edge Finish
(for laminate tops only)

w * and d * = nominal dimensions

Order Code

Dividends Horizon Tops

<i>Example:</i> DT1R5829N, 118, 118	
DT1R	Rectangular
58	Width
29	Depth
N	No Grommet
118	Bright White Laminate
118	Bright White Edge

Included With

Dividends Horizon Tops

Options

Dividends Horizon Tops

Top Finish Options:

Laminate with ABS edge
Laminate with woodgrain edge
Techwood with techwood edge

Note: When woodgrain laminates are specified on corner and 120° worksurfaces a grain direction option must be specified.

(L) = Left
(R) = Right
(D) = Diagonal (Add \$26 to list price)

Note: Techwood corner worksurfaces have a diagonal grain direction. See grain direction page for more information.

This page intentionally left blank

Dividends Horizon Conference Tables

Dividends Horizon conference tables are designed with a scale and visual language consistent with the full scope of Dividends Horizon products. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon conference tables are available in racetrack, rectangular, or boat shape and in all standard Dividends Horizon finishes.

Conference tables include a table top and base assembly. A conference table base assembly includes two Y legs, one center support T base, and two horizontal stretchers that connect the three bases. All conference table tops are produced in two pieces. Grain patterns on woodgrain laminates and veneer tops will not match at the seam in the middle of the conference tables.

Available Sizes

Width: 102- 144 inches

Depth: 36- 48 inches

Height: 28-1/2 inches

Construction

Worksurface:

- Material: 0.028 inch thick laminate or 0.6mm thick veneer on 1-1/8 inch thick particle board core
- Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge


Base:

- Stretcher: extruded aluminum
- Foot: die cast aluminum
- Column: extruded aluminum with 3/16 inch thick structural plate


Note: Dividends Horizon conference tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: Grain patterns on woodgrain laminate and veneer tops will not match at the seam in the middle of conference tables.

Rectangular Conference Table



Racetrack Conference Table



Boat Shape Conference Table




Conference Tables


Rectangular Table Top

36", 42" and 48" deep


description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
36" Deep Rectangular Conference Table	102"	101 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10236N	\$2,559.	\$2,618.	\$2,680.	\$2,922.	\$3,046.	\$3,290.
	108"	107 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10836N	2,618.	2,680.	2,741.	2,984.	3,281.	3,415.



42" Deep Rectangular Conference Table	102"	101 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10242N	2,618.	2,680.	2,741.	2,984.	3,105.	3,350.
	108"	107 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10842N	2,680.	2,741.	2,802.	3,013.	3,350.	3,515.
	120"	119 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY12042N	2,866.	2,924.	2,986.	3,130.	3,444.	3,584.
	132"	131 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY13242N	2,986.	3,048.	3,109.	3,640.	4,005.	4,167.
	144"	143 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY14442N	3,109.	3,169.	3,228.	4,148.	4,566.	4,745.



48" Deep Rectangular Conference Table	102"	101 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10248N	2,680.	2,741.	2,802.	3,046.	3,226.	3,471.
	108"	107 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10848N	2,741.	2,802.	2,863.	3,137.	3,439.	3,593.
	120"	119 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY12048N	2,933.	2,994.	3,057.	3,222.	3,547.	3,686.
	132"	131 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY13248N	3,057.	3,117.	3,177.	3,740.	4,115.	4,281.
	144"	143 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY14448N	3,177.	3,237.	3,300.	4,257.	4,684.	4,874.



w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N	• (2) Y Legs	
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (1) T leg	
3. Top Finish	A Table Assembly	• (2) Stretchers	
4. Edge Finish	R Rectangular shape	• Table Top	
	Y Y Leg Base	• Hardware Kit	
	108 Overall width in inches		
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Conference Tables


Racetrack Table Top

36", 42" and 48" deep


description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
36" Deep Racetrack Conference Table	102"	101 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10236N	\$2,559.	\$2,618.	\$2,680.	\$3,777.	\$4,141.	\$4,263.
	108"	107 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10836N	2,618.	2,680.	2,741.	3,830.	4,214.	4,382.



42" Deep Racetrack Conference Table	102"	101 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10242N	2,618.	2,680.	2,741.	3,807.	4,201.	4,384.
	108"	107 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10842N	2,680.	2,741.	2,802.	3,897.	4,263.	4,445.
	120"	119 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY12042N	2,866.	2,924.	2,986.	3,978.	4,376.	4,550.
	132"	131 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY13242N	2,986.	3,048.	3,109.	4,568.	5,022.	5,225.
	144"	143 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY14442N	3,109.	3,169.	3,228.	5,155.	5,669.	5,898.



48" Deep Racetrack Conference Table	102"	101 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10248N	2,680.	2,741.	2,802.	3,897.	4,232.	4,415.
	108"	107 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY10848N	2,741.	2,802.	2,863.	4,020.	4,324.	4,507.
	120"	119 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY12048N	2,933.	2,994.	3,057.	4,066.	4,473.	4,653.
	132"	131 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY13248N	3,057.	3,117.	3,177.	4,665.	5,132.	5,340.
	144"	143 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY14448N	3,177.	3,237.	3,300.	5,266.	5,791.	6,023.



w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N	• (2) Y Legs	
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (1) T leg	
3. Top Finish	A Table Assembly	• (2) Stretchers	
4. Edge Finish	R Rectangular shape	• Table Top	
	Y Y Leg Base	• Hardware Kit	
	108 Overall width in inches		
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Conference Tables


Boat Shape Table Top

42" and 48" deep

description	w*	w	d	t	h	pattern no.	Laminate	Laminate	Laminate	Techgrain	Techgrain	Techgrain
							Top P1 Paint	Top P2 Paint	Top P3 Paint	Top P1 Paint	Top P2 Paint	Top P3 Paint
42" Deep Boat Shape Conference Table	102"	101 13/16"	41 1/2"	1 1/4"	28 1/2"	DT1ABY10242N	\$2,618.	\$2,680.	\$2,741.	\$3,807.	\$4,201.	\$4,384.
	108"	107 13/16"	41 1/2"	1 1/4"	28 1/2"	DT1ABY10842N	2,680.	2,741.	2,802.	3,897.	4,263.	4,445.
	120"	119 13/16"	41 1/2"	1 1/4"	28 1/2"	DT1ABY12042N	2,866.	2,924.	2,986.	3,978.	4,376.	4,550.
	132"	131 13/16"	41 1/2"	1 1/4"	28 1/2"	DT1ABY13242N	2,986.	3,048.	3,109.	4,568.	5,022.	5,225.
	144"	143 13/16"	41 1/2"	1 1/4"	28 1/2"	DT1ABY14442N	3,109.	3,169.	3,228.	5,155.	5,669.	5,898.




48" Deep Boat Shape Conference Table	102"	101 13/16"	47 1/2"	1 1/4"	28 1/2"	DT1ABY10248N	2,680.	2,741.	2,802.	3,897.	4,232.	4,415.
	108"	107 13/16"	47 1/2"	1 1/4"	28 1/2"	DT1ABY10848N	2,741.	2,802.	2,863.	4,020.	4,324.	4,507.
	120"	119 13/16"	47 1/2"	1 1/4"	28 1/2"	DT1ABY12048N	2,933.	2,994.	3,057.	4,066.	4,473.	4,653.
	132"	131 13/16"	47 1/2"	1 1/4"	28 1/2"	DT1ABY13248N	3,057.	3,117.	3,177.	4,665.	5,132.	5,340.
	144"	143 13/16"	47 1/2"	1 1/4"	28 1/2"	DT1ABY14448N	3,177.	3,237.	3,300.	5,266.	5,791.	6,023.





Tables

w* = nominal width
Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N	• (2) Y Legs	
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (1) T leg	
3. Top Finish	A Table Assembly	• (2) Stretchers	
4. Edge Finish	R Rectangular shape	• Table Top	
	Y Y Leg Base	• Hardware Kit	
	108 Overall width in inches		
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

description	surface	type	w	d	h	pattern no.	P1	P2	P3	
	Laminate		29 ³ / ₄ "	29 ³ / ₄ "	29"	ET1RT30	\$887.	\$933.	\$975.	
	Laminate		35 ³ / ₄ "	35 ³ / ₄ "	29"	ET1RT36	952.	997.	1,048.	
	Laminate		41 ³ / ₄ "	41 ³ / ₄ "	29"	ET1RT42	1,266.	1,334.	1,393.	
	Laminate	4 columns - 4 legs		59 ³ / ₄ "	59 ³ / ₄ "	29"	ET1RT60	2,803.	2,949.	3,088.
	Laminate	5 legs		47 ³ / ₄ "	47 ³ / ₄ "	29"	ET1RT48	1,580.	1,658.	1,734.
	Laminate	with casters		35 ³ / ₄ "	35 ³ / ₄ "	29"	ET1RT36C	1,251.	1,316.	1,376.

description	surface	type	w	d	h	pattern no.	P1	P2	P3	
	Laminate		24"	24"	16"	ET1ST2416	641.	672.	704.	
	Laminate		29 ³ / ₄ "	29 ³ / ₄ "	29"	ET1ST30	847.	889.	933.	
	Laminate		35 ³ / ₄ "	35 ³ / ₄ "	29"	ET1ST36	903.	949.	991.	
	Laminate		41 ³ / ₄ "	41 ³ / ₄ "	29"	ET1ST42	1,206.	1,264.	1,325.	
	Laminate	4 columns - 4 legs		59 ¹ / ₂ "	59 ¹ / ₂ "	29"	ET1ST60	2,668.	2,802.	2,936.
	Laminate	6 legs		47 ³ / ₄ "	47 ³ / ₄ "	29"	ET1ST48	1,502.	1,574.	1,649.
	Laminate	with caster		22 ¹ / ₄ "	22 ¹ / ₄ "	26 ³ / ₈ "	ET1ST22C	1,027.	1,076.	1,126.

description	surface	type	w	d	h	pattern no.	P1	P2	P3	
	Laminate		47 ³ / ₄ "	29 ³ / ₄ "	29"	ET1RCT3048	1,478.	1,552.	1,626.	
	Laminate		58 ¹ / ₂ "	35 ¹ / ₂ "	29"	ET1RCT3660	2,130.	2,234.	2,343.	
	Laminate		59 ³ / ₄ "	29 ³ / ₄ "	29"	ET1RCT3060	1,803.	1,895.	1,987.	
	Laminate		71 ³ / ₄ "	29 ³ / ₄ "	29"	ET1RCT3072	2,130.	2,234.	2,343.	
	Laminate		71 ³ / ₄ "	35 ³ / ₄ "	29"	ET1RCT3672	2,522.	2,647.	2,775.	
	Laminate		83 ³ / ₄ "	41 ³ / ₄ "	29"	ET1RCT4284	3,376.	3,542.	3,712.	
	Laminate	4 columns		95 ³ / ₄ "	47 ³ / ₄ "	29"	ET1RCT4896	4,352.	4,570.	4,786.
	Laminate	Accepts Equity drawers		69 ¹ / ₄ "	34"	29"	ET1RCT3469	3,204.	3,363.	3,522.
	Laminate	Accepts Equity drawers		79 ¹ / ₄ "	34"	29"	ET1RCT3479	3,204.	3,363.	3,522.


Order Code	Specification Information
Example: ET1RCT3060, 117, 117, 117	Specify surface, trim and hardware trim color.
ET1RCT Rectangular table	If a polished chrome base is desired, add a "P" suffix and add \$11 to the P1 list price.
30 Depth	Tables are only available in EW1 profile.
60 Width	
117 Soft Grey laminate	
117 Soft Grey edge	
117 Soft Grey trim	

Specification Information	Application Notes
Specify surface, trim and hardware trim color.	Stretchers are used between two or more hubs. Two column tables have one stretcher; four column tables use four stretchers; and six column tables use seven.
If a polished chrome base is desired, add a "P" suffix and add \$11 to the P1 list price.	ET10T60144 top ships in two sections. Hidden fasteners join sections.
Tables are only available in EW1 profile.	Note: Add 10% to the list price of any table when specifying a legacy laminate.

Wood Grain and Metal edge bands:
When specifying a top with a wood grain edge band add \$26 to the standard list price.
When specifying a top with a metal edge band add \$52 to the standard list price.

Application Notes
Stretchers are used between two or more hubs. Two column tables have one stretcher; four column tables use four stretchers; and six column tables use seven.
ET10T60144 top ships in two sections. Hidden fasteners join sections.
Note: Add 10% to the list price of any table when specifying a legacy laminate.

description	surface	type	w	d	h	pattern no.	P1	P2	P3
oval table	Laminate		71 3/4"	35 3/4"	29"	ET1OT3672	\$3,333.	\$3,498.	\$3,667.
	Laminate	4 columns	95 3/4"	47"	29"	ET1OT4896	5,465.	5,743.	6,015.
	Laminate	6 columns	119 3/4"	47"	29"	ET1OT48120	6,686.	7,018.	7,354.
	Laminate	6 columns	119 3/4"	53 3/4"	29"	ET1OT54120	7,452.	7,824.	8,197.
	Laminate	6 columns	143 3/4"	59 3/4"	29"	ET1OT60144	9,733.	10,216.	10,704.



Order Code	Specification Information	Application Notes
Example: ET1RCT3060, 117, 117, 117	Specify surface, trim and hardware trim color.	<p>Stretchers are used between two or more hubs. Two column tables have one stretcher; four column tables use four stretchers; and six column tables use seven.</p> <p>ET1OT60144 top ships in two sections. Hidden fasteners join sections.</p> <p>Note: Add 10% to the list price of any table when specifying a legacy laminate.</p>
ET1RCT Rectangular table	If a polished chrome base is desired, add a "P" suffix and add \$11 to the P1 list price.	
30 Depth		
60 Width	Tables are only available in EW1 profile.	
117 Soft Grey laminate	<p><i>Wood Grain and Metal edge bands:</i> When specifying a top with a wood grain edge band add \$26 to the standard list price.</p> <p>When specifying a top with a metal edge band add \$52 to the standard list price.</p>	
117 Soft Grey edge		
117 Soft Grey trim		

Preconfigured Desks

Series 2 Single and Double Pedestal Specifications

Series 2 Single and Double Pedestal Desks

Series 2 freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer configuration is required, or when back panels are not needed.

"Preconfigured" single pedestal desks consist of a worksurface, Series 2 box/box/file pedestal, "L" shaped end panel and full height back panel.

"Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and full height back panel.

Available Sizes

- Height: 28½"
- Depths: 24", 30" and 36"
(double pedestal desk only)
- Widths: 60", 66" and 72"
- Worksurface thickness: 1¼"

"Build-to-Spec" Desks

For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction

All freestanding desks match the aesthetics and dimensions of Dividends Horizon panel components.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 desks include full-height modesty panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

Optional Edge Grommets

Edge grommets are optional for all desks except overhang desks and can be specified factory-installed, centered along the rear edge of worksurfaces. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface. When grommets are specified, a reveal of ½" is provided between the rear of the worksurface and the back panel for repositioning cables anywhere along the back panel.

Locks


Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250.

All locks are factory-installed and have a black finish.


Desk Accessory

All Series 2 pedestal accessories including the hanging file bar must be specified separately.


Series 2 Single Pedestal Desk




Series 2 Double Pedestal Desk




Series 2 Desk Components



Optional Edge Grommet






Series 2 Freestanding Desk Configurations



Preconfigured Desks

Series 2 Single and Double Pedestal

24", 30" and 36" Deep

description	w*	w	d	h	pattern no.	P1	P2	P3
 Single Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L6024N	\$1,772.	\$1,916.	\$1,982.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L6030N	1,943.	2,091.	2,165.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L6624N	1,815.	1,958.	2,029.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L6630N	2,007.	2,157.	2,231.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L7224N	1,846.	1,989.	2,060.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L7230N	2,040.	2,192.	2,266.
 Double Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L6024N	2,039.	2,206.	2,290.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L6030N	2,201.	2,374.	2,459.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L6624N	2,084.	2,251.	2,337.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L6630N	2,266.	2,442.	2,529.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L7224N	2,112.	2,283.	2,368.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L7230N	2,300.	2,475.	2,565.
 Double Pedestal Desk with Locks and 6" Front Overhang	60"	59 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L6036N	2,334.	2,504.	2,594.
	66"	65 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L6636N	2,408.	2,585.	2,671.
	72"	71 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L7236N	2,489.	2,666.	2,750.

w* = nominal width
 Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Single Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish Double Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Single Pedestal Desk <i>Example:</i> DD2S L7230N, 117, 117, 117 DD2S Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish Double Pedestal Desk <i>Example:</i> DD2D L7230N, 117, 117, 117 DD2D Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish	Single Pedestal Desk Double Pedestal Desk Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Single Pedestal Desk <ul style="list-style-type: none"> To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) <ul style="list-style-type: none"> To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$22 Double Pedestal Desk <ul style="list-style-type: none"> To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) <ul style="list-style-type: none"> To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$42

Preconfigured Desks

Single and Double Pedestal Specifications

Single and Double Pedestal Desks

Dividends freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer configuration is required, or when back panels are not needed. "Preconfigured" single pedestal desks consist of a worksurface, box/box/file pedestal, "L" shaped end panel and half-height back panel. "Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and half-height back panel.

Available Sizes

- Height: 28 1/2"
- Depths: 24", 30" and 36"
(Double pedestal desk only)
- Widths: 60", 66" and 72"
- Worksurface thickness: 1 1/4"

"Build-to-Spec" Desks

For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction

All freestanding desks match the aesthetics and dimensions of Dividends panel components.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset 3/4" from the pedestal backs and match the softly-radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.


Locks

Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250 All locks are factory-installed and have a black finish.


Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.


Single Pedestal Desk




Double Pedestal Desk




Desk Components



Freestanding Desk Configurations






Optional Edge Grommet



Preconfigured Desks

Single and Double Pedestal

24", 30" and 36" Deep

description	w*	w	d	h	pattern no.	P1	P2	P3
 Single Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1S L6024N	\$1,772.	\$1,916.	\$1,982.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1S L6030N	1,943.	2,091.	2,165.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1S L6624N	1,815.	1,958.	2,029.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1S L6630N	2,007.	2,157.	2,231.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1S L7224N	1,846.	1,989.	2,060.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1S L7230N	2,040.	2,192.	2,266.
 Double Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1D L6024N	2,039.	2,206.	2,290.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1D L6030N	2,201.	2,374.	2,459.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1D L6624N	2,084.	2,251.	2,337.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1D L6630N	2,266.	2,442.	2,529.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD1D L7224N	2,112.	2,283.	2,368.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD1D L7230N	2,300.	2,475.	2,565.
 Double Pedestal Desk with Locks and 6" Front Overhang	60"	59 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD1O L6036N	2,334.	2,504.	2,594.
	66"	65 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD1O L6636N	2,408.	2,585.	2,671.
	72"	71 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD1O L7236N	2,489.	2,666.	2,750.

w* = nominal width
 Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Single Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish 5. Pull Finish 6. Drawer Top Cap Finish	Single Pedestal Desk <i>Example:</i> DD1S L7230N, 117, 117, 117, 117, 117 DD1S Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish 117 Soft Grey pull finish Y3 Dark Grey top cap finish	Single Pedestal Desk Double Pedestal Desk Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Single Pedestal Desk <ul style="list-style-type: none"> To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) <ul style="list-style-type: none"> To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$22
Double Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish 5. Pull Finish 6. Drawer Top Cap Finish	Double Pedestal Desk <i>Example:</i> DD1D L7230N, 117, 117, 117, 117, 117 DD1D Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish 117 Soft Grey pull finish 117 Soft Grey top cap finish		Double Pedestal Desk <ul style="list-style-type: none"> To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) <ul style="list-style-type: none"> To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$42

Preconfigured Desks

Series 2 Freestanding Corner Unit Specifications

Series 2 Freestanding Corner Units (Assembly)

Dividends Horizon Series 2 freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications.

"Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two full height back panels.

Available Sizes

- Height: 28½"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit:

- Worksurface: 1¼" thick, 45 lb. density particle board core with laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel
- Series 2 Freestanding Corner Units include full height back panels

Rear Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ¾" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit

- Outer skin: 21-gauge
- Inner frame: 20-gauge
- Leveling glide: ¾" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel


Freestanding Corner End Units (Components)

Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.


Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.


Series 2 Freestanding Corner Unit Components



Edge Grommet Locations






Series 2 Freestanding Corner Unit Attached to Return to Form a "L" Shaped Workstation



Preconfigured Desks

Series 2 Freestanding Corner Unit

24" Deep

description	type	w *	w	d	h	pattern no.	P1	P2	P3
 Freestanding Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD2VD 3624 N	\$1,498.	\$1,648.	\$1,724.
		42"	41 1/2"	23 1/2"	28 1/2"	DD2VD 4224 N	1,548.	1,704.	1,782.
		48"	47 1/2"	23 1/2"	28 1/2"	DD2VD 4824 N	1,625.	1,787.	1,869.
 Freestanding Curved Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD2VL 3624 N	1,531.	1,683.	1,762.
		42"	41 1/2"	23 1/2"	28 1/2"	DD2VL 4224 N	1,624.	1,786.	1,868.
		48"	47 1/2"	23 1/2"	28 1/2"	DD2VL 4824 N	1,696.	1,868.	1,949.
 Freestanding Corner End Unit (Component)			6 9/16"	6 9/16"	26 7/8"	DD1R CU6	314.	347.	362.

w* = nominal width
 Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Corner 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Freestanding Corner <hr/> <i>Example:</i> DD2VD 3624 N, 117, 117 <hr/> DD2VD Pattern Number <hr/> 3624 <hr/> N No Grommets <hr/> 117 Soft Grey laminate <hr/> 117 Soft Grey edge finish <hr/> 117 Soft Grey paint finish <hr/> Freestanding Corner End Unit <i>Example:</i> DD1RCU6, 117 <hr/> DD1RCU6 Pattern Number <hr/> 117 Soft Grey paint finish	Freestanding Corner <ul style="list-style-type: none"> • Corner supports (3) • Back panels (2) • Corner worksurface • Connecting hardware Freestanding Corner End Unit Note: Series 2 freestanding corner units have full height modesty panels. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Freestanding Corner <ul style="list-style-type: none"> • To specify two center-mounted edge grommets, replace the suffix letter "N" with a "G". Add \$30. Freestanding Corner End Unit

Preconfigured Desks

Freestanding Corner Unit Specifications

Freestanding Corner Units (Assembly)

Dividends freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications. "Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two 11" high back panels.

Available Sizes

- Height: 28½"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit Specifications

- Worksurface: 1¼" thick, 45 lb. density particle board core with laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel

Rear Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ¾" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ¾" 16-gauge steel
- Attachment bracket: 11-gauge steel


Freestanding Corner End Units (Components)

Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.


Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.


Freestanding Corner Unit Components



Edge Grommet Locations






Freestanding Corner Unit attached to returns to form an "L" shaped workstation



Preconfigured Desks

Freestanding Corner Unit

24" Deep

description	type	w*	w	d	h	pattern no.	P1	P2	P3
 Freestanding Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD1VD 3624 N	\$1,498.	\$1,648.	\$1,724.
		42"	41 1/2"	23 1/2"	28 1/2"	DD1VD 4224 N	1,548.	1,704.	1,782.
		48"	47 1/2"	23 1/2"	28 1/2"	DD1VD 4824 N	1,625.	1,787.	1,869.
 Freestanding Curved Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD1VL 3624 N	1,531.	1,683.	1,762.
		42"	41 1/2"	23 1/2"	28 1/2"	DD1VL 4224 N	1,624.	1,786.	1,868.
		48"	47 1/2"	23 1/2"	28 1/2"	DD1VL 4824 N	1,696.	1,868.	1,949.
Freestanding Corner End Unit (Component)			6 9/16"	6 9/16"	26 7/8"	DD1R CU6	314.	347.	362.
Freestanding Corner Unit (Component)			6 9/16"	12 9/16"	26 7/8"	DD1S CU12	371.	408.	426.
 Back Panels for Freestanding Corner Unit (Component)	full height	36"	20 15/16"	26 5/8"		DD1 FBPV36	223.	244.	255.
	full height	42"	26 15/16"	26 5/8"		DD1 FBPV42	225.	247.	259.
	full height	48"	32 15/16"	26 5/8"		DD1 FBPV48	228.	252.	262.
	half height	36"	20 15/16"	11"		DD1 BPV36	187.	204.	213.
	half height	42"	26 15/16"	11"		DD1 BPV42	197.	216.	225.
	half height	48"	32 15/16"	11"		DD1 BPV48	205.	227.	239.

w* = nominal width
 Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Corner 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Freestanding Corner <i>Example:</i> DD1VD 3624 N, 117, 117 DD1VD Pattern Number 3624 N No Grommets 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish Freestanding Corner End Unit <i>Example:</i> DD1R CU6, 117 DD1R Pattern Number CU6 117 Soft Grey paint finish Freestanding Corner Back Panel <i>Example:</i> DD1 BPV42, 115 DD1 Pattern Number BPV42 115 Medium grey paint finish	Freestanding Corner <ul style="list-style-type: none"> • Corner supports (3) • Back panels (2) • Corner worksurface • Connecting hardware Freestanding Corner End Unit Freestanding Corner Back Panel Note: Series 1 freestanding corner units have a curved half modesty panel. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Freestanding Corner <ul style="list-style-type: none"> • To specify two center-mounted edge grommets, replace the suffix letter "N" with a "G". Add \$30. Freestanding Corner End Unit Freestanding Corner Back Panel

Preconfigured Desks

Series 2 Returns and Bridge Units

Specifications

Series 2 End Panel and Pedestal Returns

Dividends Horizon freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and full-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and full height back panel.

Available Sizes

- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment

Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction

All freestanding returns match the aesthetics of the Dividends Horizon panel system.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 Desk components include full-height back panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges

For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.


Bridge Units

Bridge units are used to form freestanding "U" shaped workstations.

Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.

Available Sizes

- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"




Series 2 Return Sizes Available

	18"D	24"D
30"W		
42"W		
48"W		

Series 2 Bridge Unit Sizes Available

30"W		
42"W		
48"W		

Series 2 Desk Configurations






Preconfigured Desks

Series 2 Returns and Bridge Units

18" and 24" Deep

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
 End Panel Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 3618N	\$827.	\$889.	\$914.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 3624N	904.	967.	1,000.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 4218N	870.	931.	963.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 4224N	947.	1,012.	1,046.
 Pedestal Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)3618N	1,069.	1,155.	1,196.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)3624N	1,169.	1,257.	1,302.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4218N	1,116.	1,200.	1,239.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4224N	1,215.	1,305.	1,348.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4818N	1,158.	1,239.	1,284.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4824N	1,261.	1,354.	1,401.
 Bridge Unit	30"	29 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3018N	403.	422.	428.
	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3618N	445.	465.	474.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3624N	476.	497.	505.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4218N	482.	503.	512.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4224N	523.	543.	552.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4818N	523.	543.	552.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4824N	569.	591.	601.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestal Return 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Pedestal Return <i>Example:</i> DD2P L4824N, 117, 117, 117 DP2P Pattern Number L4824N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish End Panel Return or Bridge Unit <i>Example:</i> DD2B 4224N, 117, 117, 117 DD2B Pattern Number 4424 117 Soft Grey laminate 117 Soft Grey finish 117 Soft Grey finish	Pedestal Return <ul style="list-style-type: none"> • Worksurface • Pedestal • Back panel • Half height flat bracket (1) • Connecting hardware End Panel Return or Bridge Unit <ul style="list-style-type: none"> • Worksurface • Back panel • Half height flat brackets (2) • Connecting hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Pedestal Return <ul style="list-style-type: none"> • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19 • To specify pedestal without locks, replace the 5th digit "L" from the pattern number with "N". Deduct \$22 End Panel Return or Bridge Unit <ul style="list-style-type: none"> • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19

Preconfigured Desks

Returns and Bridge Units

Specifications

End Panel and Pedestal Returns

Dividends freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and half-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and half-height back panel.

Available Sizes

- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment

Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction

All freestanding returns match the aesthetics of the Dividends panel system.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset 3/4" from the pedestal backs and match the softly radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges

For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.

Bridge Units


Bridge units are used to form freestanding "U" shaped workstations.

Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.


Available Sizes

- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"

Pedestal Return



End Panel Return



Bridge Unit





Return Sizes Available

	18D	24D
30W		
30W		
42W		
42W		
48W		

Bridge Unit Sizes Available

30W		
42W		
42W		
48W		




Freestanding Configuration



Preconfigured Desks

Returns and Bridge Units

18" and 24" Deep

description	w*	w	d	h	pattern no.	P1	P2	P3
 End Panel Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 3618N	\$827.	\$889.	\$914.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 3624N	904.	967.	1,000.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 4218N	870.	931.	963.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 4224N	947.	1,012.	1,046.
 Pedestal Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)3618N	1,069.	1,155.	1,196.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)3624N	1,169.	1,257.	1,302.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4218N	1,116.	1,200.	1,239.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4224N	1,215.	1,305.	1,348.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4818N	1,158.	1,239.	1,284.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4824N	1,261.	1,354.	1,401.
 Bridge Unit	30"	29 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3018N	403.	422.	428.
	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3618N	445.	465.	474.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3624N	476.	497.	505.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4218N	482.	503.	512.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4224N	523.	543.	552.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4818N	523.	543.	552.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4824N	569.	591.	601.

w* = nominal width
 Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestal Return 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish 5. Pull Finish 6. Drawer Top Cap Finish	Pedestal Return <i>Example:</i> DD1P L4824N, 117, 117, 117, 117, 117 DP1P Pattern Number L4824N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish 117 Soft Grey pull finish 117 Soft Grey top cap finish	Pedestal Return <ul style="list-style-type: none"> • Worksurface • Pedestal • Back panel • Half height flat bracket (1) • Connecting hardware End Panel Return or Bridge Unit <ul style="list-style-type: none"> • Worksurface • Back panel • Half height flat brackets (2) • Connecting hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Pedestal Return <ul style="list-style-type: none"> • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19 • To specify pedestal without locks, replace the 5th digit "L" from the pattern number with "N". Deduct \$22 End Panel Return or Bridge Unit <ul style="list-style-type: none"> • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19
End Panel Return or Bridge Unit 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	End Panel Return or Bridge Unit <i>Example:</i> DD1B 4224N, 117, 117, 117 DD1B Pattern Number 4424 117 Soft Grey laminate 117 Soft Grey edge band 117 Soft Grey finish		

Desk Components

End Units

Planning Guidelines

Desk End Units

Dividends desk end units are an "L" shaped, non-handed design that can be used on either end of a worksurface in freestanding and panel applications. Desk end units have the same footprint (outside dimension) as pedestals and can be interchanged with pedestals.

End units are used in "Preconfigured" single pedestal desks and end panel returns.

They can also be specified by component for "Build-to-Spec" applications.

These include when an end panel is required on one end and a desk integration unit is required on the other, or when an end unit is required on both ends of the worksurface.

Available Sizes

Depths: 18", 24" and 30"

Width: 15"

Height: 26⁷/₈"

Desk End Unit Attachment

Desk end units have mounting brackets that allow attachment to worksurfaces with supplied screws. Dividends worksurfaces are pre-drilled for end unit attachment.

Construction

End unit specifications:

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glides: ³/₈" 16-gauge steel with 1¹/₂" of height adjustment
- Attachment bracket: 11-gauge steel

Desk Integration End Units

If a back panel (modesty) is required in a systems application, a desk integration end unit can be used in place of an end unit.

Panel-to-worksurface brackets are included and make the connection between the worksurface and Dividends Horizon panels. Desk integration end units are 15" wide.

Note: The desk integration end unit is a non-structural support. Panel-to-work surface brackets provide the actual support for the worksurface.

Note: Panel width must match the depth of the connecting worksurface.

Construction

Desk integration end unit specifications:

- Outer skin: 20-gauge steel
- Panel-to-worksurface brackets: 14-gauge steel

Intermediate End Units

Intermediate end units are freestanding "T" shaped end units used to support two desks in an in-line configuration.

Units attach to 18", 24" and 30" deep worksurfaces in place of desk end units. Mounting brackets and a front worksurface alignment plate are included with intermediate end units.

Available Size


- Depth: 14"
- Width: 30"
- Height: 26⁷/₈"

Construction


Intermediate end unit specifications:

- Outer skin: 20-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel


Desk End Unit




Intermediate End Unit




Desk Integration End Unit (Non-structural)



Desk End Unit Available Sizes






End Unit Configurations



End Units

Desk End, Desk Integration and Intermediate

description	d*	d	w	h	pattern no.	P1	P2	P3
 Desk End Unit	18"	16 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU18	\$395.	\$435.	\$457.
	24"	22 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU24	436.	479.	502.
	30"	28 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU30	475.	521.	547.
 Desk Integration End Unit (Non-structural)	1 ¹ / ₂ "	1 ¹ / ₂ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 DIEU	220.	240.	250.
 Intermediate End Unit	14"	12"	31 ⁹ / ₁₆ "	26 ⁷ / ₈ "	DD1 IE30	395.	435.	457.

d* = nominal depth

Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Desk End Unit 1. Pattern Number 2. Paint Finish	Desk End Unit <i>Example:</i> DD1 EU18, 117 DD1 EU18 Pattern Number 117 Soft Grey Paint Finish	Desk End Unit Desk Integration End Unit • Panel-to-Worksurface Brackets (2) Intermediate End Unit	Desk End Unit Desk Integration End Unit Intermediate End Unit
Desk Integration End Unit 1. Pattern Number 2. Paint Finish	Desk Integration End Unit <i>Example:</i> DD1 DIEU, 117 DD1 DIEU Pattern Number 117 Soft Grey Paint Finish		
Intermediate End Unit 1. Pattern Number 2. Paint Finish	Intermediate End Unit <i>Example:</i> DD1 IE30, 117 DD1 IE30 Pattern Number 117 Soft Grey Paint Finish		

Desk Components

Half Height Back Panels

Planning Guidelines

Half Height Back Panels

Dividends back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units. Back panels are softly-radiused to match the aesthetics of the Dividends Horizon system and extend 11" down from the worksurface to provide a half-height modesty.

Back panels are used in "Preconfigured" desks or can be specified separately by component for "Build-to-Spec" applications.

Available Sizes

- Widths: 19⁵/₈" to 48¹/₄" see compatibility chart (below)
- Height: 11"

Back Panel Attachment

Back panels attach to the undersides of worksurfaces with mounting brackets and do not require attachment to adjacent pedestals or end units. Dividends Horizon worksurfaces are pre-drilled for back panel attachment.

Construction

- Back panel specifications:
- Outer skin: 22-gauge steel
 - Mounting Brace: 16-gauge


Back Panel Compatibility

The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management

When installed, back panels provide a 1/2" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations



Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	23 7/8"	DD1 BPD54	2
	60	29 7/8"	DD1 BPD60	2
	66	35 7/8"	DD1 BPD66	2
	72	41 7/8"	DD1 BPD72	2
Returns	36	21 5/8"	DD1 BPR36	1
	42	27 5/8"	DD1 BPR42	1
	48	33 5/8"	DD1 BPR48	1
	60	45 5/8"	DD1 BPR60	1
Bridge Units	30	31 3/8"	DD1 BPB30	0
	36	37 3/8"	DD1 BPB36	0
	42	43 3/8"	DD1 BPB42	0
	48	49 3/8"	DD1 BPB48	0
"U" Credenza w/2 peds	72	26 15/16"	DD1 BPU72	3
Freestanding Corner Unit (needs two back panels)	36	20 15/16"	DD1 BPV36	3
	42	26 15/16"	DD1 BPV42	3
	48	32 15/16"	DD1 BPV48	3





Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

Desk Components

Half Height Back Panels

For Desks, Returns, Bridges and 2 Pedestal Configuration

Dividends Horizon

description	top width	w *	h	pattern no.	P1	P2	P3
 Half Height Back panels for Desks	54"	29 ⁷ / ₈ "	11"	DD1 BPD54	\$221.	\$241.	\$252.
	60"	29 ⁷ / ₈ "	11"	DD1 BPD60	232.	255.	265.
	66"	35 ⁷ / ₈ "	11"	DD1 BPD66	244.	268.	279.
	72"	41 ⁷ / ₈ "	11"	DD1 BPD72	257.	281.	297.
 Half Height Back panels for Returns	36"	21 ⁵ / ₈ "	11"	DD1 BPR36	197.	216.	225.
	42"	27 ⁵ / ₈ "	11"	DD1 BPR42	204.	225.	237.
	48"	33 ³ / ₈ "	11"	DD1 BPR48	220.	240.	250.
	60"	45 ³ / ₈ "	11"	DD1 BPR60	244.	268.	279.
 Half Height Back panels for Bridges	30"	31 ³ / ₈ "	11"	DD1 BPB30	173.	191.	201.
	36"	37 ³ / ₈ "	11"	DD1 BPB36	187.	204.	213.
	42"	43 ³ / ₈ "	11"	DD1 BPB42	197.	216.	225.
	48"	49 ³ / ₈ "	11"	DD1 BPB48	207.	228.	240.
 Half Height Back panels for 2 Pedestal "U" Credenza	72"	26 ¹⁵ / ₁₆ "	11"	DD1 BPU72	197.	216.	225.

Freestanding Desks

Dimensions listed under w h are actual to the nearest¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Back Panels for Bridges 1. Pattern Number 2. Paint Finish	Back Panels for Bridges <i>Example:</i> DD1 BPB36 , 117 <hr/> DD1 Pattern Number BPB36 <hr/> 117 Soft Grey Paint Finish	Back Panels for Bridges • Attachment Hardware	Back Panels for Bridges

Desk Components

Full Back Panels

Planning Guidelines

Full Back Panels

Dividends full back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units.

Full back panels are specified separately by component for "Build-to-Spec" applications.

Available Sizes

- Widths: 19⁵/₈" to 48¹/₄" see compatibility chart (above)
- Height: 26⁵/₈"

Full Back Panel Attachment

Back panels attach to the undersides of pedestals or end units with mounting brackets.

Construction

Back panel specifications:

- Outer skin: 20-gauge steel
- Mounting Brace: 16-gauge


Back Panel Compatibility

The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management

When installed, back panels provide a 1/2" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations







Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	23 ⁷ / ₈ "	DD1 FFBDP54	2
	60	29 ⁷ / ₈ "	DD1 FFBDP60	2
	66	35 ⁷ / ₈ "	DD1 FBPD66	2
	72	41 ⁷ / ₈ "	DD1 FBPD72	2
Returns	36	21 ⁵ / ₈ "	DD1 FBPR36	1
	42	27 ⁵ / ₈ "	DD1 FBPR42	1
	48	33 ⁵ / ₈ "	DD1 FBPR48	1
	60	45 ⁵ / ₈ "	DD1 FBPR60	1
Bridge Units	30	31 ⁵ / ₈ "	DD1 FBPB30	0
	36	37 ⁵ / ₈ "	DD1 FBPB36	0
	42	43 ⁵ / ₈ "	DD1 FBPB42	0
	48	49 ⁵ / ₈ "	DD1 FBPB48	0
"U" Credenza w/2 peds	72	26 ¹⁵ / ₁₆ "	DD1 FBPU72	3
Freestanding Corner Unit (needs two back panels)	36	20 ¹⁵ / ₁₆ "	DD1 FBPV36	3
	42	26 ¹⁵ / ₁₆ "	DD1 FBPV42	3
	48	32 ¹⁵ / ₁₆ "	DD1 FBPV48	3

Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

Full Back Panels

For Desks, Returns, Bridges and 2 Pedestal Configuration

description	top width	w *	h	pattern no.	P1	P2	P3
Full Back panels for Desks 	54"	23 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD54	\$261.	\$288.	\$301.
	60"	29 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD60	266.	294.	307.
	66"	35 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD66	274.	302.	311.
	72"	41 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD72	283.	309.	325.
Full Back panels for Returns 	36"	21 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR36	246.	269.	283.
	42"	27 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR42	252.	276.	289.
	48"	33 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR48	262.	289.	302.
	60"	45 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR60	288.	312.	333.
Full Back panels for Bridges 	30"	31 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB30	231.	253.	263.
	36"	37 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB36	242.	266.	277.
	42"	43 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB42	262.	289.	302.
	48"	49 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB48	269.	298.	309.
Full Back panels for 2 Pedestal "U" Credenza 	72"	26 ¹⁵ / ₁₆ "	26 ⁵ / ₈ "	DD1 FBPU72	252.	276.	289.

Dimensions listed under w h are actual to the nearest¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Back Panels for Bridges 1. Pattern Number 2. Paint Finish	Back Panels for Bridges <i>Example:</i> DD1 FBPB36 , 117 <hr/> DD1 Pattern Number FBPB36 <hr/> 117 Soft Grey Paint Finish	Back Panels for Bridges • Attachment Hardware	Back Panels for Bridges

Pencil Tray

Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13¹/₄ wide, 5⁷/₁₆ deep and ⁷/₈ high. Black or clear finish available.

Hanging File Bar

Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.

Note: A hanging file bar is included with each file drawer when ordering desks or DS1 style pedestals.

Drawer Dividers

Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.

Stationery Inserts

Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.

Pencil Drawer

For use with freestanding desks or panel-mounted worksurfaces with depths of 24 or more. 24 wide, 17⁵/₈ deep and 2 high. Black finish.

Attachment: Mounts on underside of worksurface with included mounting hardware

Pedestal Lock Retrofit Kit

Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core (keyed randomly unless specified keyed alike) and lock rod assembly (must be specified box/box/file or file/file).

Flat Brackets

Allow same-height worksurfaces to be joined in perpendicular configurations. All flat brackets are 3³/₄ wide. Black finish.

Three sizes available to support the following worksurface depths:

- 18 deep worksurfaces
- 24 deep worksurfaces
- 30 deep worksurfaces
- Construction: 14-gauge steel
- Attachment: Mounts on underside of worksurfaces in pre-drilled locations with included mounting hardware

Worksurface Cable Management Clips

Self-adhesive, injection-molded clips adhere to any flat, nonporous surface to route cables along and beneath worksurfaces. ³/₄ x ¹/₂ internal dimension.

Worksurface Cable Management Basket


Steel wire basket attaches to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable basket slides forward to a position abutting the panel face to allow the passage of cords and cables. Black finish.

Worksurface Edge Grommet


Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.

Worksurface Reinforcement


Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.




Pencil Tray




Pencil Drawer




Stationery Inserts




Worksurface Cable Management Clip




Hanging File Bar




Drawer Divider, File Drawer




Flat Bracket




Worksurface Cable Management Basket



Drawer Divider, Box Drawer














Worksurface Reinforcement Panel Hung Application



Worksurface Edge Grommet

Drawer Organizers, Cable Management and Grommet Kits

description	type	w	d	h	pattern no.	list
 Pencil Tray	Black finish	13 1/4"	5 7/8"	7/8"	DS2PPTN	\$43.
	Clear finish	13 1/4"	5 7/8"	7/8"	DS2PPTC	50.
 Hanging File Bar		12 3/16"	2 15/16"	1/2"	DS1PFS	37.
 Drawer Divider, Box		12 3/8"	3"	3 1/8"	DS1PBD	37.
 Drawer Divider, File		10	3 7/8"	6 3/8"	DS1PFD	37.
 Stationary Inserts, box (4 trays)		13	1 5/16"	8 7/8"	DS1PST	196.
 Pencil Drawer		24"	17 3/8"	2"	DS1PCD	265.
 Workspace Cable Management Clip	Package of 10	3/4"	1/2"		D1WC	44.
 Workspace Cable Management Basket	19 1/2" wide	16 1/2"	3 1/2"	1 1/2"	D1WB20	46.
	25 1/2" wide	25 1/2"	3 1/2"	1 1/2"	D1WB26	48.
	31 1/2" wide	31 1/2"	3 1/2"	1 1/2"	D1WB32	60.
	35" wide	35"	3 1/2"	1 1/2"	D1WB36	67.
	41" wide	41"	3 1/2"	1 1/2"	D1WB42	71.
 Workspace Grommet Kit (Dark Grey)		2 3/16"	2 5/16"	1 3/8"	D1WSG	27.
 Satellite Support Assembly, Circular		16"	16"	3 7/8"	DSSAC	470.
 Satellite Support Assembly, Soft Rectangle		16"	18"	3 7/8"	DSSAR	470.




Freestanding Desks

Ordering Information	Order Code	Included with:	Options
Pencil Tray 1. Pattern Number	Pencil Tray <i>Example:</i> DS1 PPT DS1 PPT Pattern Number	Pencil Tray	

Desk Accessories

Flat Brackets and Worksurface Reinforcements

Dividends Horizon

description	w	d	pattern no.	list
Flat Bracket (single pack) 	$3\frac{3}{4}''$	$8\frac{5}{16}''$	DB1F18SP	\$27.
	$3\frac{3}{4}''$	$14\frac{5}{8}''$	DB1F24SP	31.
	$3\frac{3}{4}''$	$20\frac{15}{16}''$	DB1F30SP	35.
Flat Bracket (package of 10) 	$3\frac{3}{4}''$	$8\frac{5}{16}''$	DB1F18TP	147.
	$3\frac{3}{4}''$	$14\frac{5}{16}''$	DB1F24TP	244.
	$3\frac{3}{4}''$	$20\frac{3}{16}''$	DB1F30TP	281.
Worksurface Reinforcement 	54"	4"	DB1WR54	71.
	60"	4"	DB1WR60	72.
	66"	4"	DB1WR66	75.
	72"	4"	DB1WR72	78.

Ordering Information

Flat Bracket
1. Pattern Number

Order Code

Flat Bracket
Example: **DB1PWSP**
DB1PWSP Pattern Number

Included with:

Flat Bracket

Options

Flat Bracket

Wall Mounting Suggestions

The following information is provided only as a guide, and represents minimum recommendations only. Knoll does not accept responsibility for the attachment of any Knoll product to a Customer's site wall. Wall specification/construction is the responsibility of the Customer and its structural engineer/architect. Failure to properly attach Knoll products to adequate wall structures can lead to property damage and/or personal injury.

You should consult your own structural engineers and/or architects and must not rely on the information provided herein.

It is the responsibility of the Customer and its structural engineers/architects to verify that the permanent structural walls (studs, blocks, solid masonry, etc.) on which the Knoll products are intended to be mounted are designed appropriately to support the product weight, PLUS 3 lbs. per linear inch for each useable shelf length

NOTE: A cabinet's top is considered a "useable shelf" and MUST be included in the calculation of the total load for an overhead cabinet.

It is the responsibility of the Customer and its structural engineer/architects to specify the fasteners and method for attaching the Knoll supplied wall mounting cleat, bracket, frame, etc. to the supporting wall and to confirm that the installers have adhered to these specifications. For all local building standards and codes, and additional requirements (including, but not limited to, seismic conditions) the Customer should always consult local code agencies.

	EXISTING CONSTRUCTION					
	NEW CONSTRUCTION	Cinder Block or Poured Concrete Masonry Wall	Wood Stud Wall, the studs being FULL HEIGHT to the roof/floor above	Wood Stud Wall, the studs being only Ceiling Height	Steel Stud Wall, the studs being FULL HEIGHT to the roof/floor above	Steel Stud Wall, the studs being only Ceiling Height
Stud Specification	Wood studs, grade #2 or better, 3 1/2" minimum width, OR Metal studs, minimum 25 gage thickness, 3 5/8" minimum width	The wall must be a minimum of 6" thick, and must be full height to the roof/ floor structure above	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width
Stud Centers	Metal and wood studs must be spaced at 16" c/c maximum	N/A	Wood studs must be spaced at 16" c/c maximum	Wood studs must be spaced at 16" c/c maximum"	Metal studs must be spaced at 16" c/c maximum	Metal studs must be spaced at 16" c/c maximum
Stud Height	Metal and wood studs must extend upwards, and be securely attached to the roof/ floor structure above			Wood studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix #2 grade 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof/ floor structure above		Metal studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix metal bracing 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof / floor structure above
Mounting the Knoll Supplied Cleat, Bracket, Frame, etc*	Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the studs to accommodate the full width of the cabinet, and beyond to the next stud. Fasten the wood block to each stud using three screws at the ends of each block. (Fasten the Danback™ as directed by the manufacturer) Fasten the Knoll supplied wall mounting cleat, bracket, frame, etc directly to each wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	Fasten the Knoll supplied cabinet wall mounting cleat, bracket, frame, etc. directly to the masonry wall every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wall every 6", and fasten the lower horizontal element to the wall every 16"	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.
*Graham Wall Hung Shelf	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	Fasten the Knoll supplied wall mounting brackets directly to the masonry wall, using the holes provided in each bracket	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above
Fasten the Knoll supplied wall cleat with...	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	3/16" x 3 1/2" Tapcon Masonry Screws or equiv. @ 6" c/c with 1-1/4" embedment, screwed directly into the masonry wall	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking

Alpha-Numeric Index

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
D19 6630N	321	D1L 6642SSN	317	DIR 8418N	297	D1W S723018N	304
D19 7230N	321	D1L 6648DSN	319	DIR 8424N	297	D1W S723024N	304
D19 7830N	321	D1L 6648SDN	319	DIR 8430N	301	D1W S781824N	304
D1BD6648DL	321	D1L 6648SSN	317	DIR 8436N	301	D1W S781830N	304
D1BD6648DR	321	D1L 7242SSN	317	DIR 9015	325	D1W S782418N	304
D1BD6648SL	321	D1L 7248DSN	319	DIR 9018N	297	D1W S782430N	304
D1BD6648SR	321	D1L 7248SDN	319	DIR 9024N	297	D1W S783018N	304
D1BD7248DL	321	D1L 7248SSN	317	DIR 9030N	301	D1W S783024N	304
D1BD7248DR	321	D1L 7842SSN	317	DIR 9036N	301	D1W S841824N	304
D1BD7248SL	321	D1L 7848SSN	317	DIR 9615	325	D1W S841830N	304
D1BD7248SR	321	D1L 8448SSN	317	DIR 9618N	297	D1W S842418N	304
D1C 3618N	315	D1P 6630N	321	DIR 9624N	297	D1W S842430N	304
D1C 3624N	315	D1P 7230N	321	DIR 9630N	301	D1W S843018N	304
D1C 422430N	315	D1P 7830N	321	DIR 9636N	301	D1W S843024N	304
D1C 4224N	315	DIR 1515C	325	DIR2419N	299	D1W T482430N	312
D1C 423024N	315	DIR 1515S	325	DIR3019N	299	D1W T483024N	312
D1C 482430N	315	DIR 2415	325	DIR3619N	299	D1W T602430N	312
D1C 4824N	315	DIR 2418N	297	DIR4219N	299	D1W T603024N	312
D1C 483024N	315	DIR 2424N	297	DIR4819N	299	D1W T662430N	312
D1C 4830N	315	DIR 2430N	301	DIR5419N	299	D1W T663024N	312
D1CRL24	323	DIR 3015	325	DIR6019N	299	D1W T722430N	312
D1CRN24	323	DIR 3018N	297	DIR6619N	299	D1W T723024N	312
D1CRR24	323	DIR 3024N	297	DIR7219N	299	D1WB20	209, 387
D1CS 4224N	315	DIR 3030N	301	DIR7819N	299	D1WB26	209, 387
D1CS 4824N	315	DIR 3615	325	DIR8419N	299	D1WB32	209, 387
D1CS 4830N	315	DIR 3618N	297	DIR9019N	299	D1WB36	209, 387
D1D 4824N	321	DIR 3624N	297	DIR9619N	299	D1WB42	209, 387
D1D 4830N	321	DIR 3630N	301	D1W 362430N	303	D1WC	209, 387
D1D 6030N	321	DIR 4215	325	D1W 363024N	303	D1W5C	245, 387
D1D 6630N	321	DIR 4218N	297	D1W 422430N	303	D1WT218	173
D1D 7230N	321	DIR 4224N	297	D1W 423024N	303	D1WT224	173
D1D 7236N	321	DIR 4230N	301	D1W 482430N	303	D1WT324	173
D1H4818	323	DIR 4815	325	D1W 483024N	303	D1WT424	173
D1H5118P	323	DIR 4818N	297	D1W 721830N	303	D1WT518	173
D1H6024	323	DIR 4824N	297	D1W 722430N	303	D1WT524	173
D1H6324P	323	DIR 4830N	301	D1W 722436N	303	D1WW11481824	173
D1L 3636SSN	317	DIR 5415	325	D1W 723018N	303	D1WW11482418	173
D1L 4242SSN	317	DIR 5418N	297	D1W 723024N	303	D1WW12481824	173
D1L 4260SSN	317	DIR 5424N	297	D1W 723624N	303	D1WW12482418	173
D1L 4266SSN	317	DIR 5430N	301	D1W S481824N	304	D1WW124824L	173
D1L 4272SSN	317	DIR 6015	325	D1W S481830N	304	D1WW124824R	173
D1L 4278SSN	317	DIR 6018N	297	D1W S482418N	304	D1WW13481824	173
D1L 4848DDN	319	DIR 6024N	297	D1W S482430N	304	D1WW13482418	173
D1L 4848DSN	319	DIR 6030N	301	D1W S483018N	304	D1WW134824L	173
D1L 4848SDN	319	DIR 6036N	301	D1W S483024N	304	D1WW134824R	173
D1L 4848SSN	317	DIR 6615	325	D1W S601824N	304	D1WW34824	173
D1L 4860DSN	319	DIR 6618N	297	D1W S601830N	304	D1WW44824	173
D1L 4860SDN	319	DIR 6624N	297	D1W S602418N	304	D1WW54824L	173
D1L 4860SSN	317	DIR 6630N	301	D1W S602430N	304	D1WW54824R	173
D1L 4866DSN	319	DIR 6636N	301	D1W S603018N	304	D1WW64824L	173
D1L 4866SDN	319	DIR 7215	325	D1W S603024N	304	D1WW64824R	173
D1L 4866SSN	317	DIR 7218N	297	D1W S661824N	304	D1WW74824L	173
D1L 4872DSN	319	DIR 7224N	297	D1W S661830N	304	D1WW74824R	173
D1L 4872SDN	319	DIR 7230N	301	D1W S662418N	304	D2H4824	323
D1L 4872SSN	317	DIR 7236N	301	D1W S662430N	304	D2H4836	323
D1L 4878SSN	317	DIR 7815	325	D1W S663018N	304	D2H4848	323
D1L 4884SSN	317	DIR 7818N	297	D1W S663024N	304	D2H5124P	323
D1L 6042SSN	317	DIR 7824N	297	D1W S721824N	304	D2H5136P	323
D1L 6048DSN	319	DIR 7830N	301	D1W S721830N	304	D2H5148P	323
D1L 6048SDN	319	DIR 7836N	301	D1W S722418N	304	D2P1	81
D1L 6048SSN	317	DIR 8415	325	D1W S722430N	304	DB120C (L or R)	333

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DB1BD48SL	321	DB2CL24RS	339	DCE1R4224N	326	DD1B 3018N	379
DB1BD48SR	321	DBSCR	341	DCE1R4230N	326	DD1B 3618N	379
DB1C 18 (L or R) 10	333	DBSMLH	337	DCE1R4824N	326	DD1B 3624N	379
DB1C 24 (L or R) 10	333	DBSMRH	337	DCE1R4830N	326	DD1B 4218N	379
DB1C 30 (L or R) 10	333	DBVDC (L or R)	334	DCE1R5424N	326	DD1B 4224N	379
DB1C18 (L or R)	333	DCE1BD6648D(L/R)	327	DCE1R5430N	326	DD1B 4818N	379
DB1C24 (L or R)	333	DCE1BD6648S(L/R)	327	DCE1R6024N	326	DD1B 4824N	379
DB1C30 (L or R)	333	DCE1BD7248D(L/R)	327	DCE1R6030N	326	DD1D L6024N	371
DB1CL 24R	339	DCE1BD7248S(L/R)	327	DCE1R6624N	326	DD1D L6030N	371
DB1CL24L	339	DCE1BD7848D(L/R)	327	DCE1R6630N	326	DD1D L6624N	371
DB1CL24S	339	DCE1BD7848S(L/R)	327	DCE1R7224N	326	DD1D L6630N	371
DB1F18SP	333, 388	DCE1BD8448D(L/R)	327	DCE1R7230N	326	DD1D L7224N	371
DB1F18TP	333, 388	DCE1BD8448S(L/R)	327	DCE1R7824N	326	DD1D L7230N	371
DB1F24SP	333, 388	DCE1CR24L	329	DCE1R7830N	326	DD1E 3618N	379
DB1F24TP	333, 388	DCE1CR24N	329	DCE1R8424N	326	DD1E 3624N	379
DB1F30SP	333, 388	DCE1CR24R	329	DCE1R8430N	326	DD1E 4218N	379
DB1F30TP	333, 388	DCE1H4818	329	DCE1R9024N	326	DD1E 4224N	379
DB1LS15A	341	DCE1H4818P	329	DCE1R9030N	326	DD1O L6036N	371
DB1LS18A	341	DCE1H6024	329	DCE1R9624N	326	DD1O L6636N	371
DB1LS24A	341	DCE1H6024P	329	DCE1R9630N	326	DD1O L7236N	371
DB1LS30A	341	DCE1L3636SSN	327	DCE1W362430N	330	DD1P (L)3618N	379
DB1LS36A	341	DCE1L4242DSN	327	DCE1W363024N	330	DD1P (L)3624N	379
DB1LSP15	339	DCE1L4242SDN	327	DCE1W422430N	330	DD1P (L)4218N	379
DB1LSP18	339	DCE1L4242SSN	327	DCE1W423024N	330	DD1P (L)4224N	379
DB1LSP24	339	DCE1L4260SSN	328	DCE1W482430N	330	DD1P (L)4818N	379
DB1LSP30	339	DCE1L4266SSN	328	DCE1W483024N	330	DD1P (L)4824N	379
DB1LSP36	339	DCE1L4272SSN	328	DCE1W722430N	330	DD1R CU6	373, 375
DB1LSS15	339	DCE1L4278SSN	328	DCE1W723024N	330	DD1S CU12	375
DB1LSS18	339	DCE1L4848DDN	327	DD1 BPB30	383	DD1S L6024N	371
DB1LSS24	339	DCE1L4848DSN	327	DD1 BPB36	383	DD1S L6030N	371
DB1LSS30	339	DCE1L4848SDN	327	DD1 BPB42	383	DD1S L6624N	371
DB1LSS36	339	DCE1L4848SSN	327	DD1 BPB48	383	DD1S L6630N	371
DB1PSP15	339	DCE1L4860DSN	328	DD1 BPD54	383	DD1S L7224N	371
DB1PSP18	339	DCE1L4860SDN	328	DD1 BPD60	383	DD1S L7230N	371
DB1PSP19	339	DCE1L4860SSN	328	DD1 BPD66	383	DD1TEU24	341
DB1PSP24	339	DCE1L4866DSN	328	DD1 BPD72	383	DD1TEU30	341
DB1PSP30	339	DCE1L4866SDN	328	DD1 BPR36	383	DD1VD 3624 N	375
DB1PSP36	339	DCE1L4866SSN	328	DD1 BPR42	383	DD1VD 4224 N	375
DB1PWS24	334	DCE1L4872DSN	328	DD1 BPR48	383	DD1VD 4824 N	375
DB1PWS30	334	DCE1L4872SDN	328	DD1 BPR60	383	DD1VL 3624 N	375
DB1PWS36	334	DCE1L4872SSN	328	DD1 BPU72	383	DD1VL 4224 N	375
DB1PWS42	334	DCE1L4878SSN	328	DD1 BPV36	375	DD1VL 4824 N	375
DB1PWS48	334	DCE1L4884SSN	328	DD1 BPV42	375	DD2B 3018N	377
DB1PWSL	333	DCE1L6042SSN	328	DD1 BPV48	375	DD2B 3618N	377
DB1PWSL10	334	DCE1L6048DSN	328	DD1 DIEU	381	DD2B 3624N	377
DB1PWSLWH	334	DCE1L6048SDN	328	DD1 EU18	381	DD2B 4218N	377
DB1PWSP	333	DCE1L6048SSN	328	DD1 EU24	381	DD2B 4224N	377
DB1PWSPWH	334	DCE1L6642SSN	328	DD1 EU30	381	DD2B 4818N	377
DB1PWSR	333	DCE1L6648DSN	328	DD1 FBPB30	385	DD2B 4824N	377
DB1PWSR10	334	DCE1L6648SDN	328	DD1 FBPB36	385	DD2D L6024N	369
DB1PWSRWH	334	DCE1L6648SSN	328	DD1 FBPB42	385	DD2D L6030N	369
DB1RU18	229, 234	DCE1L7242SSN	328	DD1 FBPB48	385	DD2D L6624N	369
DB1S CR	341	DCE1L7248DSN	328	DD1 FBPD54	385	DD2D L6630N	369
DB1SWSL	337	DCE1L7248SDN	328	DD1 FBPD60	385	DD2D L7224N	369
DB1SWSP	337	DCE1L7248SSN	328	DD1 FBPD66	385	DD2D L7230N	369
DB1SWSR	337	DCE1L7842SSN	328	DD1 FBPD72	385	DD2E 3618N	377
DB1TB	341	DCE1L7848SSN	328	DD1 FBPR36	385	DD2E 3624N	377
DB1U18	229, 234	DCE1L8448SSN	328	DD1 FBPR42	385	DD2E 4218N	377
DB1WR54	333, 388	DCE1R1212G	326	DD1 FBPR48	385	DD2E 4224N	377
DB1WR60	333, 388	DCE1R2424N	326	DD1 FBPR60	385	DD2O L6036N	369
DB1WR66	333, 388	DCE1R2430N	326	DD1 FBPU72	385	DD2O L6636N	369
DB1WR72	333, 388	DCE1R3024N	326	DD1 FBPV36	375	DD2O L7236N	369
DB2CL24L	339	DCE1R3030N	326	DD1 FBPV42	375	DD2OD 36L	269
DB2CL24LS	339	DCE1R3624N	326	DD1 FBPV48	375	DD2OD 42L	269
DB2CL24R	339	DCE1R3630N	326	DD1 IE30	381	DD2OD 48L	269

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DD20D 54L	269	DE1(E,8,T) PJ18NP	179	DE40C202120 (BB/WW/WS)	193	DP1AU0717	119
DD20D 60L	269	DE1(E,8,T) PJ18WP	179	DE40C20272 (BB/WW/WS)	193	DP1AU0718	119
DD20D 66L	269	DE1(E,8,T) PJ24NP	179	DE40C202H (BB/WW/WS)	193	DP1AU0723	119
DD20D 72L	269	DE1(E,8,T) PJ24WP	179	DE40C210120 (BB/WW/WS)	193	DP1AU0724	119
DD2P (L)3618N	377	DE1(E,8,T) PJ30NP	179	DE40C21072 (BB/WW/WS)	193	DP1AU0729	119
DD2P (L)3624N	377	DE1(E,8,T) PJ30WP	179	DE40C210H (BB/WW/WS)	193	DP1AU0730	119
DD2P (L)4218N	377	DE1(E,8,T) PJ36NP	179	DE40C311120 (BB/WW/WS)	193	DP1AU0735	119
DD2P (L)4224N	377	DE1(E,8,T) PJ36WP	179	DE40C31172 (BB/WW/WS)	193	DP1AU0736	119
DD2P (L)4818N	377	DE1(E,8,T) PJ42NP	179	DE40C311H (BB/WW/WS)	193	DP1AU0741	119
DD2P (L)4824N	377	DE1(E,8,T) PJ42WP	179	DE40C412120 (BB/WW/WS)	193	DP1AU0742	119
DD2S L6024N	369	DE1(E,8,T) PJ48NP	179	DE40C41272 (BB/WW/WS)	193	DP1AU0747	119
DD2S L6030N	369	DE1(E,8,T) PJ48WP	179, 190, 199	DE40C412H (BB/WW/WS)	193	DP1AU0748	119
DD2S L6624N	369	DE1(E,8,T) PJ54WP	180, 190, 199	DE4TU202120(BB/WW/WS)	191	DP1AU0750	164
DD2S L6630N	369	DE1(E,8,T) PJ60WP	180, 190, 199	DE4TU20272(BB/WW/WS)	191	DP1AU0751	164
DD2S L7224N	369	DE1(E,8,T) PJ66WP	180, 190	DE4TU202H(BB/WW/WS)	191	DP1AU0753	119
DD2S L7230N	369	DE1(E,8,T) PJ72WP	180, 190	DE4TU210120(BB/WW/WS)	191	DP1AU0754	119
DD2VD 3624 N	373	DE1(E,8,T) PJ78WP	180, 190	DE4TU21072(BB/WW/WS)	191	DP1AU0756	164
DD2VD 4224 N	373	DE1(E,8,T) PJ84WP	180, 190	DE4TU210H(BB/WW/WS)	191	DP1AU0757	164
DD2VD 4824 N	373	DE1(E,8,T) PJ96WP	180	DE4TU311120(BB/WW/WS)	191	DP1AU0759	119
DD2VL 3624 N	373	DE1(E,8,T) PM24	179	DE4TU31172(BB/WW/WS)	191	DP1AU0760	119
DD2VL 4224 N	373	DE1(E,8,T) PM30	179	DE4TU311H(BB/WW/WS)	191	DP1AU0762	164
DD2VL 4824 N	373	DE1(E,8,T) PM36	179	DE4TU412120(BB/WW/WS)	191	DP1AU0763	164
DD3 PS36	270	DE1(E,8,T) PM42	179	DE4TU41272(BB/WW/WS)	191	DP1AU0765	119
DD3 PS42	270	DE1(E,8,T) PM48	179	DE4TU412H(BB/WW/WS)	191	DP1AU0766	119
DD3 PS48	270	DE1(E,8,T) PM60	179	DE4WSMC	194	DP1AU0768	164
DD3 PS54	270	DE1(E,8,T) PMS24	179	DE4WSME108	194	DP1AU0769	164
DD3 PS60	270	DE1(E,8,T) PMS30	179	DE4WSME72	194	DP1AU0771	119
DD3 PS66	270	DE1(E,8,T) PMS36	179	DE4WSMED108	194	DP1AU0772	119
DD3 PS72	270	DE1(E,8,T) PMS42	179	DE4WSMED72	194	DP1AU0774	164
DE1	198, 199	DE1(E,8,T) PMS48	179	DE6 FDP	190	DP1AU0775	164
DE1 FDP	189	DE1(E,8,T) PMS60	179	DE6 FDPF	189	DP1AU0777	119
DE18 B1NY1	205	DE1HPA	198	DE6 VDR1	188	DP1AU0778	119
DE18 BI56	205	DE1SPA	198	DE6 VDR1C	189	DP1AU0780	164
DE18 BI56(L/R)	201	DE1T B1NY1	205	DE6 VDR2	188	DP1AU0781	164
DE18 CI144	201	DE1T BI56	205	DE6 VDR2C	189	DP1AU0783	119
DE18 RBI56	201	DE1T BI56(L/R)	201	DE6 VDR3	188	DP1AU0784	119
DE18 RBI56SF	205	DE1T CI144	201	DE6 VDR3C	189	DP1AU0786	164
DE1DATSHD	209	DE1T RBI56	201	DE6 VDR4	188	DP1AU0787	164
DE1DATSHDF	209	DE1T RBI56SF	205	DE6 VDR4C	189	DP1AU0789	119
DE1DOR4	183	DE1USB1H	184	DE6 VDR5	188	DP1AU0790	119
DE1DOR5	183	DE1USB1V	184	DE6 VDR5C	189	DP1AU0792	164
DE1DOR6	183	DE1USB2H	184	DE6 VDR6	188	DP1AU0793	164
DE1DR1	183	DE1USB2V	184	DE6 VDR6C	189	DP1AU0795	119
DE1DR1C	183	DE1USB3H	184	DE6 VPM	188	DP1AU0796	119
DE1DR2	183	DE1USB3V	184	DL3T5E19S	237	DP1AU0798	164
DE1DR2C	183	DE1USB4H	184	DL3T5E25A	237	DP1AU0799	164
DE1DR3	183	DE1USB4V	184	DL3T5E25S	237	DP1AU1414	120
DE1DR3C	183	DE1USB5H	184	DL3T5E37A	237	DP1AU1415	120
DE1DR4	183	DE1USB5V	184	DL3T5E37S	237	DP1AU1417	120
DE1DR4C	183	DE1USB6H	184	DL3T5E49A	237	DP1AU1418	120
DE1DR5	183	DE1USB6V	184	DL3T5E49S	237	DP1AU1423	120
DE1DR5C	183	DE2	198	DL3TC	237	DP1AU1424	120
DE1DR6	183	DE2KC10	75, 183	DL4L17	237	DP1AU1429	120
DE1DR6C	183	DE4CL202120(BB/WW/WS)	192	DL4L31	237	DP1AU1430	120
DE1E B1NY1	205	DE4CL20272(BB/WW/WS)	192	DL4L44	237	DP1AU1435	120
DE1E BI56	205	DE4CL202H(BB/WW/WS)	192	DL4L58	237	DP1AU1436	120
DE1E BI56(L/R)	201	DE4CL210120(BB/WW/WS)	192	DP	101, 102, 131, 133, 134, 137	DP1AU1441	120
DE1E CI144	201	DE4CL21072(BB/WW/WS)	192	DP1	79	DP1AU1442	120
DE1E RBI56	201	DE4CL210H(BB/WW/WS)	192	DP1 CG	143	DP1AU1447	120
DE1E RBI56SF	205	DE4CL311120(BB/WW/WS)	192	DP1 CHB	143	DP1AU1448	120
DE1(E,8,T) PC21M	179, 198	DE4CL31172(BB/WW/WS)	192	DP1 CHP	143	DP1AU1450	165
DE1(E,8,T) PCNP	179	DE4CL311H(BB/WW/WS)	192	DP1 TKC	209	DP1AU1451	164
DE1(E,8,T) PCWP	179	DE4CL412120(BB/WW/WS)	192	DP1 VWG	209	DP1AU1453	120
DE1(E,8,T) PJ15NP	179	DE4CL41272(BB/WW/WS)	192	DP1AU0714	119	DP1AU1454	120
DE1(E,8,T) PJ15WP	179	DE4CL412H(BB/WW/WS)	192	DP1AU0715	119	DP1AU1456	165

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP1AU1457	164	DPISO2130	68	DPISO5042CCF	157	DP1SOS36	69
DP1AU1459	120	DPISO2136	68	DPISO5048	57, 153	DP1SOS42	69
DP1AU1460	120	DPISO2142	68	DPISO5048CCF	157	DP1SOS48	69
DP1AU1462	165	DPISO2148	68	DPISO5048EPEF	161	DP1SOS60	69
DP1AU1463	164	DPISO2160	68	DPISO5060	57, 153	DP1SOWH15	57, 152
DP1AU1465	120	DPISO2418	75	DPISO5060CCF	157	DP1SOWH15CCF	156
DP1AU1466	120	DPISO2424	75	DPISO5060EPEF	161	DP1SOWH18	57, 152
DP1AU1468	165	DPISO2430	75	DPISO5715	58, 153	DP1SOWH18CCF	156
DP1AU1469	164	DPISO2436	75	DPISO5715CCF	157	DP1SOWH24	57, 152
DP1AU1471	120	DPISO2442	75	DPISO5718	58, 153	DP1SOWH24CCF	156
DP1AU1472	120	DPISO2448	75	DPISO5718CCF	157	DP1SOWH30	57, 152
DP1AU1474	165	DPISO2460	75	DPISO5724	58, 153	DP1SOWH30CCF	156
DP1AU1475	164	DPISO2815	57, 68, 152	DPISO5724CCF	157	DP1SOWH30EPEF	160
DP1AU1477	120	DPISO2815CCF	156	DPISO5730	58, 153	DP1SOWH36	57, 152
DP1AU1478	120	DPISO2818	57, 68, 152	DPISO5730CCF	157	DP1SOWH36CCF	156
DP1AU1480	165	DPISO2818CCF	156	DPISO5730EPEF	161	DP1SOWH36EPEF	160
DP1AU1481	164	DPISO2824	57, 68, 152	DPISO5736	58, 153	DP1SOWH42	57, 152
DP1AU1483	120	DPISO2824CCF	156	DPISO5736CCF	157	DP1SOWH42CCF	156
DP1AU1484	120	DPISO2830	57, 68, 152	DPISO5736EPEF	161	DP1SOWH48	57, 152
DP1AU1486	165	DPISO2830CCF	156	DPISO5742	58, 153	DP1SOWH48CCF	156
DP1AU1487	164	DPISO2830EPEF	160	DPISO5742CCF	157	DP1SOWH48EPEF	160
DP1AU1489	120	DPISO2836	57, 68, 152	DPISO5748	58, 153	DP1SOWH60	57, 152
DP1AU1490	120	DPISO2836CCF	156	DPISO5748CCF	157	DP1SOWH60CCF	156
DP1AU1492	165	DPISO2836EPEF	160	DPISO5748EPEF	161	DP1SOWH60EPEF	160
DP1AU1493	164	DPISO2842	57, 68, 152	DPISO5760	58, 153	DP1SW0724	95
DP1AU1495	120	DPISO2842CCF	156	DPISO5760CCF	157	DP1SW0730	95
DP1AU1496	120	DPISO2848	57, 68, 152	DPISO5760EPEF	161	DP1SW0736	95
DP1AU1498	165	DPISO2848CCF	156	DPISO6415	58, 153	DP1SW0742	95
DP1AU1499	164	DPISO2848EPEF	160	DPISO6415CCF	157	DP1SW0748	95
DP1AU1499	164	DPISO2848EPEF	160	DPISO6418	58, 153	DP1SW1424	95
DP1AU1499	164	DPISO2848EPEF	160	DPISO6418CCF	157	DP1SW1430	95
DP1AUECTP	120, 165	DPISO2860	57, 68, 152	DPISO6424	58, 153	DP1SW1436	95
DP1BCT18	210	DPISO2860CCF	156	DPISO6424CCF	157	DP1SW1442	95
DP1BCT24	210	DPISO2860EPEF	160	DPISO6430	58, 153	DP1SW1448	95
DP1BCT30	210	DPISO4215	57, 152	DPISO6430CCF	157	DP1SW2124	95
DP1BCT36	210	DPISO4215CCF	156	DPISO6430EPEF	161	DP1SW2130	95
DP1BCT42	210	DPISO4218	57, 152	DPISO6436	58, 153	DP1SW2136	95
DP1BCT48	210	DPISO4218CCF	156	DPISO6436CCF	157	DP1SW2142	95
DP1BCT60	210	DPISO4224	57, 152	DPISO6436EPEF	161	DP1SW2148	95
DP1MBT24	85	DPISO4224CCF	156	DPISO6442	58, 153	DP1SW2824	95
DP1MBT30	85	DPISO4230	57, 152	DPISO6442CCF	157	DP1SW2830	95
DP1MBT36	85	DPISO4230CCF	156	DPISO6448	58, 153	DP1SW2836	95
DP1MBT42	85	DPISO4230EPEF	160	DPISO6448CCF	157	DP1SW2842	95
DP1MBT48	85	DPISO4236	57, 152	DPISO6448EPEF	161	DP1SW2848	95
DP1PRFN15	143	DPISO4236CCF	156	DPISO6460	58, 153	DP1WT57	140
DP1PRFN70	143	DPISO4236EPEF	160	DPISO6460CCF	157	DP1WT64	140
DP1PT3	137	DPISO4242	57, 152	DPISO715	67	DP1WT71	140
DP1PT4	137	DPISO4242CCF	156	DPISO718	67	DP1WT78	140
DPISO1015	67	DPISO4248	57, 152	DPISO724	67	DP1WTBTC15	140
DPISO1018	67	DPISO4248CCF	156	DPISO730	67	DP1WTBTC18	140
DPISO1024	67	DPISO4248EPEF	160	DPISO736	67	DP1WTBTC24	140
DPISO1030	67	DPISO4260	57, 152	DPISO742	67	DP1WTBTC30	140
DPISO1036	67	DPISO4260CCF	156	DPISO748	67	DP1WTBTC36	140
DPISO1042	67	DPISO4260EPEF	160	DPISO760	67	DP1WTBTC42	140
DPISO1048	67	DPISO5015	57, 153	DPISO7815	58	DP1WTBTC48	140
DPISO1060	67	DPISO5015CCF	157	DPISO7818	58	DP1WTET57	140
DPISO1415	67	DPISO5018	57, 153	DPISO7824	58	DP1WTET64	140
DPISO1418	67	DPISO5018CCF	157	DPISO7830	58	DP1WTET71	140
DPISO1424	67	DPISO5024	57, 153	DPISO7836	58	DP1WTET78	140
DPISO1430	67	DPISO5024CCF	157	DPISO7842	58	DP1WTTC15	140
DPISO1436	67	DPISO5030	57, 153	DPISO7848	58	DP1WTTC24	140
DPISO1442	67	DPISO5030CCF	157	DPISO7884	58	DP1WTTC30	140
DPISO1448	67	DPISO5030EPEF	161	DPISO7884	58	DP1WTTC36	140
DPISO1460	67	DPISO5036	57, 153	DPISO815	69	DP1WTTC42	140
DPISO2115	68	DPISO5036CCF	157	DPISO818	69	DP1WTTC30	140
DPISO2118	68	DPISO5036EPEF	161	DPISO824	69	DP1WTTC36	140
DPISO2124	68	DPISO5042	57, 153	DPISO830	69	DP1WTTC42	140

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP1WTTTC48	140	DP3L11015	71	DP3L12848F	62, 72	DP3L15724CCF	159
DP1WTTTC54	140	DP3L11018	71	DP3L12860EPEF	162	DP3L15724F	64
DP1WTTTC60	140	DP3L11024	71	DP3L12872EPEF	162	DP3L15730	63, 155
DP1WTTTC66	140	DP3L11030	71	DP3L12884EPEF	162	DP3L15730CCF	159
DP1WTTTC72	140	DP3L11036	71	DP3L14215	61, 154	DP3L15730EPEF	163
DP1WTTTC78	140	DP3L11042	71	DP3L14215CCF	158	DP3L15730F	64
DP1WTTTC84	140	DP3L11048	71	DP3L14215F	62	DP3L15736	63, 155
DP1WTTTC90	140	DP3L11415	71	DP3L14218	61, 154	DP3L15736CCF	159
DP1WTTTC96	140	DP3L11415F	72	DP3L14218CCF	158	DP3L15736EPEF	163
DP1WTTTSB	141	DP3L11418	71	DP3L14218F	62	DP3L15736F	64
DP2 STFL1418	53	DP3L11418F	72	DP3L14224	61, 154	DP3L15742	63, 155
DP2 STFL1424	53	DP3L11424	71	DP3L14224CCF	158	DP3L15742CCF	159
DP2 STFL1430	53	DP3L11424F	72	DP3L14224F	62	DP3L15742F	64
DP2 STFL1436	53	DP3L11430	71	DP3L14230	61, 154	DP3L15748	63, 155
DP2 STFL1442	53	DP3L11430F	72	DP3L14230CCF	158	DP3L15748CCF	159
DP2 STFL1448	53	DP3L11436	71	DP3L14230EPEF	162	DP3L15748EPEF	163
DP2CHTP	143	DP3L11436F	72	DP3L14230F	62	DP3L15748F	64
DP2PMS36	137	DP3L11442	71	DP3L14236	61, 154	DP3L15760EPEF	163
DP2PMS42	137	DP3L11442F	72	DP3L14236CCF	158	DP3L15772EPEF	163
DP2PMS50	137	DP3L11448	71	DP3L14236EPEF	162	DP3L15784EPEF	163
DP2PMS57	137	DP3L11448F	72	DP3L14236F	62	DP3L1WH15	61, 154
DP2PMS64	137	DP3L12115	71	DP3L14242	61, 154	DP3L1WH15CCF	158
DP2PMS78	137	DP3L12118	71	DP3L14242CCF	158	DP3L1WH15F	62
DP2PRFIC15	144	DP3L12124	71	DP3L14242F	62	DP3L1WH18	61, 154
DP2PRFIC70	144	DP3L12130	71	DP3L14248	61, 154	DP3L1WH18CCF	158
DP2PRFN15	143	DP3L12136	71	DP3L14248CCF	158	DP3L1WH18F	62
DP2PRFN70	143	DP3L12142	71	DP3L14248EPEF	162	DP3L1WH24	61, 154
DP2PRFW15	143	DP3L12148	71	DP3L14248F	62	DP3L1WH24CCF	158
DP2PRFW70	143	DP3L12415	77	DP3L14260EPEF	162	DP3L1WH24F	62
DP2PS	90	DP3L12415F	77	DP3L14272EPEF	162	DP3L1WH30	61, 154
DP2SOS15	69	DP3L12418	77	DP3L14284EPEF	162	DP3L1WH30CCF	158
DP2SOS18	69	DP3L12418F	77	DP3L15015	63, 155	DP3L1WH30EPEF	162
DP2SOS24	69	DP3L12424	77	DP3L15015CCF	159	DP3L1WH30F	62
DP2SOS30	69	DP3L12424F	77	DP3L15015F	64	DP3L1WH36	61, 154
DP2SOS36	69	DP3L12430	77	DP3L15018	63, 155	DP3L1WH36CCF	158
DP2SOS42	69	DP3L12430F	77	DP3L15018CCF	159	DP3L1WH36EPEF	162
DP2SOS48	69	DP3L12436	77	DP3L15018F	64	DP3L1WH36F	62
DP2SOS60	69	DP3L12436F	77	DP3L15024	63, 155	DP3L1WH42	61, 154
DP2SOSC	69	DP3L12442	77	DP3L15024CCF	159	DP3L1WH42CCF	158
DP2STF 2118	53	DP3L12442F	77	DP3L15024F	64	DP3L1WH42F	62
DP2STF 2124	53	DP3L12448	77	DP3L15030	63, 155	DP3L1WH48	61, 154
DP2STF 2130	53	DP3L12448F	77	DP3L15030CCF	159	DP3L1WH48CCF	158
DP2STF 2136	53	DP3L12815	61, 71, 154	DP3L15030EPEF	163	DP3L1WH48EPEF	162
DP2STF 2142	53	DP3L12815CCF	158	DP3L15030F	64	DP3L1WH48F	62
DP2STF 2148	53	DP3L12815F	62, 72	DP3L15036	63, 155	DP3L1WH60EPEF	162
DP2S(T/N)F 1418	53	DP3L12818	61, 71, 154	DP3L15036CCF	159	DP3L1WH72EPEF	162
DP2S(T/N)F 1424	53	DP3L12818CCF	158	DP3L15036EPEF	163	DP3L1WH84EPEF	162
DP2S(T/N)F 1430	53	DP3L12818F	62, 72	DP3L15036F	64	DP3MB	84, 85
DP2S(T/N)F 1436	53	DP3L12824	61, 71, 154	DP3L15042	63, 155	DP3PSB	76, 89, 90
DP2S(T/N)F 1442	53	DP3L12824CCF	158	DP3L15042CCF	159	DP3PWS36	137
DP2S(T/N)F 1448	53	DP3L12824F	62, 72	DP3L15042F	64	DP3PWS42	137
DP2S(T/N)F 2818	53	DP3L12830	61, 71, 154	DP3L15048	63, 155	DP3PWS50	137
DP2S(T/N)F 2824	53	DP3L12830CCF	158	DP3L15048CCF	159	DP3PWS57	137
DP2S(T/N)F 2830	53	DP3L12830EPEF	162	DP3L15048EPEF	163	DP3PWS64	137
DP2S(T/N)F 2836	53	DP3L12830F	62, 72	DP3L15048F	64	DP3PWS78	137
DP2S(T/N)F 2842	53	DP3L12836	61, 71, 154	DP3L15060EPEF	163	DP3SS	76, 87, 88
DP2S(T/N)F 2848	53	DP3L12836CCF	158	DP3L15072EPEF	163	DP5PT29CP	149
DP3ESB	76, 91, 92	DP3L12836EPEF	162	DP3L15084EPEF	163	DP5PT30CP	149
DP3L10715	71	DP3L12836F	62, 72	DP3L15715	63, 155	DP5PT35CP	149
DP3L10718	71	DP3L12842	61, 71, 154	DP3L15715CCF	159	DP5PT36CP	149
DP3L10724	71	DP3L12842CCF	158	DP3L15715F	64	DP5PT47CP	149
DP3L10730	71	DP3L12842F	62, 72	DP3L15718	63, 155	DP5PT48CP	149
DP3L10736	71	DP3L12848	61, 71, 154	DP3L15718CCF	159	DP5PT59CP	149
DP3L10742	71	DP3L12848CCF	158	DP3L15718F	64	DP5PT60CP	149
DP3L10748	71	DP3L12848EPEF	162	DP3L15724	63, 155	DP5PT71CP	149

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP5PT72CP	149	DP7HRRKS30	206	DP8120SPO 14	169	DP8CBBRR5760	42
DP5PT83CP	149	DP7HRRKS36	206	DP8120SPO 21	169	DP8CBBRR6418	42
DP5PT84CP	149	DP7HRRKS42	206	DP8120SPO 28	169	DP8CBBRR6424	42
DP5PT95CP	149	DP7HRRKS48	206	DP820P057	170	DP8CBBRR6430	42
DP5PT96CP	149	DP7HRRKS60	206	DP8BC18K	75	DP8CBBRR6436	42
DP6PE08	132	DP7PP36S	202	DP8BC24K	75	DP8CBBRR6442	42
DP6PE14	132	DP7PP36T	202	DP8BC30K	75	DP8CBBRR6448	42
DP6PE22	132	DP7PP42S	202	DP8BC36K	75	DP8CBBRR6460	42
DP6PE28	132	DP7PP42T	202	DP8BC42K	75	DP8CBBRR7818	42
DP6PE36	132	DP7PP50S	202	DP8BC48K	75	DP8CBBRR7824	42
DP6PE36F	132	DP7PP50T	202	DP8BC60K	75	DP8CBBRR7830	42
DP6PE42	132	DP7PP57S	202	DP8CBBFR4218	43	DP8CBBRR7836	42
DP6PE42H	132	DP7PP57T	202	DP8CBBFR4224	43	DP8CBBRR7842	42
DP6PE50	132	DP7PP64S	202	DP8CBBFR4230	43	DP8CBBRR7848	42
DP6PE57	132	DP7PP64T	202	DP8CBBFR4236	43	DP8CMMFR3615	19
DP6PE64	132	DP7PP78S	202	DP8CBBFR4242	43	DP8CMMFR3618	19
DP6PE78	132	DP7PP78T	202	DP8CBBFR4248	43	DP8CMMFR3624	19
DP6PEWH	132	DP7RCCH24	206	DP8CBBFR4260	43	DP8CMMFR3630	19
DP6PEWH36	132	DP7RCCH30	206	DP8CBBFR5018	43	DP8CMMFR3636	19
DP6PEWH42	132	DP7RCCH36	206	DP8CBBFR5024	43	DP8CMMFR3642	19
DP6PEWH50	132	DP7RCCH42	206	DP8CBBFR5030	43	DP8CMMFR3648	19
DP6PEWH57	132	DP7RCCH48	206	DP8CBBFR5036	43	DP8CMMFR3660	19
DP6PEWH64	132	DP7RCCH60	206	DP8CBBFR5042	43	DP8CMMFR4215	19
DP6PEWH78	132	DP7S	108, 109, 110, 111	DP8CBBFR5048	43	DP8CMMFR4218	19
DP6PEWHS14	132	DP7SS	114, 116	DP8CBBFR5060	43	DP8CMMFR4224	19
DP6PEWHS21	132	DP7SSWT1424	113	DP8CBBFR5718	44	DP8CMMFR4230	19
DP6PEWHS28	132	DP7SSWT1430	113	DP8CBBFR5724	44	DP8CMMFR4236	19
DP6TF	97	DP7SSWT1436	113	DP8CBBFR5730	44	DP8CMMFR4242	19
DP6TS	98	DP7SSWT1442	113	DP8CBBFR5736	44	DP8CMMFR4248	19
DP71RCT18	210	DP7SSWT1448	113	DP8CBBFR5742	44	DP8CMMFR4260	19
DP71RCT24	210	DP7SSWT2124	113	DP8CBBFR5748	44	DP8CMMFR5015	20
DP71RCT30	210	DP7SSWT2130	113	DP8CBBFR5760	44	DP8CMMFR5018	20
DP71RCT36	210	DP7SSWT2136	113	DP8CBBFR6418	44	DP8CMMFR5024	20
DP71RCT42	210	DP7SSWT2142	113	DP8CBBFR6424	44	DP8CMMFR5030	20
DP71RCT48	210	DP7SSWT2148	113	DP8CBBFR6430	44	DP8CMMFR5036	20
DP71RCT60	210	DP7SSWT2824	113	DP8CBBFR6436	44	DP8CMMFR5042	20
DP72RCT18	210	DP7SSWT2830	113	DP8CBBFR6442	44	DP8CMMFR5048	20
DP72RCT24	210	DP7SSWT2836	113	DP8CBBFR6448	44	DP8CMMFR5060	20
DP72RCT30	210	DP7SSWT2842	113	DP8CBBFR6460	44	DP8CMMFR5715	20
DP72RCT36	210	DP7SSWT2848	113	DP8CBBFR7818	45	DP8CMMFR5718	20
DP72RCT42	210	DP7SWT	106, 107	DP8CBBFR7824	45	DP8CMMFR5724	20
DP72RCT48	210	DP7SWTFK24	107	DP8CBBFR7830	45	DP8CMMFR5730	20
DP72RCT60	210	DP7SWTFK30	107	DP8CBBFR7836	45	DP8CMMFR5736	20
DP7BF	127	DP7SWTFK36	107	DP8CBBFR7842	45	DP8CMMFR5742	20
DP7CERK	205	DP7SWTFK42	107	DP8CBBFR7848	45	DP8CMMFR5748	20
DP7HIRKD24	206	DP7SWTFK48	107	DP8CBBRR4218	41	DP8CMMFR5760	20
DP7HIRKD30	206	DP7SWTFKD	107	DP8CBBRR4224	41	DP8CMMFR6415	20
DP7HIRKD36	206	DP8	48, 49, 50	DP8CBBRR4230	41	DP8CMMFR6418	20
DP7HIRKD42	206	DP8120PC08S	170	DP8CBBRR4236	41	DP8CMMFR6424	20
DP7HIRKD48	206	DP8120PC14S	170	DP8CBBRR4242	41	DP8CMMFR6430	20
DP7HIRKD60	206	DP8120PC22S	170	DP8CBBRR4248	41	DP8CMMFR6436	20
DP7HIRKS24	206	DP8120PC28S	170	DP8CBBRR4260	41	DP8CMMFR6442	20
DP7HIRKS30	206	DP8120PC36S	170	DP8CBBRR5018	41	DP8CMMFR6448	20
DP7HIRKS36	206	DP8120PC36SF	170	DP8CBBRR5024	41	DP8CMMFR6460	20
DP7HIRKS42	206	DP8120PC42S	170	DP8CBBRR5030	41	DP8CMMFR7815	21
DP7HIRKS48	206	DP8120PC42SH	170	DP8CBBRR5036	41	DP8CMMFR7818	21
DP7HIRKS60	206	DP8120PC50S	170	DP8CBBRR5042	41	DP8CMMFR7824	21
DP7HLCWH	127	DP8120PC57S	170	DP8CBBRR5048	41	DP8CMMFR7830	21
DP7HRRKD24	206	DP8120PC64S	170	DP8CBBRR5060	41	DP8CMMFR7836	21
DP7HRRKD30	206	DP8120PC78S	170	DP8CBBRR5718	42	DP8CMMFR7842	21
DP7HRRKD36	206	DP8120PO36	170	DP8CBBRR5724	42	DP8CMMFR7848	21
DP7HRRKD42	206	DP8120PO42	170	DP8CBBRR5730	42	DP8CMMFRWH15	19
DP7HRRKD48	206	DP8120PO50	170	DP8CBBRR5736	42	DP8CMMFRWH18	19
DP7HRRKD60	206	DP8120PO64	170	DP8CBBRR5742	42	DP8CMMFRWH24	19
DP7HRRKS24	206	DP8120PO78	170	DP8CBBRR5748	42	DP8CMMFRWH30	19

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP8CMMFRWH36	19	DP8CMMRR4242	15	DP8CPPFR5760	38	DP8CPPRR5060	31
DP8CMMFRWH42	19	DP8CMMRR4248	15	DP8CPPFR6415	38	DP8CPPRR5715	32
DP8CMMFRWH48	19	DP8CMMRR4260	15	DP8CPPFR6418	38	DP8CPPRR5718	32
DP8CMMFRWH60	19	DP8CMMRR5015	15	DP8CPPFR6424	38	DP8CPPRR5724	32
DP8CMMMLL3618	17	DP8CMMRR5018	15	DP8CPPFR6430	38	DP8CPPRR5730	32
DP8CMMMLL3624	17	DP8CMMRR5024	15	DP8CPPFR6436	38	DP8CPPRR5736	32
DP8CMMMLL3630	17	DP8CMMRR5030	15	DP8CPPFR6442	38	DP8CPPRR5742	32
DP8CMMMLL3636	17	DP8CMMRR5036	15	DP8CPPFR6448	38	DP8CPPRR5748	32
DP8CMMMLL3642	17	DP8CMMRR5042	15	DP8CPPFR6460	38	DP8CPPRR5760	32
DP8CMMMLL3648	17	DP8CMMRR5048	15	DP8CPPFR7815	39	DP8CPPRR6415	32
DP8CMMMLL3660	17	DP8CMMRR5060	15	DP8CPPFR7818	39	DP8CPPRR6418	32
DP8CMMMLL4218	17	DP8CMMRR5715	16	DP8CPPFR7824	39	DP8CPPRR6424	32
DP8CMMMLL4224	17	DP8CMMRR5718	16	DP8CPPFR7830	39	DP8CPPRR6430	32
DP8CMMMLL4230	17	DP8CMMRR5724	16	DP8CPPFR7836	39	DP8CPPRR6436	32
DP8CMMMLL4236	17	DP8CMMRR5730	16	DP8CPPFR7842	39	DP8CPPRR6442	32
DP8CMMMLL4242	17	DP8CMMRR5736	16	DP8CPPFR7848	39	DP8CPPRR6448	32
DP8CMMMLL4248	17	DP8CMMRR5742	16	DP8CPPLL4218	34	DP8CPPRR6460	32
DP8CMMMLL4260	17	DP8CMMRR5748	16	DP8CPPLL4224	34	DP8CPPRR7815	33
DP8CMMMLL5018	17	DP8CMMRR5760	16	DP8CPPLL4230	34	DP8CPPRR7818	33
DP8CMMMLL5024	17	DP8CMMRR6415	16	DP8CPPLL4236	34	DP8CPPRR7824	33
DP8CMMMLL5030	17	DP8CMMRR6418	16	DP8CPPLL4242	34	DP8CPPRR7830	33
DP8CMMMLL5036	17	DP8CMMRR6424	16	DP8CPPLL4248	34	DP8CPPRR7836	33
DP8CMMMLL5042	17	DP8CMMRR6430	16	DP8CPPLL4260	34	DP8CPPRR7842	33
DP8CMMMLL5048	17	DP8CMMRR6436	16	DP8CPPLL5018	34	DP8CPPRR7848	33
DP8CMMMLL5060	17	DP8CMMRR6442	16	DP8CPPLL5024	34	DP8CTTFR3615	28
DP8CMMMLL5718	18	DP8CMMRR6448	16	DP8CPPLL5030	34	DP8CTTFR3618	28
DP8CMMMLL5724	18	DP8CMMRR6460	16	DP8CPPLL5036	34	DP8CTTFR3624	28
DP8CMMMLL5730	18	DP8CMMRR7815	16	DP8CPPLL5042	34	DP8CTTFR3630	28
DP8CMMMLL5736	18	DP8CMMRR7818	16	DP8CPPLL5048	34	DP8CTTFR3636	28
DP8CMMMLL5742	18	DP8CMMRR7824	16	DP8CPPLL5060	34	DP8CTTFR3642	28
DP8CMMMLL5748	18	DP8CMMRR7830	16	DP8CPPLL5718	35	DP8CTTFR3648	28
DP8CMMMLL5760	18	DP8CMMRR7836	16	DP8CPPLL5724	35	DP8CTTFR3660	28
DP8CMMMLL6418	18	DP8CMMRR7842	16	DP8CPPLL5730	35	DP8CTTFR4215	28
DP8CMMMLL6424	18	DP8CMMRR7848	16	DP8CPPLL5736	35	DP8CTTFR4218	28
DP8CMMMLL6430	18	DP8CMMRRWH15	15	DP8CPPLL5742	35	DP8CTTFR4224	28
DP8CMMMLL6436	18	DP8CMMRRWH18	15	DP8CPPLL5748	35	DP8CTTFR4230	28
DP8CMMMLL6442	18	DP8CMMRRWH24	15	DP8CPPLL5760	35	DP8CTTFR4236	28
DP8CMMMLL6448	18	DP8CMMRRWH30	15	DP8CPPLL6418	35	DP8CTTFR4242	28
DP8CMMMLL6460	18	DP8CMMRRWH36	15	DP8CPPLL6424	35	DP8CTTFR4248	28
DP8CMMMLL7818	18	DP8CMMRRWH42	15	DP8CPPLL6430	35	DP8CTTFR4260	28
DP8CMMMLL7824	18	DP8CMMRRWH48	15	DP8CPPLL6436	35	DP8CTTFR5015	29
DP8CMMMLL7830	18	DP8CMMRRWH60	15	DP8CPPLL6442	35	DP8CTTFR5018	29
DP8CMMMLL7836	18	DP8CPPFR4215	37	DP8CPPLL6448	35	DP8CTTFR5024	29
DP8CMMMLL7842	18	DP8CPPFR4218	37	DP8CPPLL6460	35	DP8CTTFR5030	29
DP8CMMMLL7848	18	DP8CPPFR4224	37	DP8CPPLL7818	36	DP8CTTFR5036	29
DP8CMMMLLWH18	17	DP8CPPFR4230	37	DP8CPPLL7824	36	DP8CTTFR5042	29
DP8CMMMLLWH24	17	DP8CPPFR4236	37	DP8CPPLL7830	36	DP8CTTFR5048	29
DP8CMMMLLWH30	17	DP8CPPFR4242	37	DP8CPPLL7836	36	DP8CTTFR5060	29
DP8CMMMLLWH36	17	DP8CPPFR4248	37	DP8CPPLL7842	36	DP8CTTFR5715	29
DP8CMMMLLWH42	17	DP8CPPFR4260	37	DP8CPPLL7848	36	DP8CTTFR5718	29
DP8CMMMLLWH48	17	DP8CPPFR5015	37	DP8CPPRR4215	31	DP8CTTFR5724	29
DP8CMMMLLWH60	17	DP8CPPFR5018	37	DP8CPPRR4218	31	DP8CTTFR5730	29
DP8CMMRR3615	15	DP8CPPFR5024	37	DP8CPPRR4224	31	DP8CTTFR5736	29
DP8CMMRR3618	15	DP8CPPFR5030	37	DP8CPPRR4230	31	DP8CTTFR5742	29
DP8CMMRR3624	15	DP8CPPFR5036	37	DP8CPPRR4236	31	DP8CTTFR5748	29
DP8CMMRR3630	15	DP8CPPFR5042	37	DP8CPPRR4242	31	DP8CTTFR5760	29
DP8CMMRR3636	15	DP8CPPFR5048	37	DP8CPPRR4248	31	DP8CTTFR6415	30
DP8CMMRR3642	15	DP8CPPFR5060	37	DP8CPPRR4260	31	DP8CTTFR6418	30
DP8CMMRR3648	15	DP8CPPFR5715	38	DP8CPPRR5015	31	DP8CTTFR6424	30
DP8CMMRR3660	15	DP8CPPFR5718	38	DP8CPPRR5018	31	DP8CTTFR6430	30
DP8CMMRR4215	15	DP8CPPFR5724	38	DP8CPPRR5024	31	DP8CTTFR6436	30
DP8CMMRR4218	15	DP8CPPFR5730	38	DP8CPPRR5030	31	DP8CTTFR6442	30
DP8CMMRR4224	15	DP8CPPFR5736	38	DP8CPPRR5036	31	DP8CTTFR6448	30
DP8CMMRR4230	15	DP8CPPFR5742	38	DP8CPPRR5042	31	DP8CTTFR6460	30
DP8CMMRR4236	15	DP8CPPFR5748	38	DP8CPPRR5048	31	DP8CTTFR7815	30

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP8CTTFR7818	30	DP8CTTFR7818	30	DP8(C/V/U)PO362	126	DP8PCWH36	128
DP8CTTFR7824	30	DP8CTTFR7824	30	DP8(C/V/U)PO363	126	DP8PCWH42	128
DP8CTTFR7830	30	DP8CTTFR7830	30	DP8(C/V/U)PO364	126	DP8PCWH50	128
DP8CTTFR7836	30	DP8CTTFR7836	30	DP8(C/V/U)PO36S	126	DP8PCWH57	128
DP8CTTFR7842	30	DP8CTTFR7842	30	DP8(C/V/U)PO422	126	DP8PCWH64	128
DP8CTTFR7848	30	DP8CTTFR7848	30	DP8(C/V/U)PO423	126	DP8PCWH78	128
DP8CTTLL3618	26	DP8CTTLL3618	26	DP8(C/V/U)PO424	126	DP8PCWHS14	128
DP8CTTLL3624	26	DP8CTTLL3624	26	DP8(C/V/U)PO42S	126	DP8PCWHS142	128
DP8CTTLL3630	26	DP8CTTLL3630	26	DP8(C/V/U)PO502	126	DP8PCWHS21	128
DP8CTTLL3636	26	DP8CTTLL3636	26	DP8(C/V/U)PO503	126	DP8PCWHS212	128
DP8CTTLL3642	26	DP8CTTLL3642	26	DP8(C/V/U)PO504	126	DP8PCWHS28	128
DP8CTTLL3648	26	DP8CTTLL3648	26	DP8(C/V/U)PO50S	126	DP8PCWHS282	128
DP8CTTLL3660	26	DP8CTTLL3660	26	DP8(C/V/U)PO572	126	DP8PCWHU	129
DP8CTTLL4218	26	DP8CTTLL4218	26	DP8(C/V/U)PO573	126	DP8PO36	126
DP8CTTLL4224	26	DP8CTTLL4224	26	DP8(C/V/U)PO574	126	DP8PO36CPF	148
DP8CTTLL4230	26	DP8CTTLL4230	26	DP8(C/V/U)PO57S	126	DP8PO42	126
DP8CTTLL4236	26	DP8CTTLL4236	26	DP8(C/V/U)PO642	126	DP8PO42CPF	148
DP8CTTLL4242	26	DP8CTTLL4242	26	DP8(C/V/U)PO643	126	DP8PO50	126
DP8CTTLL4248	26	DP8CTTLL4248	26	DP8(C/V/U)PO644	126	DP8PO50CPF	148
DP8CTTLL4260	26	DP8CTTLL4260	26	DP8(C/V/U)PO64S	126	DP8PO57	126
DP8CTTLL5018	26	DP8CTTLL5018	26	DP8(C/V/U)PO782	126	DP8PO57CPF	148
DP8CTTLL5024	26	DP8CTTLL5024	26	DP8(C/V/U)PO783	126	DP8PO64	126
DP8CTTLL5030	26	DP8CTTLL5030	26	DP8(C/V/U)PO784	126	DP8PO64CPF	148
DP8CTTLL5036	26	DP8CTTLL5036	26	DP8(C/V/U)PO78S	126	DP8PO78	126
DP8CTTLL5042	26	DP8CTTLL5042	26	DP8(C/V/U)POWH2	126	DP8POWH	126
DP8CTTLL5048	26	DP8CTTLL5048	26	DP8(C/V/U)POWH3	126	DP8POWHCPF	148
DP8CTTLL5060	26	DP8CTTLL5060	26	DP8(C/V/U)POWH4	126	DP8PPC	127
DP8CTTLL5718	27	DP8CTTLL5718	27	DP8(C/V/U)POWHS	126	DP8PRFN24	115
DP8CTTLL5724	27	DP8CTTLL5724	27	DP8(C/V/U)PT1	127	DP8PRFN30	115
DP8CTTLL5730	27	DP8CTTLL5730	27	DP8(C/V/U)PT2	127	DP8PRFN36	115
DP8CTTLL5736	27	DP8CTTLL5736	27	DP8(C/V/U)PT3	127	DP8PRFN42	115
DP8CTTLL5742	27	DP8CTTLL5742	27	DP8(C/V/U)PT4	127	DP8PRFN48	115
DP8CTTLL5748	27	DP8CTTLL5748	27	DP8(C/V/U)PTCP	148	DP8PRFN60	115
DP8CTTLL5760	27	DP8CTTLL5760	27	DP8(C/V/U)PTCPH	148	DP8SPO14	127
DP8CTTLL6418	27	DP8CTTLL6418	27	DP8(C/V/U)PTS	127	DP8SPO21	127
DP8CTTLL6424	27	DP8CTTLL6424	27	DP8HLC	127	DP8SPO28	127
DP8CTTLL6430	27	DP8CTTLL6430	27	DP8PC07	128, 129	DPRD15736(L/R)L	101
DP8CTTLL6436	27	DP8CTTLL6436	27	DP8PC07UH	129	DPRD15736(L/R)N	101
DP8CTTLL6442	27	DP8CTTLL6442	27	DP8PC14	128, 129	DPRD15742(L/R)L	101
DP8CTTLL6448	27	DP8CTTLL6448	27	DP8PC14UH	129	DPRD15742(L/R)N	101
DP8CTTLL6460	27	DP8CTTLL6460	27	DP8PC21	128, 129	DPRD15748(L/R)L	101
DP8CTTLL7818	27	DP8CTTLL7818	27	DP8PC21UH	129	DPRD15748(L/R)N	101
DP8CTTLL7824	27	DP8CTTLL7824	27	DP8PC28	128	DPRD16436(L/R)L	101
DP8CTTLL7830	27	DP8CTTLL7830	27	DP8PC28UH	129	DPRD16436(L/R)N	101
DP8CTTLL7836	27	DP8CTTLL7836	27	DP8PC36	128	DPRD16442(L/R)L	101
DP8CTTLL7842	27	DP8CTTLL7842	27	DP8PC362	128	DPRD16442(L/R)N	101
DP8CTTLL7848	27	DP8CTTLL7848	27	DP8PC36U	129	DPRD16448(L/R)L	101
DP8CTTRR3615	24	DP8CTTRR3615	24	DP8PC36UH	129	DPRD16448(L/R)N	101
DP8CTTRR3618	24	DP8CTTRR3618	24	DP8PC42	128	DPRD17836(L/R)L	101
DP8CTTRR3624	24	DP8CTTRR3624	24	DP8PC422	128	DPRD17836(L/R)N	101
DP8CTTRR3630	24	DP8CTTRR3630	24	DP8PC42U	129	DPRD17842(L/R)L	101
DP8CTTRR3636	24	DP8CTTRR3636	24	DP8PC50	128	DPRD17842(L/R)N	101
DP8CTTRR3642	24	DP8CTTRR3642	24	DP8PC502	128	DPRD17848(L/R)L	101
DP8CTTRR3648	24	DP8CTTRR3648	24	DP8PC50U	129	DPRD17848(L/R)N	101
DP8CTTRR3660	24	DP8CTTRR3660	24	DP8PC57	128	DPRD1JPM	102
DP8CTTRR4215	24	DP8CTTRR4215	24	DP8PC572	128	DPRD1SSB	102
DP8CTTRR4218	24	DP8CTTRR4218	24	DP8PC57U	129	DPS7V1418	54
DP8CTTRR4224	24	DP8CTTRR4224	24	DP8PC64	128	DPS7V1424	54
DP8CTTRR4230	24	DP8CTTRR4230	24	DP8PC642	128	DPS7V1430	54
DP8CTTRR4236	24	DP8CTTRR4236	24	DP8PC64U	129	DPS7V1436	54
DP8CTTRR4242	24	DP8CTTRR4242	24	DP8PC78	128	DPS7V1442	54
DP8CTTRR4248	24	DP8CTTRR4248	24	DP8PC782	128	DPS7V1448	54
DP8CTTRR4260	24	DP8CTTRR4260	24	DP8PC78U	129	DPS7V2118	54
DP8CTTRR5015	24	DP8CTTRR5015	24	DP8PCWH	128	DPS7V2124	54
DP8CTTRR5018	24	DP8CTTRR5018	24	DP8PCWH2	128	DPS7V2130	54

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DPS7V2136	54	DS1S 48	231	DS3CMSL4814L	226	DS3ODSL1643614LT	286
DPS7V2142	54	DS1S 54	231	DS3CMSL6014L	226	DS3ODSL1644214L	276
DPS7V2148	54	DS1S 60	231	DS3CMSL7214L	226	DS3ODSL1644214LT	286
DPS7V2818	54	DS1S 66	231	DS3CMSS3614L	225	DS3ODSL1644814L	276
DPS7V2824	54	DS1S 72	231	DS3CMSS4214L	225	DS3ODSL1644814LT	286
DPS7V2830	54	DS1SWM 30	233	DS3CMSS4814L	225	DS3ODSL1646014L	276
DPS7V2836	54	DS1SWM 36	233	DS3CMSS6014L	225	DS3ODSL1646014LT	286
DPS7V2842	54	DS1SWM 42	233	DS3CMSS7214L	225	DS3ODSL1646614L	276
DPS7V2848	54	DS1SWM 48	233	DS3CMSV3614L	226	DS3ODSL1646614LT	286
DS1 OHL	234	DS1WM 24	233	DS3CMSV4214L	226	DS3ODSL1647214L	276
DS1 VD	234, 269	DS1WM 30	233	DS3CMSV4814L	226	DS3ODSL1647214LT	286
DS1BS 24	233	DS1WM 36	233	DS3CMSV6014L	226	DS3ODSL2573021FL	274
DS1BS 30	233	DS1WM 42	233	DS3CMSV7214L	226	DS3ODSL2573021FLT	283
DS1BS 36	233	DS1WM 48	233	DS3CMT(S/G)3614L	225	DS3ODSL2573621FL	274
DS1BS 42	233	DS2DW 30L	242	DS3CMT(S/G)4214L	225	DS3ODSL2573621FLT	283
DS1BS 48	233	DS2DW 36L	242	DS3CMT(S/G)4814L	225	DS3ODSL2574221FL	274
DS1BS 54	233	DS2DWDPL30	245	DS3CMT(S/G)6014L	225	DS3ODSL2574221FLT	283
DS1BS 60	233	DS2DWDPL36	245	DS3CMT(S/G)7214L	225	DS3ODSL2574821FL	274
DS1BS 66	233	DS2LKKT	245	DS3ODNS	274, 278, 283, 288	DS3ODSL2574821FLT	283
DS1BS 72	233	DS2OD 36L	269	DS3ODNS1573014	273	DS3ODSL2576021FL	274
DS1CS 36	231	DS2OD 42L	269	DS3ODNS1573014T	281	DS3ODSL2576021FLT	283
DS1CS 42	231	DS2OD 48L	269	DS3ODNS1573614	273	DS3ODSL2576621FL	274
DS1CS 48	231	DS2OD 54L	269	DS3ODNS1573614T	281	DS3ODSL2576621FLT	283
DS1DW 30L	239	DS2OD 60L	269	DS3ODNS1574214	273	DS3ODSL2577221FL	274
DS1DWDPL	245	DS2OD 66L	269	DS3ODNS1574214T	281	DS3ODSL2577221FLT	283
DS1E30L	229	DS2OD 72L	269	DS3ODNS1574814	273	DS3ODSL2643021FL	278
DS1E36L	229	DS2PF L18A	241	DS3ODNS1574814T	281	DS3ODSL2643021FLT	288
DS1E42L	229	DS2PF L18B	241	DS3ODNS1576014	273	DS3ODSL2643621FL	278
DS1E48L	229	DS2PF L24A	241	DS3ODNS1576014T	281	DS3ODSL2643621FLT	288
DS1E54L	229	DS2PF L24B	241	DS3ODNS1576614	273	DS3ODSL2644221FL	278
DS1E60L	229	DS2PF L30A	241	DS3ODNS1576614T	281	DS3ODSL2644221FLT	288
DS1E66L	229	DS2PF L30B	241	DS3ODNS1577214	273	DS3ODSL2644821FL	278
DS1E72L	229	DS2PM L18A	241	DS3ODNS1577214T	281	DS3ODSL2644821FLT	288
DS1EAKIT	213	DS2PM L18B	241	DS3ODNS1643014	276	DS3ODSL2646021FL	278
DS1LKKT	245	DS2PM L18F	241	DS3ODNS1643014T	286	DS3ODSL2646021FLT	288
DS1O24L	213	DS2PM L24A	241	DS3ODNS1643614	276	DS3ODSL2646621FL	278
DS1O30L	213	DS2PM L24B	241	DS3ODNS1643614T	286	DS3ODSL2646621FLT	288
DS1O36L	213	DS2PM L24F	241	DS3ODNS1644214	276	DS3ODSL2647221FL	278
DS1O42L	213	DS2PM24L	213	DS3ODNS1644214T	286	DS3ODSL2647221FLT	288
DS1O48L	213	DS2PM30L	213	DS3ODNS1644814	276	DS3ODSS	275, 280, 285, 290
DS1O54L	213	DS2PM36L	213	DS3ODNS1644814T	286	DS3ODSS1573014L	273
DS1O60L	213	DS2PM42L	213	DS3ODNS1646014	276	DS3ODSS1573014LT	281
DS1O66L	213	DS2PM48L	213	DS3ODNS1646014T	286	DS3ODSS1573614L	273
DS1O72L	213	DS2PM54L	213	DS3ODNS1646614	276	DS3ODSS1573614LT	281
DS1PBD	245, 387	DS2PM60L	213	DS3ODNS1646614T	286	DS3ODSS1574214L	273
DS1PCD	245, 387	DS2PM66L	213	DS3ODNS1647214	276	DS3ODSS1574214LT	281
DS1PF L18A	239	DS2PM72L	213	DS3ODNS1647214T	286	DS3ODSS1574814L	273
DS1PF L18B	239	DS2PPTC	245, 387	DS3ODSL	275, 280, 285, 290	DS3ODSS1574814LT	281
DS1PF L24A	239	DS2PPTN	245, 387	DS3ODSL1573014L	273	DS3ODSS1576014L	273
DS1PF L24B	239	DS2UM30L	229	DS3ODSL1573014LT	281	DS3ODSS1576014LT	281
DS1PF L30A	239	DS2UM36L	229	DS3ODSL1573614L	273	DS3ODSS1576614L	273
DS1PF L30B	239	DS2UM42L	229	DS3ODSL1573614LT	281	DS3ODSS1576614LT	281
DS1PFD	245, 387	DS2UM48L	229	DS3ODSL1574214L	273	DS3ODSS1577214L	273
DS1PFS	245, 387	DS2UM54L	229	DS3ODSL1574214LT	281	DS3ODSS1577214LT	281
DS1PM L18A	239	DS2UM60L	229	DS3ODSL1574814L	273	DS3ODSS1643014L	276
DS1PM L18B	239	DS2UM66L	229	DS3ODSL1574814LT	281	DS3ODSS1643014LT	286
DS1PM L18F	239	DS2UM72L	229	DS3ODSL1576014L	273	DS3ODSS1643614L	276
DS1PM L24A	239	DS2XPB	241	DS3ODSL1576014LT	281	DS3ODSS1643614LT	286
DS1PM L24B	239	DS3CMN3614	225	DS3ODSL1576614L	273	DS3ODSS1644214L	276
DS1PM L24F	239	DS3CMN4214	225	DS3ODSL1576614LT	281	DS3ODSS1644214LT	286
DS1PST	245, 387	DS3CMN4814	225	DS3ODSL1577214L	273	DS3ODSS1644814L	276
DS1S 24	231	DS3CMN6014	225	DS3ODSL1577214LT	281	DS3ODSS1644814LT	286
DS1S 30	231	DS3CMN7214	225	DS3ODSL1643014L	276	DS3ODSS1646014L	276
DS1S 36	231	DS3CMSL3614L	226	DS3ODSL1643014LT	286	DS3ODSS1646014LT	286
DS1S 42	231	DS3CMSL4214L	226	DS3ODSL1643614L	276	DS3ODSS1646614L	276

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DS3ODSS1646614LT	286	DS3ODSV2574221FLT	284	DS3PMSL6021PL	220	DS3SMN7214	223
DS3ODSS1647214L	276	DS3ODSV2574821FL	274	DS3PMSL6614L	217	DS3SMSL3614L	223
DS3ODSS1647214LT	286	DS3ODSV2574821FLT	284	DS3PMSL6621FL	219	DS3SMSL4214L	223
DS3ODSS2573021FL	274	DS3ODSV2576021FL	274	DS3PMSL6621PL	220	DS3SMSL4814L	223
DS3ODSS2573021FLT	283	DS3ODSV2576021FLT	284	DS3PMSL7214L	217	DS3SMSL6014L	223
DS3ODSS2573621FL	274	DS3ODSV2576621FL	274	DS3PMSL7221FL	219	DS3SMSL7214L	223
DS3ODSS2573621FLT	283	DS3ODSV2576621FLT	284	DS3PMSL7221PL	220	DS3SMSS3614L	223
DS3ODSS2574221FL	274	DS3ODSV2577221FL	274	DS3PMSS3014L	217	DS3SMSS4214L	223
DS3ODSS2574221FLT	283	DS3ODSV2577221FLT	284	DS3PMSS3021FL	219	DS3SMSS4814L	223
DS3ODSS2574821FL	274	DS3ODSV2643021FL	279	DS3PMSS3021PL	220	DS3SMSS6014L	223
DS3ODSS2574821FLT	283	DS3ODSV2643021FLT	289	DS3PMSS3614L	217	DS3SMSS7214L	223
DS3ODSS2576021FL	274	DS3ODSV2643621FL	279	DS3PMSS3621FL	219	DS3SMSV3614L	224
DS3ODSS2576021FLT	283	DS3ODSV2643621FLT	289	DS3PMSS3621PL	220	DS3SMSV4214L	224
DS3ODSS2576621FL	274	DS3ODSV2644221FL	279	DS3PMSS4214L	217	DS3SMSV4814L	224
DS3ODSS2576621FLT	283	DS3ODSV2644221FLT	289	DS3PMSS4221FL	219	DS3SMSS6014L	224
DS3ODSS2577221FL	274	DS3ODSV2644821FL	279	DS3PMSS4221PL	220	DS3SMSV7214L	224
DS3ODSS2577221FLT	283	DS3ODSV2644821FLT	289	DS3PMSS4814L	217	DS3SMT(S/G)3614L	223
DS3ODSS2643021FL	278	DS3ODSV2646021FL	279	DS3PMSS4821FL	219	DS3SMT(S/G)4214L	223
DS3ODSS2643021FLT	288	DS3ODSV2646021FLT	289	DS3PMSS4821PL	220	DS3SMT(S/G)4814L	223
DS3ODSS2643621FL	278	DS3ODSV2646621FL	279	DS3PMSS6014L	217	DS3SMT(S/G)6014L	223
DS3ODSS2643621FLT	288	DS3ODSV2646621FLT	289	DS3PMSS6021FL	219	DS3SMT(S/G)7214L	223
DS3ODSS2644221FL	278	DS3ODSV2647221FL	279	DS3PMSS6021PL	220	DS3WMN3614	221
DS3ODSS2644221FLT	288	DS3ODSV2647221FLT	289	DS3PMSS6614L	217	DS3WMN4214	221
DS3ODSS2644821FL	278	DS3PML30L	214	DS3PMSS6621FL	219	DS3WMN4814	221
DS3ODSS2644821FLT	288	DS3PML36L	214	DS3PMSS6621PL	220	DS3WMN6014	221
DS3ODSS2646021FL	278	DS3PML42L	214	DS3PMSS7214L	217	DS3WMN7214	221
DS3ODSS2646021FLT	288	DS3PML48L	214	DS3PMSS7221FL	219	DS3WMSL3614L	221
DS3ODSS2646621FL	278	DS3PML60L	214	DS3PMSS7221PL	220	DS3WMSL4214L	221
DS3ODSS2646621FLT	288	DS3PML66L	214	DS3PMSV3014L	218	DS3WMSL4814L	221
DS3ODSS2647221FL	278	DS3PML72L	214	DS3PMSV3021FL	219	DS3WMSL6014L	221
DS3ODSS2647221FLT	288	DS3PMNS3014	217	DS3PMSV3021PL	220	DS3WMSL7214L	221
DS3ODSV	275, 280, 285, 290	DS3PMNS3021	219	DS3PMSV3614L	218	DS3WMS3614L	221
DS3ODSV1573014L	273	DS3PMNS3614	217	DS3PMSV3621FL	219	DS3WMS4214L	221
DS3ODSV1573014LT	282	DS3PMNS3621	219	DS3PMSV3621PL	220	DS3WMS4814L	221
DS3ODSV1573614L	273	DS3PMNS4214	217	DS3PMSV4214L	218	DS3WMS6014L	221
DS3ODSV1573614LT	282	DS3PMNS4221	219	DS3PMSV4221FL	219	DS3WMS7214L	221
DS3ODSV1574214L	273	DS3PMNS4814	217	DS3PMSV4221PL	220	DS3WMSV3614L	221
DS3ODSV1574214LT	282	DS3PMNS4821	219	DS3PMSV4814L	218	DS3WMSV4214L	221
DS3ODSV1574814L	273	DS3PMNS6014	217	DS3PMSV4821FL	219	DS3WMSV4814L	221
DS3ODSV1574814LT	282	DS3PMNS6021	219	DS3PMSV4821PL	220	DS3WMSV6014L	221
DS3ODSV1576014L	273	DS3PMNS6614	217	DS3PMSV6014L	218	DS3WMSV7214L	221
DS3ODSV1576014LT	282	DS3PMNS6621	219	DS3PMSV6021FL	219	DS3WMT(S/G)3614L	222
DS3ODSV1576614L	273	DS3PMNS7214	217	DS3PMSV6021PL	220	DS3WMT(S/G)4214L	222
DS3ODSV1576614LT	282	DS3PMNS7221	219	DS3PMSV6614L	218	DS3WMT(S/G)4814L	222
DS3ODSV1577214L	273	DS3PMS30L	213	DS3PMSV6621FL	219	DS3WMT(S/G)6014L	222
DS3ODSV1577214LT	282	DS3PMS36L	213	DS3PMSV6621PL	220	DS3WMT(S/G)7214L	222
DS3ODSV1643014L	277	DS3PMS42L	213	DS3PMSV7214L	218	DS4LC1ANL24N	250
DS3ODSV1643014LT	287	DS3PMS48L	213	DS3PMSV7221FL	219	DS4LC1ANL30N	250
DS3ODSV1643614L	277	DS3PMS60L	213	DS3PMSV7221PL	220	DS4LC1ANL36N	250
DS3ODSV1643614LT	287	DS3PMS66L	213	DS3PMT(S/G)3614L	217	DS4LC1ANL42N	250
DS3ODSV1644214L	277	DS3PMS72L	213	DS3PMT(S/G)4214L	217	DS4LC1ANL48N	250
DS3ODSV1644214LT	287	DS3PMSL3014L	217	DS3PMT(S/G)4814L	217	DS4LC1ANL54N	250
DS3ODSV1644814L	277	DS3PMSL3021FL	219	DS3PMT(S/G)6014L	217	DS4LC1ANL60N	250
DS3ODSV1644814LT	287	DS3PMSL3021PL	220	DS3PMT(S/G)7214L	217	DS4LC1ANL66N	250
DS3ODSV1646014L	277	DS3PMSL3614L	217	DS3PMV30L	214	DS4LC1ANL72N	250
DS3ODSV1646014LT	287	DS3PMSL3621FL	219	DS3PMV36L	214	DS4LC1ANS42N	247
DS3ODSV1646614L	277	DS3PMSL3621PL	220	DS3PMV42L	214	DS4LC1ANS48N	247
DS3ODSV1646614LT	287	DS3PMSL4214L	217	DS3PMV48L	214	DS4LC1ANS54N	247
DS3ODSV1647214L	277	DS3PMSL4221FL	219	DS3PMV60L	214	DS4LC1ANS60N	247
DS3ODSV1647214LT	287	DS3PMSL4221PL	220	DS3PMV66L	214	DS4LC1ANS66N	247
DS3ODSV2573021FL	274	DS3PMSL4814L	217	DS3PMV72L	214	DS4LC1ANS72N	247
DS3ODSV2573021FLT	284	DS3PMSL4821FL	219	DS3SMN3614	223	DS4LC1ANV24N	254
DS3ODSV2573621FL	274	DS3PMSL4821PL	220	DS3SMN4214	223	DS4LC1ANV30N	254
DS3ODSV2573621FLT	284	DS3PMSL6014L	217	DS3SMN4814	223	DS4LC1ANV36N	254
DS3ODSV2574221FL	274	DS3PMSL6021FL	219	DS3SMN6014	223	DS4LC1ANV42N	254

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DS4LC1ANV48N	254	DS4LC1BVV42L	255	DS4LC1CVV36L	256	DS4LC1DVV30L	257
DS4LC1ANV54N	254	DS4LC1BVV48L	255	DS4LC1CVV42L	256	DS4LC1DVV36L	257
DS4LC1ANV60N	254	DS4LC1BVV54L	255	DS4LC1CVV48L	256	DS4LC1DVV42L	257
DS4LC1ANV66N	254	DS4LC1BVV60L	255	DS4LC1CVV54L	256	DS4LC1DVV48L	257
DS4LC1ANV72N	254	DS4LC1BVV66L	255	DS4LC1CVV60L	256	DS4LC1DVV54L	257
DS4LC1BLL30L	250	DS4LC1BVV72L	255	DS4LC1CVV66L	256	DS4LC1DVV60L	257
DS4LC1BLL36L	250	DS4LC1CLL30L	252	DS4LC1CVV72L	256	DS4LC1DVV66L	257
DS4LC1BLL42L	250	DS4LC1CLL36L	252	DS4LC1DLL30L	253	DS4LC1DVV72L	257
DS4LC1BLL48L	250	DS4LC1CLL42L	252	DS4LC1DLL36L	253	DS4LC2ANL24N	259
DS4LC1BLL54L	250	DS4LC1CLL48L	252	DS4LC1DLL42L	253	DS4LC2ANL30N	259
DS4LC1BLL60L	250	DS4LC1CLL54L	252	DS4LC1DLL48L	253	DS4LC2ANL36N	259
DS4LC1BLL66L	250	DS4LC1CLL60L	252	DS4LC1DLL54L	253	DS4LC2ANL42N	259
DS4LC1BLL72L	250	DS4LC1CLL66L	252	DS4LC1DLL60L	253	DS4LC2ANL48N	259
DS4LC1BLS42L	247	DS4LC1CLL72L	252	DS4LC1DLL66L	253	DS4LC2ANL54N	259
DS4LC1BLS48L	247	DS4LC1CLS42L	248	DS4LC1DLL72L	253	DS4LC2ANL60N	259
DS4LC1BLS54L	247	DS4LC1CLS48L	248	DS4LC1DLS42L	249	DS4LC2ANL66N	259
DS4LC1BLS60L	247	DS4LC1CLS54L	248	DS4LC1DLS48L	249	DS4LC2ANL72N	259
DS4LC1BLS66L	247	DS4LC1CLS60L	248	DS4LC1DLS54L	249	DS4LC2ANV24N	263
DS4LC1BLS72L	247	DS4LC1CLS66L	248	DS4LC1DLS60L	249	DS4LC2ANV30N	263
DS4LC1BLV30L	254	DS4LC1CLS72L	248	DS4LC1DLS66L	249	DS4LC2ANV36N	263
DS4LC1BLV36L	254	DS4LC1CLV30L	256	DS4LC1DLS72L	249	DS4LC2ANV42N	263
DS4LC1BLV42L	254	DS4LC1CLV36L	256	DS4LC1DLV30L	257	DS4LC2ANV48N	263
DS4LC1BLV48L	254	DS4LC1CLV42L	256	DS4LC1DLV36L	257	DS4LC2ANV54N	263
DS4LC1BLV54L	254	DS4LC1CLV48L	256	DS4LC1DLV42L	257	DS4LC2ANV60N	263
DS4LC1BLV60L	254	DS4LC1CLV54L	256	DS4LC1DLV48L	257	DS4LC2ANV66N	263
DS4LC1BLV66L	254	DS4LC1CLV60L	256	DS4LC1DLV54L	257	DS4LC2ANV72N	263
DS4LC1BLV72L	254	DS4LC1CLV66L	256	DS4LC1DLV60L	257	DS4LC2BLL30L	259
DS4LC1BSL30L	250	DS4LC1CLV72L	256	DS4LC1DLV66L	257	DS4LC2BLL36L	259
DS4LC1BSL36L	250	DS4LC1CSL30L	252	DS4LC1DLV72L	257	DS4LC2BLL42L	259
DS4LC1BSL42L	250	DS4LC1CSL36L	252	DS4LC1DSL30L	253	DS4LC2BLL48L	259
DS4LC1BSL48L	250	DS4LC1CSL42L	252	DS4LC1DSL36L	253	DS4LC2BLL54L	259
DS4LC1BSL54L	250	DS4LC1CSL48L	252	DS4LC1DSL42L	253	DS4LC2BLL60L	259
DS4LC1BSL60L	250	DS4LC1CSL54L	252	DS4LC1DSL48L	253	DS4LC2BLL66L	259
DS4LC1BSL66L	250	DS4LC1CSL60L	252	DS4LC1DSL54L	253	DS4LC2BLL72L	259
DS4LC1BSL72L	250	DS4LC1CSL66L	252	DS4LC1DSL60L	253	DS4LC2BLV30L	263
DS4LC1BSS42L	247	DS4LC1CSL72L	252	DS4LC1DSL66L	253	DS4LC2BLV36L	263
DS4LC1BSS48L	247	DS4LC1CSS42L	248	DS4LC1DSL72L	253	DS4LC2BLV42L	263
DS4LC1BSS54L	247	DS4LC1CSS48L	248	DS4LC1DSS42L	249	DS4LC2BLV48L	263
DS4LC1BSS60L	247	DS4LC1CSS54L	248	DS4LC1DSS48L	249	DS4LC2BLV54L	263
DS4LC1BSS66L	247	DS4LC1CSS60L	248	DS4LC1DSS54L	249	DS4LC2BLV60L	263
DS4LC1BSS72L	247	DS4LC1CSS66L	248	DS4LC1DSS60L	249	DS4LC2BLV66L	263
DS4LC1BSV30L	254	DS4LC1CSS72L	248	DS4LC1DSS66L	249	DS4LC2BLV72L	263
DS4LC1BSV36L	254	DS4LC1CSV30L	256	DS4LC1DSS72L	249	DS4LC2BSL30L	259
DS4LC1BSV42L	254	DS4LC1CSV36L	256	DS4LC1DSV30L	257	DS4LC2BSL36L	259
DS4LC1BSV48L	254	DS4LC1CSV42L	256	DS4LC1DSV36L	257	DS4LC2BSL42L	259
DS4LC1BSV54L	254	DS4LC1CSV48L	256	DS4LC1DSV42L	257	DS4LC2BSL48L	259
DS4LC1BSV60L	254	DS4LC1CSV54L	256	DS4LC1DSV48L	257	DS4LC2BSL54L	259
DS4LC1BSV66L	254	DS4LC1CSV60L	256	DS4LC1DSV54L	257	DS4LC2BSL60L	259
DS4LC1BSV72L	254	DS4LC1CSV66L	256	DS4LC1DSV60L	257	DS4LC2BSL66L	259
DS4LC1BVL30L	251	DS4LC1CSV72L	256	DS4LC1DSV66L	257	DS4LC2BSL72L	259
DS4LC1BVL36L	251	DS4LC1CVL30L	252	DS4LC1DSV72L	257	DS4LC2BSV30L	263
DS4LC1BVL42L	251	DS4LC1CVL36L	252	DS4LC1DVL30L	253	DS4LC2BSV36L	263
DS4LC1BVL48L	251	DS4LC1CVL42L	252	DS4LC1DVL36L	253	DS4LC2BSV42L	263
DS4LC1BVL54L	251	DS4LC1CVL48L	252	DS4LC1DVL42L	253	DS4LC2BSV48L	263
DS4LC1BVL60L	251	DS4LC1CVL54L	252	DS4LC1DVL48L	253	DS4LC2BSV54L	263
DS4LC1BVL66L	251	DS4LC1CVL60L	252	DS4LC1DVL54L	253	DS4LC2BSV60L	263
DS4LC1BVL72L	251	DS4LC1CVL66L	252	DS4LC1DVL60L	253	DS4LC2BSV66L	263
DS4LC1BVS42L	247	DS4LC1CVL72L	252	DS4LC1DVL66L	253	DS4LC2BSV72L	263
DS4LC1BVS48L	247	DS4LC1CVS42L	248	DS4LC1DVL72L	253	DS4LC2BVL30L	260
DS4LC1BVS54L	247	DS4LC1CVS48L	248	DS4LC1DVS42L	249	DS4LC2BVL36L	260
DS4LC1BVS60L	247	DS4LC1CVS54L	248	DS4LC1DVS48L	249	DS4LC2BVL42L	260
DS4LC1BVS66L	247	DS4LC1CVS60L	248	DS4LC1DVS54L	249	DS4LC2BVL48L	260
DS4LC1BVS72L	247	DS4LC1CVS66L	248	DS4LC1DVS60L	249	DS4LC2BVL54L	260
DS4LC1BVV30L	255	DS4LC1CVS72L	248	DS4LC1DVS66L	249	DS4LC2BVL60L	260
DS4LC1BVV36L	255	DS4LC1CVV30L	256	DS4LC1DVS72L	249	DS4LC2BVL66L	260

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DS4LC2BVL72L	260	DS4LC2DLV30L	266	DTIACX3636	352	DTIARY9630NS	343
DS4LC2BVV30L	264	DS4LC2DLV36L	266	DTIACX3642	352	DTIARY9636N	344
DS4LC2BVV36L	264	DS4LC2DLV42L	266	DTIACX42	352	DTIARY9642N	344
DS4LC2BVV42L	264	DS4LC2DLV48L	266	DTIACX4217	352	DTIASX3030	351
DS4LC2BVV48L	264	DS4LC2DLV54L	266	DTIACX4221	352	DTIASX303017	351
DS4LC2BVV54L	264	DS4LC2DLV60L	266	DTIACX4236	352	DTIASX303021	351
DS4LC2BVV60L	264	DS4LC2DLV66L	266	DTIACX4242	352	DTIASX303036	351
DS4LC2BVV66L	264	DS4LC2DLV72L	266	DTIACX48	352	DTIASX303042	351
DS4LC2BVV72L	264	DS4LC2DSL30L	262	DTIACX4817	352	DTIASX3636	351
DS4LC2CLL30L	261	DS4LC2DSL36L	262	DTIACX4821	352	DTIASX363617	351
DS4LC2CLL36L	261	DS4LC2DSL42L	262	DTIACX4836	352	DTIASX363621	351
DS4LC2CLL42L	261	DS4LC2DSL48L	262	DTIACX4842	352	DTIASX363636	351
DS4LC2CLL48L	261	DS4LC2DSL54L	262	DTIADX3030	353	DTIASX363642	351
DS4LC2CLL54L	261	DS4LC2DSL60L	262	DTIADX303017	353	DTIASX4242	351
DS4LC2CLL60L	261	DS4LC2DSL66L	262	DTIADX303021	353	DTIASX424217	351
DS4LC2CLL66L	261	DS4LC2DSL72L	262	DTIADX303036	353	DTIASX424221	351
DS4LC2CLL72L	261	DS4LC2DSV30L	266	DTIADX303042	354	DTIASX424236	351
DS4LC2CLV30L	265	DS4LC2DSV36L	266	DTIADX3636	353	DTIASX424242	351
DS4LC2CLV36L	265	DS4LC2DSV42L	266	DTIADX363617	353	DTIASX4848	351
DS4LC2CLV42L	265	DS4LC2DSV48L	266	DTIADX363621	353	DTIASX484817	351
DS4LC2CLV48L	265	DS4LC2DSV54L	266	DTIADX363636	353	DTIASX484821	351
DS4LC2CLV54L	265	DS4LC2DSV60L	266	DTIADX363642	354	DTIASX484836	351
DS4LC2CLV60L	265	DS4LC2DSV66L	266	DTIADX4242	353	DTIASX484842	351
DS4LC2CLV66L	265	DS4LC2DSV72L	266	DTIADX424217	353	DTIATY10236N	364
DS4LC2CLV72L	265	DS4LC2DVL30L	262	DTIADX424221	353	DTIATY10242N	364
DS4LC2CSL30L	261	DS4LC2DVL36L	262	DTIADX424236	353	DTIATY10248N	364
DS4LC2CSL36L	261	DS4LC2DVL42L	262	DTIADX424242	354	DTIATY10836N	364
DS4LC2CSL42L	261	DS4LC2DVL48L	262	DTIADX4848	353	DTIATY10842N	364
DS4LC2CSL48L	261	DS4LC2DVL54L	262	DTIADX484817	353	DTIATY10848N	364
DS4LC2CSL54L	261	DS4LC2DVL60L	262	DTIADX484821	353	DTIATY12042N	364
DS4LC2CSL60L	261	DS4LC2DVL66L	262	DTIADX484836	353	DTIATY12048N	364
DS4LC2CSL66L	261	DS4LC2DVL72L	262	DTIADX484842	354	DTIATY13242N	364
DS4LC2CSL72L	261	DS4LC2DVV30L	266	DTIARY10236N	363	DTIATY13248N	364
DS4LC2CSV30L	265	DS4LC2DVV36L	266	DTIARY10242N	363	DTIATY14442N	364
DS4LC2CSV36L	265	DS4LC2DVV42L	266	DTIARY10248N	363	DTIATY14448N	364
DS4LC2CSV42L	265	DS4LC2DVV48L	266	DTIARY10836N	363	DTIATY6024NS	345
DS4LC2CSV48L	265	DS4LC2DVV54L	266	DTIARY10842N	363	DTIATY6030NS	345
DS4LC2CSV54L	265	DS4LC2DVV60L	266	DTIARY10848N	363	DTIATY6036N	346
DS4LC2CSV60L	265	DS4LC2DVV66L	266	DTIARY12042N	363	DTIATY6624NS	345
DS4LC2CSV66L	265	DS4LC2DVV72L	266	DTIARY12048N	363	DTIATY6630NS	345
DS4LC2CSV72L	265	DSCSWDB24	233	DTIARY13242N	363	DTIATY6636N	346
DS4LC2CVL30L	261	DSCSWDB30	233	DTIARY13248N	363	DTIATY7224NS	345
DS4LC2CVL36L	261	DSCSWDB36	233	DTIARY14442N	363	DTIATY7230NS	345
DS4LC2CVL42L	261	DSCSWDB42	233	DTIARY14448N	363	DTIATY7236N	346
DS4LC2CVL48L	261	DSCSWDB48	233	DTIARY6024NS	343	DTIATY7824NS	345
DS4LC2CVL54L	261	DSSAC	387	DTIARY6030NS	343	DTIATY7830NS	345
DS4LC2CVL60L	261	DSSAR	387	DTIARY6036N	344	DTIATY7836N	346
DS4LC2CVL66L	261	DTIABY10242N	365	DTIARY6624NS	343	DTIATY8424NS	345
DS4LC2CVL72L	261	DTIABY10248N	365	DTIARY6630NS	343	DTIATY8430NS	345
DS4LC2CVV30L	265	DTIABY10842N	365	DTIARY6636N	344	DTIATY8436N	346
DS4LC2CVV36L	265	DTIABY10848N	365	DTIARY7224NS	343	DTIATY8442N	346
DS4LC2CVV42L	265	DTIABY12042N	365	DTIARY7230NS	343	DTIATY9024NS	345
DS4LC2CVV48L	265	DTIABY12048N	365	DTIARY7236N	344	DTIATY9030NS	345
DS4LC2CVV54L	265	DTIABY13242N	365	DTIARY7824NS	343	DTIATY9036N	346
DS4LC2CVV60L	265	DTIABY13248N	365	DTIARY7830NS	343	DTIATY9042N	346
DS4LC2CVV66L	265	DTIABY14442N	365	DTIARY7836N	344	DTIATY9624NS	345
DS4LC2CVV72L	265	DTIABY14448N	365	DTIARY8424NS	343	DTIATY9630NS	345
DS4LC2DLL30L	262	DTIACX30	352	DTIARY8430NS	343	DTIATY9636N	346
DS4LC2DLL36L	262	DTIACX3017	352	DTIARY8436N	344	DTIATY9642N	346
DS4LC2DLL42L	262	DTIACX3021	352	DTIARY8442N	344	DTIBC3423	357
DS4LC2DLL48L	262	DTIACX3036	352	DTIARY9024NS	343	DTIBC3429	357
DS4LC2DLL54L	262	DTIACX3042	352	DTIARY9030NS	343	DTIBC4023	357
DS4LC2DLL60L	262	DTIACX36	352	DTIARY9036N	344	DTIBC4029	357
DS4LC2DLL66L	262	DTIACX3617	352	DTIARY9042N	344	DTIBC4623	357
DS4LC2DLL72L	262	DTIACX3621	352	DTIARY9624NS	343	DTIBC4629	357

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DT1BC5223	357	DT1CTY8436N	348	DVDP6630LN	308	SISDDPS	359
DT1BC5229	357	DT1CTY9024N	348	DVDP6630RN	308	SISLC4	359
DT1BC5823	357	DT1CTY9030N	348	DVDP7224LN	308	SISPGH	359
DT1BC5829	357	DT1CTY9036N	348	DVDP7224RN	308		
DT1BC6423	357	DT1CTY9624N	348	DVDP7230LN	308		
DT1BC6429	357	DT1CTY9630N	348	DVDP7230RN	308		
DT1BC7023	357	DT1CTY9636N	348	DVDP7824LN	308		
DT1BC7029	357	DT1L4040SSN	360	DVDP7824RN	308		
DT1BK464616	358	DT1L4646DDN	360	DVDP7830LN	308		
DT1BT3029	358	DT1L4646SSN	360	DVDP7830RN	308		
DT1BT3429	358	DT1R3423N	360	DVDP8424LN	308		
DT1BT4629	357	DT1R3429N	360	DVDP8424RN	308		
DT1BT5229	357	DT1R4023N	360	DVDP8430LN	308		
DT1BT5829	357	DT1R4029N	360	DVDP8430RN	308		
DT1BT6429	357	DT1R4623N	360	DVDP9024LN	308		
DT1BT7029	357	DT1R4629N	360	DVDP9024RN	308		
DT1BTL	355	DT1R4635N	360	DVDP9030LN	308		
DT1BTS	355	DT1R5223N	360	DVDP9030RN	308		
DT1BXL	355	DT1R5229N	360	DVDP9624LN	308		
DT1BXL17	355	DT1R5235N	360	DVDP9624RN	308		
DT1BXL21	355	DT1R5823N	360	DVDP9630LN	308		
DT1BXL36	355	DT1R5829N	360	DVDP9630RN	308		
DT1BXL42	355	DT1R5835N	360	DVDS6020LN	309		
DT1BXS	355	DT1R6423N	360	DVDS6020RN	309		
DT1BXS17	355	DT1R6429N	360	DVDS6620LN	309		
DT1BXS21	355	DT1R6435N	360	DVDS6620RN	309		
DT1BXS36	355	DT1R7023N	360	DVDS7220LN	309		
DT1BXS42	355	DT1R7029N	360	DVDS7220RN	309		
DT1BY464616	358	DT1R7035N	360	DVDS7820LN	309		
DT1CK4	356	DT1S	355	DVDS7820RN	309		
DT1CRY6024N	347	DT1Y4623N	360	DVDS8420LN	309		
DT1CRY6030N	347	DVDB6024LN	311	DVDS8420RN	309		
DT1CRY6036N	347	DVDB6024RN	311	DVDS9020LN	309		
DT1CRY6624N	347	DVDB6030LN	311	DVDS9020RN	309		
DT1CRY6630N	347	DVDB6030RN	311	DVDS9620LN	309		
DT1CRY6636N	347	DVDB6624LN	311	DVDS9620RN	309		
DT1CRY7224N	347	DVDB6624RN	311	ET1OT3672	367		
DT1CRY7230N	347	DVDB6630LN	311	ET1OT48120	367		
DT1CRY7236N	347	DVDB6630RN	311	ET1OT4896	367		
DT1CRY7824N	347	DVDB7224LN	311	ET1OT54120	367		
DT1CRY7830N	347	DVDB7224RN	311	ET1OT60144	367		
DT1CRY7836N	347	DVDB7230LN	311	ETIRCT3048	366		
DT1CRY8424N	347	DVDB7230RN	311	ETIRCT3060	366		
DT1CRY8430N	347	DVDB7824LN	311	ETIRCT3072	366		
DT1CRY8436N	347	DVDB7824RN	311	ETIRCT3469	366		
DT1CRY9024N	347	DVDB7830LN	311	ETIRCT3479	366		
DT1CRY9030N	347	DVDB7830RN	311	ETIRCT3660	366		
DT1CRY9036N	347	DVDB8424LN	311	ETIRCT3672	366		
DT1CRY9624N	347	DVDB8424RN	311	ETIRCT4284	366		
DT1CRY9630N	347	DVDB8430LN	311	ETIRCT4896	366		
DT1CRY9636N	347	DVDB8430RN	311	ETIRT30	366		
DT1CTY6024N	348	DVDB9024LN	311	ETIRT36	366		
DT1CTY6030N	348	DVDB9024RN	311	ETIRT36C	366		
DT1CTY6036N	348	DVDB9030LN	311	ETIRT42	366		
DT1CTY6624N	348	DVDB9030RN	311	ETIRT48	366		
DT1CTY6630N	348	DVDB9624LN	311	ETIRT60	366		
DT1CTY6636N	348	DVDB9624RN	311	ET1ST22C	366		
DT1CTY7224N	348	DVDB9630LN	311	ET1ST2416	366		
DT1CTY7230N	348	DVDB9630RN	311	ET1ST30	366		
DT1CTY7236N	348	DVDP6024LN	308	ET1ST36	366		
DT1CTY7824N	348	DVDP6024RN	308	ET1ST42	366		
DT1CTY7830N	348	DVDP6030LN	308	ET1ST48	366		
DT1CTY7836N	348	DVDP6030RN	308	ET1ST60	366		
DT1CTY8424N	348	DVDP6624LN	308	RO1-DPB	234		
DT1CTY8430N	348	DVDP6624RN	308	RS1-DPB	234		

Selling Policy

	<p>This Selling Policy supercedes all previous selling policies. Prices, discounts and product offerings are subject to change without notice.</p>
Terms & Conditions of Sales	<p>Sales by Knoll, Inc. or Knoll North America Corp. ("Seller") of Knoll Product Lines (hereinafter "Products") within the United States and Canada are made only on the terms which are contained in this Selling Policy. Seller hereby gives notice of its objection to any different or additional terms and conditions. This sale is expressly conditional upon Purchaser's assent to the terms and conditions set forth below. Additional terms and conditions may apply to KnollStudio and KnollTextiles orders. These terms and conditions may be modified or supplemented only by a written document signed by an authorized representative of Seller. These terms and conditions supercede any prior and/or contemporaneous agreements or correspondence between Purchaser and Seller. Written quotations expire thirty (30) days from the date of issuance and can be withdrawn by written notice anytime during that period. Where Purchaser and Seller have entered into the Knoll Electronic Terms and Conditions, all orders, acknowledgements, invoices and other business communications placed or transmitted in accordance with the Knoll Electronic Terms and Conditions shall be deemed to be in writing and signed and shall be valid for all purposes as if they were originated and maintained in documentary form.</p>
Ordering Information	<p>All orders must be in writing. The product pattern number(s) contained on Seller's order acknowledgement shall be the final expression of the order.</p>
Order Confirmation	<p>A purchase order is not binding on Seller until Purchaser has received Seller's order confirmation or acknowledgment.</p>
Pricing Policies	<p>List prices are subject to change without notice.</p> <p>List prices shall be those prices in effect on the date of receipt of a complete purchase order unless shipment is requested more than ninety (90) days after order entry in which case prices in effect on the date of shipment apply. List prices include specified freight costs. Unless specified in writing by Seller, no other charges are included in Seller's list prices.</p>
Taxes	<p>All sales, use, excise and other taxes applicable to the sale of the Products shall be paid by Purchaser. If Purchaser claims an exemption from any tax, Purchaser shall submit to Seller the appropriate exemption certificates.</p>
Terms of Payment	<p>Payment for one hundred percent (100%) of the net order amount is due within thirty (30) days of the date of invoice, which is generally issued upon shipment. In case of any discrepancies, such as shortages, and Seller is notified in writing within ten (10) days of receipt of Product, only that portion may be deducted and the balance paid. For orders greater than \$100,000 net, a fifty percent (50%) deposit is due at the time of order placement, with the remainder due within thirty (30) days of the date of invoice.</p> <p>KnollStudio orders less than \$2,000 require payment for one hundred percent (100%) of the net order amount (including any applicable sales tax and charges for inside delivery, special packaging, etc.), due at time of order placement. For KnollStudio orders greater than \$2,000, a one-half (50%) deposit is due at time of order placement with the remainder (including any applicable sales tax and charges for inside delivery, special packaging, etc.) due prior to shipment.</p> <p>If, in the judgment of Seller, Purchaser's financial condition does not justify the terms of the payment, Seller may require full or partial payment in advance.</p> <p>Past due accounts shall be charged one and one-half percent (1.5%) per month, or the highest rate permitted by law, whichever is less, and will be added to the outstanding balance. In the event Purchaser defaults on payment, Purchaser shall be liable for all collection costs, including reasonable attorney's fees and costs.</p>
Changes and Cancellation	<p>Purchase orders may not be changed or cancelled, in whole or in part, without prior written consent of Seller. Changes may effect delivery dates. Expenses incurred because of changes shall be charged to Purchaser. In the event of cancellations, Purchaser will be liable for reasonable cancellation charges established by Seller. Orders for special Product, orders including "COM" (hereinafter defined) material and orders pursuant to expedited delivery programs, may not be canceled.</p>
Freight Prepaid	<p>Freight is prepaid and included in the price of all Products, except KnollTextiles, within the 48 contiguous United States for orders placed with Knoll, Inc. and within Canada, excluding the Yukon, Northwest Territories, Nunavut and Newfoundland for orders placed with Knoll North America Corp. Packing is tested for rigorous motion and transportation but is not guaranteed to protect furniture from all conditions. If special packaging is required for any reason, please consult with your sales representative or dealer. Seller shall select the method of shipment and routing. Freight for all KnollTextiles orders is prepaid and added to the invoice.</p>
Delivery/Freight Charges	<p>Shipments outside the contiguous 48 United States and Canada shall be shipped F.O.B. Origin.</p> <p>For shipments outside the contiguous United States and Canada, Purchaser is responsible for the cost of freight from point of embarkation, including any handling and transportation charges incidental to loading at the point of departure and unloading at the final destination.</p> <p>Conditions beyond the control of Seller, including weather, available facilities and traffic conditions, may affect exact time of delivery. Seller shall not be responsible for specific carrier delivery date or time unless it has made a specific delivery commitment, in writing.</p> <p>Nonstandard methods of shipment and/or additional services are available upon request. Purchaser will be billed for the differential cost of any special services in excess of standard surface carrier freight costs. Premium charges, at Purchaser's request, will be added for airfreight, exclusive use of vehicle and extra, export or special packaging. Accessorial charges will be added for inside delivery, extra labor, reconsignment and redelivery.</p> <p>Partial shipments may be made and invoiced by Seller.</p>
Claims	<p>All shipments for Knoll Products within the contiguous United States and Canada are F.O.B. Origin. All risk of loss passes to Purchaser at time of delivery to carrier. Purchaser shall inspect all Products upon receipt and notify Seller within ten (10) working days after receipt of any damage or defects which are, or should be, apparent from an inspection of the Product and its packaging. Failure of Purchaser to notify Seller during the ten (10) working day period shall constitute acceptance of the Products and waiver of any apparent defects, errors or shortages. For all claims relating to Product damaged in transit or for any other claims relating to or arising out of the transportation of the Product, Purchaser must seek recovery from the carrier and Seller has no liability to Purchaser for such claims. Seller may, upon request, assist Purchaser with filing of such claims with the carrier, but Seller will not be liable for any of these transportation related claims.</p>
Seller's Security Interest	<p>Until Seller receives the full payment for the Product, Seller shall have a security interest in the Product. Purchaser agrees to perform all acts, including but not limited to the execution and filing of documentation, which may be necessary to perfect and assure the security interest of Seller.</p>
Returns	<p>The return of Products without a written authorization by Seller shall not be accepted. To receive authorization for Product return, please call Customer Service. All Products that are returned pursuant to a valid authorization shall be subject to a twenty-five percent (25%) of list restocking charge. Products not currently offered for sale by Seller (including COM) shall not be authorized for return. All returned Products must be unused, in original condition and in the original Seller packing cartons. No refund or credit shall be given for damaged Products.</p>
Held Orders/Storage	<p>If Purchaser requests that an order be held or delayed, prices and terms and conditions in effect at the time of shipment shall apply. If Purchaser requests a delay after the time when Seller can defer production, Purchaser will be invoiced for the Product, payable in accordance with standard terms, when the order is ready for shipment. Seller may transfer the Product to storage, in which case all expenses incurred in connection with storage, including demurrage, preparation for storage, storage charges and handling shall be payable by Purchaser upon submission of invoices by Seller. Risk of loss to the Product shall pass to the Purchaser upon delivery of the Product into storage.</p>

Selling Policy

Customer's Own Material	A Purchaser who requests a fabric or other surface material not standard to Seller's line of Products ("COM") must submit samples of the requested material to Seller prior to entry of a purchaser order. Seller shall determine if the material is suitable to its manufacturing processes and meets any requirements of Underwriters Laboratories. If the COM is acceptable, Seller will then establish a price for using the COM or the Product in question. For a description of the procedures for submitting samples and testing, contact customer resources or your sales representative. Seller shall have no responsibility for the appearance, condition, performance, durability, colorfastness or any other physical attribute of the COM. Purchaser shall indemnify and hold Seller harmless for any damages, injuries or losses arising out of or related to use of the COM on the Product.
Warranty	<p>Seller warrants to the original Purchaser only that the Products Seller manufactures and sells to Purchaser are free of defects in workmanship and materials, during the applicable warranty period set forth below.</p> <p>Warranty period set forth below is for 24-hour, 7 days a week, multi shift use (includes parts and labor to repair).</p> <p>Should any failure to conform with this limited warranty appear to a Product listed below during the applicable warranty period from the date of shipment, Seller shall, upon prompt written notice, repair or replace, at its option and costs, the affected part or parts.</p> <p><i>Product and Period of Warranty</i></p> <p><i>Lifetime: Antenna Workspaces, AutoStrada, Calibre, Crinion Open Table, Currents, Dividends Horizon, Morrison, Reff Profiles laminate, Rockwell Unscripted, Series 2 Storage, Template and other non-wood components (except cascade edge worksurfaces, operational parts, controls, electrical, Lighting, Series 2 Veneer Front Storage, upholstery, textiles and leathers, special or custom products, see below)</i></p> <p><i>12 Years: Chadwick, Essentials Work Chairs, Generation by Knoll, k. task, Life, Moment, MultiGeneration by Knoll, ReGeneration by Knoll, Remix, and Toboggan seating (except seating upholstery, textiles, leathers and finishes, see below).</i></p> <p><i>10 Years: Anchor Storage except digital keypad lock, Antenna Workspaces, AutoStrada, Crinion Open Table, Dividends Horizon, Dividends Horizon Satellite Surfaces, Reff Profiles, Rockwell Unscripted, Template wood components, Series 2 Veneer Front Storage, cascade edge worksurfaces, Wood Casegoods (The Graham Collection) (except wood casegoods upholstered surfaces, see below), Reuter overheads, Reuter vertical storage, KnollExtra Sapper Monitor Arm Collection, Sapper XYZ Monitor Arm, Adjustable keyboard mechanisms and platforms, Communication Boards (except fabric board textiles, cork and FilzFelt, see below), Smokador collection (except leathers, see below), and Orchestra Universal Systems Accessories, k. lounge structural components, Tone Height-Adjustable Tables.</i></p> <p><i>5 Years: Operational parts, controls, electrical, Lighting (except light ballasts, bulbs and power supply, see below), special or custom product, wood veneer products and plywood, Currents handcrank, Interaction Counterforce, KnollStudio, Rockwell Unscripted wire bases, Spark Series seating structural elements, structural elements of all KnollStudio outdoor products including all Richard Schultz designed products, KnollExtra CPU storage and all universal storage drawers and Power Collection, k. stand (except changes in finish, see below).</i></p> <p><i>3 Years: Rockwell Unscripted upholstery (except textiles and leather), Office Seating upholstery, textiles, leathers and finishes. Fabric boards textiles and Smokador Collection leathers, KnollExtra Pop Up Screens.</i></p> <p><i>2 Years: Anchor Storage digital keypad lock, all other KnollExtra product</i></p> <p><i>1 Year: Light ballasts, bulbs and power supply, seating upholstered armpads and soft armpads, wood casegoods upholstered surfaces. KnollStudio, outdoor product finishes, k. lounge upholstery and k. lounge fabric. Rockwell Unscripted fabric and accessories.</i></p> <p>This warranty does not apply to:</p> <ul style="list-style-type: none">• Damage caused by a carrier other than the Seller.• Normal wear and tear or acts or omissions of parties other than Seller (including user modification, improper use or installation of Products).• COM or other third party materials applied to Products.• Products not installed by or under the auspices of a Knoll Dealer.• Dramatic temperature variations or exposure to unusual conditions.• Changes in surface finishes, including colorfastness due to aging or exposure to light.• Except as specifically noted above, textiles and upholstery supplied by KnollTextiles and Spinneybeck FilzFelt (consult current price lists for applicable warranties). <p>Natural variations occurring in wood, marble, and leather shall not be considered defects, and the Seller does not guarantee the colorfastness or matching of the colors, grains or textures, or surface hardness of such materials. The Seller also does not guarantee the colorfastness of fiberglass panel surfaces.</p> <p>THE EXPRESS WARRANTIES CONTAINED HEREIN ARE IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY WARRANTIES OF MERCHANTABILITY AND FITNESS FOR PARTICULAR PURPOSE AND ALL OTHER WARRANTIES ARISING FROM COURSE OF DEALING OR USAGE OF TRADE.</p> <p>The remedies provided above are the Purchaser's sole remedies for any failure of Seller to comply with its obligations regarding the workmanship of its Products. Correction of any nonconformity in the manner and for the period of time provided shall constitute complete fulfillment of all liabilities of Seller, with respect to or arising out of the Product furnished hereunder.</p>
Delay/Force Majeure	Seller shall not be liable for failure to perform or for delay in performance due to fire, flood, strike or other labor difficulty, act of God, act of any governmental authority or of the Purchaser, riot, embargo, fuel or energy shortage, wrecks or delay in transportation, inability to obtain necessary labor, materials or manufacturing facilities from usual sources or failure of suppliers to meet their contractual obligations, or due to any cause beyond its reasonable control. If any such event occurs, Seller may extend delivery dates by a period of time necessary to overcome the effect of such delay, allocate available Product or cancel any purchase order.
Compliance with Law	PURCHASER IS SOLELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, ORDINANCES, REGULATIONS, RULES AND STANDARDS RELATING TO THE INSTALLATION, MAINTENANCE, USE AND OPERATION OF THE PRODUCTS.
Patents	<p>Subject to the following provisions, Seller shall, at its own expense, defend or, at its option, settle any claim, suit or proceeding brought against the Purchaser, and/or its vendees, mediate and immediate, so far as based on an allegation that any Product or any part thereof furnished hereunder constitutes a direct or a contributory infringement of any claim of any patent of the United States or Canada. This obligation shall be effective only if Purchaser shall have made all payments then due hereunder and if Seller is notified promptly in writing and given authority, information and assistance for the defense of said claim, suit or proceeding. Seller shall pay all damages and costs awarded in such suit or proceedings so defended.</p> <p>The foregoing indemnity does not apply to the following:</p> <ul style="list-style-type: none">• Products supplied according to a design other than that of Seller, and which is required by the Purchaser.• Combination of the Product with another product not furnished hereunder unless Seller is a contributory infringer.• Any settlements of a suit or proceeding made without Seller's written consent.
Limitations of Liability	<p>SELLER, ITS CONTRACTORS, AUTHORIZED DEALERS AND SUBCONTRACTORS OR SUPPLIERS OF ANY TIER SHALL NOT BE LIABLE TO PURCHASER FOR ANY SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES ARISING FROM A BREACH OF THIS AGREEMENT.</p> <p>Purchaser's remedies set forth herein are exclusive and the liability of Seller with respect to the breach of this agreement or any contract entered into between the parties pursuant hereto shall not exceed the price of the Product or part on which such liability is based.</p>

KnollKey Lock Program

KnollKey Lock Program General Information

Following is the KnollKey lock policy, applicable to all products.

Knoll furniture can be ordered keyed-alike or random keyed. Key-alike and random keying instructions cannot be mixed on any single order. Only one of the two instructions can be used on an individual order. When an order is submitted with mixed (key-alike and random) instructions, Knoll will release the order as key-alike only and lock cores will have to be specified separately.

Key-alike

For the convenience of the user, furniture may be keyed alike at no charge. Write "Key-alike" in the description of your purchase order for any pedestal, overhead, file or other item you wish to have keyed alike.

Using the key-alike instructions, order cores and keys as line items on your purchase order. Do NOT submit a key-alike form. The Knoll East Greenville Lock Center will select key numbers from the standard range of K 001 - K 250. Key numbers will not be repeated unless over 250 sets are ordered. Lock cores keyed-alike will ship separately from the product, ready for field installation.

There is no charge for key-alike orders if placed with the furniture order.

IF THE KEY-ALIKE ORDER IS NOT PLACED AT LEAST TWO WEEKS PRIOR TO THE FURNITURE SHIP DATE, A \$50 HANDLING CHARGE AND AIR FREIGHT CHARGES WILL APPLY.

If product is ordered and shipped random-keyed, additional lock cores for key-alike are billable.

Random-Keying

To specify product keyed-random, write "key-random" in the product description. Random-keyed product is shipped with the lock core factory installed. A shrouded key is included. Random means no effort has been made to match key numbers, or to make them different.

Keys

A Knoll shrouded key is shipped with every lock core. 250 Key numbers are available. For numbers above 250, contact Custom Product Development. Additional keys and key blanks are available. See service parts for more information.

Master Keying

Knoll locks can be controlled by means of a master key. There is no additional per-lock charge for master keying. A letter of approval from the client must accompany orders for master keys.

Installing Lock Cores

Lock cores can be installed or removed in the field by using a change key. Cores must be in the unlocked position to be removed. See service parts for change key pattern number and pricing.


Lock Distribution

All orders for key-alike lock cores/keys are packaged and shipped from the East Greenville Lock Center, regardless of where the pedestals, overhead, or other units are produced. Random keyed product will have cores factory-installed.

How to Specify Key-Alike

Following is an example of how to specify key-alike for a cluster of 10 workstations.

Step 1 - Using the project floorplan, count the number of locks in each workstation.



Step 2 - Count the number of workstations with the same quantity of locks. Group together the workstations with a like number of locks.

5 workstations with 2 locks per station
3 workstations with 4 locks per station
2 workstations with 5 locks per station

Step 3 - For the first group (5 sets of 2 locks), enter the number of workstations in the quantity column.

Qty	Pattern #	Description	Unit List	Ext. List
5				

Step 4 - Then enter the pattern number "KSPEC_ _" and add a suffix for the number of locks for that group (i.e., for 2 locks per station, add the suffix "2"). Up to 30 lock cores are available in a set (i.e., KSPEC 30).

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C

Step 5 - Repeat for other groups.

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C
3	KSPEC 4	Set of 4 cores/keys	N / C	N / C
2	KSPEC 5	Set of 5 cores/keys	N / C	N / C

Your Key instructions are complete.

Knoll will select key numbers for each set from 250 available numbers. Additional key numbers are available through Custom Product Development. **For additions to existing installations, specify desired key numbers in the description.**

Service Parts

Pattern #	Description	List Price
KKEY_ _ _	Shrouded Key Specify key number desired	\$10
KBLANK	Shrouded Key Blank	\$10
KSPECB_ _ _	Retrofit Universal Core/Key Specify key number desired	\$22
KCHANGE	Change Key	\$10
HLKRKMASTER*	Master Key	\$10

*Note: A letter of approval on company letterhead from the client must accompany all orders for master keys.

General Ordering Information

The Products

This guide encompasses all standard products for this product group.

Sizes

Dimensions listed in this guide are indicated as:

H = height

W = width

D = depth

Dia. = diameter

Rad. = radius

Pricing

All prices shown are list.

How to Order

Select pattern numbers and quantities required for your complete installation. Product questions can be addressed in the specific sections of this guide or by contacting your sales representative or customer resource representative at 1-800-343-5665.

Next, select options (if required), along with colors and finishes appropriate to each product. Reference the Finishes and Fabrics pages for color designations.

On large installations, an item's "designated area" can be specified to assist in product organization and handling.

To expedite complete / correct entry of your order, be certain all pattern numbers, quantities, colors and area identifications are completely specified. Also, include complete purchase order numbers, bill-to and ship-to addresses, a contact name and specific factory shipping dates required.

Mail all orders to:

Knoll, Inc.

1235 Water Street

P.O. Box 157

East Greenville, PA 18041

Attention: Order Entry

Once your order is entered at Knoll, an acknowledgment will be mailed to you. You will be advised of your scheduled shipping date within five days of the original acknowledgment. If it is necessary to revise your order, please contact your customer resource representative.

Sustainability Statement

Sustainable design is a key component of Knoll's environmental focus. Our commitment to social responsibility and a healthy environment has prompted us to further articulate our longstanding environmental programs and, with encouragement and support from our colleagues in the industry, we have re-energized our focus on such "green" initiatives as life cycle analysis and LEED™ certification. Knoll is proud to have contributed to projects that have received LEED certification from the U.S. Green Building Council.

For the latest information on Knoll products that help our customers achieve LEED certification, log on to knoll.com, click on "About Knoll" and then "Environmental Focus."